

**Fort Bend County Tabulation
 Bid 12-055
 Drainage and Paving Improvements for West Bellfort Road Widening**

**Recommendation: Mar-Con Services
 Funding: Mobility**

Vendor	Base Bid	Alternate: Traffic Signal	Completion Time in Calendar Days
Mar-Con Services Deer Park	\$1,404,134.56	\$199,161.60	120
Durwood Greene Stafford	\$1,496,981.50	\$186,576.00	120
Tripple B Services Huffman	\$1,576,077.85	\$180,596.00	120
Conrad Constructions Houston	\$1,600,367.00	\$189,060.50	120
Metro City Houston	Disqualified: Did not provide references as required.		

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

	Mar-Con Services Deer Park	Durwood Greene Stafford	Triple B Services Huffman	Conrad Construction Houston	
SECTION I - WEST BELLFORT ROAD WITHIN TxDOT RIGHT-OF-WAY					
A.	DRAINAGE ITEMS	\$16,306.70	\$21,877.00	\$23,275.70	\$30,170.00
B.	PAVING ITEMS	\$107,979.44	\$124,451.00	\$150,451.00	\$156,996.00
C.	TRAFFIC SIGNAL ITEMS - SH99 NBFR AT W BELLFORT	\$65,783.00	\$71,645.00	\$67,177.00	\$63,817.75
D.	PAVEMENT MARKING RELATED ITEMS	\$6,130.90	\$7,050.00	\$5,354.20	\$6,152.00
E.	EROSION & SEDIMENTATION CONTROL ITEMS	\$5,826.00	\$5,665.00	\$5,124.50	\$5,945.00
F.	SUPPLEMENTAL ITEMS	\$6,225.00	\$6,225.00	\$2,175.00	\$7,000.00
	SECTION I - SUBTOTAL	\$208,251.04	\$236,913.00	\$253,557.40	\$270,080.75
SECTION II - WEST BELLFORT ROAD WITHIN FORT BEND COUNTY RIGHT-OF-WAY					
G.	DRAINAGE ITEMS	\$275,120.50	\$333,710.00	\$306,236.30	\$383,997.00
H.	PAVING ITEMS	\$528,107.22	\$552,729.00	\$646,384.85	\$546,744.00
I.	ASPHALT TRANSITION RELATED ITEMS	\$117,378.40	\$117,291.00	\$127,848.05	\$127,837.00
J.	TRAFFIC SIGNAL ITEMS FOR MEADOW RANCH PKWY AT W. BELLFORT - OPTION 2	\$176,897.60	\$173,926.00	\$171,933.50	\$171,783.50
K.	PAVEMENT MARKING RELATED ITEMS	\$5,702.70	\$5,947.50	\$4,952.50	\$6,237.25
L.	EROSION & SEDIMENTATION CONTROL ITEMS	\$11,738.60	\$18,325.00	\$11,625.25	\$13,867.50
M.	SUPPLEMENTAL ITEMS	\$80,938.50	\$58,050.00	\$53,540.00	\$79,820.00
	SECTION II - SUBTOTAL	\$1,195,883.52	\$1,259,978.50	\$1,322,520.45	\$1,330,286.25
	TOTAL AMOUNT OF BASE BID	\$1,404,134.56	\$1,496,891.50 *	\$1,576,077.85	\$1,600,367.00
ALTERNATE BID ITEMS					
N.	TRAFFIC SIGNAL ITEMS FOR MEADOW RANCH PKWY AT W. BELLFORT - OPTION 1	\$199,161.60	\$186,576.00	\$180,596.00	\$189,060.50

* Error in bid tabulation

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

Item No.	Spec. No.	Description of Item	Quantity	Unit	Mar-Con Services Deer Park		Durwood Greene Stafford		Triple B Services Huffman		Conrad Construction Houston	
					Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total
SECTION I - WEST BELLFORT ROAD WITHIN TxDOT RIGHT-OF-WAY												
A. DRAINAGE ITEMS												
1 .	460	24" Inlet Lead, To Include Adjusting Existing Inlet, Breaking into Existing Inlet and Connect the Prop. 24" RCP	157	LF	\$64.70	\$10,157.90	\$80.00	\$12,560.00	\$80.00	\$12,560.00	\$125.00	\$19,625.00
2 .	472	Type "C" Inlet with an Additional Depth Up To 5 Feet (Stages I and II)	2	EA	\$1,750.60	\$3,501.20	\$2,700.00	\$5,400.00	\$2,650.00	\$5,300.00	\$2,800.00	\$5,600.00
3 .	465	Remove Existing 24" Storm Sewer Lead	144	LF	\$8.70	\$1,252.80	\$15.00	\$2,160.00	\$25.00	\$3,600.00	\$15.00	\$2,160.00
4 .	495	Remove and Dispose of Existing Storm Sewer Inlet, Including Manhole	4	EA	\$285.90	\$1,143.60	\$400.00	\$1,600.00	\$450.00	\$1,800.00	\$500.00	\$2,000.00
5 .	429	Trench Safety Systems, 5' to 10' Depth	157	LF	\$1.60	\$251.20	\$1.00	\$157.00	\$0.10	\$15.70	\$5.00	\$785.00
DRAINAGE ITEMS SUBTOTAL						\$16,306.70		\$21,877.00		\$23,275.70		\$30,170.00
B. PAVING ITEMS												
6 .	102	Clearing & Grubbing	0.6	AC	\$6,090.40	\$3,654.24	\$7,000.00	\$4,200.00	\$8,475.00	\$5,085.00	\$1,500.00	\$900.00
7 .	110	Roadway Excavation	2,650	CY	\$8.30	\$21,995.00	\$7.00	\$18,550.00	\$11.00	\$29,150.00	\$1.00	\$2,650.00
8 .	220	6-inch Lime Stabilized Subgrade	670	SY	\$3.20	\$2,144.00	\$6.00	\$4,020.00	\$3.10	\$2,077.00	\$6.00	\$4,020.00
9 .	221	Lime for Subgrade (8% or (48 lbs per SY)	17	TON	\$159.90	\$2,718.30	\$150.00	\$2,550.00	\$190.00	\$3,230.00	\$200.00	\$3,400.00
9a .	TxDOT Item 292	6" Cement Stabilized Base as per TxDOT Item 292-2224 "CEM TRT (PLNT MX)(CL N)(TY E)(GR 4)(6")"	670	SY	\$15.20	\$10,184.00	\$20.00	\$13,400.00	\$22.30	\$14,941.00	\$12.00	\$8,040.00
9b .	TxDOT Item 292	Asph Stabilized Base (1" Bond Breaker) as Per TxDOT Item 292-2017 "ASPHALT STAB BASE (GR 4)(PG 64)"	37	TON	\$311.90	\$11,540.30	\$150.00	\$5,550.00	\$218.50	\$8,084.50	\$260.00	\$9,620.00
10 .	360	10-inch Reinforced Concrete Pavement (3,500 psi), To Include Standard Paving Header (Load Transfer Device), Saw Cutting, and any Block Out for Inlets	670	SY	\$44.30	\$29,681.00	\$52.00	\$34,840.00	\$82.65	\$55,375.50	\$85.00	\$56,950.00
11 .	535	6-inch Concrete/ Rip Rap for Raised Median	102	SY	\$48.40	\$4,936.80	\$75.00	\$7,650.00	\$110.00	\$11,220.00	\$45.00	\$4,590.00
12 .	530	6-inch Concrete Curb	580	LF	\$2.10	\$1,218.00	\$3.00	\$1,740.00	\$4.85	\$2,813.00	\$5.00	\$2,900.00
13 .	624, 646	Traffic Signs	1	EA	\$345.00	\$345.00	\$400.00	\$400.00	\$300.00	\$300.00	\$340.00	\$340.00
14 .	671	Traffic Control Handling (All Phases)	4	MO	\$4,100.90	\$16,403.60	\$5,000.00	\$20,000.00	\$1,620.00	\$6,480.00	\$14,900.00	\$59,600.00
15 .	500	Relocate Existing Sign	1	EA	\$125.80	\$125.80	\$400.00	\$400.00	\$100.00	\$100.00	\$325.00	\$325.00
16 .	104	Remove & Dispose of Exist. Concrete Pavement, Island, Curb, and Wheelchair Ramp	375	SY	\$5.80	\$2,175.00	\$25.00	\$9,375.00	\$25.00	\$9,375.00	\$7.00	\$2,625.00
17 .	540	Remove & Dispose of Exist. Asphalt Pavement (surface and Base Material)	148	SY	\$5.80	\$858.40	\$12.00	\$1,776.00	\$15.00	\$2,220.00	\$7.00	\$1,036.00
PAVING ITEMS SUBTOTAL						\$107,979.44		\$124,451.00		\$150,451.00		\$156,996.00

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

Item No.	Spec. No.	Description of Item	Quantity	Unit	Mar-Con Services Deer Park		Durwood Greene Stafford		Triple B Services Huffman		Conrad Construction Houston	
					Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total
C. TRAFFIC SIGNAL ITEMS - SH99 NBFR AT W BELLFORT												
18 .	416 - 2032 (TxDOT)	DRILL SHAFT (TRF SIG POLE) (36 IN.)	31	LF	\$253.00	\$7,843.00	\$240.00	\$7,440.00	\$160.00	\$4,960.00	\$245.00	\$7,595.00
19 .	531 - 2005 (TxDOT)	CURB RAMP (TY 1)	1	EA	\$924.80	\$924.80	\$1,500.00	\$1,500.00	\$1,925.00	\$1,925.00	\$1,300.00	\$1,300.00
20 .	531 - 2011 (TxDOT)	CURB RAMP (TY 8)	2	EA	\$924.80	\$1,849.60	\$1,500.00	\$3,000.00	\$1,925.00	\$3,850.00	\$1,300.00	\$2,600.00
21 .	531 - 2014 (TxDOT)	CURB RAMP (TY 22)	1	EA	\$2,326.90	\$2,326.90	\$3,500.00	\$3,500.00	\$3,250.00	\$3,250.00	\$1,600.00	\$1,600.00
22 .	618 - 2034 (TxDOT)	CONDUIT (PVC) (SCHD 80) (2")	90	LF	\$5.80	\$522.00	\$5.00	\$450.00	\$8.50	\$765.00	\$5.50	\$495.00
23 .	618 - 2038 (TxDOT)	CONDUIT (PVC) (SCHD 80) (3")	470	LF	\$8.10	\$3,807.00	\$7.00	\$3,290.00	\$11.50	\$5,405.00	\$7.70	\$3,619.00
24 .	618 - 2039 (TxDOT)	CONDUIT (PVC) (SCHD 80) (3") (BORE)	500	LF	\$11.50	\$5,750.00	\$10.00	\$5,000.00	\$12.00	\$6,000.00	\$11.00	\$5,500.00
25 .	620 - 2009 (TxDOT)	ELEC CONDR (NO. 6) BARE	720	LF	\$1.00	\$720.00	\$1.00	\$720.00	\$0.90	\$648.00	\$1.00	\$720.00
26 .	621 - 2004 (TxDOT)	TRAY CABLE (4 CONDR) (12 AWG)	335	LF	\$1.70	\$569.50	\$2.00	\$670.00	\$1.40	\$469.00	\$1.65	\$552.75
27 .	624 - 2014 (TxDOT)	GROUND BOX TY D (162922) W/APRON	5	EA	\$649.80	\$3,249.00	\$600.00	\$3,000.00	\$700.00	\$3,500.00	\$622.00	\$3,110.00
28 .	682 - 2001 (TxDOT)	BACK PLATE (12 IN) (3 SEC)	4	EA	\$63.30	\$253.20	\$60.00	\$240.00	\$0.50	\$2.00	\$61.00	\$244.00
29 .	682 - 2002 (TxDOT)	BACK PLATE (12 IN) (4 SEC)	1	EA	\$74.80	\$74.80	\$70.00	\$70.00	\$90.00	\$90.00	\$72.00	\$72.00
30 .	682 - 2014 (TxDOT)	PED SIG SEC (12 IN) LED (2 INDICATIONS)	4	EA	\$414.00	\$1,656.00	\$400.00	\$1,600.00	\$400.00	\$1,600.00	\$400.00	\$1,600.00
31 .	682 - 2022 (TxDOT)	VEH SEC (12 IN) LED (GRN ARW)	1	EA	\$195.50	\$195.50	\$200.00	\$200.00	\$180.00	\$180.00	\$190.00	\$190.00
32 .	682 - 2023 (TxDOT)	VEH SEC (12 IN) LED (GRN)	4	EA	\$195.50	\$782.00	\$200.00	\$800.00	\$180.00	\$720.00	\$190.00	\$760.00
33 .	682 - 2024 (TxDOT)	VEH SEC (12 IN) LED (YEL ARW)	1	EA	\$184.00	\$184.00	\$200.00	\$200.00	\$175.00	\$175.00	\$180.00	\$180.00
34 .	682 - 2025 (TxDOT)	VEH SEC (12 IN) LED (YEL)	4	EA	\$195.50	\$782.00	\$200.00	\$800.00	\$180.00	\$720.00	\$190.00	\$760.00
35 .	682 - 2027 (TxDOT)	VEH SEC (12 IN) LED (RED)	6	EA	\$184.00	\$1,104.00	\$200.00	\$1,200.00	\$175.00	\$1,050.00	\$190.00	\$1,140.00

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

Item No.	Spec. No.	Description of Item	Quantity	Unit	Mar-Con Services Deer Park		Durwood Greene Stafford		Triple B Services Huffman		Conrad Construction Houston	
					Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total
36 .	684 - 2007 (TxDOT)	TRAF SIG CBL (TY A) (12 AWG) (2 CONDR)	1,210	LF	\$1.00	\$1,210.00	\$1.00	\$1,210.00	\$0.80	\$968.00	\$1.00	\$1,210.00
37 .	684 - 2009 (TxDOT)	TRAF SIG CBL (TY A) (12 AWG) (4 CONDR)	1,210	LF	\$1.30	\$1,573.00	\$1.50	\$1,815.00	\$1.00	\$1,210.00	\$1.20	\$1,452.00
38 .	684 - 2012 (TxDOT)	TRAF SIG CBL (TY A) (12 AWG) (7 CONDR)	1,070	LF	\$2.00	\$2,140.00	\$2.00	\$2,140.00	\$2.00	\$2,140.00	\$1.90	\$2,033.00
39 .	686 - 2039 (TxDOT)	INS TRAF SIG PL AM (S) 1 ARM (40')	1	EA	\$6,900.00	\$6,900.00	\$7,500.00	\$7,500.00	\$6,700.00	\$6,700.00	\$6,600.00	\$6,600.00
40 .	686 - 2045 (TxDOT)	INS TRAF SIG PL AM (S) 1 ARM (44') LUM	1	EA	\$9,085.00	\$9,085.00	\$8,000.00	\$8,000.00	\$8,100.00	\$8,100.00	\$8,700.00	\$8,700.00
41 .	687 - 2001 (TxDOT)	PED POLE ASSEMBLY	1	EA	\$1,069.50	\$1,069.50	\$1,000.00	\$1,000.00	\$1,200.00	\$1,200.00	\$1,025.00	\$1,025.00
42 .	688 - 2001 (TxDOT)	PED DETECT (2 IN PUSH BTN)	4	EA	\$87.40	\$349.60	\$100.00	\$400.00	\$100.00	\$400.00	\$85.00	\$340.00
43 .	6007 - 2001 (TxDOT)	REMOVING TRAFFIC SIGNALS (PARTIAL)	1	EA	\$1,897.50	\$1,897.50	\$5,000.00	\$5,000.00	\$2,000.00	\$2,000.00	\$1,820.00	\$1,820.00
44 .	6266 - 2001 (TxDOT)	VIVDS PROCESSOR SYSTEM	1	EA	\$4,370.00	\$4,370.00	\$6,000.00	\$6,000.00	\$3,000.00	\$3,000.00	\$4,200.00	\$4,200.00
45 .	6266 - 2002 (TxDOT)	VIVDS CAMERA ASSEMBLY	2	EA	\$1,523.80	\$3,047.60	\$1,500.00	\$3,000.00	\$1,300.00	\$2,600.00	\$1,450.00	\$2,900.00
46 .	6266 - 2003 (TxDOT)	VIVDS SET - UP SYSTEM	1	EA	\$287.50	\$287.50	\$500.00	\$500.00	\$2,500.00	\$2,500.00	\$275.00	\$275.00
47 .	6266 - 2005 (TxDOT)	VIVDS COMMUNICATION CABLE (COAXIAL)	700	LF	\$1.80	\$1,260.00	\$2.00	\$1,400.00	\$1.50	\$1,050.00	\$1.75	\$1,225.00
TRAFFIC SIGNAL ITEMS - SH99 NBFR AT W BELLFORT SUBTOTAL						\$65,783.00		\$71,645.00		\$67,177.00		\$63,817.75
D. PAVEMENT MARKING RELATED ITEMS												
48 .	660	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	415	LF	\$1.30	\$539.50	\$1.50	\$622.50	\$1.10	\$456.50	\$1.25	\$518.75
49 .	660	REFL PAV MRK TY I (W) 12" (SLD) (100MIL)	525	LF	\$3.30	\$1,732.50	\$3.50	\$1,837.50	\$2.90	\$1,522.50	\$3.25	\$1,706.25
50 .	660	REFL PAV MRK TY I (W) 24" (SLD) (100MIL)	220	LF	\$5.60	\$1,232.00	\$7.00	\$1,540.00	\$4.90	\$1,078.00	\$5.50	\$1,210.00
51 .	660	REFL PAV MRK TY I (Y) 4" (SLD) (100MIL)	680	LF	\$0.60	\$408.00	\$0.70	\$476.00	\$0.53	\$360.40	\$0.75	\$510.00
52 .	660	REFL PAV MRK TY I (Y) 24" (SLD) (100MIL)	280	LF	\$5.60	\$1,568.00	\$7.00	\$1,960.00	\$4.90	\$1,372.00	\$5.50	\$1,540.00
53 .	663	TRAFFIC BUTTON TY II - C - R	10	EA	\$4.40	\$44.00	\$4.00	\$40.00	\$3.80	\$38.00	\$4.50	\$45.00
54 .	663	TRAFFIC BUTTON TY II - A - A	36	EA	\$4.40	\$158.40	\$4.00	\$144.00	\$3.80	\$136.80	\$4.50	\$162.00
55 .	666	REFL PAV MRK TY I (W) (ARROW) (100MIL)	1	EA	\$184.00	\$184.00	\$200.00	\$200.00	\$160.00	\$160.00	\$200.00	\$200.00
56 .	666	REFL PAV MRK TY I (W) (WORD) (100MIL)	1	EA	\$264.50	\$264.50	\$230.00	\$230.00	\$230.00	\$230.00	\$260.00	\$260.00
PAVEMENT MARKING RELATED ITEMS SUBTOTAL						\$6,130.90		\$7,050.00		\$5,354.20		\$6,152.00

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

Item No.	Spec. No.	Description of Item	Quantity	Unit	Mar-Con Services Deer Park		Durwood Greene Stafford		Triple B Services Huffman		Conrad Construction Houston	
					Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total
E. EROSION & SEDIMENTATION CONTROL ITEMS												
57 .	713	Reinforced Filter Fabric Fence	410	LF	\$1.30	\$533.00	\$1.50	\$615.00	\$1.10	\$451.00	\$2.00	\$820.00
58 .	719	Filter Fence Barrier around Inlets (per Inlet)	3	EA	\$46.00	\$138.00	\$100.00	\$300.00	\$35.00	\$105.00	\$75.00	\$225.00
59 .	741	Gravel Bag Barrier around Inlets	30	LF	\$4.00	\$120.00	\$10.00	\$300.00	\$4.00	\$120.00	\$5.00	\$150.00
60 .	165	Turf Establishment by Hydromulch Seeding	0.3	AC	\$3,450.00	\$1,035.00	\$1,500.00	\$450.00	\$1,495.00	\$448.50	\$2,500.00	\$750.00
61 .	751	SWPPP Inspection and Maintenance	4	MO	\$1,000.00	\$4,000.00	\$1,000.00	\$4,000.00	\$1,000.00	\$4,000.00	\$1,000.00	\$4,000.00
EROSION & SEDIMENTATION CONTROL ITEMS SUBTOTAL						\$5,826.00		\$5,665.00		\$5,124.50		\$5,945.00
F. SUPPLEMENTAL ITEMS												
62 .	436	Well Point Dewatering System	50	LF	\$20.00	\$1,000.00	\$20.00	\$1,000.00	\$20.00	\$1,000.00	\$20.00	\$1,000.00
63 .	402	Extra Bank Sand Backfill	10	CY	\$10.00	\$100.00	\$10.00	\$100.00	\$10.00	\$100.00	\$10.00	\$100.00
64 .	433, SP 433	Cement Stabilized Sand (Based on 8-inch Thickness)	10	SY	\$12.50	\$125.00	\$12.50	\$125.00	\$12.50	\$125.00	\$15.00	\$150.00
65 .		Additional Cost for Bedding for Unsatisfactory Soil Conditions per City of Houston Drawing No. 2317-02	50	LF	\$10.00	\$500.00	\$10.00	\$500.00	\$10.00	\$500.00	\$10.00	\$500.00
66 .	360	Rapid Setting High Early Strength Concrete - 10-inch in Depth (3,500 psi), To Include Standard Paving Header (Load Transfer Device), and Saw Cutting	15	CY	\$300.00	\$4,500.00	\$300.00	\$4,500.00	\$30.00	\$450.00	\$350.00	\$5,250.00
SUPPLEMENTAL ITEMS SUBTOTAL						\$6,225.00		\$6,225.00		\$2,175.00		\$7,000.00
SECTION II - WEST BELLFORT ROAD WITHIN FORT BEND COUNTY RIGHT-OF-WAY												
G. DRAINAGE ITEMS												
67 .	460	24" Inlet Lead	65	LF	\$59.20	\$3,848.00	\$75.00	\$4,875.00	\$80.00	\$5,200.00	\$95.00	\$6,175.00
68 .	460, 431	24" Inlet Lead By Bore & Jack	95	LF	\$172.40	\$16,378.00	\$170.00	\$16,150.00	\$150.00	\$14,250.00	\$170.00	\$16,150.00
69 .	460	30" Inlet Lead	39	LF	\$84.40	\$3,291.60	\$95.00	\$3,705.00	\$100.00	\$3,900.00	\$115.00	\$4,485.00
70 .	460, 431	30" Inlet Lead By Bore & Jack	41	LF	\$213.50	\$8,753.50	\$275.00	\$11,275.00	\$225.00	\$9,225.00	\$250.00	\$10,250.00
71 .	460	24" RCP Storm Sewer	401	LF	\$65.70	\$26,345.70	\$80.00	\$32,080.00	\$80.00	\$32,080.00	\$90.00	\$36,090.00
72 .	460, 433	36" RCP Storm Sewer	504	LF	\$103.00	\$51,912.00	\$135.00	\$68,040.00	\$143.00	\$72,072.00	\$155.00	\$78,120.00
73 .	460, 433	54" RCP Storm Sewer, To Include Breaking into Exist. Storm Manhole and Connecting the Prop. 54" RCP	584	LF	\$219.20	\$128,012.80	\$260.00	\$151,840.00	\$225.00	\$131,400.00	\$325.00	\$189,800.00
74 .	472	Type "B-B" Inlet with an Additional Depth Up To 5 Feet (Stages I and II)	2	EA	\$2,068.00	\$4,136.00	\$2,400.00	\$4,800.00	\$2,575.00	\$5,150.00	\$2,500.00	\$5,000.00
75 .	472	Type "C-1" Inlet with an Additional Depth Up To 5 Feet and 5' Extension on Each Side (Stages I and II)	1	EA	\$2,534.70	\$2,534.70	\$3,200.00	\$3,200.00	\$4,050.00	\$4,050.00	\$3,300.00	\$3,300.00

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

Item No.	Spec. No.	Description of Item	Quantity	Unit	Mar-Con Services Deer Park		Durwood Greene Stafford		Triple B Services Huffman		Conrad Construction Houston	
					Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total
76 .	472	Type "C-1" Curb Inlet with an Additional Depth Up To 5 Feet (Stages I and II)	2	EA	\$2,468.00	\$4,936.00	\$3,100.00	\$6,200.00	\$4,050.00	\$8,100.00	\$3,200.00	\$6,400.00
77 .	472	Type "C-1" Curb Inlet with an Additional Depth Up To 5 Feet and 5' Extension on Each Side (Stages I and II)	1	EA	\$2,215.00	\$2,215.00	\$2,700.00	\$2,700.00	\$4,850.00	\$4,850.00	\$2,950.00	\$2,950.00
78 .	471	Type "M" Storm Sewer Manhole (Junction Box with Access)	1	EA	\$7,509.50	\$7,509.50	\$9,500.00	\$9,500.00	\$8,100.00	\$8,100.00	\$7,900.00	\$7,900.00
79 .	471	Type "C" Extra Depth Storm Sewer Manhole (48" pipe and larger)	2	EA	\$6,588.40	\$13,176.80	\$8,000.00	\$16,000.00	\$3,850.00	\$7,700.00	\$7,600.00	\$15,200.00
80 .	429	Trench Safety Systems, 10' to 15' Depth	1,009	LF	\$1.30	\$1,311.70	\$1.00	\$1,009.00	\$0.10	\$100.90	\$1.00	\$1,009.00
81 .	429	Trench Safety Systems, 15' to 20' Depth	584	LF	\$1.30	\$759.20	\$4.00	\$2,336.00	\$0.10	\$58.40	\$2.00	\$1,168.00
DRIANAGE ITEMS SUBTOTAL						\$275,120.50		\$333,710.00		\$306,236.30		\$383,997.00
H. PAVING ITEMS												
82 .	102	Clearing & Grubbing	2.7	AC	\$44,940.60	\$121,339.62	\$25,000.00	\$67,500.00	\$8,475.00	\$22,882.50	\$1,500.00	\$4,050.00
83 .	132	Embankment	92	CY	\$15.60	\$1,435.20	\$15.00	\$1,380.00	\$1.80	\$165.60	\$15.00	\$1,380.00
84 .	110	Roadway Excavation, To include Roadside Ditch	6,325	CY	\$8.30	\$52,497.50	\$7.00	\$44,275.00	\$11.00	\$69,575.00	\$10.00	\$63,250.00
85 .	220	8-inch Lime Stabilized Subgrade	7,510	SY	\$2.10	\$15,771.00	\$4.00	\$30,040.00	\$3.10	\$23,281.00	\$3.00	\$22,530.00
86 .	221	Lime for Subgrade (8%) or (48 lbs per SY)	180	TON	\$158.70	\$28,566.00	\$150.00	\$27,000.00	\$190.00	\$34,200.00	\$150.00	\$27,000.00
87 .	360	8-inch Reinforced Concrete Pavement (3,500 psi), To Include Standard Paving Header (Load Transfer Device), Saw Cutting, and any Block Out for Inlets	6,842	SY	\$34.50	\$236,049.00	\$34.00	\$232,628.00	\$64.50	\$441,309.00	\$41.00	\$280,522.00
88 .	530	6-inch Concrete Curb	3,005	LF	\$2.10	\$6,310.50	\$3.00	\$9,015.00	\$3.60	\$10,818.00	\$3.00	\$9,015.00
89 .	530	6-inch Concrete Dowelled on Curb	125	LF	\$5.60	\$700.00	\$10.00	\$1,250.00	\$7.00	\$875.00	\$8.00	\$1,000.00
90 .	530	Channelized Mountable (3") Median Type I Curb and Gutter	32	LF	\$5.50	\$176.00	\$30.00	\$960.00	\$18.00	\$576.00	\$20.00	\$640.00
91 .	535	3-inch Concrete/ Rip Rap within the Raised Median at Driveway	15	SY	\$50.40	\$756.00	\$75.00	\$1,125.00	\$110.00	\$1,650.00	\$80.00	\$1,200.00
92 .	624, 646	Traffic Signs	4	EA	\$448.50	\$1,794.00	\$400.00	\$1,600.00	\$390.00	\$1,560.00	\$440.00	\$1,760.00
93 .	464	6" Irrigation Sleeves	272	LF	\$9.90	\$2,692.80	\$20.00	\$5,440.00	\$27.50	\$7,480.00	\$20.00	\$5,440.00
94 .	671	Traffic Control Handling (All Phases)	4	MO	\$2,765.50	\$11,062.00	\$25,000.00	\$100,000.00	\$2,300.00	\$9,200.00	\$27,400.00	\$109,600.00
95 .	465	Remove Existing Culverts, Including any Safety End Treatments	243	LF	\$8.70	\$2,114.10	\$15.00	\$3,645.00	\$25.00	\$6,075.00	\$15.00	\$3,645.00
96 .	500	Remove Existing Sign	5	EA	\$66.00	\$330.00	\$100.00	\$500.00	\$100.00	\$500.00	\$110.00	\$550.00
97 .	500	Relocate Existing Sign	2	EA	\$125.80	\$251.60	\$400.00	\$800.00	\$250.00	\$500.00	\$325.00	\$650.00
98 .	500	Relocate Existing Mailbox	1	EA	\$143.50	\$143.50	\$350.00	\$350.00	\$425.00	\$425.00	\$100.00	\$100.00
99 .	540	Remove & Dispose of Exist. Asphaltic Pavement (Surface and Base), Including any Dowelled on Curbs and All Driveways	3,603	SY	\$12.80	\$46,118.40	\$7.00	\$25,221.00	\$4.25	\$15,312.75	\$4.00	\$14,412.00
PAVING ITEMS SUBTOTAL						\$528,107.22		\$552,729.00		\$646,384.85		\$546,744.00

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

Item No.	Spec. No.	Description of Item	Quantity	Unit	Mar-Con Services Deer Park		Durwood Greene Stafford		Triple B Services Huffman		Conrad Construction Houston	
					Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total
I. ASPHALT TRANSITION RELATED ITEMS												
100 .	102	Clearing & Grubbing	0.9	AC	\$3,894.00	\$3,504.60	\$7,000.00	\$6,300.00	\$8,475.00	\$7,627.50	\$1,500.00	\$1,350.00
101 .	132	Embankment	55	CY	\$15.90	\$874.50	\$15.00	\$825.00	\$1.80	\$99.00	\$15.00	\$825.00
102 .	110	Roadway Excavation, To include Roadside Ditch	610	CY	\$8.30	\$5,063.00	\$10.00	\$6,100.00	\$11.00	\$6,710.00	\$12.00	\$7,320.00
103 .	460	54" RCP Storm Sewer	26	LF	\$205.30	\$5,337.80	\$255.00	\$6,630.00	\$225.00	\$5,850.00	\$265.00	\$6,890.00
104 .	460, 431	54" RCP Storm Sewer By Bore & Jack	32	LF	\$1,016.30	\$32,521.60	\$840.00	\$26,880.00	\$775.00	\$24,800.00	\$800.00	\$25,600.00
105 .	472	Modified Type "AD" Inlet	2	EA	\$3,316.70	\$6,633.40	\$4,200.00	\$8,400.00	\$6,500.00	\$13,000.00	\$4,000.00	\$8,000.00
106 .	360	4-inch Concrete Slope Paving for Modified Type "AD" Inlet as per Detail on Sheet 13 of 22	19	SY	\$94.70	\$1,799.30	\$120.00	\$2,280.00	\$240.00	\$4,560.00	\$75.00	\$1,425.00
107 .	530	6" Concrete Dowelled on Curb	150	LF	\$5.60	\$840.00	\$10.00	\$1,500.00	\$7.00	\$1,050.00	\$10.00	\$1,500.00
108 .	340	3-inch Type "D" Hot Mix-Hot Laid Asphalt Concrete Paving (HMAC)	193	TON	\$110.90	\$21,403.70	\$110.00	\$21,230.00	\$120.00	\$23,160.00	\$152.00	\$29,336.00
109 .	250	5-inch Hot Mix Asphaltic Concrete Base Course (Black Base)	321	TON	\$91.90	\$29,499.90	\$70.00	\$22,470.00	\$97.00	\$31,137.00	\$115.00	\$36,915.00
110 .	220	8-inch Lime Stabilized Subgrade	1,128	SY	\$3.20	\$3,609.60	\$5.00	\$5,640.00	\$3.10	\$3,496.80	\$3.00	\$3,384.00
111 .	221	Lime for Subgrade (8%) or (48 lbs per SY)	24	TON	\$159.90	\$3,837.60	\$165.00	\$3,960.00	\$190.00	\$4,560.00	\$150.00	\$3,600.00
112 .	540	Remove & Dispose of Exist. Asphaltic Pavement (Surface and Base), Including All Driveways	423	SY	\$5.80	\$2,453.40	\$12.00	\$5,076.00	\$4.25	\$1,797.75	\$4.00	\$1,692.00
ASPHALT TRANSITION RELATED ITEMS SUBTOTAL						\$117,378.40		\$117,291.00 *		\$127,848.05		\$127,837.00
J. TRAFFIC SIGNAL ITEMS FOR MEADOW RANCH PKWY AT W. BELLFORT - OPTION 2												
113 .	416 - 2032 (TxDOT)	DRILL SHAFT (TRF SIG POLE) (36 IN.)	32	LF	\$253.00	\$8,096.00	\$240.00	\$7,680.00	\$160.00	\$5,120.00	\$240.00	\$7,680.00
114 .	416 - 2034 (TxDOT)	DRILL SHAFT (TRF SIG POLE) (48 IN.)	44	LF	\$391.00	\$17,204.00	\$350.00	\$15,400.00	\$300.00	\$13,200.00	\$375.00	\$16,500.00
115 .	502 - 2001 (TxDOT)	BARRICADES, SIGNS AND TRAFFIC HANDLING	1	MO	\$1,725.00	\$1,725.00	\$5,000.00	\$5,000.00	\$1,620.00	\$1,620.00	\$2,330.00	\$2,330.00
116 .	531 - 2010 (TxDOT)	CURB RAMP (TY 7)	1	EA	\$924.80	\$924.80	\$1,500.00	\$1,500.00	\$1,925.00	\$1,925.00	\$1,300.00	\$1,300.00
117 .	531 - 2011 (TxDOT)	CURB RAMP (TY 8)	3	EA	\$924.80	\$2,774.40	\$1,500.00	\$4,500.00	\$1,925.00	\$5,775.00	\$1,300.00	\$3,900.00
118 .	618 - 2034 (TxDOT)	CONDUIT (PVC) (SCHD 80) (2")	125	LF	\$5.80	\$725.00	\$5.00	\$625.00	\$8.50	\$1,062.50	\$5.50	\$687.50
119 .	618 - 2038 (TxDOT)	CONDUIT (PVC) (SCHD 80) (3")	150	LF	\$8.10	\$1,215.00	\$7.00	\$1,050.00	\$11.50	\$1,725.00	\$7.70	\$1,155.00
120 .	619 - 2039 (TxDOT)	CONDUIT (PVC) (SCHD 80) (3") (BORE)	700	LF	\$11.50	\$8,050.00	\$10.00	\$7,000.00	\$12.00	\$8,400.00	\$11.00	\$7,700.00

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

Item No.	Spec. No.	Description of Item	Quantity	Unit	Mar-Con Services Deer Park		Durwood Greene Stafford		Triple B Services Huffman		Conrad Construction Houston	
					Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total
121 .	620 - 2009 (TxDOT)	ELEC CONDR (NO. 6) BARE	575	LF	\$1.00	\$575.00	\$1.00	\$575.00	\$0.90	\$517.50	\$1.00	\$575.00
122 .	621 - 2010 (TxDOT)	ELEC CONDR (NO. 6) INSULATED	80	LF	\$1.20	\$96.00	\$1.50	\$120.00	\$2.00	\$160.00	\$1.10	\$88.00
123 .	621 - 2002 (TxDOT)	TRAY CABLE (3 CONDR) (12 AWG)	400	LF	\$1.70	\$680.00	\$2.00	\$800.00	\$1.40	\$560.00	\$1.70	\$680.00
124 .	624 - 2014 (TxDOT)	GROUND BOX TY D (162922) W/APRON	5	EA	\$649.80	\$3,249.00	\$600.00	\$3,000.00	\$700.00	\$3,500.00	\$620.00	\$3,100.00
125 .	628 - 2100 (TxDOT)	ELEC SRV TY D 120 / 240 070 (NS) SS (E) SP (O)	1	EA	\$3,795.00	\$3,795.00	\$3,500.00	\$3,500.00	\$3,000.00	\$3,000.00	\$3,630.00	\$3,630.00
126 .	636 - 2001 (TxDOT)	ALUMINUM SIGN (TY A)	48	SF	\$19.60	\$940.80	\$22.00	\$1,056.00	\$17.00	\$816.00	\$19.00	\$912.00
127 .	644 - 2004 (TxDOT)	INS SM RD SN SUP & AM TY 10BWG (1) SA (T)	3	EA	\$448.50	\$1,345.50	\$400.00	\$1,200.00	\$390.00	\$1,170.00	\$430.00	\$1,290.00
128 .	666 - 2048 (TxDOT)	REFL PAV MRK TY I (W) 24" (SLD)	850	LF	\$5.80	\$4,930.00	\$7.00	\$5,950.00	\$5.00	\$4,250.00	\$5.50	\$4,675.00
129 .	666 - 2195 (TxDOT)	PAVEMENT SEALER 24"	850	LF	\$0.80	\$680.00	\$1.00	\$850.00	\$0.67	\$569.50	\$0.75	\$637.50
130 .	678 - 2006 (TxDOT)	PAV SURF PREP FOR MRK 24"	850	LF	\$0.30	\$255.00	\$0.50	\$425.00	\$0.28	\$238.00	\$0.30	\$255.00
131 .	680 - 2003 (TxDOT)	INSTALL HWY TRAF SIG (SYSTEM)	1	EA	\$29,325.00	\$29,325.00	\$27,000.00	\$27,000.00	\$36,000.00	\$36,000.00	\$28,000.00	\$28,000.00
132 .	682 - 2001 (TxDOT)	BACK PLATE (12 IN) (3 SEC)	8	EA	\$63.30	\$506.40	\$60.00	\$480.00	\$50.00	\$400.00	\$61.00	\$488.00
133 .	682 - 2002 (TxDOT)	BACK PLATE (12 IN) (4 SEC)	5	EA	\$74.80	\$374.00	\$70.00	\$350.00	\$70.00	\$350.00	\$72.00	\$360.00
134 .	682 - 2014 (TxDOT)	PED SIG SEC (12 IN) LED (2 INDICATIONS)	8	EA	\$414.00	\$3,312.00	\$400.00	\$3,200.00	\$400.00	\$3,200.00	\$400.00	\$3,200.00
135 .	682 - 2022 (TxDOT)	VEH SEC (12 IN) LED (GRN ARW)	5	EA	\$195.50	\$977.50	\$200.00	\$1,000.00	\$180.00	\$900.00	\$190.00	\$950.00
136 .	682 - 2023 (TxDOT)	VEH SEC (12 IN) LED (GRN)	8	EA	\$195.50	\$1,564.00	\$200.00	\$1,600.00	\$180.00	\$1,440.00	\$190.00	\$1,520.00
137 .	682 - 2024 (TxDOT)	VEH SEC (12 IN) LED (YEL ARW)	5	EA	\$184.00	\$920.00	\$200.00	\$1,000.00	\$175.00	\$875.00	\$180.00	\$900.00
138 .	682 - 2025 (TxDOT)	VEH SEC (12 IN) LED (YEL)	8	EA	\$195.50	\$1,564.00	\$200.00	\$1,600.00	\$180.00	\$1,440.00	\$190.00	\$1,520.00

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

Item No.	Spec. No.	Description of Item	Quantity	Unit	Mar-Con Services Deer Park		Durwood Greene Stafford		Triple B Services Huffman		Conrad Construction Houston	
					Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total
139	682 - 2026 (TxDOT)	VEH SEC (12 IN) LED (RED ARW)	10	EA	\$184.00	\$1,840.00	\$200.00	\$2,000.00	\$175.00	\$1,750.00	\$180.00	\$1,800.00
140	682 - 2027 (TxDOT)	VEH SEC (12 IN) LED (RED)	8	EA	\$184.00	\$1,472.00	\$200.00	\$1,600.00	\$175.00	\$1,400.00	\$180.00	\$1,440.00
141	682 - 2043 (TxDOT)	PED SIG SEC (12")(2 IND)(HOUSING ONLY)	8	EA	\$207.00	\$1,656.00	\$200.00	\$1,600.00	\$250.00	\$2,000.00	\$200.00	\$1,600.00
142	684 - 2007 (TxDOT)	TRAF SIG CBL (TY A) (12 AWG) (2 CONDR)	1,450	LF	\$1.00	\$1,450.00	\$1.00	\$1,450.00	\$0.80	\$1,160.00	\$1.00	\$1,450.00
143	684 - 2009 (TxDOT)	TRAF SIG CBL (TY A) (12 AWG) (4 CONDR)	1,450	LF	\$1.30	\$1,885.00	\$1.50	\$2,175.00	\$1.00	\$1,450.00	\$1.25	\$1,812.50
144	684 - 2012 (TxDOT)	TRAF SIG CBL (TY A) (12 AWG) (7 CONDR)	3,000	LF	\$2.00	\$6,000.00	\$2.00	\$6,000.00	\$1.70	\$5,100.00	\$1.90	\$5,700.00
145	686 - 2045 (TxDOT)	INS TRAF SIG PL AM (S) 1 ARM (44') LUM	2	EA	\$8,625.00	\$17,250.00	\$8,000.00	\$16,000.00	\$7,800.00	\$15,600.00	\$8,250.00	\$16,500.00
146	686 - 2055 (TxDOT)	INS TRF SIG PL AM (S) 1 ARM (55')	1	EA	\$11,730.00	\$11,730.00	\$11,000.00	\$11,000.00	\$11,400.00	\$11,400.00	\$11,220.00	\$11,220.00
147	686 - 2063 (TxDOT)	INS TRF SIG PL AM (S) 1 ARM (65')	1	EA	\$12,650.00	\$12,650.00	\$12,000.00	\$12,000.00	\$11,800.00	\$11,800.00	\$12,100.00	\$12,100.00
148	687 - 2001 (TxDOT)	PED POLE ASSEMBLY	2	EA	\$1,069.50	\$2,139.00	\$1,000.00	\$2,000.00	\$1,200.00	\$2,400.00	\$1,025.00	\$2,050.00
149	688 - 2001 (TxDOT)	PED DETECT (2 IN PUSH BTN)	8	EA	\$87.40	\$699.20	\$100.00	\$800.00	\$100.00	\$800.00	\$85.00	\$680.00
150	6006 - 2001 (TxDOT)	SPREAD SPECTRUM RADIO	1	EA	\$4,485.00	\$4,485.00	\$4,000.00	\$4,000.00	\$1,800.00	\$1,800.00	\$4,300.00	\$4,300.00
151	6006 - 2003 (TxDOT)	HELIAX CABLE	80	LF	\$3.20	\$256.00	\$3.00	\$240.00	\$2.00	\$160.00	\$3.10	\$248.00
152	6006 - 2005 (TxDOT)	ANTENNA (UNI-DIRECTIONAL)	1	EA	\$759.00	\$759.00	\$700.00	\$700.00	\$400.00	\$400.00	\$725.00	\$725.00
153	6266 - 2001 (TxDOT)	VIVDS PROCESSOR SYSTEM	1	EA	\$6,900.00	\$6,900.00	\$6,000.00	\$6,000.00	\$5,800.00	\$5,800.00	\$6,600.00	\$6,600.00
154	6266 - 2002 (TxDOT)	VIVDS CAMERA ASSEMBLY	4	EA	\$1,495.00	\$5,980.00	\$1,500.00	\$6,000.00	\$1,300.00	\$5,200.00	\$1,430.00	\$5,720.00
155	6266 - 2003 (TxDOT)	VIVDS SET - UP SYSTEM	1	EA	\$575.00	\$575.00	\$500.00	\$500.00	\$2,500.00	\$2,500.00	\$550.00	\$550.00
156	6266 - 2005 (TxDOT)	VIVDS COMMUNICATION CABLE (COAXIAL)	900	LF	\$1.80	\$1,620.00	\$2.00	\$1,800.00	\$2.00	\$1,800.00	\$1.75	\$1,575.00
157	8260 - 2001 (TxDOT)	LED COUNTDOWN PEDESTRIAN MODULE	8	EA	\$218.50	\$1,748.00	\$200.00	\$1,600.00	\$150.00	\$1,200.00	\$210.00	\$1,680.00
TRAFFIC SIGNAL ITEMS FOR MEADOW RANCH PKWY AT W. BELLFORT - OPTION 2 SUBTOTAL						\$176,897.60		\$173,926.00		\$171,933.50		\$171,783.50

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

Item No.	Spec. No.	Description of Item	Quantity	Unit	Mar-Con Services Deer Park		Durwood Greene Stafford		Triple B Services Huffman		Conrad Construction Houston	
					Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total
K. PAVEMENT MARKING RELATED ITEMS												
158 .	660	REFL PAV MRK TY I (W) 4" (SLD) (100MIL)	80	LF	\$0.60	\$48.00	\$0.70	\$56.00	\$0.51	\$40.80	\$1.00	\$80.00
159 .	660	REFL PAV MRK TY I (W) 4" (BRK) (100MIL)	400	LF	\$0.60	\$240.00	\$0.70	\$280.00	\$0.53	\$212.00	\$0.75	\$300.00
160 .	660	REFL PAV MRK TY I (W) 8" (SLD) (100MIL)	545	LF	\$1.30	\$708.50	\$1.50	\$817.50	\$1.10	\$599.50	\$1.25	\$681.25
161 .	660	REFL PAV MRK TY I (Y) 4" (SLD) (100MIL)	1,060	LF	\$0.60	\$636.00	\$0.70	\$742.00	\$0.53	\$561.80	\$1.00	\$1,060.00
162 .	660	REFL PAV MRK TY I (Y) 24" (SLD) (100MIL)	160	LF	\$6.20	\$992.00	\$7.00	\$1,120.00	\$5.40	\$864.00	\$6.00	\$960.00
163 .	663	REFL PAV MRKR TY II - C - R	30	EA	\$4.40	\$132.00	\$4.00	\$120.00	\$3.80	\$114.00	\$4.50	\$135.00
164 .	663	TRAFFIC BUTTON TY II - A - A	58	EA	\$4.40	\$255.20	\$4.00	\$232.00	\$3.80	\$220.40	\$4.50	\$261.00
165 .	666	REFL PAV MRK TY I (W) (ARROW) (100MIL)	6	EA	\$184.00	\$1,104.00	\$200.00	\$1,200.00	\$160.00	\$960.00	\$200.00	\$1,200.00
166 .	666	REFL PAV MRK TY I (W) (WORD) (100MIL)	6	EA	\$264.50	\$1,587.00	\$230.00	\$1,380.00	\$230.00	\$1,380.00	\$260.00	\$1,560.00
PAVMENT MARKING RELATED ITEMS SUBTOTAL						\$5,702.70	\$5,947.50	\$4,952.50	\$6,237.25			
L. EROSION & SEDIMENTATION CONTROL ITEMS												
167 .	713	Reinforced Filter Fabric Fence	3,600	LF	\$1.30	\$4,680.00	\$1.50	\$5,400.00	\$1.10	\$3,960.00	\$1.50	\$5,400.00
168 .	719	Filter Fence Barrier around Inlets (per Inlet)	10	EA	\$46.00	\$460.00	\$100.00	\$1,000.00	\$35.00	\$350.00	\$75.00	\$750.00
169 .	741	Gravel Bag Barrier around Inlets	100	LF	\$4.30	\$430.00	\$10.00	\$1,000.00	\$4.00	\$400.00	\$5.00	\$500.00
170 .	165	Turf Establishment by Hydromulch Seeding	1.95	AC	\$1,112.10	\$2,168.60	\$1,500.00	\$2,925.00	\$1,495.00	\$2,915.25	\$1,650.00	\$3,217.50
171 .	751	SWPPP Inspection and Maintenance	4	MO	\$1,000.00	\$4,000.00	\$2,000.00	\$8,000.00	\$1,000.00	\$4,000.00	\$1,000.00	\$4,000.00
EROSION & SEDIMENTATION CONTROL ITEMS SUBTOTAL						\$11,738.60	\$18,325.00	\$11,625.25	\$13,867.50			
M. SUPPLEMENTAL ITEMS												
172 .	436	Well Point Dewatering System	500	LF	\$20.00	\$10,000.00	\$20.00	\$10,000.00	\$20.00	\$10,000.00	\$20.00	\$10,000.00
173 .	402	Extra Bank Sand Backfill	50	CY	\$10.00	\$500.00	\$10.00	\$500.00	\$10.00	\$500.00	\$10.00	\$500.00
174 .	433, SP 433	Cement Stabilized Sand (Based on 8-inch Thickness)	100	SY	\$12.50	\$1,250.00	\$12.50	\$1,250.00	\$12.50	\$1,250.00	\$15.00	\$1,500.00
175 .		Additional Cost for Bedding for Unsatisfactory Soil Conditions per City of Houston Drawing No. 2317-02	100	LF	\$10.00	\$1,000.00	\$10.00	\$1,000.00	\$10.00	\$1,000.00	\$10.00	\$1,000.00
176 .	360	Rapid Setting High Early Strength Concrete - 8-inch in Depth (3,500 psi), To Include Standard Paving Header (Load Transfer Device), and Saw Cutting	140	CY	\$262.70	\$36,778.00	\$160.00	\$22,400.00	\$108.00	\$15,120.00	\$250.00	\$35,000.00
177 .	221	Additional Lime	100	TON	\$159.90	\$15,990.00	\$165.00	\$16,500.00	\$190.00	\$19,000.00	\$150.00	\$15,000.00
178 .	624, 646	Traffic Signs	3	EA	\$448.50	\$1,345.50	\$300.00	\$900.00	\$390.00	\$1,170.00	\$440.00	\$1,320.00
178a .		Bracing/ Extra Trenching Effort for Construction of the Proposed 54" RCP, if the 16" Surface Waterline (NFBWA) was already Constructed	1	LS	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00	\$12,000.00	\$12,000.00
178b .		Bracing Existing Power Pole and Down Guy	7	EA	\$1,725.00	\$12,075.00	\$500.00	\$3,500.00	\$500.00	\$3,500.00	\$500.00	\$3,500.00
SUPPLEMENTAL ITEMS SUBTOTAL						\$80,938.50	\$58,050.00	\$53,540.00	\$79,820.00			
TOTAL AMOUNT OF BASE BID					\$1,404,134.56	\$1,496,891.50	\$1,576,077.85	\$1,600,367.00				

* Error in bid tabulation

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

Item No.	Spec. No.	Description of Item	Quantity	Unit	Mar-Con Services Deer Park		Durwood Greene Stafford		Triple B Services Huffman		Conrad Construction Houston	
					Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total
ALTERNATE BID ITEMS												
N.TRAFFIC SIGNAL ITEMS FOR MEADOW RANCH PKWY AT W. BELLFORT - OPTION 1												
179 .	416 - 2032 (TxDOT)	DRILL SHAFT (TRF SIG POLE) (36 IN.)	32	LF	\$253.00	\$8,096.00	\$240.00	\$7,680.00	\$160.00	\$5,120.00	\$245.00	\$7,840.00
180 .	416 - 2034 (TxDOT)	DRILL SHAFT (TRF SIG POLE) (48 IN.)	44	LF	\$391.00	\$17,204.00	\$350.00	\$15,400.00	\$300.00	\$13,200.00	\$375.00	\$16,500.00
181 .	416 - 2034 (TxDOT)	DRILL SHAFT (TRF SIG POLE) (48 IN.)	44	LF	\$391.00	\$17,204.00	\$350.00	\$15,400.00	\$300.00	\$13,200.00	\$375.00	\$16,500.00
182 .	502 - 2001 (TxDOT)	BARRICADES, SIGNS AND TRAFFIC HANDLING	1	MO	\$1,725.00	\$1,725.00	\$5,000.00	\$5,000.00	\$1,620.00	\$1,620.00	\$2,400.00	\$2,400.00
183 .	531 - 2005 (TxDOT)	CURB RAMP (TY 1)	2	EA	\$924.80	\$1,849.60	\$1,500.00	\$3,000.00	\$1,950.00	\$3,900.00	\$1,300.00	\$2,600.00
184 .	531 - 2011 (TxDOT)	CURB RAMP (TY 8)	2	EA	\$924.80	\$1,849.60	\$1,500.00	\$3,000.00	\$1,950.00	\$3,900.00	\$1,300.00	\$2,600.00
185 .	618 - 2034 (TxDOT)	CONDUIT (PVC) (SCHD 80) (2")	125	LF	\$5.80	\$725.00	\$5.00	\$625.00	\$8.50	\$1,062.50	\$5.50	\$687.50
186 .	618 - 2038 (TxDOT)	CONDUIT (PVC) (SCHD 80) (3")	150	LF	\$8.10	\$1,215.00	\$7.00	\$1,050.00	\$11.50	\$1,725.00	\$7.70	\$1,155.00
187 .	618 - 2039 (TxDOT)	CONDUIT (PVC) (SCHD 80) (3") (BORE)	700	LF	\$11.50	\$8,050.00	\$10.00	\$7,000.00	\$12.00	\$8,400.00	\$11.00	\$7,700.00
188 .	620 - 2009 (TxDOT)	ELEC CONDR (NO. 6) BARE	575	LF	\$1.00	\$575.00	\$1.00	\$575.00	\$0.90	\$517.50	\$1.00	\$575.00
189 .	620 - 2010 (TxDOT)	ELEC CONDR (NO. 6) INSULATED	80	LF	\$1.20	\$96.00	\$1.50	\$120.00	\$2.00	\$160.00	\$1.10	\$88.00
190 .	621 - 2002 (TxDOT)	TRAY CABLE (3 CONDR) (12 AWG)	400	LF	\$1.70	\$680.00	\$2.00	\$800.00	\$1.40	\$560.00	\$1.70	\$680.00
191 .	624 - 2014 (TxDOT)	GROUND BOX TY D (162922) W/APRON	5	EA	\$649.80	\$3,249.00	\$600.00	\$3,000.00	\$700.00	\$3,500.00	\$625.00	\$3,125.00
192 .	628 - 2100 (TxDOT)	ELEC SRV TY D 120 / 240 070 (NS) SS (E) SP (O)	1	EA	\$3,795.00	\$3,795.00	\$3,500.00	\$3,500.00	\$300.00	\$300.00	\$6,360.00	\$6,360.00
193 .	636 - 2001 (TxDOT)	ALUMINUM SIGN (TY A)	48	SF	\$19.60	\$940.80	\$22.00	\$1,056.00	\$17.00	\$816.00	\$19.00	\$912.00
194 .	644 - 2004 (TxDOT)	INS SM RD SUP & AM TY 10BWG (1) SA (T)	3	EA	\$448.50	\$1,345.50	\$400.00	\$1,200.00	\$390.00	\$1,170.00	\$430.00	\$1,290.00
195 .	666 - 2048 (TxDOT)	REFL PAV MRK TY I (W) 24" (SLD)	600	LF	\$5.80	\$3,480.00	\$7.00	\$4,200.00	\$5.00	\$3,000.00	\$5.50	\$3,300.00
196 .	666 - 2195 (TxDOT)	PAVEMENT SEALER 24"	600	LF	\$0.80	\$480.00	\$1.00	\$600.00	\$0.67	\$402.00	\$0.75	\$450.00

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

Item No.	Spec. No.	Description of Item	Quantity	Unit	Mar-Con Services Deer Park		Durwood Greene Stafford		Triple B Services Huffman		Conrad Construction Houston	
					Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total
197 .	678 - 2006 (TxDOT)	PAV SURF PREP FOR MRK 24"	600	LF	\$0.30	\$180.00	\$0.50	\$300.00	\$0.28	\$168.00	\$0.30	\$180.00
198 .	680 - 2003 (TxDOT)	INSTALL HWY TRAF SIG (SYSTEM)	1	EA	\$29,325.00	\$29,325.00	\$27,000.00	\$27,000.00	\$36,000.00	\$36,000.00	\$28,000.00	\$28,000.00
199 .	682 - 2001 (TxDOT)	BACK PLATE (12 IN) (3 SEC)	8	EA	\$63.30	\$506.40	\$60.00	\$480.00	\$50.00	\$400.00	\$61.00	\$488.00
200 .	682 - 2002 (TxDOT)	BACK PLATE (12 IN) (4 SEC)	5	EA	\$74.80	\$374.00	\$70.00	\$350.00	\$70.00	\$350.00	\$72.00	\$360.00
201 .	682 - 2014 (TxDOT)	PED SIG SEC (12 IN) LED (2 INDICATIONS)	8	EA	\$414.00	\$3,312.00	\$400.00	\$3,200.00	\$400.00	\$3,200.00	\$400.00	\$3,200.00
202 .	682 - 2022 (TxDOT)	VEH SEC (12 IN) LED (GRN ARW)	5	EA	\$195.50	\$977.50	\$200.00	\$1,000.00	\$180.00	\$900.00	\$190.00	\$950.00
203 .	682 - 2023 (TxDOT)	VEH SEC (12 IN) LED (GRN)	8	EA	\$195.50	\$1,564.00	\$200.00	\$1,600.00	\$180.00	\$1,440.00	\$190.00	\$1,520.00
204 .	682 - 2024 (TxDOT)	VEH SEC (12 IN) LED (YEL ARW)	5	EA	\$184.00	\$920.00	\$200.00	\$1,000.00	\$175.00	\$875.00	\$180.00	\$900.00
205 .	682 - 2025 (TxDOT)	VEH SEC (12 IN) LED (YEL)	8	EA	\$195.50	\$1,564.00	\$200.00	\$1,600.00	\$180.00	\$1,440.00	\$190.00	\$1,520.00
206 .	682 - 2026 (TxDOT)	VEH SEC (12 IN) LED (RED ARW)	10	EA	\$184.00	\$1,840.00	\$200.00	\$2,000.00	\$175.00	\$1,750.00	\$180.00	\$1,800.00
207 .	682 - 2027 (TxDOT)	VEH SEC (12 IN) LED (RED)	8	EA	\$184.00	\$1,472.00	\$200.00	\$1,600.00	\$175.00	\$1,400.00	\$180.00	\$1,440.00
208 .	682 - 2043 (TxDOT)	PED SIG SEC (12")(2 IND)(HOUSING ONLY)	8	EA	\$207.00	\$1,656.00	\$200.00	\$1,600.00	\$250.00	\$2,000.00	\$200.00	\$1,600.00
209 .	684 - 2007 (TxDOT)	TRAF SIG CBL (TY A) (12 AWG) (2 CONDR)	1,200	LF	\$1.00	\$1,200.00	\$1.00	\$1,200.00	\$0.80	\$960.00	\$1.00	\$1,200.00
210 .	684 - 2009 (TxDOT)	TRAF SIG CBL (TY A) (12 AWG) (4 CONDR)	1,200	LF	\$1.30	\$1,560.00	\$1.50	\$1,800.00	\$1.00	\$1,200.00	\$1.25	\$1,500.00
211 .	684 - 2012 (TxDOT)	TRAF SIG CBL (TY A) (12 AWG) (7 CONDR)	3,000	LF	\$2.00	\$6,000.00	\$2.00	\$6,000.00	\$1.70	\$5,100.00	\$1.90	\$5,700.00
212 .	686 - 2045 (TxDOT)	INS TRAF SIG PL AM (S) 1 ARM (44') LUM	2	EA	\$8,625.00	\$17,250.00	\$8,000.00	\$16,000.00	\$7,800.00	\$15,600.00	\$8,250.00	\$16,500.00
213 .	686 - 2055 (TxDOT)	INS TRF SIG PL AM (S) 1 ARM (55')	1	EA	\$11,730.00	\$11,730.00	\$11,000.00	\$11,000.00	\$11,400.00	\$11,400.00	\$11,220.00	\$11,220.00
214 .	686 - 2063 (TxDOT)	INS TRF SIG PL AM (S) 1 ARM (65')	1	EA	\$12,650.00	\$12,650.00	\$12,000.00	\$12,000.00	\$11,800.00	\$11,800.00	\$12,100.00	\$12,100.00

Bid Tabulation for Construction of Drainage and Paving Improvements
for West Bellfort Road Widening for Fort Bend County
Bids Received June 21, 2012

BID 12-055

Item No.	Spec. No.	Description of Item	Quantity	Unit	Mar-Con Services Deer Park		Durwood Greene Stafford		Triple B Services Huffman		Conrad Construction Houston	
					Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total
215 .	687 - 2001 (TxDOT)	PED POLE ASSEMBLY	2	EA	\$1,069.50	\$2,139.00	\$1,000.00	\$2,000.00	\$1,200.00	\$2,400.00	\$1,025.00	\$2,050.00
216 .	688 - 2001 (TxDOT)	PED DETECT (2 IN PUSH BTN)	8	EA	\$87.40	\$699.20	\$100.00	\$800.00	\$100.00	\$800.00	\$84.00	\$672.00
217 .	6006 - 2001 (TxDOT)	SPREAD SPECTRUM RADIO	1	EA	\$4,485.00	\$4,485.00	\$4,000.00	\$4,000.00	\$1,800.00	\$1,800.00	\$4,300.00	\$4,300.00
218 .	6006 - 2003 (TxDOT)	HELIAX CABLE	80	LF	\$3.20	\$256.00	\$3.00	\$240.00	\$2.00	\$160.00	\$3.10	\$248.00
219 .	6006 - 2005 (TxDOT)	ANTENNA (UNI-DIRECTIONAL)	1	EA	\$759.00	\$759.00	\$700.00	\$700.00	\$400.00	\$400.00	\$725.00	\$725.00
220 .	6266 - 2001 (TxDOT)	VIVDS PROCESSOR SYSTEM	1	EA	\$6,900.00	\$6,900.00	\$6,000.00	\$6,000.00	\$5,800.00	\$5,800.00	\$6,600.00	\$6,600.00
221 .	6266 - 2002 (TxDOT)	VIVDS CAMERA ASSEMBLY	4	EA	\$1,495.00	\$5,980.00	\$1,500.00	\$6,000.00	\$1,300.00	\$5,200.00	\$1,430.00	\$5,720.00
222 .	6266 - 2003 (TxDOT)	VIVDS SET - UP SYSTEM	1	EA	\$575.00	\$575.00	\$500.00	\$500.00	\$2,500.00	\$2,500.00	\$550.00	\$550.00
223 .	6266 - 2005 (TxDOT)	VIVDS COMMUNICATION CABLE (COAXIAL)	900	LF	\$1.80	\$1,620.00	\$2.00	\$1,800.00	\$2.00	\$1,800.00	\$1.75	\$1,575.00
224 .	8260 - 2001 (TxDOT)	LED COUNTDOWN PEDESTRIAN MODULE	8	EA	\$1,138.50	\$9,108.00	\$200.00	\$1,600.00	\$150.00	\$1,200.00	\$210.00	\$1,680.00
TRAFFIC SIGNAL ITEMS FOR MEADOW RANCH PKWY AT W BELLFORT - OPTION 1 SUBTOTAL						\$199,161.60		\$186,576.00		\$180,596.00		\$189,060.50
TOTAL AMOUNT OF ALTERNATE BID ITEMS						\$199,161.60		\$186,576.00		\$180,596.00		\$189,060.50