



February 18, 2015

Mr. Paul Smith
 Ft. Bend County EMS
 Email: smithpau@co.fort-bend.tx.us

Quote #9611C

Mr. Smith,

Per your request we are quoting remounting and refurbishing your Frazer Type I 12' Generator Powered Module, E-1237/X-505, onto your 2015 Dodge Ram 3500 6.7L diesel chassis, with a Granning air suspension system. For your convenience all pricing has been itemized below.

Heat shielding for diesel chassis	\$ 1,500.00
Granning air suspension system	\$ 7,000.00
Remount of Module (see Incl. Items below)	\$ 15,000.00
Chassis Exterior Upgrades	\$ 50.00
Chassis Interior Upgrades	\$ 500.00
Module Exterior Upgrades	\$ 18,525.00
Module Interior Upgrades	\$ 14,325.00
Buy Board Fee #400-12	\$ 800.00
Total	\$ 57,700.00

Items included in above total:

Chassis Exterior Upgrades:

1. Items included in remount fee:
 - a) Credit for not installing Ranch Hand grille guard \$ -250.00
 - b) (2) Whelen M4 grille lights w/ clear lenses \$ incl.
Layout: red, amber
 - c) (2) Whelen M4 intersects w/ clear lenses mounted on chassis fenders \$ 200.00
Layout: red, red
 - d) Credit for not installing (2) Federal Signal AS124 speakers \$ -250.00
 - e) Frazer aluminum rear window pass through plate \$ incl.
 - f) (2) Mega fuses with new wiring \$ incl.
 - h) New mounting rubber \$ incl.
 - i) Make old chassis road ready, if applicable \$ incl.
 1. Install rear mud flaps on chassis \$ incl.
 2. Install rear BTT lights \$ incl.
 3. Remove and reinstall compressor on chassis, if applicable \$ incl.
2. Furnish & install (2) through the bumper Cast aluminum speakers \$ 750.00
3. Credit issued for not striping chassis \$ -400.00

Total \$ 50.00

Chassis Interior Upgrades

4 . Items included in remount fee:		
a) Furnish & install pinned powder coated aluminum six position console	\$	incl.
b) Credit for not installing new Whelen 295SLSA1 siren	\$	-175.00
5 . Front of Console –	\$	incl.
6 . Slot 1 – Single Blank Plate		
7 . Slot 2 – Single Blank Plate		
8 . Slot 3 – Radio Plate		
9 . Slot 4/5 – Double Switch Panel		
10 . Slot 6 – Siren, with low pressure indicator		
<i>Layout: Primary, Secondary, Siren 1, Siren 2, Blank, Blank, Blank</i>		
<i>blank, Side Scene, Side Scene, Start/Stop</i>		
11 . Rear of Console –		
12 . Furnish & install Whelen TIR3 exhaust warning LED, on forward corner of drivers side of console	\$	200.00
12 . Remove speaker from floor in front of console, and reinstall on rear wall of chassis cab	\$	50.00
13 . Remove and reinstall power supply, remote mount 800mHz radio head, and flashlight chargers	\$	225.00
14 . Furnish & install arm rests on console	\$	200.00
15 . Terminate existing shore power ignition kill switch to new chassis	\$	incl.
16 . Do not install Tap 2	\$	N/C
17 . Terminate siren signal wire from siren in electrical compartment to siren #1 switch	\$	incl.
18 . Ensure Tomar emitter on front wall is activate with Siren #2 switch	\$	incl.
Total \$	\$	500.00

Module Exterior Upgrades

19 . Items included in remount fee:		
a) Install new ignition & fail safe solenoids on electrical shelf	\$	incl.
b) Full electrical check	\$	incl.
c) Generator system check and inspect all generator cabling, replace as needed	\$	incl.
d) Terminate existing Onan buzzer kill switch to new chassis (if available)	\$	incl.
e) Rewire tail lights	\$	incl.
f) New passthrough rubber boot	\$	incl.
g) Replace all door compartment bumpers	\$	incl.
h) Replace weather stripping	\$	incl.
i) Add new insulation to side & rear entry doors, if applicable	\$	incl.
j) Replace entry door windows with double pane windows, if applicable	\$	incl.
k) New ribbed rubber in applicable compartments	\$	incl.
l) Replace all halogen compartment lights	\$	incl.
m) Time save exterior compartment panels, if applicable	\$	incl.
20 . Strip, prime, and repaint 12' module Frazer white		
Note – Items sub-listed are included with paint unless stated other wise	\$	6,500.00
a) Furnish & install painted corner caps on module	\$	incl.
b) Furnish & install painted module trims	\$	incl.
c) Replace compartment and entry door latches	\$	N/C
d) Replace marker lights	\$	incl.

e) Remove & reinstall rear bumper	\$	incl.
f) Remove & reinstall treadbrite panels	\$	incl.
g) Remove & reinstall all listed emergency lighting below:	\$	incl.
(5) Whelen 600 series front wall lights	\$	incl.
<i>Front wall layout: red, blue, red, blue, red</i>		
(1) Whelen 600 series rear wall light	\$	incl.
<i>Rear wall layout: amber</i>		
(2) 508 series rear load lights	\$	incl.
(2) Whelen 600 series rear red BTT	\$	incl.
(2) 500 watt Kwik Raze side scene light	\$	incl.
(1) 2060 Tomar Emitter on front wall		
21 . Furnish & install (8) Whelen M9 series red corner box lights with converter flange (ship existing loose)	\$	2,800.00
22 . Repair elongated dent damage on passenger side of module	\$	1,800.00
23 . Remove 120v receptacle on front passenger side wall and add plate, discard	\$	N/C
24 . Replace red shore power indicator LED (ID#13498), retain existing location (check clearance with new shore power plug)	\$	50.00
25 . Wire battery charger off shore power only	\$	N/C
26 . Remove and replace existing shore power plug with new twist lock style with pigtail adapter shipped loose	\$	225.00
27 . Replace long lower storage cables with gas shock	\$	100.00
28 . Repair welds on rear backboard compartment and trim compartment insert	\$	N/C
29 . Remove ramp at rear entry doors (ship loose)	\$	N/C
30 . Replace entire rear bumper (ship existing loose)	\$	850.00
31 . Replace treadbrite at front corners, wheel wells, and rear corners	\$	850.00
32 . Replace side entry door hold open spring with new, discard existing	\$	N/C
33 . Replace damaged forward box light bezel on passengers side	\$	50.00
34 . Furnish & install new rear entry door grabbers (discard existing)	\$	50.00
35 . Furnish & install cast LED license plate light (discard existing)	\$	50.00
36 . Furnish & install new Onan 5.5kW generator with non permeable hoses, emissions canister kit and add new (Dodge 20) gal fuel tank and fuel pump, reuse existing exterior door		
Note – Please remove your Onan generator prior to remount delivery at Frazer.	\$	5,200.00
	Total \$	18,525.00

Module Interior Upgrades:

37 . Items included in remount fee:	\$	incl.
a) Replace all non-skid material on threshold(s) with 3M non-skid material	\$	incl.
b) Complete detail of module interior	\$	incl.
Clean & wipe down lasco walls	\$	incl.
Clean & wipe down floor of module	\$	incl.
Clean & wipe down exterior & interior of cabinets	\$	incl.
Clean & wipe down compartments and shelves	\$	incl.
38 . Replace existing O2 box with new powder coated aluminum box with new polycarbonate access door (discard existing)	\$	400.00
39 . Add stainless steel cladding over CPR seat base and replace seat lid with aluminum lid	\$	300.00
40 . Replace lower drivers side wall with stainless steel	\$	750.00
41 . New squad bench stainless steel wrapper with hole for trash can in top	\$	650.00

42 . Furnish & install new Wise cobalt cushions with magnetic strips for new style squad bench	\$ 1,500.00
43 . Add protective powder coated plating between new seat backs and squad bench stainless on lasco if replacing seats with current style	\$ 100.00
44 . Furnish & install triple glove box holder on end of squad bench; remove and reinstall custom end rail onto this holder in standard end rail location	\$ 300.00
45 . New wise cobalt corner trim throughout interior of module	\$ 300.00
46 . Replace Captains chair with new cobalt Wise Captains chair with built in child safety seat, discard existing	\$ 1,350.00
47 . Replace interior fluorescent ceiling lights with (8) Grote LED's, retain existing custom switch setup at side entry well, and at rear doors for single light activation	\$ 3,000.00
48 . Remove and reinstall trashcan bracket on side entry door	\$ N/C
49 . Remove "L" shelf in front I/O and replace with standard shelf in standard location	\$ 175.00
50 . Replace air conditioner w/ new Dometic self-contained A/C unit including breathe easy plenum with germicidal UV light protection compartment and relocate thermostat to action wall	
Note – Please remove A/C prior to delivery of remount to Frazer.	
This includes making necessary modifications not limited to:	
Interior – walls, register, and vents	
Exterior – relocation of (2) emergency rear lights with painted A/C retrofit plating, installation of a new style A/C vent, furnish new vented style A/C door (if needed)	
	\$ 5,500.00
Total	\$ 14,325.00

Terms and Conditions

- 1 . This quote is valid for 90 days.
- 2 . All pricing is F.O.B. Houston.
- 3 . Please note, payment for the entire purchase is due upon receipt and acceptance of completed unit.
- 4 . Please make your purchase order out to Frazer, Ltd. (P.O.Box 5000, Houston, TX 77402). Please email a copy of your purchase order and this quote to Adam Fischer at sales@frazerbilt.com.
- 5 . To minimize delays, customer provided items should be present prior to unit production start.
- 6 . Please remove your A/C prior to remount delivery at Frazer.
- 7 . Please remove your Onan generator prior to remount delivery at Frazer.
- 8 . Fair condition of module is assumed when quoting paint. Large or excessive dents, deep or excessive scratches and unforeseen body work will require a revision to the quoted paint price.

Thank you for the opportunity to quote this job. If you have any questions please call me at 888-372-9371.

Best Regards,



Laura Richardson
Frazer, Ltd.

LGR:CH