



April 7, 2015

Mr. Paul Smith
 Ft. Bend County EMS
 Email: smithpau@co.fort-bend.tx.us

Quote #9748B

Mr. Smith,

Per your request we are quoting remounting and refurbishing your Frazer Type I 12' Generator Powered Module, E-1887, onto your 2015 Dodge Ram 3500 6.7L diesel chassis, with a Granning air suspension system. For your convenience all pricing has been itemized below.

| | |
|-------------------------------------------|---------------------|
| Heat shielding for diesel chassis | \$ 1,500.00 |
| Granning air suspension system | \$ 7,000.00 |
| Remount of Module (see Incl. Items below) | \$ 15,000.00 |
| Chassis Exterior Upgrades | \$ 50.00 |
| Chassis Interior Upgrades | \$ 250.00 |
| Module Exterior Upgrades | \$ 16,575.00 |
| Module Interior Upgrades | \$ 10,400.00 |
| Buy Board Fee #400-12 | \$ 800.00 |
| Total | \$ 51,575.00 |

Items included in above total:

Chassis Exterior Upgrades:

1. Items included in remount fee:
 - a) Credit for not installing Ranch Hand grille guard \$ -250.00
 - b) (2) Whelen M4 grille lights w/ clear lenses \$ incl.
Layout: red, amber
 - c) (2) Whelen M4 intersects w/ clear lenses mounted on chassis fenders \$ 200.00
Layout: red, red
 - d) Credit for not installing (2) Federal Signal AS124 speakers \$ -250.00
 - e) Frazer aluminum rear window pass through plate \$ incl.
 - f) (2) Mega fuses with new wiring \$ incl.
 - h) New mounting rubber \$ incl.
 - i) Make old chassis road ready, if applicable \$ incl.
 1. Install rear mud flaps on chassis \$ incl.
 2. Install rear BTT lights \$ incl.
 3. Remove and reinstall compressor on chassis, if applicable \$ incl.

| | | |
|--------------------------------------------------------------------|-----------|--------------|
| 2. Furnish & install (2) through the bumper Cast aluminum speakers | \$ | 750.00 |
| 3. Credit issued for not striping chassis | \$ | -400.00 |
| Total | \$ | 50.00 |

Chassis Interior Upgrades

| | | |
|----------------------------------------------------------------------------------------------------------------------|-----------|---------------|
| 4. Items included in remount fee: | | |
| a) Furnish & install pinned powder coated aluminum four position console | \$ | incl. |
| b) Credit for not installing new Whelen 295SLSA1 siren | \$ | -175.00 |
| 5. Slot 1 – MDT plate with fuel gauge (ID#23065) | | |
| 6. Slot 2 – Single Switch Plate | | |
| <i>Layout: Primary, Secondary, Siren 1, Siren 2, Side Scene (left), Side Scene (right), Start/Stop, Blank, Blank</i> | | |
| 7. Slot 3 – Siren #2 | | |
| 8. Slot 4 – Radio | | |
| 9. Bolt console to chassis using nuts and bolts to prevent loosening and rattling | \$ | N/C |
| 10. Remove and reinstall remote radio head in slot 3 of console, and speaker on rear wall of chassis cab | \$ | 225.00 |
| 11. Furnish & install arm rests on console | \$ | 200.00 |
| 12. DO NOT reconnect shore power ignition kill switch | \$ | N/C |
| 13. Do not install Tap 2 | \$ | N/C |
| 14. Terminate siren signal wire from siren in electrical compartment to siren #1 switch | \$ | incl. |
| 15. Coil back up camera cable behind drivers seat | \$ | incl. |
| 16. Ensure Tomar emitter on front wall is activated with Siren #2 switch | \$ | incl. |
| Total | \$ | 250.00 |

Module Exterior Upgrades

| | | |
|--------------------------------------------------------------------------------|----|----------|
| 17. Items included in remount fee: | | |
| a) Install new ignition & fail safe solenoids on electrical shelf | \$ | incl. |
| b) Full electrical check | \$ | incl. |
| c) Generator system check and inspect all generator cabling, replace as needed | \$ | incl. |
| d) Terminate existing Onan buzzer kill switch to new chassis (if available) | \$ | incl. |
| e) Rewire tail lights | \$ | incl. |
| f) New passthrough rubber boot | \$ | incl. |
| g) Replace all door compartment bumpers | \$ | incl. |
| h) Replace weather stripping | \$ | incl. |
| i) Add new insulation to side & rear entry doors, if applicable | \$ | incl. |
| j) Replace entry door windows with double pane windows, if applicable | \$ | incl. |
| k) New ribbed rubber in applicable compartments | \$ | incl. |
| l) Replace all halogen compartment lights | \$ | incl. |
| m) Time save exterior compartment panels, if applicable | \$ | incl. |
| 18. Strip, prime, and repaint 12' module Frazer white | | |
| Note – Items sub-listed are included with paint unless stated other wise | \$ | 6,500.00 |
| a) Furnish & install painted corner caps on module | \$ | incl. |
| b) Replace compartment and entry door latches | \$ | N/C |
| c) Replace marker lights | \$ | incl. |

| | | |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|------------------|
| d) Remove & reinstall rear bumper | \$ | incl. |
| e) Remove & reinstall treadbrite panels | \$ | incl. |
| f) Remove & reinstall all listed emergency lighting below: | \$ | incl. |
| (5) Whelen 600 series front wall lights | \$ | incl. |
| <i>Front wall layout: red, blue, red, blue, red</i> | | |
| (1) Whelen 600 series rear wall light | \$ | incl. |
| <i>Rear wall layout: amber</i> | | |
| (2) 508 series rear load lights | \$ | incl. |
| (2) Whelen 600 series rear red BTT | \$ | incl. |
| (2) 500 watt Kwik Raze side scene light | \$ | incl. |
| (1) 2060 Tomar Emitter on front wall | | |
| 19 . Replace front, drivers side corner trim with new (with paint) | \$ | incl. |
| 20 . Furnish & install (8) Whelen M9 series red corner box lights with converter flange (ship existing loose) | \$ | 2,800.00 |
| 21 . Remove 120v receptacle on front passenger side wall and add plate, discard | \$ | N/C |
| 22 . Replace red shore power indicator LED (ID#13498), retain existing location (check clearance with new shore power plug) | \$ | 50.00 |
| 23 . Wire battery charger off shore power only | \$ | N/C |
| 24 . Remove and replace existing shore power plug with new twist lock style with pigtail adapter shipped loose | \$ | 225.00 |
| 25 . Repair welds on rear backboard compartment and trim compartment insert | \$ | N/C |
| 26 . Replace entire rear bumper (ship existing loose) | \$ | 850.00 |
| 27 . Remove and reinstall lower B/T/T signals | \$ | incl. |
| 28 . Replace treadbrite at front corners, wheel wells, and rear corners | \$ | 850.00 |
| 29 . Furnish & install new rear entry door grabbers (discard existing) | \$ | 50.00 |
| 30 . Furnish & install cast LED license plate light (discard existing) | \$ | 50.00 |
| 31 . Furnish & install new Onan 5.5kW generator with non permeable hoses, emissions canister kit and add new (Dodge 20) gal fuel tank and fuel pump, reuse existing exterior door | | |
| Note – Please remove your Onan generator prior to remount delivery at Frazer. | \$ | 5,200.00 |
| | Total \$ | 16,575.00 |

Module Interior Upgrades:

| | | |
|-------------------------------------------------------------------------------------------------------------------------------------------|----|----------|
| 32 . Items included in remount fee: | \$ | incl. |
| a) Replace all non-skid material on threshold(s) with 3M non-skid material | \$ | incl. |
| b) Complete detail of module interior | \$ | incl. |
| Clean & wipe down lasco walls | \$ | incl. |
| Clean & wipe down floor of module | \$ | incl. |
| Clean & wipe down exterior & interior of cabinets | \$ | incl. |
| Clean & wipe down compartments and shelves | \$ | incl. |
| 33 . Move cot hook to center of rear entry doorway, 4" from back of threshold | \$ | N/C |
| 34 . Furnish & install new Wise cobalt cushions with magnetic strips for new style squad bench and CPR seat | \$ | 1,500.00 |
| 35 . Add protective powder coated plating between new seat backs and squad bench stainless on lasco if replacing seats with current style | \$ | 100.00 |
| 36 . New wise cobalt corner trim throughout interior of module, discard existing | \$ | 300.00 |

| | | |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|------------------|
| 37 . Replace interior fluorescent ceiling lights with (8) Grote LED's, retain existing custom switch setup at side entry well, and at rear doors for single light activation | \$ | 3,000.00 |
| 38 . Remove and reinstall trashcan bracket on side entry door | \$ | N/C |
| 39 . Remove and discard hand sanitizer dispenser on side entry door | \$ | N/C |
| 40 . Replace air conditioner w/ new Dometic self-contained A/C unit including breathe easy plenum with germicidal UV light protection compartment and relocate thermostat to action wall | | |
| Note – Please remove A/C prior to delivery of remount to Frazer. | | |
| This includes making necessary modifications not limited to: | | |
| Interior – walls, register, and vents | | |
| Exterior – relocation of (2) emergency rear lights with painted A/C retrofit plating, installation of a new style A/C vent, furnish new vented style A/C door (if needed) | | |
| | \$ | 5,500.00 |
| Total | \$ | 10,400.00 |

Terms and Conditions

- 1 . This quote is valid for 90 days.
- 2 . All pricing is F.O.B. Houston.
- 3 . Please note, payment for the entire purchase is due upon receipt and acceptance of completed unit.
- 4 . Please make your purchase order out to Frazer, Ltd. (P.O.Box 5000, Houston, TX 77402). Please email a copy of your purchase order and this quote to Adam Fischer at sales@frazerbilt.com.
- 5 . To minimize delays, customer provided items should be present prior to unit production start.
- 6 . Please remove your A/C prior to remount delivery at Frazer.
- 7 . Please remove your Onan generator prior to remount delivery at Frazer.
- 8 . Fair condition of module is assumed when quoting paint. Large or excessive dents, deep or excessive scratches and unforeseen body work will require a revision to the quoted paint price.

Thank you for the opportunity to quote this job. If you have any questions please call me at 888-372-9371.



Laura Richardson
Frazer, Ltd.

LGR:CH