

REVIEW BY FORT BEND COUNTY COMMISSIONERS COURT

On this 9th day of August, 2016, Commissioners Court came on to be heard and reviewed the accompanying notice of Byers Engineering / AT & T
Job Location 3329 Lake Olympia Pkwy, Missouri City, TX 77459
Date 7/28/2016 Bond No. CHI-001686693-01, Permit No. 2016-8676 to make use of certain Fort Bend County property subject to, "A Revised Order Regulating the Laying, Construction, Maintenance, and Repair of Buried Cables, Conduits, and Pole Lines, In, Under, Across or Along Roads, Streets, Highways, and Drainage Ditches in Fort Bend County, Texas, Under the Jurisdiction of the Commissioners Court of Fort Bend County, Texas," as passed by the Commissioners Court of Fort Bend County, Texas the 3rd day of August, 1987, recorded in Volume _____ of the Minutes of the Commissioners Court of Fort Bend County, Texas, to the extent that such order is not inconsistent with Article 1436a, Vernon's Texas Civil Statutes. Upon Motion of Commissioner _____, seconded by Commissioner _____, duly put and carried, it is ORDERED, ADJUDGED AND DECREED that said notice of said above purpose is hereby acknowledged by the Commissioners Court of Fort Bend County, Texas, and that said notice be placed on record according to the regulation order thereof.

Notes:

1. Evidence of review by the Commissioners Court must be kept on the job site and failure to do so constitutes grounds for job shutdown.
2. Written notices are required:
 - a. 48 hours in advance of construction start up, and
 - b. when construction is completed and ready for final inspectionMail notices to: Permit Administrator
Fort Bend County Engineering
301 Jackson Street
Richmond, Texas 77469
281-633-7500
3. This permit expires one (1) year from date of permit if construction has not commenced.

By: _____

Charles O. [Signature]
County Engineer

Presented to Commissioners Court and approved.
Recorded in Volume _____

Minutes of Commissioners Court

By: _____

N/A

Drainage District Engineer/Manager

Clerk of Commissioners Court

By: _____

Deputy

Engineering Department

Phone: (281) 633-7500

Permit No. 2016-8676

X (1) Complete Application Form:

X	c. Plans and specifications
---	-----------------------------

X Perpetual bond currently posted.

Amount: \$25,000.00

Performance bond submitted.

No:

Amount:

Cashier's Check

No:

Amount:

(3) Verbal permission given for emergencies, to start construction before approved in Commissioner's Court.

Date _____

Date _____

Drainage District Approval when applicable

[Signature] Ortega CFM

7/28/2014
Date

Ortega, Johnny

From: Gary Gehbauer <ggehbauer@browngay.com>
Sent: Thursday, July 28, 2016 12:07 PM
To: Ortega, Johnny
Cc: Phil Martin (philmartin@mikestoneassociates.com); Eric Liu
Subject: FW: app-9051
Attachments: document.pdf@fortbendcountytexas.gov_20160718_112045.pdf

Johnny,

The engineering group from Byer /AT&T finally contacted us this morning. We have no objection to this work as long as the following notes are placed on the plans:

Utility Permit Notes for work within FBGPTRA and FBCTRA (collectively as FBTRA) Right of Way

- * All work must meet TxDOT / State of Texas utility accommodation requirements
- * Notify Phil Martin with FBTRA at least 48 hours prior to commencing work at (713) 574-5261: philmartin@mikestoneassociates.com
- * Utility owner must provide owner's responsible person's name and contact information (not contractor's contact information).
- * Any work within the toll road right of way requires a traffic control plan; even if lanes are not affected. TCP must meet TxDOT or TMUTCD requirements and be reviewed by FBTRA with no objections prior to starting work.
- * Access to SH 99 or Fort Bend Parkway must be coordinated with Phil Martin prior to work.
- * Bore pits within the right of way must be protected during non-work hours.
- * Contractor must clean roadway of dirt and debris prior at the end of each work day or prior to opening roadway to traffic
- * Peak hours are from 5am to 9am, and 3pm to 7pm. No lane closures permitted during peak hours without authorization from FBTRA.
- * Work areas that have been disturbed must be returned to the original condition and may be required to place grass sod and continual watering.
- * Upon completion of work, submit CADD/Microstation files and pdf of Record Drawings to Phil Martin with FBTRA.

Thanks,
Gary

Gary Gehbauer, PE
Brown & Gay Engineers, Inc.
10777 Westheimer, Suite 400
Houston, Texas 77042
(281)558-8700 voice
(281)558-9706 fax

-----Original Message-----

From: Ortega, Johnny [<mailto:Johnny.Ortega@fortbendcountytexas.gov>]
Sent: Monday, July 18, 2016 11:31 AM
To: Gary Gehbauer <ggehbauer@browngay.com>; philmartin@mikestoneassociates.com
Cc: mikestone@mikestoneassociates.com
Subject: app-9051





Gary
Please review and comment
Thanks

Johnny Ortega, CFM
Fort Bend County Engineering
Permit Supervisor



App-9091

FORT BEND COUNTY SPECIFICATIONS

1. NO MORE TRENCH OPENED AT ONE TIME THAN CAN BE BACKFILLED AND COMPACTED IN 30' LEFTS AT THE END OF EACH WORK DAY. ONE TRENCH LEFT OPEN OVERNIGHT.
2. ALL EXCESS EXCAVATION TO BE REMOVED FROM ROAD RIGHT OF WAY AT THE END OF EACH WORK DAY.
3. TRENCHES TO BE OPENED AT END OF EACH DAY TO ASSURE ADEQUATE DRAINAGE.
4. ROAD MUST BE KEPT OPEN TO TRAFFIC AND CONTRACTOR MUST PROVIDE ADEQUATE FLAGMEN, SIGNS, SIGNALS, ETC. TO PROVIDE COMPLETE SAFETY TO THE PUBLIC.
5. IF IT BECOMES NECESSARY FOR EQUIPMENT TO OPERATE ON A PORTION OF THE PAVEMENT, PRECAUTIONS SHOULD BE TAKEN TO PREVENT ANY DAMAGE WHATSOEVER TO THE PAVEMENT.
6. CONDITION OF ROAD UPON COMPLETION OF JOB SHALL BE AS GOOD OR BETTER THAN PRIOR TO STARTING.
7. MIN DEPTH TO TOP OF CABLE OR CONDUIT IS TO BE 60" BELOW CROWN OF ROAD AND 42" BELOW ANY ROADSIDE DITCH.



Location Map



RW012-W87438-ROUTE3;

NO SCALE
A00A4W
281-437



Byers Engineer	
DRAWN BY:	JCS
DATE:	July 15, 2015
KEY MAP:	810H
PLAT:	1 of 1
DWG NAME:	Vicksburg Blvd

Ft Bend County PERMIT PRINT