

**Fort Bend County Tabulation
 Bid 17-038
 Construction of Williams Way Boulevard
 from FM 762 to US 59/IH 69 NB Frontage Road**

**Recommendation: Allgood Construction Co., Inc.
 Funding: Engineering, 2013 Mobility**

Company	Bid Price	Completion Time in Calendar Days	Form 1295
Allgood Construction Co., Inc. Richmond	\$4,645,912.45	335	Yes
Triple B Services, LLP Huffman	\$4,728,839.45	335	
Angel Brothers Enterprises, Ltd. Baytown	\$4,869,379.90	335	
Conrad Construction Co., Ltd Houston	\$4,959,010.35	335	
Durwood Greene Construction Co Stafford	\$5,094,379.35	300	
Rodriguez Construction Group Stafford	\$5,145,045.38	335	
Mar-Con Services, LLC Pasadena	\$5,266,377.00	335	
John Reed and Company LLC Houston	\$5,591,805.22	335	
James Construction Group, LLC Spring	\$5,686,472.66	335	

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Engineer's Estimate		Allgood Construction Co., Inc.		Triple B Services, LLP	
					Unit Price	Total in Figures	Unit Price	Total in Figures	Unit Price	Total in Figures
A. SITE PREPARATION										
1	100(DWG)	FORT BEND COUNTY PROJECT SIGN	EACH	2	\$900.00	\$1,800.00	\$569.25	\$1,138.50	\$775.00	\$1,550.00
2	102(DWGS)	CLEARING AND GRUBBING (INCLUDING OUTFALLS)	LS	1	\$300,000.00	\$300,000.00	\$61,893.00	\$61,893.00	\$53,200.00	\$53,200.00
3	104	REMOVING OLD CONCRETE PAVEMENT	SY	5,440	\$12.00	\$65,280.00	\$2.59	\$14,089.60	\$3.30	\$17,952.00
4	104	REMOVING OLD CONCRETE PAVEMENT, 6" REINFORCED CONCRETE CURB	LF	2,800	\$8.00	\$22,400.00	\$2.30	\$6,440.00	\$1.10	\$3,080.00
5	110(SP110)	ROADWAY EXCAVATION (INCLUDING 3" STRIPING)	CY	15,987	\$10.00	\$159,870.00	\$7.48	\$119,582.76	\$6.50	\$103,915.50
6	465	REMOVE AND DISPOSE OF EXISTING, CONCRETE OR METAL PIPE (18" - 36")	LF	723	\$15.00	\$10,845.00	\$11.50	\$8,314.50	\$9.90	\$7,157.70
7	465	REMOVE AND DISPOSE OF EXISTING PLASTIC PIPE (ALL TYPE AND ALL SIZES)	LF	60	\$12.00	\$720.00	\$11.50	\$690.00	\$9.85	\$591.00
8	495	REMOVING OLD STRUCTURES - INLETS (ALL DEPTHS)	EACH	3	\$600.00	\$1,800.00	\$402.50	\$1,207.50	\$450.00	\$1,350.00
9	495	REMOVING OLD STRUCTURES - SAFETY END TREATMENTS	EACH	2	\$350.00	\$700.00	\$402.50	\$805.00	\$450.00	\$900.00
10	495	REMOVING OLD STRUCTURES - HEADWALLS INCLUDING WINGWALLS	EACH	7	\$800.00	\$5,600.00	\$575.00	\$4,025.00	\$2,375.00	\$16,625.00
11	495	REMOVING FLEX BEAM GUARD RAIL	LF	256	\$20.00	\$5,120.00	\$5.75	\$1,472.00	\$4.70	\$1,203.20
12	495	REMOVING TURN DOWN SECTION	EACH	2	\$150.00	\$300.00	\$575.00	\$1,150.00	\$243.00	\$486.00
13	495	REMOVING OLD STRUCTURE - WOODEN BRIDGE	EACH	1	\$20,000.00	\$20,000.00	\$5,750.00	\$5,750.00	\$16,500.00	\$16,500.00
14	500	REMOVE AND RELOCATE TRAFFIC SIGNS, MAIL BOXES, ROADWAY SIGNS	LS	1	\$3,000.00	\$3,000.00	\$1,725.00	\$1,725.00	\$1,560.00	\$1,560.00
15	500	REMOVE AND RELOCATE TRAFFIC SIGNAL ITEMS (AS REQUIRED)	LS	1	\$2,000.00	\$2,000.00	\$5,456.75	\$5,456.75	\$5,260.00	\$5,260.00
16	540	REMOVE AND DISPOSE OF EXISTING ASPHALTIC SURFACE AND BASE MATERIAL	SY	4,118	\$4.00	\$16,472.00	\$2.53	\$10,418.54	\$3.60	\$14,824.80
SUB-TOTAL SITE PREPARATION ITEMS						\$615,907.00		\$244,158.15		\$246,155.20

B. SUBGRADE AND PAVING										
17	221	HYDRATED LIME (SLURRY APPLIED) FOR STABILIZATION (6% BY DRY WEIGHT)	TON	614	\$165.00	\$101,310.00	\$171.35	\$105,208.90	\$145.00	\$89,030.00
18	223	FLY ASH FOR STABILIZATION (8% BY DRY WEIGHT)	TON	818	\$95.00	\$77,710.00	\$92.00	\$75,256.00	\$73.00	\$59,714.00
19	226(DWGS)	LIME-FLY ASH STABILIZED SUBGRADE, 2 MANIPULATIONS AT 8" DEPTH	SY	30,994	\$4.25	\$131,724.50	\$2.53	\$78,414.82	\$2.20	\$68,186.80
20	250	HOT MIX ASPHALTIC CONCRETE BASE COURSE, 8" DEPTH	TON	274	\$115.00	\$31,510.00	\$109.25	\$29,934.50	\$74.00	\$20,276.00
21	310	PRIME COAT FOR BASE COURSE (1.30 GAL/SY)	GAL	189	\$3.00	\$567.00	\$5.75	\$1,086.75	\$3.30	\$623.70
22	340	HMAC - TACK COAT (0.15 GAL/SY)	GAL	95	\$4.00	\$380.00	\$5.75	\$546.25	\$3.30	\$313.50
23	340	HMAC TYPE "D" SURFACE COURSE - 2" THICK	TON	69	\$130.00	\$8,970.00	\$112.70	\$7,776.30	\$143.50	\$9,901.50
24	360	REINFORCED CONCRETE PAVEMENT - 8" DEPTH	SY	26,549	\$57.00	\$1,513,293.00	\$43.10	\$1,144,261.90	\$39.55	\$1,050,012.95
25	360	REINFORCED CONCRETE PAVEMENT, HIGH EARLY STRENGTH - 8" DEPTH	SY	4,450	\$59.00	\$262,550.00	\$46.00	\$204,700.00	\$55.75	\$248,087.50
26	360	REINFORCED CONCRETE PAVEMENT, HIGH EARLY STRENGTH - 8" DEPTH FOR DRIVEWAYS	SY	710	\$61.00	\$43,310.00	\$80.50	\$57,155.00	\$92.15	\$65,426.50
27	433	CEMENT STABILIZED SAND, 8" THICK	SY	5,620	\$16.00	\$89,920.00	\$9.27	\$52,097.40	\$6.55	\$36,811.00
28	521(DWGS)	FLEX BEAM GUARD RAIL, 12 GAUGE WITH MOWING STRIP	LF	534	\$60.00	\$32,040.00	\$43.13	\$23,031.42	\$50.00	\$26,700.00
29	522(DWGS)	TURN DOWN TERMINAL SECTION (25' LONG), 12 GAUGE, WITH ANCHOR	EACH	12	\$1,700.00	\$20,400.00	\$805.00	\$9,660.00	\$1,055.00	\$12,660.00
30	530	6" CONCRETE CURBS	LF	21,695	\$4.25	\$92,203.75	\$2.53	\$54,888.35	\$3.30	\$71,593.50
31	535	ESPLANADES, MEDIANS, AND DIRECTIONAL ISLANDS	SY	264	\$100.00	\$26,400.00	\$69.00	\$18,216.00	\$67.35	\$17,780.40
32	536	COLOR CONCRETE MEDIANS (BLACK)	SY	264	\$100.00	\$26,400.00	\$5.75	\$1,518.00	\$4.25	\$1,122.00
SUB-TOTAL PAVING						\$2,458,688.25		\$1,863,751.59		\$1,778,239.35

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Engineer's Estimate			Allgood Construction Co., Inc.			Triple B Services, LLP		
					Unit Price	Total in Figures	Unit Price	Unit Price	Total in Figures	Unit Price	Unit Price	Total in Figures	Total in Figures

C. STORM SEWER

33	421	STRUCTURAL CONCRETE, WINGWALLS	CY	15	\$2,000.00	\$0.00	\$1,092.50	\$1,040.00	\$16,387.50	\$1,040.00		\$15,600.00	
34	421	STRUCTURAL CONCRETE, HEADWALLS	CY	20	\$1,900.00	\$0.00	\$1,092.50	\$926.00	\$21,850.00	\$926.00		\$18,520.00	
35	429	TRENCH SAFETY SYSTEMS, 5' TO 10' DEPTH	LF	6,256	\$2.50	\$15,640.00	\$0.12	\$0.10	\$750.72	\$0.10		\$625.60	
36	459	TIMBER BENT FOR 48" PIPE	EACH	1	\$1,500.00	\$1,500.00	\$1,150.00	\$1,120.00	\$1,150.00	\$1,120.00		\$1,120.00	
37	460	CORRUGATED PLASTIC PIPE, PRE-COATED (12")	LF	30	\$65.00	\$1,950.00	\$28.75	\$47.50	\$862.50	\$47.50		\$1,425.00	
38	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (24")	LF	3,130	\$90.00	\$281,700.00	\$40.12	\$49.60	\$125,575.60	\$49.60		\$155,248.00	
39	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (EQUIVALENT 24") ELLIPTICAL 19" X 30"	LF	410	\$120.00	\$49,200.00	\$91.16	\$105.15	\$37,375.60	\$105.15		\$43,111.50	
40	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (30")	LF	744	\$105.00	\$78,120.00	\$52.87	\$54.65	\$39,335.28	\$54.65		\$40,659.60	
41	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (42")	LF	601	\$120.00	\$72,120.00	\$86.10	\$81.50	\$51,746.10	\$81.50		\$48,981.50	
42	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (42")	LF	1,101	\$150.00	\$165,150.00	\$99.99	\$97.05	\$110,088.99	\$97.05		\$106,852.05	
43	461	CORRUGATED METAL PIPE-PRE-COATED-GALVANIZED (16 GAUGE)(24")	LF	129	\$135.00	\$17,415.00	\$39.10	\$88.00	\$5,043.90	\$88.00		\$11,352.00	
44	461	CORRUGATED METAL PIPE-PRE-COATED-GALVANIZED (16 GAUGE)(30")	LF	133	\$145.00	\$19,285.00	\$49.45	\$101.15	\$6,576.85	\$101.15		\$13,452.95	
45	461	CORRUGATED METAL PIPE-PRE-COATED-GALVANIZED (16 GAUGE)(48")	LF	118	\$180.00	\$21,240.00	\$95.45	\$132.70	\$11,263.10	\$132.70		\$15,658.60	
46	463	SAFETY END TREATMENT - TYPE II, (6:1) (PD-SPR) 24" RCP	EACH	2	\$2,500.00	\$5,000.00	\$1,477.75	\$1,925.00	\$2,955.50	\$1,925.00		\$3,850.00	
47	467-2288	SAFETY END TREATMENT SET (TY II) (24IN) (RCP) (6:1) (P)	EACH	2	\$3,000.00	\$6,000.00	\$1,006.25	\$1,425.00	\$2,012.50	\$1,425.00		\$2,850.00	
48	471	PRECAST CONCRETE SHALLOW MANHOLE, DEPTH LESS THAN 6 FEET	EACH	16	\$3,500.00	\$56,000.00	\$2,587.50	\$2,450.00	\$41,400.00	\$2,450.00		\$39,200.00	
49	471	PRECAST CONCRETE STANDARD MANHOLE, DEPTH GREATER THAN 6 FEET & LESS THAN 10 FEET	EACH	3	\$5,000.00	\$15,000.00	\$2,725.50	\$3,475.00	\$8,176.50	\$3,475.00		\$10,425.00	
50	471	PRECAST CONCRETE EXTRA DEPTH MANHOLE, DEPTH GREATER THAN 10 FEET	EACH	11	\$6,000.00	\$66,000.00	\$5,163.50	\$5,325.00	\$56,798.50	\$5,325.00		\$58,575.00	
51	472	TYPE "A" INLET, ADDITIONAL DEPTH GREATER THAN 6'	EACH	4	\$2,800.00	\$11,200.00	\$1,569.75	\$2,130.00	\$6,279.00	\$2,130.00		\$8,520.00	
52	472	STANDARD TYPE "A" INLET MODIFIED SQUARE (PRE-CAST OR CAST) GREATER THAN 6'	EACH	7	\$3,000.00	\$21,000.00	\$1,144.25	\$2,760.00	\$8,009.75	\$2,760.00		\$19,320.00	
53	472	TYPE "B-B" INLET STANDARD TYPE "B-B" INLET	EACH	12	\$3,500.00	\$42,000.00	\$1,788.25	\$2,400.00	\$21,459.00	\$2,400.00		\$28,800.00	
54	472	TYPE "B-B" INLET WITH ADDITIONAL DEPTH GREATER THAN 6'	EACH	6	\$4,000.00	\$24,000.00	\$2,179.25	\$2,500.00	\$13,075.50	\$2,500.00		\$15,000.00	
55	472	TYPE "B-B" (MODIFIED) INLET, ADDITIONAL DEPTH GREATER THAN 6'	EACH	6	\$3,000.00	\$18,000.00	\$2,380.50	\$2,500.00	\$14,283.00	\$2,500.00		\$15,000.00	
56	480	REINFORCED CONCRETE BOX, C1433 (ALL DEPTHS)(5' X 3')	LF	174	\$500.00	\$87,000.00	\$162.60	\$153.00	\$28,292.40	\$153.00		\$26,622.00	
57	491	REINFORCED CONCRETE SLOPE PAVING (4" THICK)	SY	215	\$65.00	\$13,975.00	\$92.00	\$61.00	\$19,780.00	\$61.00		\$13,115.00	
58	491	REINFORCED CONCRETE SLOPE PAVING (5" THICK)	SY	1,492	\$70.00	\$104,400.00	\$78.20	\$66.50	\$116,674.40	\$66.50		\$99,218.00	
59	2378	RIPRAP - GRADATION NO. 1 (18" THICK)	SY	110	\$65.00	\$7,150.00	\$86.25	\$72.00	\$9,487.50	\$72.00		\$7,920.00	
SUB-TOTAL STORM SEWER						\$1,200,085.00			\$776,689.69			\$821,021.80	

D. TRAFFIC CONTROL

60	665	WORK ZONE PAVEMENT MARKINGS 4" WHITE/SOLID (REMOVABLE) APPLIED, REMOVED	LF	934	\$0.50	\$467.00	\$0.69	\$0.60	\$644.46	\$0.60		\$560.40	
61	665	WORK ZONE PAVEMENT MARKINGS 8" WHITE/SOLID (REMOVABLE) APPLIED, REMOVED	LF	120	\$1.00	\$120.00	\$1.73	\$1.10	\$207.60	\$1.10		\$132.00	
62	665	WORK ZONE PAVEMENT MARKINGS 24" WHITE/SOLID (REMOVABLE) APPLIED, REMOVED	LF	57	\$1.50	\$85.50	\$4.03	\$2.25	\$229.71	\$2.25		\$128.25	
63	665	WORK ZONE PAVEMENT MARKINGS 4" YELLOW/SOLID (REMOVABLE) APPLIED, REMOVED	LF	8,716	\$1.00	\$8,716.00	\$0.59	\$0.60	\$5,142.44	\$0.60		\$5,229.60	

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Engineer's Estimate		Allgood Construction Co., Inc.		Triple B Services, LLP	
					Unit Price	Total in Figures	Unit Price	Total in Figures	Unit Price	Total in Figures
64	665	WORK ZONE PAVEMENT MARKINGS 8" WHITE/DASHED (REMOVABLE) APPLIED, REMOVED (4' OVER 8')	LF	105	\$1.00	\$105.00	\$2.30	\$241.50	\$1.10	\$115.50
65	671	TRAFFIC CONTROL - FURNISH-INSTALL & REMOVE	MONTH	11	\$6,000.00	\$66,000.00	\$1,790.55	\$19,696.05	\$1,785.00	\$19,635.00
66	671	TEMPORARY COMMERCIAL DRIVEWAYS - INSTALL & REMOVE	EACH	3	\$1,000.00	\$3,000.00	\$2,875.00	\$8,625.00	\$1,220.00	\$3,660.00
67	671	TEMPORARY TRAFFIC SIGNAL AT FM 762 AND WILLIAMS WAY BOULEVARD (RELOCATE SIGNAL HEADS/BAG)	LS	1	\$5,000.00	\$5,000.00	\$9,487.50	\$9,487.50	\$9,150.00	\$9,150.00
68	673	CONSTRUCTING DETOURS FOR TWO-WAY TRAFFIC (8" BLACK BASE) FOR INSTALLING-MAINTAINING & REMOVING	SY	206	\$70.00	\$14,420.00	\$65.96	\$13,587.76	\$48.60	\$10,011.60
69	696	LOW PROFILE CONCRETE BARRIER TYPE 1 (INSTALL)	LF	805	\$18.00	\$14,490.00	\$28.75	\$23,143.75	\$10.00	\$8,050.00
70	696	LOW PROFILE CONCRETE BARRIER TYPE 1 (RELOCATE)	LF	2,474	\$8.00	\$19,792.00	\$11.50	\$28,451.00	\$6.00	\$14,844.00
71	696	LOW PROFILE CONCRETE BARRIER TYPE 1 (REMOVE)	LF	805	\$12.00	\$9,660.00	\$17.25	\$13,886.25	\$10.00	\$8,050.00
72	696	LOW PROFILE CONCRETE BARRIER TYPE 2 (INSTALL)	LF	80	\$18.00	\$1,440.00	\$28.75	\$2,300.00	\$10.00	\$800.00
73	696	LOW PROFILE CONCRETE BARRIER TYPE 2 (RELOCATE)	LF	140	\$8.00	\$1,120.00	\$11.50	\$1,610.00	\$6.00	\$840.00
74	696	LOW PROFILE CONCRETE BARRIER TYPE 2 (REMOVE)	LF	80	\$12.00	\$960.00	\$17.25	\$1,380.00	\$10.00	\$800.00
SUB-TOTAL TRAFFIC CONTROL						\$145,375.50		\$128,633.02		\$82,006.35

E. SIGNING AND PAVEMENT MARKING										
75	448	SOLID CAST ALUMINIUM BRIDGE PLAQUE	EACH	1	\$2,500.00	\$2,500.00	\$2,300.00	\$2,300.00	\$1,665.00	\$1,665.00
76	624	ALUMINIUM SIGNS (GROUND MOUNTED)	EACH	58	\$500.00	\$29,000.00	\$253.00	\$14,674.00	\$355.00	\$20,590.00
77	658	FURNISH AND INSTALL OBJECT MARKER (TEXAS MUTCD: "OM-3R/L")	EACH	2	\$200.00	\$400.00	\$151.80	\$303.60	\$88.75	\$177.50
78	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 4" WHITE/SOLID	LF	397	\$1.00	\$397.00	\$0.67	\$265.99	\$0.50	\$198.50
79	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 8" WHITE/SOLID	LF	922	\$1.50	\$1,383.00	\$1.21	\$1,115.62	\$1.05	\$968.10
80	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 12" WHITE/SOLID	LF	584	\$3.25	\$1,898.00	\$2.47	\$1,442.48	\$2.60	\$1,518.40
81	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 24" WHITE/SOLID	LF	292	\$8.00	\$2,336.00	\$5.18	\$1,512.56	\$4.45	\$1,299.40
82	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 4" WHITE/DASHED (15' OVER 40')	LF	8,395	\$2.00	\$16,790.00	\$0.71	\$5,960.45	\$0.50	\$4,197.50
83	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) SINGLE ARROW-LEFT	EACH	8	\$160.00	\$1,280.00	\$132.25	\$1,058.00	\$122.00	\$976.00
84	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) RIGHT-STRAIGHT COMBINATION ARROWS	EACH	2	\$180.00	\$360.00	\$132.25	\$264.50	\$122.00	\$244.00
85	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) WORD "ONLY"	EACH	5	\$210.00	\$1,050.00	\$126.50	\$632.50	\$144.15	\$720.75
86	660	REFLECTORIZED PAVEMENT MARKINGS TYPE II, 12" YELLOW/SOLID, FOR 6" CURB PER DETAIL "D"	LF	2,830	\$2.00	\$5,660.00	\$0.92	\$2,603.60	\$1.10	\$3,113.00
87	663	REFLECTORIZED PAVEMENT MARKERS TYPE I-C	EACH	296	\$5.00	\$1,480.00	\$3.16	\$935.36	\$4.45	\$1,317.20
88	663	REFLECTORIZED PAVEMENT MARKERS TYPE II-C-R	EACH	195	\$5.00	\$975.00	\$3.16	\$616.20	\$4.45	\$867.75
89	663	NON-REFLECTORIZED CERAMIC TRAFFIC BUTTONS (WHITE)	EACH	201	\$6.00	\$1,206.00	\$2.59	\$520.59	\$3.30	\$663.30
SUB-TOTAL SIGNING AND PAVEMENT MARKINGS						\$66,715.00		\$34,205.45		\$38,516.40

F. PERMANENT TRAFFIC SIGNALS (TXDOT SPECIFICATIONS)										
90	416-2032	DRILLED SHAFT FOUNDATION (TRF SIG. POLE)	LF	30	\$350.00	\$10,500.00	\$417.83	\$12,534.90	\$403.00	\$12,090.00
91	618-2052	CONDUIT (PVC) (SCHD 80) (2")	LF	150	\$10.50	\$1,575.00	\$7.39	\$1,085.50	\$7.15	\$1,072.50
92	620-2009	ELECTRICAL CONDUCTORS (NO. 6) BARE	LF	145	\$2.00	\$290.00	\$2.20	\$319.00	\$2.15	\$311.75
93	621-2004	TRAY CABLE (4 CONR) (12 AWG)	LF	400	\$2.50	\$1,000.00	\$2.40	\$960.00	\$2.40	\$960.00
94	624-2014	GROUND BOXES TY D (162922) W/ APRON	EACH	1	\$700.00	\$700.00	\$1,270.75	\$1,270.75	\$1,225.00	\$1,225.00
95	625-2001	ZINC-COATED STEEL WIRE STRAND (5/16 IN)	LF	400	\$2.90	\$1,160.00	\$4.27	\$1,708.00	\$4.10	\$1,640.00

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Engineer's Estimate			Allgood Construction Co., Inc.			Triple B Services, LLP	
					Unit Price	Total in Figures	Unit Price	Unit Price	Total in Figures	Unit Price	Unit Price	Total in Figures
96	625-2003	ZINC-COATED STEEL WIRE STRAND (1/4 IN)	LF	400	\$2.50	\$1,000.00	\$4.19	\$4.05	\$1,676.00	\$4.05	\$4.05	\$1,620.00
97	625-2004	ZINC-COATED STEEL WIRE STRAND (3/8 IN)	LF	400	\$3.30	\$1,320.00	\$4.35	\$4.20	\$1,740.00	\$4.20	\$4.20	\$1,680.00
98	644-2100	INSTALL SMALL ROADSIDE SIGN ASSEMBLIES TY 10BWG (1) SA (P)	EACH	2	\$500.00	\$1,000.00	\$784.88	\$757.00	\$1,569.76	\$757.00	\$757.00	\$1,514.00
99	644-2100	"NO PEDESTRIAN CROSSING" (R9-3) (12" X 18")	EACH	2	\$250.00	\$500.00	\$373.75	\$360.00	\$747.50	\$360.00	\$360.00	\$720.00
100	644-2100	"NO PEDESTRIAN CROSSING" (R9-3A) (18" X 18")	EACH	2	\$500.00	\$1,000.00	\$373.75	\$360.00	\$747.50	\$360.00	\$360.00	\$720.00
101	666-2048	RETROREFLECTORIZED PAVEMENT MARKINGS TY 1 (W) 24" (SLD) (100 MIL)	LF	125	\$4.90	\$612.50	\$5.75	\$4.45	\$718.75	\$4.45	\$4.45	\$556.25
102	666-2195	PAVEMENT SEALER 24"	LF	125	\$2.50	\$312.50	\$0.60	\$0.55	\$75.00	\$0.55	\$0.55	\$68.75
103	678-2005	PAVEMENT SURFACE PREPARATION FOR MARKING (BLAST CLN) (24")	LF	125	\$1.85	\$231.25	\$0.60	\$0.30	\$75.00	\$0.30	\$0.30	\$37.50
104	680-2002	INSTALL HIGHWAY TRAFFIC SIGNALS (ISOLATED)	EACH	1	\$9,000.00	\$9,000.00	\$16,445.00	\$15,850.00	\$16,445.00	\$15,850.00	\$15,850.00	\$15,850.00
105	680-2002	POLE 34' STEEL STRAIN	EACH	2	\$5,000.00	\$10,000.00	\$7,624.50	\$7,350.00	\$15,249.00	\$7,350.00	\$7,350.00	\$14,700.00
106	680-2002	RDWY LIGHT ON TRAF SIGNAL POLE (250 WATT H.P.S.)	EACH	1	\$3,000.00	\$3,000.00	\$867.10	\$840.00	\$867.10	\$840.00	\$840.00	\$840.00
107	680-2002	MAST ARM, 10' LUMINAIRE	EACH	2	\$1,900.00	\$3,800.00	\$1,304.40	\$1,255.00	\$2,608.80	\$1,255.00	\$1,255.00	\$2,510.00
108	684-2009	TRAFFIC SIGNAL CABLES (TY A) (12 AWG) (4 COND)	LF	270	\$2.50	\$675.00	\$2.25	\$2.15	\$607.50	\$2.15	\$2.15	\$580.50
109	684-2012	TRAFFIC SIGNAL CABLES (TY A) (12 AWG) (7 COND)	LF	1,050	\$2.90	\$3,045.00	\$2.55	\$2.50	\$2,677.50	\$2.50	\$2.50	\$2,625.00
110	6266-2005	VIVDS COMMUNICATION CABLE (COAXIAL)	LF	1,310	\$5.50	\$7,205.00	\$2.61	\$2.50	\$3,419.10	\$2.50	\$2.50	\$3,275.00
111	6266-2005	3/C #16 - VIVDS POWER CABLE	LF	1,310	\$3.50	\$4,585.00	\$2.61	\$2.50	\$3,419.10	\$2.50	\$2.50	\$3,275.00
SUB-TOTAL PERMANENT TRAFFIC SIGNALS						\$62,511.25			\$70,571.76			\$67,871.25

G. BRIDGE STRUCTURE (TXDOT SPECIFICATIONS)												
112	400-6005	CEMENT STABILIZED BACKFILL	CY	180	\$40.00	\$7,200.00	\$89.25	\$89.25	\$16,065.00	\$89.25	\$89.25	\$16,065.00
113	416-6001	DRILLED SHAFT FOUNDATIONS (18-INCH)	LF	112	\$95.00	\$10,640.00	\$68.25	\$68.25	\$7,644.00	\$68.25	\$68.25	\$7,644.00
114	416-6004	DRILLED SHAFT FOUNDATIONS (36-INCH)	LF	1,736	\$192.00	\$333,312.00	\$231.00	\$231.00	\$401,016.00	\$231.00	\$231.00	\$401,016.00
115	420-6013	CONCRETE STRUCTURES (CLASS C CONCRETE) - ABUTMENTS	CY	86	\$885.00	\$76,110.00	\$866.25	\$866.25	\$74,497.50	\$866.25	\$866.25	\$74,497.50
116	420-4025	CONCRETE STRUCTURES (CLASS C CONCRETE) - BENTS	CY	117	\$1,040.00	\$121,680.00	\$918.75	\$918.75	\$107,493.75	\$918.75	\$918.75	\$107,493.75
117	422-6001	REINFORCED CONCRETE SLAB	SF	14,904	\$15.00	\$223,560.00	\$15.23	\$15.23	\$226,987.92	\$15.23	\$15.23	\$226,987.92
118	422-6011	BRIDGE MEDIAN	SF	1,776	\$5.00	\$8,880.00	\$15.59	\$15.59	\$27,687.84	\$15.59	\$15.59	\$27,687.84
119	422-6013	BRIDGE SIDEWALK	SF	4,440	\$10.00	\$44,400.00	\$13.13	\$13.13	\$58,297.20	\$13.13	\$13.13	\$58,297.20
120	422-6015	BRIDGE APPROACH SLAB	CY	242	\$590.00	\$142,780.00	\$446.25	\$446.25	\$107,992.50	\$446.25	\$446.25	\$107,992.50
121	425-6036	PRECAST PRESTRESSED CONCRETE STRUCTURAL MEMBERS (PRESTRESSED CONCRETE GIRDER, TX34)	LF	1,715	\$136.00	\$233,240.00	\$132.83	\$132.83	\$227,803.45	\$132.83	\$132.83	\$227,803.45
122	442-6007	METAL FOR STRUCTURES (STRUCTURAL STEEL) (MISC NON BRIDGE)	LB	582	\$8.00	\$4,656.00	\$11.55	\$11.55	\$6,722.10	\$11.55	\$11.55	\$6,722.10
123	450-6032	RAILING (TY C223)	LF	492	\$116.00	\$57,072.00	\$136.50	\$136.50	\$67,158.00	\$136.50	\$136.50	\$67,158.00
124	454-6001	BRIDGE EXPANSION JOINTS, SEALED EXPANSION JOINT (4-INCH) (SEJ-A)	LF	130	\$102.00	\$13,260.00	\$128.10	\$128.10	\$16,653.00	\$128.10	\$128.10	\$16,653.00
SUB-TOTAL BRIDGE ITEMS						\$1,276,790.00			\$1,346,018.26			\$1,514,891.50

H. STORM WATER POLLUTION PREVENTION												
125	162	SODDING FOR EROSION CONTROL AND STABILIZATION	LF	11,858	\$2.50	\$29,645.00	\$3.16	\$3.16	\$37,471.28	\$3.16	\$3.16	\$37,471.28
126	165	HYDRO-MULCH SEEDING	ACRE	5	\$1,650.00	\$8,250.00	\$1,437.50	\$1,437.50	\$7,187.50	\$1,437.50	\$1,437.50	\$7,187.50
127	713	REINFORCED FILTER FABRIC BARRIER	LF	5,520	\$2.50	\$13,800.00	\$1.44	\$1.44	\$7,948.80	\$1.44	\$1.44	\$7,948.80
128	719	INLET PROTECTION BARRIER (STAGE I, WITH FIBER ROLLS)	EACH	31	\$90.00	\$2,790.00	\$51.75	\$51.75	\$1,604.25	\$51.75	\$51.75	\$1,604.25
129	724	STABILIZED CONSTRUCTION ACCESS, TYPE 1 ROCK	SY	222	\$25.00	\$5,550.00	\$11.50	\$11.50	\$2,550.00	\$11.50	\$11.50	\$2,550.00
130	730	CONCRETE TRUCK WASHOUT STRUCTURES	LS	1	\$1,500.00	\$1,500.00	\$977.50	\$977.50	\$977.50	\$977.50	\$977.50	\$977.50
131	741	INLET PROTECTION BARRIER (FOR STAGES II INLETS, GRAVEL BAGS)	EACH	24	\$80.00	\$1,920.00	\$11.50	\$11.50	\$276.00	\$11.50	\$11.50	\$276.00
132	750	ROCK FILTER DAM (TYPE 3)	LF	80	\$60.00	\$4,800.00	\$29.90	\$29.90	\$2,392.00	\$29.90	\$29.90	\$2,392.00
133	HCPCD 2361	REINFORCED SLIT FENCE	LF	680	\$40.00	\$27,200.00	\$1.44	\$1.44	\$979.20	\$1.44	\$1.44	\$979.20
134	751(DWGS)	SWPPP INSPECTION AND MAINTENANCE (MIN. BID - \$6,000/MONTH)	MONTH	11	\$6,000.00	\$66,000.00	\$6,000.00	\$6,000.00	\$66,000.00	\$6,000.00	\$6,000.00	\$66,000.00

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Engineer's Estimate		Allgood Construction Co., Inc.		Triple B Services, LLP	
					Unit Price	Total in Figures	Unit Price	Total in Figures	Unit Price	Total in Figures
135	700 (PROJECT MANUAL)	TPDES GENERAL PERMIT NO. TXR 150000, NOTICE OF INTENT (NOI) APPLICATION FEES (CONTRACTORS NOI FEE & FORT BEND COUNTY'S NOI FEE, EACH FEE SHALL BE SET PRICE OF \$325.00)	EACH	2	\$325.00	\$650.00	\$325.00	\$650.00	\$325.00	\$650.00
SUB-TOTAL OF STORM WATER POLLUTION PREVENTION ITEMS					\$162,105.00	\$128,039.53				\$118,517.60

I. EXTRA WORK										
136	430	SEAL SLAB, CLASS D CONCRETE, 7" THICKNESS (MIN. BID \$25/SY)	SY	200	\$25.00	\$5,000.00	\$25.00	\$5,000.00	\$25.00	\$5,000.00
137	436	WELL POINTING SYSTEM (MIN. BID \$15/LF)	LF	500	\$15.00	\$7,500.00	\$15.00	\$7,500.00	\$17.00	\$8,500.00
138	552-6001	5-STRAND BARBED WIRE FENCE	LF	1,500	\$20.00	\$30,000.00	\$6.49	\$9,735.00	\$7.20	\$10,800.00
139	552-6002	5-STRAND SLICK WIRE FENCE	LF	1,000	\$20.00	\$20,000.00	\$6.50	\$6,500.00	\$7.20	\$7,200.00
140	552-6006	GALVANIZED TUBE GATES, TY 2 GATE	EA	2	\$2,000.00	\$4,000.00	\$550.00	\$1,100.00	\$600.00	\$1,200.00
141	559	CONSTRUCTION SAFETY FENCE	LF	1,000	\$2.50	\$2,500.00	\$1.25	\$1,250.00	\$2.50	\$2,500.00
142	0560 (SP 560)	MOWING PROJECT SITE	CYCLE	4	\$400.00	\$1,600.00	\$500.00	\$2,000.00	\$555.00	\$2,220.00
143	672	UNIFORM PEACE OFFICER (MINIMUM: \$25/HR)	HOUR	200	\$25.00	\$5,000.00	\$25.00	\$5,000.00	\$45.00	\$9,000.00
144	SS8006	ELECTRICAL ROSER RELOCATION FOR PROPERTY OWNER (CUSTOMER OWNED)-CONNECTION TO CENTERPOINT ENERGY ELECTRICAL SERVICE - SINGLE PHASE, 120 VOLT 3-WIRE ELECTRICAL SERVICES	LF	200	\$50.00	\$10,000.00	\$35.66	\$7,132.00	\$34.40	\$6,880.00
145	SS8006	ELECTRICAL ROSER RELOCATION FOR PROPERTY OWNER (CUSTOMER OWNED)-CONNECTION TO CENTERPOINT ENERGY ELECTRICAL SERVICE - THREE PHASE (COMMERCIAL CUSTOMER) ELECTRICAL SERVICES	LF	200	\$50.00	\$10,000.00	\$43.14	\$8,628.00	\$41.60	\$8,320.00
SUB-TOTAL EXTRA WORK ITEMS					\$95,600.00	\$53,845.00				\$61,620.00

A. SITE PREPARATION										
Engineer's Estimate					Allgood Construction Co., Inc.		Triple B Services, LLP			
					\$615,907.00	\$244,158.15				\$246,155.20
B. SUBGRADE AND PAVING					\$2,458,688.25	\$1,863,751.59				\$1,778,239.35
C. STORM SEWER					\$1,200,085.00	\$776,689.69				\$821,021.80
D. TRAFFIC CONTROL					\$145,375.50	\$128,633.02				\$82,006.35
E. SIGNING AND PAVEMENT MARKING					\$66,715.00	\$34,205.45				\$38,516.40
F. PERMANENT TRAFFIC SIGNALS (TXDOT SPECIFICATIONS)					\$62,511.25	\$70,571.76				\$67,871.25
G. BRIDGE STRUCTURE (TXDOT SPECIFICATIONS)					\$1,276,790.00	\$1,346,018.26				\$1,514,891.50
H. STORM WATER POLLUTION PREVENTION					\$162,105.00	\$128,039.53				\$118,517.60
I. EXTRA WORK					\$95,600.00	\$53,845.00				\$61,620.00
TOTAL BID PRICE (SUM OF ITEMS A THROUGH I)					\$6,083,777.00	\$4,645,912.45				\$4,728,839.45

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Unit Price	Total in Figures	Conrad Construction Co., LTD.	Total in Figures	Unit Price	Total in Figures	Durwood Greene Construction Co.	Total in Figures
A. SITE PREPARATION												
1	100(DWG)	FORT BEND COUNTY PROJECT SIGN	EACH	2	\$850.00	\$1,700.00		\$1,300.00	\$650.00	\$1,300.00	\$900.00	\$1,800.00
2	102(DWGS)	CLEARING AND GRUBBING (INCLUDING OUTFALLS)	LS	1	\$93,000.00	\$93,000.00		\$100,000.00	\$100,000.00	\$100,000.00	\$65,000.00	\$65,000.00
3	104	REMOVING OLD CONCRETE PAVEMENT	SY	5,440	\$1.50	\$8,160.00		\$16,320.00	\$3.00	\$16,320.00	\$8.00	\$43,520.00
4	104	REMOVING OLD CONCRETE PAVEMENT, 6" REINFORCED CONCRETE CURB	LF	2,800	\$0.25	\$700.00		\$3,500.00	\$1.25	\$3,500.00	\$5.00	\$14,000.00
5	110(SP110)	ROADWAY EXCAVATION (INCLUDING 3" STRIPING)	CY	15,987	\$10.50	\$167,863.50		\$191,844.00	\$12.00	\$191,844.00	\$8.50	\$135,889.50
6	465	REMOVE AND DISPOSE OF EXISTING, CONCRETE OR METAL PIPE (18" - 36")	LF	723	\$13.00	\$9,399.00		\$7,230.00	\$10.00	\$7,230.00	\$15.00	\$10,845.00
7	465	REMOVE AND DISPOSE OF EXISTING PLASTIC PIPE (ALL TYPE AND ALL SIZES)	LF	60	\$10.00	\$600.00		\$600.00	\$10.00	\$600.00	\$15.00	\$900.00
8	495	REMOVING OLD STRUCTURES - INLETS (ALL DEPTHS)	EACH	3	\$325.00	\$1,575.00		\$1,200.00	\$400.00	\$1,200.00	\$500.00	\$1,500.00
9	495	REMOVING OLD STRUCTURES - SAFETY END TREATMENTS	EACH	2	\$325.00	\$1,050.00		\$700.00	\$350.00	\$700.00	\$600.00	\$1,200.00
10	495	REMOVING OLD STRUCTURES - HEADWALLS INCLUDING WINGWALLS	EACH	7	\$950.00	\$6,650.00		\$5,600.00	\$800.00	\$5,600.00	\$650.00	\$4,550.00
11	495	REMOVING FLEX BEAM GUARD RAIL	LF	256	\$5.50	\$1,408.00		\$1,920.00	\$7.50	\$1,920.00	\$2.50	\$640.00
12	495	REMOVING TURN DOWN SECTION	EACH	2	\$550.00	\$1,100.00		\$1,200.00	\$600.00	\$1,200.00	\$350.00	\$700.00
13	495	REMOVING OLD STRUCTURE - WOODEN BRIDGE	EACH	1	\$8,300.00	\$8,300.00		\$27,500.00	\$27,500.00	\$27,500.00	\$35,000.00	\$35,000.00
14	500	REMOVE AND RELOCATE TRAFFIC SIGNS, MAIL BOXES, ROADWAY SIGNS	LS	1	\$6,400.00	\$6,400.00		\$1,500.00	\$1,500.00	\$1,500.00	\$3,500.00	\$3,500.00
15	500	REMOVE AND RELOCATE TRAFFIC SIGNAL ITEMS (AS REQUIRED)	LS	1	\$5,200.00	\$5,200.00		\$4,500.00	\$4,500.00	\$4,500.00	\$6,000.00	\$6,000.00
16	540	REMOVE AND DISPOSE OF EXISTING ASPHALTIC SURFACE AND BASE MATERIAL	SY	4,118	\$6.00	\$24,708.00		\$12,354.00	\$3.00	\$12,354.00	\$10.00	\$41,180.00
SUB-TOTAL SITE PREPARATION ITEMS						\$337,813.50		\$337,268.00		\$337,268.00		\$366,224.50

B. SUBGRADE AND PAVING												
17	221	HYDRATED LIME (SLURRY APPLIED) FOR STABILIZATION (6% BY DRY WEIGHT)	TON	614	\$165.00	\$101,310.00		\$98,240.00	\$160.00	\$98,240.00	\$160.00	\$98,240.00
18	223	FLY ASH FOR STABILIZATION (8% BY DRY WEIGHT)	TON	818	\$73.00	\$61,350.00		\$58,896.00	\$72.00	\$58,896.00	\$77.00	\$62,986.00
19	226(DWGS)	LIME-FLY ASH STABILIZED SUBGRADE, 2 MANIPULATIONS AT 8" DEPTH	SY	30,994	\$2.50	\$77,485.00		\$69,736.50	\$2.25	\$69,736.50	\$3.00	\$92,982.00
20	250	HOT MIX ASPHALTIC CONCRETE BASE COURSE, 8" DEPTH	TON	274	\$87.00	\$23,838.00		\$30,140.00	\$110.00	\$30,140.00	\$100.00	\$27,400.00
21	310	PRIME COAT FOR BASE COURSE (1.30 GAL/SY)	GAL	189	\$1.00	\$189.00		\$945.00	\$5.00	\$945.00	\$5.00	\$945.00
22	340	HMAC - TACK COAT (0.15 GAL/SY)	GAL	95	\$1.00	\$95.00		\$475.00	\$5.00	\$475.00	\$5.00	\$475.00
23	340	HMAC TYPE "D" SURFACE COURSE - 2" THICK	TON	69	\$150.00	\$10,350.00		\$12,075.00	\$175.00	\$12,075.00	\$150.00	\$10,350.00
24	360	REINFORCED CONCRETE PAVEMENT - 8" DEPTH	SY	26,549	\$45.00	\$1,194,705.00		\$1,115,058.00	\$42.00	\$1,115,058.00	\$44.00	\$1,168,156.00
25	360	REINFORCED CONCRETE PAVEMENT, HIGH EARLY STRENGTH - 8" DEPTH	SY	4,450	\$51.50	\$229,175.00		\$226,950.00	\$51.00	\$226,950.00	\$50.00	\$222,500.00
26	360	REINFORCED CONCRETE PAVEMENT, HIGH EARLY STRENGTH - 8" DEPTH FOR DRIVEWAYS	SY	710	\$56.50	\$40,115.00		\$42,600.00	\$60.00	\$42,600.00	\$54.00	\$38,340.00
27	433	CEMENT STABILIZED SAND, 8" THICK	SY	5,620	\$13.25	\$85,705.00		\$73,060.00	\$13.00	\$73,060.00	\$18.00	\$101,160.00
28	521(DWGS)	FLEX BEAM GUARD RAIL, 12 GAUGE WITH MOWING STRIP	LF	534	\$51.00	\$27,234.00		\$23,496.00	\$44.00	\$23,496.00	\$45.00	\$24,030.00
29	522(DWGS)	TURN DOWN TERMINAL SECTION (25' LONG), 12 GAUGE, WITH ANCHOR	EACH	12	\$1,050.00	\$12,600.00		\$15,000.00	\$1,250.00	\$15,000.00	\$900.00	\$10,800.00
30	530	6" CONCRETE CURBS	LF	21,695	\$3.00	\$65,085.00		\$61,830.75	\$2.85	\$61,830.75	\$2.50	\$54,237.50
31	535	ESPLANADES, MEDIANS, AND DIRECTIONAL ISLANDS	SY	264	\$52.00	\$13,728.00		\$13,200.00	\$50.00	\$13,200.00	\$75.00	\$19,800.00
32	536	COLOR CONCRETE MEDIANS (BLACK)	SY	264	\$5.00	\$1,320.00		\$264.00	\$1.00	\$264.00	\$10.00	\$2,640.00
SUB-TOTAL PAVING						\$1,944,284.00		\$1,841,966.25		\$1,841,966.25		\$1,935,041.50

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Unit Price	Total in Figures	Conrad Construction Co., LTD.	Unit Price	Total in Figures	Unit Price	Total in Figures
C. STORM SEWER											
33	421	STRUCTURAL CONCRETE, WINGWALLS	CY	15	\$1,025.00	\$15,375.00		\$1,250.00	\$18,750.00	\$1,500.00	\$22,500.00
34	421	STRUCTURAL CONCRETE, HEADWALLS	CY	20	\$975.00	\$19,500.00		\$1,250.00	\$25,000.00	\$1,500.00	\$30,000.00
35	429	TRENCH SAFETY SYSTEMS, 5' TO 10' DEPTH	LF	6,256	\$1.00	\$6,256.00		\$0.75	\$4,692.00	\$0.15	\$938.40
36	459	TIMBER BENT FOR 48" PIPE	EACH	1	\$1,350.00	\$1,350.00		\$2,500.00	\$2,500.00	\$1,200.00	\$1,200.00
37	460	CORRUGATED PLASTIC PIPE, PRE-COATED (12")	LF	30	\$30.00	\$900.00		\$50.00	\$1,500.00	\$45.00	\$1,350.00
38	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (24")	LF	3,130	\$53.00	\$165,890.00		\$56.50	\$176,845.00	\$46.00	\$143,980.00
39	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (EQUIVALENT 24") ELLIPTICAL 19" X 30"	LF	410	\$137.00	\$56,170.00		\$99.00	\$40,590.00	\$82.00	\$33,620.00
40	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (30")	LF	744	\$75.00	\$55,800.00		\$71.00	\$52,824.00	\$58.00	\$43,152.00
41	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (42")	LF	601	\$114.00	\$68,514.00		\$105.00	\$63,105.00	\$90.00	\$54,090.00
42	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (24")	LF	1,101	\$135.00	\$148,635.00		\$125.00	\$137,625.00	\$110.00	\$121,110.00
43	461	CORRUGATED METAL PIPE-PRE-COATED-GALVANIZED (16 GAUGE) (24")	LF	129	\$60.00	\$7,740.00		\$92.50	\$11,932.50	\$90.00	\$11,610.00
44	461	CORRUGATED METAL PIPE-PRE-COATED-GALVANIZED (16 GAUGE) (30")	LF	133	\$84.00	\$11,172.00		\$95.00	\$12,635.00	\$107.00	\$14,231.00
45	461	CORRUGATED METAL PIPE-PRE-COATED-GALVANIZED (16 GAUGE) (48")	LF	118	\$139.00	\$16,402.00		\$165.00	\$19,470.00	\$160.00	\$18,880.00
46	463	SAFETY END TREATMENT - TYPE II, (6:1) (PD-SPR) 24" RCP	EACH	2	\$1,675.00	\$3,350.00		\$1,725.00	\$3,450.00	\$1,750.00	\$3,500.00
47	467-2288	SAFETY END TREATMENT SET (TY II) (24IN) (RCP) (6:1) (P)	EACH	2	\$1,675.00	\$3,350.00		\$1,725.00	\$3,450.00	\$1,750.00	\$3,500.00
48	471	PRECAST CONCRETE SHALLOW MANHOLE, DEPTH LESS THAN 6 FEET	EACH	16	\$2,100.00	\$33,600.00		\$2,750.00	\$44,000.00	\$2,600.00	\$41,600.00
49	471	PRECAST CONCRETE STANDARD MANHOLE, DEPTH GREATER THAN 6 FEET & LESS THAN 10 FEET	EACH	3	\$3,100.00	\$9,300.00		\$3,300.00	\$9,900.00	\$5,400.00	\$16,200.00
50	471	PRECAST CONCRETE EXTRA DEPTH MANHOLE, DEPTH GREATER THAN 10 FEET	EACH	11	\$4,900.00	\$53,900.00		\$5,350.00	\$58,850.00	\$3,400.00	\$37,400.00
51	472	TYPE "A" INLET, ADDITIONAL DEPTH GREATER THAN 6'	EACH	4	\$2,025.00	\$8,100.00		\$2,400.00	\$9,600.00	\$2,900.00	\$11,600.00
52	472	STANDARD TYPE "A" INLET MODIFIED SQUARE (PRE-CAST OR CAST) GREATER THAN 6'	EACH	7	\$2,550.00	\$17,850.00		\$3,350.00	\$23,450.00	\$4,000.00	\$28,000.00
53	472	STANDARD TYPE "B-B" INLET	EACH	12	\$2,000.00	\$24,000.00		\$2,100.00	\$25,200.00	\$2,300.00	\$27,600.00
54	472	TYPE "B-B" INLET WITH ADDITIONAL DEPTH GREATER THAN 6'	EACH	6	\$2,250.00	\$13,500.00		\$2,650.00	\$15,900.00	\$2,600.00	\$15,600.00
55	472	TYPE "B-B" (MODIFIED) INLET, ADDITIONAL DEPTH GREATER THAN 6'	EACH	6	\$3,500.00	\$21,000.00		\$4,200.00	\$25,200.00	\$3,500.00	\$21,000.00
56	480	REINFORCED CONCRETE BOX, C1433 (ALL DEPTHS) (5' X 3')	LF	174	\$201.00	\$34,974.00		\$170.00	\$29,580.00	\$218.00	\$37,932.00
57	491	REINFORCED CONCRETE SLOPE PAVING (4" THICK)	SY	215	\$68.00	\$14,620.00		\$80.00	\$17,200.00	\$70.00	\$15,050.00
58	491	REINFORCED CONCRETE SLOPE PAVING (5" THICK)	SY	1,492	\$70.00	\$104,440.00		\$81.00	\$120,852.00	\$77.00	\$114,884.00
59	2378	RIPRAP - GRADATION NO. 1 (18" THICK)	SY	110	\$68.00	\$7,480.00		\$75.00	\$8,250.00	\$66.00	\$7,260.00
SUB-TOTAL STORM SEWER						\$923,168.00		\$962,350.50		\$877,787.40	
D. TRAFFIC CONTROL											
60	665	WORK ZONE PAVEMENT MARKINGS 4" WHITE/SOLID (REMOVABLE) APPLIED, REMOVED	LF	934	\$0.60	\$560.40		\$1.00	\$934.00	\$0.65	\$607.10
61	665	WORK ZONE PAVEMENT MARKINGS 8" WHITE/SOLID (REMOVABLE) APPLIED, REMOVED	LF	120	\$1.10	\$132.00		\$2.00	\$240.00	\$1.10	\$132.00
62	665	WORK ZONE PAVEMENT MARKINGS 24" WHITE/SOLID (REMOVABLE) APPLIED, REMOVED	LF	57	\$2.20	\$125.40		\$4.00	\$228.00	\$7.00	\$399.00
63	665	WORK ZONE PAVEMENT MARKINGS 4" YELLOW/SOLID (REMOVABLE) APPLIED, REMOVED	LF	8,716	\$0.60	\$5,229.60		\$0.60	\$5,229.60	\$0.65	\$5,665.40

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Angel Brothers Enterprises, LTD.		Conrad Construction Co., LTD.		Durwood Greene Construction Co.	
					Unit Price	Total in Figures	Unit Price	Total in Figures	Unit Price	Total in Figures
64	665	WORK ZONE PAVEMENT MARKINGS 8" WHITE/DASHED (REMOVABLE) APPLIED, REMOVED (4' OVER 8')	LF	105	\$1.10	\$115.50	\$2.00	\$210.00	\$2.50	\$262.50
65	671	TRAFFIC CONTROL - FURNISH-INSTALL & REMOVE TEMPORARY COMMERCIAL DRIVEWAYS - INSTALL & REMOVE	MONTH	11	\$4,600.00	\$50,600.00	\$1,000.00	\$11,000.00	\$3,500.00	\$38,500.00
66	671	TEMPORARY TRAFFIC SIGNAL AT FM 762 AND WILLIAMS WAY BOULEVARD (RELOCATE SIGNAL HEADS/BAG)	EACH	3	\$450.00	\$1,350.00	\$900.00	\$2,700.00	\$2,500.00	\$7,500.00
67	671	CONSTRUCTING DETOURS FOR TWO-WAY TRAFFIC (8" BLACK BASE) FOR INSTALLING-MAINTAINING & REMOVING	LS	1	\$9,000.00	\$9,000.00	\$7,250.00	\$7,250.00	\$9,000.00	\$9,000.00
68	673	LOW PROFILE CONCRETE BARRIER TYPE 1 (INSTALL)	SY	206	\$55.00	\$11,330.00	\$52.50	\$10,815.00	\$80.00	\$16,480.00
69	696	LOW PROFILE CONCRETE BARRIER TYPE 1 (RELOCATE)	LF	805	\$10.00	\$8,050.00	\$18.00	\$14,490.00	\$30.00	\$24,150.00
70	696	LOW PROFILE CONCRETE BARRIER TYPE 1 (RELOCATE)	LF	2,474	\$6.00	\$14,844.00	\$5.00	\$12,370.00	\$10.00	\$24,740.00
71	696	LOW PROFILE CONCRETE BARRIER TYPE 1 (RELOCATE)	LF	805	\$10.00	\$8,050.00	\$15.00	\$12,075.00	\$12.50	\$10,062.50
72	696	LOW PROFILE CONCRETE BARRIER TYPE 2 (INSTALL)	LF	80	\$10.00	\$800.00	\$18.00	\$1,440.00	\$55.00	\$4,400.00
73	696	LOW PROFILE CONCRETE BARRIER TYPE 2 (RELOCATE)	LF	140	\$6.00	\$840.00	\$5.00	\$700.00	\$10.00	\$1,400.00
74	696	LOW PROFILE CONCRETE BARRIER TYPE 2 (RELOCATE)	LF	80	\$10.00	\$800.00	\$15.00	\$1,200.00	\$12.50	\$1,000.00
SUB-TOTAL TRAFFIC CONTROL						\$111,826.90		\$80,881.60		\$144,298.50

E. SIGNING AND PAVEMENT MARKING										
75	448	SOLID CAST ALUMINIUM BRIDGE PLAQUE	EACH	1	\$1,100.00	\$1,100.00	\$1,500.00	\$1,500.00	\$1,200.00	\$1,200.00
76	624	ALUMINIUM SIGNS (GROUND MOUNTED)	EACH	58	\$350.00	\$20,300.00	\$240.00	\$13,920.00	\$800.00	\$46,400.00
77	658	FURNISH AND INSTALL OBJECT MARKER (TEXAS MUTCD: "OM-3R/L")	EACH	2	\$88.00	\$176.00	\$200.00	\$400.00	\$300.00	\$600.00
78	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 4" WHITE/SOLID	LF	397	\$0.50	\$198.50	\$1.00	\$397.00	\$0.65	\$258.05
79	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 8" WHITE/SOLID	LF	922	\$1.00	\$922.00	\$1.50	\$1,383.00	\$1.20	\$1,106.40
80	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 12" WHITE/SOLID	LF	584	\$2.50	\$1,460.00	\$2.50	\$1,460.00	\$3.00	\$1,752.00
81	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 24" WHITE/SOLID	LF	292	\$4.50	\$1,314.00	\$6.50	\$1,898.00	\$7.00	\$2,044.00
82	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 4" WHITE/DASHED (15' OVER 40')	LF	8,395	\$0.50	\$4,197.50	\$0.70	\$5,876.50	\$0.65	\$5,456.75
83	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) SINGLE ARROW-LEFT	EACH	8	\$120.00	\$960.00	\$120.00	\$960.00	\$150.00	\$1,200.00
84	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) RIGHT-STRAIGHT COMBINATION ARROWS	EACH	2	\$120.00	\$240.00	\$200.00	\$400.00	\$150.00	\$300.00
85	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) WORD "ONLY"	EACH	5	\$150.00	\$750.00	\$120.00	\$600.00	\$200.00	\$1,000.00
86	660	REFLECTORIZED PAVEMENT MARKINGS TYPE II, 12" YELLOW/SOLID, FOR 6" CURB PER DETAIL "D"	LF	2,830	\$1.10	\$3,113.00	\$1.50	\$4,245.00	\$1.50	\$4,245.00
87	663	REFLECTORIZED PAVEMENT MARKERS TYPE I-C	EACH	296	\$4.50	\$1,332.00	\$4.50	\$1,332.00	\$5.00	\$1,480.00
88	663	REFLECTORIZED PAVEMENT MARKERS TYPE II-C-R	EACH	195	\$4.50	\$877.50	\$4.50	\$877.50	\$5.00	\$975.00
89	663	NON-REFLECTORIZED CERAMIC TRAFFIC BUTTONS (WHITE)	EACH	201	\$3.50	\$703.50	\$3.50	\$703.50	\$4.75	\$954.75
SUB-TOTAL SIGNING AND PAVEMENT MARKINGS						\$37,644.00		\$35,952.50		\$68,971.95

F. PERMANENT TRAFFIC SIGNALS (TXDOT SPECIFICATIONS)										
90	416-2032	DRILLED SHAFT FOUNDATION (TRF SIG. POLE)	LF	30	\$400.00	\$12,000.00	\$450.00	\$13,500.00	\$400.00	\$12,000.00
91	618-2052	CONDUIT (PVC) (SCHD 80) (2")	LF	150	\$7.00	\$1,050.00	\$16.50	\$2,475.00	\$7.00	\$1,050.00
92	620-2009	ELECTRICAL CONDUCTORS (NO. 6) BARE	LF	145	\$2.00	\$290.00	\$2.50	\$362.50	\$2.00	\$290.00
93	621-2004	TRAY CABLE (4 CONR) (12 AWG)	LF	400	\$2.40	\$960.00	\$2.50	\$1,000.00	\$2.25	\$900.00
94	624-2014	GROUND BOXES TY D (162922) W/ APRON	EACH	1	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00
95	625-2001	ZINC-COATED STEEL WIRE STRAND (5/16 IN)	LF	400	\$4.00	\$1,600.00	\$6.00	\$2,400.00	\$4.00	\$1,600.00

Item No.	Spec. No.	Item Description	Unit Measure	Unit Price	Total in Figures	Conrad Construction Co., LTD.	Durwood Greene Construction Co.
96	625-2003	ZINC-COATED STEEL WIRE STRAND (1/4 IN)	LF	\$4.00	\$1,600.00	\$5.00	\$3.75
97	625-2004	ZINC-COATED STEEL WIRE STRAND (3/8 IN)	LF	\$4.00	\$1,600.00	\$6.00	\$4.00
98	644-2100	INSTALL SMALL ROADSIDE SIGN ASSEMBLIES TY 10BWG (1) SA (P)	EACH	\$750.00	\$1,500.00	\$600.00	\$700.00
99	644-2100	"NO PEDESTRIAN CROSSING" (R9-3) (12" X 18)	EACH	\$360.00	\$720.00	\$300.00	\$400.00
100	644-2100	"NO PEDESTRIAN CROSSING" (R9-3A) (18" X 18")	EACH	\$360.00	\$720.00	\$300.00	\$400.00
101	666-2048	RETROREFLECTORIZED PAVEMENT MARKINGS TY 1 (W) 24" (SLD) (100 MIL)	LF	\$4.50	\$562.50	\$6.50	\$7.00
102	666-2195	PAVEMENT SEALER 24"	LF	\$0.50	\$62.50	\$2.00	\$2.00
103	678-2005	PAVEMENT SURFACE PREPARATION FOR MARKING (BLAST CLN) (24")	LF	\$0.30	\$37.50	\$2.00	\$1.50
104	680-2002	INSTALL HIGHWAY TRAFFIC SIGNALS (ISOLATED)	EACH	\$16,000.00	\$16,000.00	\$22,150.00	\$15,000.00
105	680-2002	POLE 34' STEEL STRAIN	EACH	\$7,300.00	\$14,600.00	\$5,500.00	\$7,000.00
106	680-2002	RDWY LIGHT ON TRAF SIGNAL POLE (250 WATT H.P.S.)	EACH	\$830.00	\$830.00	\$1,100.00	\$950.00
107	680-2002	MAST ARM, 10' LUMINAIRE	EACH	\$1,250.00	\$2,500.00	\$2,200.00	\$1,200.00
108	684-2009	TRAFFIC SIGNAL CABLES (TY A) (12 AWG) (4 COND)	LF	\$2.00	\$540.00	\$2.25	\$2.30
109	684-2012	TRAFFIC SIGNAL CABLES (TY A) (12 AWG) (7 COND)	LF	\$2.50	\$2,625.00	\$4.00	\$2.50
110	6266-2005	VIVDS COMMUNICATION CABLE (COAXIAL)	LF	\$2.50	\$3,275.00	\$2.25	\$2.50
111	6266-2005	3/C #16 - VIVDS POWER CABLE	LF	\$2.50	\$3,275.00	\$2.25	\$2.50
SUB-TOTAL PERMANENT TRAFFIC SIGNALS					\$67,547.50	\$78,402.50	\$66,598.50

G. BRIDGE STRUCTURE (TXDOT SPECIFICATIONS)							
112	400-6005	CEMENT STABILIZED BACKFILL	CY	\$84.50	\$15,210.00	\$75.00	\$13,500.00
113	416-6001	DRILLED SHAFT FOUNDATIONS (18-INCH)	LF	\$61.00	\$6,832.00	\$80.00	\$100.00
114	416-6004	DRILLED SHAFT FOUNDATIONS (36-INCH)	LF	\$188.00	\$326,368.00	\$265.00	\$468,720.00
115	420-6013	CONCRETE STRUCTURES (CLASS C CONCRETE) - ABUTMENTS	CY	\$730.00	\$62,780.00	\$900.00	\$1,000.00
116	420-4025	CONCRETE STRUCTURES (CLASS C CONCRETE) - BENTS	CY	\$900.00	\$105,300.00	\$900.00	\$1,000.00
117	422-6001	REINFORCED CONCRETE SLAB	SF	\$17.50	\$260,820.00	\$14.00	\$13,000.00
118	422-6011	BRIDGE MEDIAN	SF	\$18,648.00	\$18,648.00	\$7.50	\$8.00
119	422-6013	BRIDGE SIDEWALK	SF	\$11.25	\$49,950.00	\$7.50	\$8.00
120	422-6015	BRIDGE APPROACH SLAB	CY	\$500.00	\$121,000.00	\$425.00	\$400.00
121	425-6036	PRECAST PRESTRESSED CONCRETE STRUCTURAL MEMBERS (PRESTRESSED CONCRETE GIRDER, TX34)	LF	\$150.00	\$257,250.00	\$190.00	\$325,850.00
122	442-6007	METAL FOR STRUCTURES (STRUCTURAL STEEL) (MISC NON BRIDGE)	LB	\$7.50	\$4,365.00	\$16.00	\$15.00
123	450-6032	RAILING (TY C223)	LF	\$137.00	\$67,404.00	\$127.00	\$125.00
124	454-6001	BRIDGE EXPANSION JOINTS, SEALED EXPANSION JOINT (4-INCH) (SEJ-A)	LF	\$108.00	\$14,040.00	\$90.00	\$90.00
SUB-TOTAL BRIDGE ITEMS					\$1,309,967.00	\$1,432,672.00	\$1,445,380.00

H. STORM WATER POLLUTION PREVENTION							
125	162	SODDING FOR EROSION CONTROL AND STABILIZATION	LF	\$0.50	\$5,929.00	\$1.50	\$17,787.00
126	165	HYDRO-MULCH SEEDING	ACRE	\$1,500.00	\$7,500.00	\$1,300.00	\$7,500.00
127	713	REINFORCED FILTER FABRIC BARRIER	LF	\$1.50	\$8,280.00	\$1.50	\$16,560.00
128	719	INLET PROTECTION BARRIER (STAGE I, WITH FIBER ROLLS)	EACH	\$80.00	\$2,480.00	\$95.00	\$1,860.00
129	724	STABILIZED CONSTRUCTION ACCESS, TYPE 1 ROCK	SY	\$23.00	\$5,550.00	\$17.50	\$4,440.00
130	730	CONCRETE TRUCK WASHOUT STRUCTURES	LS	\$1,800.00	\$1,800.00	\$500.00	\$1,500.00
131	741	INLET PROTECTION BARRIER (FOR STAGES II INLETS, GRAVEL BAGS)	EACH	\$50.00	\$1,200.00	\$75.00	\$1,440.00
132	750	ROCK FILTER DAM (TYPE 3)	LF	\$34.00	\$2,720.00	\$30.00	\$8,000.00
133	HCFC0 2361	REINFORCED SLIT FENCE	LF	\$1.50	\$1,020.00	\$1.50	\$2,040.00
134	751(DWGS)	SWPPP INSPECTION AND MAINTENANCE (MIN. BID - \$6,000/MONTH)	MONTH	\$6,000.00	\$66,000.00	\$6,000.00	\$66,000.00

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Unit Price	Total in Figures	Conrad Construction Co., LTD.	Unit Price	Total in Figures	Durwood Greene Construction Co.
135	700 (PROJECT MANUAL)	TPDES GENERAL PERMIT NO. TXR 150000, NOTICE OF INTENT (NOI) APPLICATION FEES (CONTRACTOR'S NOI FEE & FORT BEND COUNTY'S NOI FEE, EACH FEE SHALL BE SET PRICE OF \$325.00)	EACH	2	\$325.00	\$650.00		\$325.00	\$650.00	\$650.00
SUB-TOTAL OF STORM WATER POLLUTION PREVENTION ITEMS						\$103,129.00			\$111,767.00	\$127,777.00

SUB-TOTAL OF STORM WATER POLLUTION PREVENTION ITEMS

I. EXTRA WORK										
136	430	SEAL SLAB, CLASS D CONCRETE, 7" THICKNESS (MIN. BID \$25/SY)	SY	200	\$25.00	\$5,000.00		\$25.00	\$5,000.00	\$5,000.00
137	436	WELL POINTING SYSTEM (MIN. BID \$15/LF)	LF	500	\$15.00	\$7,500.00		\$15.00	\$7,500.00	\$7,500.00
138	552-6001	5-STRAND BARBED WIRE FENCE	LF	1,500	\$5.00	\$7,500.00		\$6.50	\$9,750.00	\$11,250.00
139	552-6002	5-STRAND SLICK WIRE FENCE	LF	1,000	\$5.00	\$5,000.00		\$6.00	\$6,000.00	\$7,000.00
140	552-6006	GALVANIZED TUBE GATES, TY 2 GATE	EA	2	\$450.00	\$900.00		\$550.00	\$1,100.00	\$1,000.00
141	559	CONSTRUCTION SAFETY FENCE	LF	1,000	\$1.50	\$1,500.00		\$2.00	\$2,000.00	\$2,750.00
142	0560 (SP 560)	MOWING PROJECT SITE	CYCLE	4	\$300.00	\$1,200.00		\$250.00	\$1,000.00	\$2,000.00
143	672	UNIFORM PEACE OFFICER (MINIMUM: \$25/HR)	HOURL	200	\$25.00	\$5,000.00		\$25.00	\$5,000.00	\$8,000.00
144	SS8006	ELECTRICAL ROSER RELOCATION FOR PROPERTY OWNER (CUSTOMER OWNED)-CONNECTION TO CENTERPOINT ENERGY ELECTRICAL SERVICE - SINGLE PHASE, 120 VOLT 3-WIRE ELECTRICAL SERVICES	LF	200	\$1.00	\$200.00		\$1.00	\$200.00	\$7,000.00
145	SS8006	ELECTRICAL ROSER RELOCATION FOR PROPERTY OWNER (CUSTOMER OWNED)-CONNECTION TO CENTERPOINT ENERGY ELECTRICAL SERVICE - THREE PHASE (COMMERCIAL CUSTOMER) ELECTRICAL SERVICES	LF	200	\$1.00	\$200.00		\$1.00	\$200.00	\$8,800.00
SUB-TOTAL EXTRA WORK ITEMS						\$34,000.00			\$37,750.00	\$62,300.00

SUB-TOTAL EXTRA WORK ITEMS

A. SITE PREPARATION										
						\$337,813.50	Angel Brothers Enterprises, LTD.		\$377,268.00	Durwood Greene Construction Co.
B. SUBGRADE AND PAVING						\$1,944,284.00			\$1,841,966.25	\$1,935,041.50
C. STORM SEWER						\$923,168.00			\$962,350.50	\$877,787.40
D. TRAFFIC CONTROL						\$111,826.90			\$80,881.60	\$144,298.50
E. SIGNING AND PAVEMENT MARKING						\$37,644.00			\$35,952.50	\$68,971.95
F. PERMANENT TRAFFIC SIGNALS (TXDOT SPECIFICATIONS)						\$67,547.50			\$78,402.50	\$66,598.50
G. BRIDGE STRUCTURE (TXDOT SPECIFICATIONS)						\$1,309,967.00			\$1,432,672.00	\$1,445,380.00
H. STORM WATER POLLUTION PREVENTION						\$103,129.00			\$111,767.00	\$127,777.00
I. EXTRA WORK						\$34,000.00			\$37,750.00	\$62,300.00
TOTAL BID PRICE (SUM OF ITEMS A THROUGH I)						\$4,869,379.90			\$4,959,010.35	\$5,094,379.35

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Unit Price	Total in Figures	Mar-Con Services, LLC	Unit Price	Total in Figures	John Reed and Company LLC	Unit Price	Total in Figures
A. SITE PREPARATION												
1	100(DWG)	FORT BEND COUNTY PROJECT SIGN	EACH	2	\$535.00	\$1,070.00		\$678.00	\$1,356.00		\$495.00	\$990.00
2	102(DWGS)	CLEARING AND GRUBBING (INCLUDING OUTFALLS)	LS	1	\$183,487.50	\$183,487.50		\$445,232.40	\$445,232.40		\$100,000.00	\$100,000.00
3	104	REMOVING OLD CONCRETE PAVEMENT	SY	5,440	\$2.14	\$11,641.60		\$2.70	\$14,688.00		\$2.00	\$10,880.00
4	104	REMOVING OLD CONCRETE PAVEMENT; 6" REINFORCED CONCRETE CURB	LF	2,800	\$1.07	\$2,996.00		\$0.90	\$2,520.00		\$1.00	\$2,800.00
5	110(SP110)	ROADWAY EXCAVATION (INCLUDING 3" STRIPING)	CY	15,987	\$7.49	\$119,742.63		\$7.30	\$116,705.10		\$10.00	\$159,870.00
6	465	REMOVE AND DISPOSE OF EXISTING, CONCRETE OR METAL PIPE (18" - 36")	LF	723	\$12.84	\$9,283.32		\$13.20	\$9,543.60		\$5.00	\$3,615.00
7	465	REMOVE AND DISPOSE OF EXISTING PLASTIC PIPE (ALL TYPE AND ALL SIZES)	LF	60	\$10.70	\$642.00		\$13.20	\$792.00		\$5.00	\$300.00
8	495	REMOVING OLD STRUCTURES - INLETS (ALL DEPTHS)	EACH	3	\$535.00	\$1,605.00		\$440.70	\$1,322.10		\$400.00	\$1,200.00
9	495	REMOVING OLD STRUCTURES - SAFETY END TREATMENTS	EACH	2	\$535.00	\$1,070.00		\$440.70	\$881.40		\$100.00	\$200.00
10	495	REMOVING OLD STRUCTURES - HEADWALLS INCLUDING WINGWALLS	EACH	7	\$2,675.00	\$18,725.00		\$571.60	\$4,001.20		\$500.00	\$3,500.00
11	495	REMOVING FLEX BEAM GUARD RAIL	LF	256	\$8.56	\$2,191.36		\$5.50	\$1,408.00		\$3.00	\$768.00
12	495	REMOVING TURN DOWN SECTION	EACH	2	\$695.50	\$1,391.00		\$235.80	\$471.60		\$200.00	\$400.00
13	495	REMOVING OLD STRUCTURE - WOODEN BRIDGE	EACH	1	\$5,350.00	\$5,350.00		\$19,775.00	\$19,775.00		\$50,000.00	\$50,000.00
14	500	REMOVE AND RELOCATE TRAFFIC SIGNS, MAIL BOXES, ROADWAY SIGNS	LS	1	\$1,605.00	\$1,605.00		\$804.10	\$804.10		\$5,000.00	\$5,000.00
15	500	REMOVE AND RELOCATE TRAFFIC SIGNAL ITEMS (AS REQUIRED)	LS	1	\$5,350.00	\$5,350.00		\$5,361.90	\$5,361.90		\$5,000.00	\$5,000.00
16	540	REMOVE AND DISPOSE OF EXISTING ASPHALTIC SURFACE AND BASE MATERIAL	SY	4,118	\$3.75	\$15,442.50		\$2.00	\$8,236.00		\$3.00	\$12,354.00
SUB-TOTAL SITE PREPARATION ITEMS						\$381,592.91			\$633,098.40			\$356,877.00

B. SUBGRADE AND PAVING												
17	221	HYDRATED LIME (SLURRY APPLIED) FOR STABILIZATION (6% BY DRY WEIGHT)			TON	614	\$176.55	\$108,401.70	\$172.90	\$106,160.60	\$190.00	\$116,660.00
18	223	FLY ASH FOR STABILIZATION (8% BY DRY WEIGHT)			TON	818	\$90.95	\$74,397.10	\$82.70	\$67,648.60	\$110.00	\$89,980.00
19	226(DWGS)	LIME-FLY ASH STABILIZED SUBGRADE, 2 MANIPULATIONS AT 8" DEPTH			SY	30,994	\$3.42	\$105,999.48	\$2.10	\$65,087.40	\$3.20	\$99,180.80
20	250	HOT MIX ASPHALTIC CONCRETE BASE COURSE, 8" DEPTH			TON	274	\$107.00	\$29,318.00	\$87.30	\$23,920.20	\$80.00	\$21,920.00
21	310	PRIME COAT FOR BASE COURSE (1.30 GAL/SY)			GAL	189	\$5.35	\$1,011.15	\$2.80	\$529.20	\$10.00	\$1,890.00
22	340	HMAC - TACK COAT (0.15 GAL/SY)			GAL	95	\$10.70	\$1,016.50	\$2.80	\$266.00	\$5.00	\$475.00
23	340	HMAC TYPE "D" SURFACE COURSE - 2" THICK			TON	69	\$128.40	\$8,859.60	\$235.20	\$16,228.80	\$120.00	\$8,280.00
24	360	REINFORCED CONCRETE PAVEMENT - 8" DEPTH			SY	26,549	\$41.73	\$1,107,889.77	\$44.90	\$1,192,050.10	\$50.00	\$1,327,450.00
25	360	REINFORCED CONCRETE PAVEMENT, HIGH EARLY STRENGTH - 8" DEPTH			SY	4,450	\$58.85	\$261,882.50	\$49.30	\$219,385.00	\$56.00	\$249,200.00
26	360	REINFORCED CONCRETE PAVEMENT, HIGH EARLY STRENGTH - 8" DEPTH FOR DRIVEWAYS			SY	710	\$64.20	\$45,582.00	\$60.40	\$42,884.00	\$62.00	\$44,020.00
27	433	CEMENT STABILIZED SAND, 8" THICK			SY	5,620	\$10.54	\$59,234.80	\$11.80	\$66,316.00	\$12.00	\$67,440.00
28	521(DWGS)	FLEX BEAM GUARD RAIL, 12 GAUGE WITH MOWING STRIP			LF	534	\$41.73	\$22,283.82	\$58.00	\$30,972.00	\$35.00	\$18,690.00
29	522(DWGS)	TURN DOWN TERMINAL SECTION (25' LONG), 12 GAUGE, WITH ANCHOR			EACH	12	\$1,230.50	\$14,766.00	\$2,069.40	\$24,832.80	\$1,250.00	\$15,000.00
30	530	6" CONCRETE CURBS			LF	21,695	\$2.62	\$56,840.90	\$2.50	\$54,237.50	\$3.00	\$65,085.00
31	535	ESPLANADES, MEDIANS, AND DIRECTIONAL ISLANDS			SY	264	\$48.15	\$12,711.60	\$48.50	\$12,804.00	\$80.00	\$21,120.00
32	536	COLORED CONCRETE MEDIANS (BLACK)			SY	264	\$10.70	\$2,824.80	\$1.10	\$290.40	\$80.00	\$21,120.00
SUB-TOTAL PAVING							\$1,913,019.72	\$1,923,612.60	\$2,167,510.80			

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Unit Price	Total in Figures	Mar-Con Services, LLC	Unit Price	Total in Figures	John Reed and Company LLC	Unit Price	Total in Figures
----------	-----------	------------------	--------------	---------------	------------	------------------	-----------------------	------------	------------------	---------------------------	------------	------------------

C. STORM SEWER												
33	421	STRUCTURAL CONCRETE, WINGWALLS	CY	15	\$1,284.00	\$19,260.00		\$717.60	\$10,764.00		\$500.00	\$7,500.00
34	421	STRUCTURAL CONCRETE, HEADWALLS	CY	20	\$1,177.00	\$23,540.00		\$717.60	\$14,352.00		\$500.00	\$10,000.00
35	429	TRENCH SAFETY SYSTEMS, 5' TO 10' DEPTH	LF	6,256	\$0.11	\$688.16		\$1.00	\$6,256.00		\$1.00	\$6,256.00
36	459	TIMBER BENT FOR 48" PIPE	EACH	1	\$1,070.00	\$1,070.00		\$2,090.30	\$2,090.30		\$1,400.00	\$1,400.00
37	460	CORRUGATED PLASTIC PIPE, PRE-COATED (12")	LF	30	\$35.31	\$1,059.30		\$50.80	\$1,524.00		\$35.00	\$1,050.00
38	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (24")	LF	3,130	\$35.41	\$110,833.30		\$60.10	\$189,113.00		\$60.00	\$187,800.00
39	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (EQUIVALENT 24") ELLIPTICAL 19" X 30"	LF	410	\$80.20	\$32,882.00		\$101.70	\$41,697.00		\$110.00	\$45,100.00
40	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (30")	LF	744	\$47.18	\$35,101.92		\$83.40	\$62,049.60		\$75.00	\$55,800.00
41	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (42")	LF	601	\$76.09	\$45,730.09		\$118.40	\$71,158.40		\$130.00	\$78,130.00
42	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (42")	LF	1,101	\$95.52	\$105,167.52		\$157.00	\$172,857.00		\$160.00	\$176,160.00
43	461	CORRUGATED METAL PIPE-PRE-COATED-GALVANIZED (16 GAUGE) (24")	LF	129	\$48.15	\$6,211.35		\$83.40	\$10,758.60		\$45.00	\$5,805.00
44	461	CORRUGATED METAL PIPE-PRE-COATED-GALVANIZED (16 GAUGE) (30")	LF	133	\$58.85	\$7,827.05		\$91.70	\$12,196.10		\$50.00	\$6,650.00
45	461	CORRUGATED METAL PIPE-PRE-COATED-GALVANIZED (16 GAUGE) (48")	LF	118	\$96.30	\$11,363.40		\$207.10	\$24,437.80		\$75.00	\$8,850.00
46	463	SAFETY END TREATMENT - TYPE II, (6:1) (PD-SPR) 24" RCP	EACH	2	\$2,675.00	\$5,350.00		\$2,040.90	\$4,081.80		\$1,200.00	\$2,400.00
47	467-2288	SAFETY END TREATMENT SET (TY II) (24IN) (RCP) (6:1) (P)	EACH	2	\$1,765.50	\$3,531.00		\$2,040.90	\$4,081.80		\$1,000.00	\$2,000.00
48	471	PRECAST CONCRETE SHALLOW MANHOLE, DEPTH LESS THAN 6 FEET	EACH	16	\$2,675.00	\$42,800.00		\$2,292.40	\$36,678.40		\$3,000.00	\$48,000.00
49	471	PRECAST CONCRETE STANDARD MANHOLE, DEPTH GREATER THAN 6 FEET & LESS THAN 10 FEET	EACH	3	\$3,103.00	\$9,309.00		\$3,095.30	\$9,285.90		\$3,500.00	\$10,500.00
50	471	PRECAST CONCRETE EXTRA DEPTH MANHOLE, DEPTH GREATER THAN 10 FEET	EACH	11	\$3,745.00	\$41,195.00		\$5,866.10	\$64,527.10		\$4,500.00	\$49,500.00
51	472	TYPE "A" INLET, ADDITIONAL DEPTH GREATER THAN 6'	EACH	4	\$1,765.50	\$7,062.00		\$2,646.70	\$10,586.80		\$2,000.00	\$8,000.00
52	472	STANDARD TYPE "A" INLET MODIFIED SQUARE (PRE-CAST OR CAST) GREATER THAN 6'	EACH	7	\$2,568.00	\$17,976.00		\$2,248.50	\$15,739.50		\$2,600.00	\$18,200.00
53	472	STANDARD TYPE "B-B" INLET	EACH	12	\$1,979.50	\$23,754.00		\$2,211.70	\$26,540.40		\$2,000.00	\$24,000.00
54	472	TYPE "B-B" INLET WITH ADDITIONAL DEPTH GREATER THAN 6'	EACH	6	\$2,300.50	\$13,803.00		\$2,590.20	\$15,541.20		\$2,500.00	\$15,000.00
55	472	TYPE "B-B" (MODIFIED) INLET, ADDITIONAL DEPTH GREATER THAN 6'	EACH	6	\$2,782.00	\$16,692.00		\$3,340.00	\$20,040.00		\$2,600.00	\$15,600.00
56	480	REINFORCED CONCRETE BOX, C1433 (ALL DEPTHS) (5' X 3')	LF	174	\$140.74	\$24,488.76		\$214.00	\$37,236.00		\$200.00	\$34,800.00
57	491	REINFORCED CONCRETE SLOPE PAVING (4" THICK)	SY	215	\$69.55	\$14,953.25		\$79.30	\$17,049.50		\$70.00	\$15,050.00
58	491	REINFORCED CONCRETE SLOPE PAVING (5" THICK)	SY	1,492	\$73.83	\$110,154.36		\$54.70	\$81,612.40		\$75.00	\$111,900.00
59	2378	RIPRAP - GRADATION NO. 1 (18" THICK)	SY	110	\$53.50	\$5,885.00		\$58.20	\$6,402.00		\$60.00	\$6,600.00
SUB-TOTAL STORM SEWER						\$737,687.46			\$967,656.60			\$952,051.00

D. TRAFFIC CONTROL												
60	665	WORK ZONE PAVEMENT MARKINGS 4" WHITE/SOLID (REMOVABLE) APPLIED, REMOVED	LF	934	\$0.64	\$597.76		\$0.70	\$653.80		\$0.60	\$560.40
61	665	WORK ZONE PAVEMENT MARKINGS 8" WHITE/SOLID (REMOVABLE) APPLIED, REMOVED	LF	120	\$1.61	\$193.20		\$1.70	\$204.00		\$1.50	\$180.00
62	665	WORK ZONE PAVEMENT MARKINGS 24" WHITE/SOLID (REMOVABLE) APPLIED, REMOVED	LF	57	\$3.75	\$213.75		\$4.00	\$228.00		\$3.50	\$199.50
63	665	WORK ZONE PAVEMENT MARKINGS 4" YELLOW/SOLID (REMOVABLE) APPLIED, REMOVED	LF	8,716	\$0.64	\$5,578.24		\$0.60	\$5,229.60		\$0.51	\$4,445.16

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Rodriguez Construction Group LLC		Mar-Con Services, LLC		John Reed and Company LLC	
					Unit Price	Total in Figures	Unit Price	Total in Figures	Unit Price	Total in Figures
64	665	WORK ZONE PAVEMENT MARKINGS 8" WHITE/DASHED (REMOVABLE) APPLIED, REMOVED (4 OVER 8)	LF	105	\$2.14	\$224.70	\$2.30	\$241.50	\$2.00	\$210.00
65	671	TRAFFIC CONTROL - FURNISH-INSTALL & REMOVE	MONTH	11	\$2,407.50	\$26,482.50	\$1,759.20	\$19,351.20	\$2,000.00	\$22,000.00
66	671	TEMPORARY COMMERCIAL DRIVEWAYS - INSTALL & REMOVE	EACH	3	\$3,210.00	\$9,630.00	\$722.70	\$2,168.10	\$4,000.00	\$12,000.00
67	671	TEMPORARY TRAFFIC SIGNAL AT FM 762 AND WILLIAMS WAY BOULEVARD (RELOCATE SIGNAL HEADS/BAG)	LS	1	\$5,350.00	\$5,350.00	\$28,363.60	\$28,363.60	\$30,000.00	\$30,000.00
68	673	CONSTRUCTING DETOURS FOR TWO-WAY TRAFFIC (8" BLACK BASE) FOR INSTALLING-MAINTAINING & REMOVING	SY	206	\$58.85	\$12,123.10	\$47.10	\$9,702.60	\$30.00	\$6,180.00
69	696	LOW PROFILE CONCRETE BARRIER TYPE 1 (INSTALL)	LF	805	\$53.30	\$43,067.50	\$15.80	\$12,719.00	\$9.00	\$7,245.00
70	696	LOW PROFILE CONCRETE BARRIER TYPE 1 (RELOCATE)	LF	2,474	\$5.35	\$13,235.90	\$4.30	\$10,638.20	\$4.00	\$9,896.00
71	696	LOW PROFILE CONCRETE BARRIER TYPE 1 (REMOVE)	LF	805	\$10.70	\$8,613.50	\$13.00	\$10,465.00	\$9.00	\$7,245.00
72	696	LOW PROFILE CONCRETE BARRIER TYPE 2 (INSTALL)	LF	80	\$53.50	\$4,280.00	\$16.10	\$1,288.00	\$9.00	\$720.00
73	696	LOW PROFILE CONCRETE BARRIER TYPE 2 (RELOCATE)	LF	140	\$5.35	\$749.00	\$4.20	\$588.00	\$1.00	\$140.00
74	696	LOW PROFILE CONCRETE BARRIER TYPE 2 (REMOVE)	LF	80	\$10.70	\$856.00	\$13.30	\$1,064.00	\$9.00	\$720.00
SUB-TOTAL TRAFFIC CONTROL						\$131,195.15		\$102,904.60		\$101,741.06

E. SIGNING AND PAVEMENT MARKING										
75	448	SOLID CAST ALUMINIUM BRIDGE PLAQUE	EACH	1	\$1,605.00	\$1,605.00	\$1,983.40	\$1,983.40	\$3,000.00	\$3,000.00
76	624	ALUMINIUM SIGNS (GROUND MOUNTED)	EACH	58	\$235.40	\$13,653.20	\$248.60	\$14,418.80	\$220.00	\$12,760.00
77	658	FURNISH AND INSTALL OBJECT MARKER (TEXAS MUTCD: "OM-3R/L")	EACH	2	\$141.24	\$282.48	\$149.20	\$298.40	\$132.00	\$264.00
78	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 4" WHITE/SOLID	LF	397	\$0.64	\$254.08	\$0.70	\$277.90	\$0.58	\$230.26
79	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 8" WHITE/SOLID	LF	922	\$1.12	\$1,032.64	\$1.20	\$1,106.40	\$1.05	\$968.10
80	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 12" WHITE/SOLID	LF	584	\$2.30	\$1,343.20	\$2.40	\$1,401.60	\$2.15	\$1,255.60
81	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 24" WHITE/SOLID	LF	292	\$4.82	\$1,407.44	\$5.10	\$1,489.20	\$4.50	\$1,314.00
82	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 4" WHITE/DASHED (15' OVER 40')	LF	8,395	\$0.70	\$5,876.50	\$0.70	\$5,876.50	\$0.62	\$5,204.90
83	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) SINGLE ARROW-LEFT	EACH	8	\$160.50	\$1,284.00	\$130.00	\$1,040.00	\$115.00	\$920.00
84	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) RIGHT-STRAIGHT COMBINATION ARROWS	EACH	2	\$160.50	\$321.00	\$130.00	\$260.00	\$115.00	\$230.00
85	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) WORD "ONLY"	EACH	5	\$149.80	\$749.00	\$124.30	\$621.50	\$110.00	\$550.00
86	660	REFLECTORIZED PAVEMENT MARKINGS TYPE II, 12" YELLOW/SOLID, FOR 6" CURB PER DETAIL "D"	LF	2,830	\$1.07	\$3,028.10	\$0.90	\$2,547.00	\$0.80	\$2,264.00
87	663	REFLECTORIZED PAVEMENT MARKERS TYPE I-C	EACH	296	\$3.21	\$950.16	\$3.10	\$917.60	\$2.75	\$814.00
88	663	REFLECTORIZED PAVEMENT MARKERS TYPE II-C-R	EACH	195	\$3.21	\$625.95	\$3.10	\$604.50	\$2.75	\$536.25
89	663	NON-REFLECTORIZED CERAMIC TRAFFIC BUTTONS (WHITE)	EACH	201	\$2.68	\$538.68	\$2.50	\$502.50	\$2.25	\$452.25
SUB-TOTAL SIGNING AND PAVEMENT MARKINGS						\$32,951.43		\$33,345.30		\$30,763.36

F. PERMANENT TRAFFIC SIGNALS (TXDOT SPECIFICATIONS)										
90	416-2032	DRILLED SHAFT FOUNDATION (TRF SIG. POLE)	LF	30	\$420.00	\$12,600.00	\$410.60	\$12,318.00	\$250.00	\$7,500.00
91	618-2052	CONDUIT (PVC) (SCHD 80) (2")	LF	150	\$15.75	\$2,362.50	\$7.30	\$1,095.00	\$10.00	\$1,500.00
92	620-2009	ELECTRICAL CONDUCTORS (NO. 6) BARE	LF	145	\$2.10	\$304.50	\$2.20	\$319.00	\$4.00	\$580.00
93	621-2004	TRAY CABLE (4 CONR) (12 AWG)	LF	400	\$2.10	\$840.00	\$2.40	\$960.00	\$4.00	\$1,600.00
94	624-2014	GROUND BOXES TY D (162922) W/ APRON	EACH	1	\$1,575.00	\$1,575.00	\$1,248.70	\$1,248.70	\$2,000.00	\$2,000.00
95	625-2001	ZINC-COATED STEEL WIRE STRAND (5/16 IN)	LF	400	\$5.78	\$2,312.00	\$4.20	\$1,680.00	\$6.00	\$2,400.00

Rodriguez Construction Group LLC					Mar-Con Services, LLC		John Reed and Company LLC			
Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Unit Price	Total in Figures	Unit Price	Total in Figures	Unit Price	Total in Figures
96	625-2003	ZINC-COATED STEEL WIRE STRAND (1/4 IN)	LF	400	\$4.73	\$1,892.00	\$4.10	\$1,640.00	\$5.00	\$2,000.00
97	625-2004	ZINC-COATED STEEL WIRE STRAND (3/8 IN)	LF	400	\$5.78	\$2,312.00	\$4.30	\$1,720.00	\$6.00	\$2,400.00
98	644-2100	INSTALL SMALL ROADSIDE SIGN ASSEMBLIES TY 10BWG (1) SA (P)	EACH	2	\$367.50	\$735.00	\$508.50	\$1,017.00	\$900.00	\$1,800.00
99	644-2100	"NO PEDESTRIAN CROSSING" (R9-3) (12" X 18)	EACH	2	\$420.00	\$840.00	\$367.30	\$734.60	\$800.00	\$1,600.00
100	644-2100	"NO PEDESTRIAN CROSSING" (R9-3A) (18" X 18")	EACH	2	\$472.50	\$945.00	\$367.30	\$734.60	\$800.00	\$1,600.00
101	666-2048	RETROREFLECTORIZED PAVEMENT MARKINGS TY 1 (W) 24" (SLD) (100 MIL)	LF	125	\$5.25	\$656.25	\$5.70	\$712.50	\$5.00	\$625.00
102	666-2195	PAVEMENT SEALER 24"	LF	125	\$0.58	\$72.50	\$0.60	\$75.00	\$0.52	\$65.00
103	678-2005	PAVEMENT SURFACE PREPARATION FOR MARKING (BLAST CLN) (24")	LF	125	\$0.58	\$72.50	\$0.60	\$75.00	\$0.52	\$65.00
104	680-2002	INSTALL HIGHWAY TRAFFIC SIGNALS (ISOLATED)	EACH	1	\$23,766.75	\$23,766.75	\$16,159.00	\$16,159.00	\$30,000.00	\$30,000.00
105	680-2002	POLE 34' STEEL STRAIN	EACH	2	\$5,250.00	\$10,500.00	\$7,491.90	\$14,983.80	\$3,000.00	\$6,000.00
106	680-2002	RDWY LIGHT ON TRAF SIGNAL POLE (250 WATT H.P.S.)	EACH	1	\$1,575.00	\$1,575.00	\$852.00	\$852.00	\$35,000.00	\$35,000.00
107	680-2002	MAST ARM, 10' LUMINAIRE	EACH	2	\$2,100.00	\$4,200.00	\$1,281.70	\$2,563.40	\$8,000.00	\$16,000.00
108	684-2009	TRAFFIC SIGNAL CABLES (TY A) (12 AWG) (4 COND)	LF	270	\$2.10	\$567.00	\$2.20	\$594.00	\$4.00	\$1,080.00
109	684-2012	TRAFFIC SIGNAL CABLES (TY A) (12 AWG) (7 COND)	LF	1,050	\$3.68	\$3,864.00	\$2.50	\$2,625.00	\$4.00	\$4,200.00
110	6266-2005	VIVIDS COMMUNICATION CABLE (COAXIAL)	LF	1,310	\$2.10	\$2,751.00	\$2.60	\$3,406.00	\$3.00	\$3,930.00
111	6266-2005	3/C #16 - VIVIDS POWER CABLE	LF	1,310	\$2.10	\$2,751.00	\$2.60	\$3,406.00	\$3.00	\$6,550.00
SUB-TOTAL PERMANENT TRAFFIC SIGNALS						\$77,494.00	\$68,918.60		\$128,495.00	

G. BRIDGE STRUCTURE (TXDOT SPECIFICATIONS)												
112	400-6005	CEMENT STABILIZED BACKFILL	CY	180	\$70.35	\$12,663.00	\$87.90	\$15,822.00	\$48.00	\$8,640.00	\$48.00	\$8,640.00
113	416-6001	DRILLED SHAFT FOUNDATIONS (18-INCH)	LF	112	\$131.25	\$14,700.00	\$57.50	\$6,440.00	\$200.00	\$22,400.00	\$200.00	\$22,400.00
114	416-6004	DRILLED SHAFT FOUNDATIONS (36-INCH)	LF	1,736	\$225.75	\$391,902.00	\$183.20	\$318,035.20	\$350.00	\$607,600.00	\$350.00	\$607,600.00
115	420-6013	CONCRETE STRUCTURES (CLASS C CONCRETE) - ABUTMENTS	CY	86	\$1,207.50	\$103,845.00	\$1,030.00	\$88,580.00	\$1,400.00	\$120,400.00	\$1,400.00	\$120,400.00
116	420-4025	CONCRETE STRUCTURES (CLASS C CONCRETE) - BENTS	CY	117	\$1,181.25	\$138,206.25	\$1,469.80	\$171,966.60	\$1,500.00	\$175,500.00	\$1,500.00	\$175,500.00
117	422-6001	REINFORCED CONCRETE SLAB	SF	14,904	\$18.38	\$273,935.52	\$21.90	\$326,397.60	\$11.00	\$163,944.00	\$11.00	\$163,944.00
118	422-6011	BRIDGE MEDIAN	SF	1,776	\$10.50	\$18,648.00	\$6.50	\$11,544.00	\$10.00	\$17,760.00	\$10.00	\$17,760.00
119	422-6013	BRIDGE SIDEWALK	SF	4,440	\$12.60	\$55,944.00	\$10.00	\$44,400.00	\$8.00	\$35,520.00	\$8.00	\$35,520.00
120	422-6015	BRIDGE APPROACH SLAB	CY	242	\$393.75	\$95,287.50	\$248.20	\$60,064.40	\$620.00	\$150,040.00	\$620.00	\$150,040.00
121	425-6036	PRECAST PRESTRESSED CONCRETE STRUCTURAL MEMBERS (PRESTRESSED CONCRETE GIRDER, TX34)	LF	1,715	\$262.50	\$450,187.50	\$145.30	\$249,189.50	\$180.00	\$308,700.00	\$180.00	\$308,700.00
122	442-6007	METAL FOR STRUCTURES (STRUCTURAL STEEL) (MISC NON BRIDGE)	LB	582	\$18.38	\$10,697.16	\$10.70	\$6,227.40	\$10.00	\$5,820.00	\$10.00	\$5,820.00
123	450-6032	RAILING (TY C223)	LF	492	\$267.75	\$131,733.00	\$130.60	\$64,255.20	\$100.00	\$49,200.00	\$100.00	\$49,200.00
124	454-6001	BRIDGE EXPANSION JOINTS, SEALED EXPANSION JOINT (4-INCH) (SEI-A)	LF	130	\$183.75	\$23,887.50	\$87.30	\$11,349.00	\$48.00	\$6,240.00	\$48.00	\$6,240.00
SUB-TOTAL BRIDGE ITEMS						\$1,721,636.43		\$1,374,270.90		\$1,671,764.00		\$1,671,764.00

H. STORM WATER POLLUTION PREVENTION												
125	162	SODDING FOR EROSION CONTROL AND STABILIZATION	LF	11,858	\$1.18	\$13,992.44	\$0.60	\$7,114.80	\$2.00	\$23,716.00	\$2.00	\$23,716.00
126	165	HYDRO-MULCH SEEDING	ACRE	5	\$1,310.75	\$6,553.75	\$1,186.50	\$5,932.50	\$1,145.00	\$5,725.00	\$1,145.00	\$5,725.00
127	713	REINFORCED FILTER FABRIC BARRIER	LF	5,520	\$1.28	\$7,065.60	\$1.70	\$9,384.00	\$3.00	\$16,560.00	\$3.00	\$16,560.00
128	719	INLET PROTECTION BARRIER (STAGE 1, WITH FIBER ROLLS)	EACH	31	\$58.85	\$1,824.35	\$60.50	\$1,874.50	\$100.00	\$3,100.00	\$100.00	\$3,100.00
129	724	STABILIZED CONSTRUCTION ACCESS, TYPE 1 ROCK	SY	222	\$2,612.94	\$585,600.00	\$18.30	\$4,062.60	\$36.00	\$7,992.00	\$36.00	\$7,992.00
130	730	CONCRETE TRUCK WASHOUT STRUCTURES	LS	1	\$856.00	\$856.00	\$1,356.00	\$1,356.00	\$3,000.00	\$3,000.00	\$3,000.00	\$3,000.00
131	741	INLET PROTECTION BARRIER (FOR STAGES II INLETS, GRAVEL BAGS)	EACH	24	\$42.80	\$1,027.20	\$60.50	\$1,452.00	\$55.00	\$1,320.00	\$55.00	\$1,320.00
132	750	ROCK FILTER DAM (TYPE 3)	LF	80	\$69.55	\$5,564.00	\$63.30	\$5,064.00	\$25.00	\$2,000.00	\$25.00	\$2,000.00
133	HCFCD 2361	REINFORCED SLIT FENCE	LF	680	\$1.50	\$1,020.00	\$2.00	\$1,360.00	\$3.00	\$2,040.00	\$3.00	\$2,040.00
134	751(DWGS)	SWPPP INSPECTION AND MAINTENANCE (MIN. BID - \$6,000/MONTH)	MONTH	11	\$6,000.00	\$66,000.00	\$6,000.00	\$66,000.00	\$1,500.00	\$16,500.00	\$1,500.00	\$16,500.00

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Rodriguez Construction Group LLC Unit Price	Total in Figures	Mar-Con Services, LLC Unit Price	Total in Figures	John Reed and Company LLC Unit Price	Total in Figures
135	700 (PROJECT MANUAL)	TPDES GENERAL PERMIT NO. TXR 150000. NOTICE OF INTENT (NOI) APPLICATION FEES (CONTRACTOR'S NOI FEE & FORT BEND COUNTY'S NOI FEE, EACH FEE SHALL BE SET PRICE OF \$325.00)	EACH	2	\$325.00	\$650.00	\$325.00	\$650.00	\$325.00	\$650.00

SUB-TOTAL OF STORM WATER POLLUTION PREVENTION ITEMS

\$107,166.28 \$104,251.40 \$82,603.00

I. EXTRA WORK										
136	430	SEAL SLAB, CLASS D CONCRETE, 7" THICKNESS (MIN. BID \$25/SY)	SY	200	\$25.00	\$5,000.00	\$25.00	\$5,000.00	\$25.00	\$5,000.00
137	436	WELL POINTING SYSTEM (MIN. BID \$15/LF)	LF	500	\$15.00	\$7,500.00	\$25.00	\$12,500.00	\$20.00	\$10,000.00
138	552-6001	5-STRAND BARBED WIRE FENCE	LF	1,500	\$4.55	\$6,825.00	\$7.30	\$10,950.00	\$10.00	\$15,000.00
139	552-6002	5-STRAND SLICK WIRE FENCE	LF	1,000	\$3.75	\$3,750.00	\$7.30	\$7,300.00	\$10.00	\$10,000.00
140	552-6006	GALVANIZED TUBE GATES, TY 2 GATE	EA	2	\$588.50	\$1,177.00	\$611.30	\$1,222.60	\$2,000.00	\$4,000.00
141	559	CONSTRUCTION SAFETY FENCE	LF	1,000	\$1.28	\$1,280.00	\$1.90	\$1,900.00	\$5.00	\$5,000.00
142	0560 (SP 560)	MOWING PROJECT SITE	CYCLE	4	\$335.00	\$2,140.00	\$565.00	\$2,260.00	\$1,500.00	\$6,000.00
143	672	UNIFORM PEACE OFFICER (MINIMUM: \$25/HR)	HOURL	200	\$25.00	\$5,000.00	\$46.30	\$9,260.00	\$25.00	\$5,000.00
144	SS8006	ELECTRICAL ROSER RELOCATION FOR PROPERTY OWNER (CUSTOMER OWNED)-CONNECTION TO CENTERPOINT ENERGY ELECTRICAL SERVICE - SINGLE PHASE, 120 VOLT 3-WIRE ELECTRICAL SERVICES	LF	200	\$21.40	\$4,280.00	\$17.00	\$3,400.00	\$100.00	\$20,000.00
145	SS8006	ELECTRICAL ROSER RELOCATION FOR PROPERTY OWNER (CUSTOMER OWNED)-CONNECTION TO CENTERPOINT ENERGY ELECTRICAL SERVICE - THREE PHASE (COMMERCIAL CUSTOMER) ELECTRICAL SERVICES	LF	200	\$26.75	\$5,350.00	\$22.63	\$4,526.00	\$100.00	\$20,000.00

SUB-TOTAL EXTRA WORK ITEMS

\$42,302.00 \$58,318.60 \$100,000.00

A. SITE PREPARATION										
					Rodriguez Construction Group LLC	\$381,592.91	Mar-Con Services, LLC	\$633,098.40	John Reed and Company LLC	\$356,877.00
B. SUBGRADE AND PAVING						\$1,913,019.72		\$1,923,612.60		\$2,167,510.80
C. STORM SEWER						\$737,687.46		\$967,656.60		\$952,051.00
D. TRAFFIC CONTROL						\$131,195.15		\$102,904.60		\$101,741.06
E. SIGNING AND PAVEMENT MARKING						\$32,951.43		\$33,345.30		\$30,763.36
F. PERMANENT TRAFFIC SIGNALS (TXDOT SPECIFICATIONS)						\$77,494.00		\$68,918.60		\$128,495.00
G. BRIDGE STRUCTURE (TXDOT SPECIFICATIONS)						\$1,721,636.43		\$1,374,270.90		\$1,671,764.00
H. STORM WATER POLLUTION PREVENTION						\$107,166.28		\$104,251.40		\$82,603.00
I. EXTRA WORK						\$42,302.00		\$58,318.60		\$100,000.00
TOTAL BID PRICE (SUM OF ITEMS A THROUGH I)						\$5,145,045.38		\$5,266,377.00		\$5,591,805.22

*Italicized numbers represent mathematical error.

Bid Date 12/13/2016

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Unit Price	Total in Figures
A. SITE PREPARATION						
1	100(DWG)	FORT BEND COUNTY PROJECT SIGN	EACH	2	\$495.00	\$990.00
2	102(DWGS)	CLEARING AND GRUBBING (INCLUDING OUTFALLS)	LS	1	\$100,000.00	\$100,000.00
3	104	REMOVING OLD CONCRETE PAVEMENT	SY	5,440	\$3.63	\$19,747.20
4	104	REMOVING OLD CONCRETE PAVEMENT, 6" REINFORCED CONCRETE CURB	LF	2,800	\$1.00	\$2,800.00
5	110(SP110)	ROADWAY EXCAVATION (INCLUDING 3" STRIPING)	CY	15,987	\$12.97	\$207,351.39
6	465	REMOVE AND DISPOSE OF EXISTING, CONCRETE OR METAL PIPE (18" - 36")	LF	723	\$21.74	\$15,718.02
7	465	REMOVE AND DISPOSE OF EXISTING PLASTIC PIPE (ALL TYPE AND ALL SIZES)	LF	60	\$13.04	\$782.40
8	495	REMOVING OLD STRUCTURES - INLETS (ALL DEPTHS)	EACH	3	\$593.00	\$1,779.00
9	495	REMOVING OLD STRUCTURES - SAFETY END TREATMENTS	EACH	2	\$795.03	\$1,590.06
10	495	REMOVING OLD STRUCTURES - HEADWALLS INCLUDING WINGWALLS	EACH	7	\$3,693.48	\$25,854.36
11	495	REMOVING FLEX BEAM GUARD RAIL	LF	256	\$5.00	\$1,280.00
12	495	REMOVING TURN DOWN SECTION	EACH	2	\$500.00	\$1,000.00
13	495	REMOVING OLD STRUCTURE - WOODEN BRIDGE	EACH	1	\$11,634.72	\$11,634.72
14	500	REMOVE AND RELOCATE TRAFFIC SIGNS, MAIL BOXES, ROADWAY SIGNS	LS	1	\$2,500.00	\$2,500.00
15	500	REMOVE AND RELOCATE TRAFFIC SIGNAL ITEMS (AS REQUIRED)	LS	1	\$2,500.00	\$2,500.00
16	540	REMOVE AND DISPOSE OF EXISTING ASPHALTIC SURFACE AND BASE MATERIAL	SY	4,118	\$2.00	\$8,236.00

B. SUBGRADE AND PAVING						
17	221	HYDRATED LIME (SLURRY APPLIED) FOR STABILIZATION (6% BY DRY WEIGHT)	TON	614	\$203.40	\$124,887.60
18	223	FLY ASH FOR STABILIZATION (8% BY DRY WEIGHT)	TON	818	\$210.18	\$171,927.24
19	226(DWGS)	LIME-FLY ASH STABILIZED SUBGRADE, 2 MANIPULATIONS AT 8" DEPTH	SY	30,994	\$4.28	\$132,654.32
20	250	HOT MIX ASPHALTIC CONCRETE BASE COURSE, 8" DEPTH	TON	274	\$135.60	\$37,154.40
21	310	PRIME COAT FOR BASE COURSE (1.30 GAL/SY)	GAL	189	\$4.07	\$769.23
22	340	HMAC - TACK COAT (0.15 GAL/SY)	GAL	95	\$6.78	\$644.10
23	340	HMAC TYPE "D" SURFACE COURSE - 2" THICK	TON	69	\$271.20	\$18,712.80
24	360	REINFORCED CONCRETE PAVEMENT - 8" DEPTH	SY	26,549	\$48.37	\$1,284,175.13
25	360	REINFORCED CONCRETE PAVEMENT, HIGH EARLY STRENGTH - 8" DEPTH	SY	4,450	\$72.62	\$323,159.00
26	360	REINFORCED CONCRETE PAVEMENT, HIGH EARLY STRENGTH - 8" DEPTH FOR DRIVEWAYS	SY	710	\$76.81	\$54,535.10
27	433	CEMENT STABILIZED SAND, 8" THICK	SY	5,620	\$20.25	\$113,805.00
28	521(DWGS)	FLEX BEAM GUARD RAIL, 12 GAUGE WITH MOWING STRIP	LF	534	\$32.00	\$17,088.00
29	522(DWGS)	TURN DOWN TERMINAL, SECTION (25' LONG), 12 GAUGE, WITH ANCHOR	EACH	12	\$950.00	\$11,400.00
30	530	6" CONCRETE CURBS	LF	21,695	\$3.38	\$73,329.10
31	535	ESPLANADES, MEDIANS, AND DIRECTIONAL ISLANDS	SY	264	\$77.70	\$20,512.80
32	536	COLORLED CONCRETE MEDIANS (BLACK)	SY	264	\$111.12	\$29,335.68

			James Construction Group, LLC			
Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Unit Price	Total in Figures
C. STORM SEWER						
33	421	STRUCTURAL CONCRETE, WINGWALLS	CY	15	\$1,826.36	\$27,395.40
34	421	STRUCTURAL CONCRETE, HEADWALLS	CY	20	\$1,697.64	\$33,952.80
35	429	TRENCH SAFETY SYSTEMS, 5' TO 10' DEPTH	LF	6,256	\$0.75	\$4,692.00
36	459	TIMBER BENT FOR 48" PIPE	EACH	1	\$2,785.41	\$2,785.41
37	460	CORRUGATED PLASTIC PIPE, PRE-COATED (12")	LF	30	\$93.96	\$2,818.80
38	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (24")	LF	3,130	\$73.13	\$228,896.90
39	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (EQUIVALENT 24") ELLIPTICAL 19" X 30"	LF	410	\$114.97	\$47,137.70
40	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (30")	LF	744	\$103.28	\$76,840.32
41	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (42")	LF	601	\$178.17	\$107,080.17
42	460	REINFORCED CONCRETE PIPE, C76, CLASS III, RUBBER GASKET (42")	LF	1,101	\$217.39	\$239,346.39
43	461	CORRUGATED METAL PIPE-PRE-COATED-GALVANIZED (16 GAUGE) (24")	LF	129	\$206.36	\$26,620.44
44	461	CORRUGATED METAL PIPE-PRE-COATED-GALVANIZED (16 GAUGE) (30")	LF	133	\$128.93	\$17,147.69
45	461	CORRUGATED METAL PIPE-PRE-COATED-GALVANIZED (16 GAUGE) (48")	LF	118	\$207.42	\$24,475.56
46	463	SAFETY END TREATMENT - TYPE II, (6:1) (PD-SPR) 24" RCP	EACH	2	\$2,687.91	\$5,375.82
47	467-2288	SAFETY END TREATMENT SET (TY II) (24IN) (RCP) (6:1) (P)	EACH	2	\$2,763.85	\$5,527.70
48	471	PRECAST CONCRETE SHALLOW MANHOLE, DEPTH LESS THAN 6 FEET	EACH	16	\$3,938.58	\$63,017.28
49	471	PRECAST CONCRETE STANDARD MANHOLE, DEPTH GREATER THAN 6 FEET & LESS THAN 10 FEET	EACH	3	\$3,925.02	\$11,775.06
50	471	PRECAST CONCRETE EXTRA DEPTH MANHOLE, DEPTH GREATER THAN 10 FEET	EACH	11	\$3,993.09	\$43,923.99
51	472	TYPE "A" INLET, ADDITIONAL DEPTH GREATER THAN 6'	EACH	4	\$3,432.06	\$13,728.24
52	472	STANDARD TYPE "A" INLET MODIFIED SQUARE (PRE-CAST OR CAST) GREATER THAN 6'	EACH	7	\$3,038.81	\$21,271.67
53	472	STANDARD TYPE "B-B" INLET	EACH	12	\$2,625.79	\$31,509.48
54	472	TYPE "B-B" INLET WITH ADDITIONAL DEPTH GREATER THAN 6'	EACH	6	\$2,625.79	\$15,754.74
55	472	TYPE "B-B" (MODIFIED) INLET, ADDITIONAL DEPTH GREATER THAN 6'	EACH	6	\$2,625.79	\$15,754.74
56	480	REINFORCED CONCRETE BOX, C1433 (ALL DEPTHS) (5' X 3')	LF	174	\$288.40	\$50,181.60
57	491	REINFORCED CONCRETE SLOPE PAVING (4" THICK)	SY	215	\$65.24	\$14,026.60
58	491	REINFORCED CONCRETE SLOPE PAVING (5" THICK)	SY	1,492	\$85.77	\$127,968.84
59	2378	RIPRAP - GRADATION NO. 1 (18" THICK)	SY	110	\$179.37	\$19,730.70
SUB-TOTAL STORM SEWER						\$1,278,736.04

D. TRAFFIC CONTROL						
60	665	WORK ZONE PAVEMENT MARKINGS 4" WHITE/SOLID (REMOVABLE) APPLIED, REMOVED	LF	934	\$0.60	\$560.40
61	665	WORK ZONE PAVEMENT MARKINGS 8" WHITE/SOLID (REMOVABLE) APPLIED, REMOVED	LF	120	\$1.50	\$180.00
62	665	WORK ZONE PAVEMENT MARKINGS 24" WHITE/SOLID (REMOVABLE) APPLIED, REMOVED	LF	57	\$3.50	\$199.50
63	665	WORK ZONE PAVEMENT MARKINGS 4" YELLOW/SOLID (REMOVABLE) APPLIED, REMOVED	LF	8,716	\$0.51	\$4,445.16

James Construction Group, LLC						
Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Unit Price	Total in Figures
64	665	WORK ZONE PAVEMENT MARKINGS 8" WHITE/DASHED (REMOVABLE) APPLIED, REMOVED (4' OVER 8')	LF	105	\$2.00	\$210.00
65	671	TRAFFIC CONTROL - FURNISH-INSTALL & REMOVE	MONTH	11	\$2,996.64	\$32,963.04
66	671	TEMPORARY COMMERCIAL DRIVEWAYS - INSTALL & REMOVE	EACH	3	\$2,753.69	\$8,261.07
67	671	TEMPORARY TRAFFIC SIGNAL AT FM 762 AND WILLIAMS WAY BOULEVARD (RELOCATE SIGNAL HEADS/BAG)	LS	1	\$4,800.00	\$4,800.00
68	673	CONSTRUCTING DETOURS FOR TWO-WAY TRAFFIC (8" BLACK BASE) FOR INSTALLING-MAINTAINING & REMOVING	SY	206	\$108.48	\$22,346.88
69	696	LOW PROFILE CONCRETE BARRIER TYPE 1 (INSTALL)	LF	805	\$61.20	\$49,266.00
70	696	LOW PROFILE CONCRETE BARRIER TYPE 1 (RELOCATE)	LF	2,474	\$5.81	\$14,373.94
71	696	LOW PROFILE CONCRETE BARRIER TYPE 1 (REMOVE)	LF	805	\$9.80	\$7,889.00
72	696	LOW PROFILE CONCRETE BARRIER TYPE 2 (INSTALL)	LF	80	\$61.20	\$4,896.00
73	696	LOW PROFILE CONCRETE BARRIER TYPE 2 (RELOCATE)	LF	140	\$9.49	\$1,328.60
74	696	LOW PROFILE CONCRETE BARRIER TYPE 2 (REMOVE)	LF	80	\$9.79	\$783.20
SUB-TOTAL TRAFFIC CONTROL						\$152,502.79

E. SIGNING AND PAVEMENT MARKING						
75	448	SOLID CAST ALUMINIUM BRIDGE PLAQUE	EACH	1	\$1,623.05	\$1,623.05
76	624	ALUMINIUM SIGNS (GROUND MOUNTED)	EACH	58	\$220.00	\$12,760.00
77	658	FURNISH AND INSTALL OBJECT MARKER (TEXAS MUTCD: "OM-3R/L")	EACH	2	\$132.00	\$264.00
78	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 4" WHITE/SOLID	LF	397	\$0.58	\$230.26
79	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 8" WHITE/SOLID	LF	922	\$1.05	\$968.10
80	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 12" WHITE/SOLID	LF	584	\$2.15	\$1,255.60
81	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 24" WHITE/SOLID	LF	292	\$4.50	\$1,314.00
82	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) 4" WHITE/DASHED (15' OVER 40')	LF	8,395	\$0.62	\$5,204.90
83	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) SINGLE ARROW-LEFT	EACH	8	\$115.00	\$920.00
84	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) RIGHT-STRAIGHT COMBINATION ARROWS	EACH	2	\$115.00	\$230.00
85	660	REFLECTORIZED PAVEMENT MARKINGS TYPE I (THERMOPLASTIC) WORD "ONLY"	EACH	5	\$110.00	\$550.00
86	660	REFLECTORIZED PAVEMENT MARKINGS TYPE II, 12" YELLOW/SOLID, FOR 6" CURB PER DETAIL "D"	LF	2,830	\$0.80	\$2,264.00
87	663	REFLECTORIZED PAVEMENT MARKERS TYPE I-C	EACH	296	\$2.75	\$814.00
88	663	REFLECTORIZED PAVEMENT MARKERS TYPE II-C-R	EACH	195	\$2.75	\$536.25
89	663	NON-REFLECTORIZED CERAMIC TRAFFIC BUTTONS (WHITE)	EACH	201	\$2.25	\$452.25
SUB-TOTAL SIGNING AND PAVEMENT MARKINGS						\$29,386.41

F. PERMANENT TRAFFIC SIGNALS (TXDOT SPECIFICATIONS)						
90	416-2032	DRILLED SHAFT FOUNDATION (TRF SIG. POLE)	LF	30	\$400.00	\$12,000.00
91	618-2052	CONDUIT (PVC) (SCHD 80) (2")	LF	150	\$15.00	\$2,250.00
92	620-2009	ELECTRICAL CONDUCTORS (NO. 6) BARE	LF	145	\$2.00	\$290.00
93	621-2004	TRAY CABLE (4 CONR) (12 AWG)	LF	400	\$2.00	\$800.00
94	624-2014	GROUND BOXES TY D (162922) W/ APRON	EACH	1	\$1,000.00	\$1,000.00
95	625-2001	ZINC-COATED STEEL WIRE STRAND (5/16 IN)	LF	400	\$5.50	\$2,200.00

James Construction Group, LLC					
Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Total in Figures
96	625-2003	ZINC-COATED STEEL WIRE STRAND (1/4 IN)	LF	400	\$1,800.00
97	625-2004	ZINC-COATED STEEL WIRE STRAND (3/8 IN)	LF	400	\$2,200.00
98	644-2100	INSTALL SMALL ROADSIDE SIGN ASSEMBLIES TY 10BWG (1) SA (P)	EACH	2	\$1,500.00
99	644-2100	"NO PEDESTRIAN CROSSING" (R9-3) (12" X 18)	EACH	2	\$1,000.00
100	644-2100	"NO PEDESTRIAN CROSSING" (R9-3A) (18" X 18")	EACH	2	\$1,000.00
101	666-2048	RETROREFLECTORIZED PAVEMENT MARKINGS TY 1 (W) 24" (SLD) (100 MIL)	LF	125	\$625.00
102	666-2195	PAVEMENT SEALER 24"	LF	125	\$65.00
103	678-2005	PAVEMENT SURFACE PREPARATION FOR MARKING (BLAST CLN) (24")	LF	125	\$65.00
104	680-2002	INSTALL HIGHWAY TRAFFIC SIGNALS (ISOLATED)	EACH	1	\$20,135.00
105	680-2002	POLE 34' STEEL STRAIN	EACH	2	\$10,000.00
106	680-2002	RDWY LIGHT ON TRAF SIGNAL POLE (250 WATT H.P.S.)	EACH	1	\$1,000.00
107	680-2002	MAST ARM, 10' LUMINAIRE	EACH	2	\$4,000.00
108	684-2009	TRAFFIC SIGNAL CABLES (TY A) (12 AWG) (4 CONDR)	LF	270	\$540.00
109	684-2012	TRAFFIC SIGNAL CABLES (TY A) (12 AWG) (7 CONDR)	LF	1,050	\$3,675.00
110	6266-2005	VIVDS COMMUNICATION CABLE (COAXIAL)	LF	1,310	\$2,620.00
111	6266-2005	3/C #16 - VIVDS POWER CABLE	LF	1,310	\$2,620.00
SUB-TOTAL PERMANENT TRAFFIC SIGNALS					\$71,385.00

G. BRIDGE STRUCTURE (TXDOT SPECIFICATIONS)					
112	400-6005	CEMENT STABILIZED BACKFILL	CY	180	\$18,835.20
113	416-6001	DRILLED SHAFT FOUNDATIONS (18-INCH)	LF	112	\$4,499.04
114	416-6004	DRILLED SHAFT FOUNDATIONS (36-INCH)	LF	1,736	\$257,969.60
115	420-6013	CONCRETE STRUCTURES (CLASS C CONCRETE) - ABUTMENTS	CY	86	\$78,638.40
116	420-4025	CONCRETE STRUCTURES (CLASS C CONCRETE) - BENTS	CY	117	\$125,849.88
117	422-6001	REINFORCED CONCRETE SLAB	SF	14,904	\$228,478.32
118	422-6011	BRIDGE MEDIAN	SF	1,776	\$25,236.96
119	422-6013	BRIDGE SIDEWALK	SF	4,440	\$49,728.00
120	422-6015	BRIDGE APPROACH SLAB	CY	242	\$90,844.38
121	425-6036	PRECAST PRESTRESSED CONCRETE STRUCTURAL MEMBERS (PRESTRESSED CONCRETE GIRDER, TX34)	LF	1,715	\$258,399.05
122	442-6007	METAL FOR STRUCTURES (STRUCTURAL STEEL) (MISC NON BRIDGE)	LB	582	\$9,870.72
123	450-6032	RAILING (TY C223)	LF	492	\$64,363.44
124	454-6001	BRIDGE EXPANSION JOINTS, SEALED EXPANSION JOINT (4-INCH) (SEJ-A)	LF	130	\$13,596.70
SUB-TOTAL BRIDGE ITEMS					\$1,226,309.69

H. STORM WATER POLLUTION PREVENTION					
125	162	SODDING FOR EROSION CONTROL AND STABILIZATION	LF	11,858	\$23,716.00
126	165	HYDRO-MULCH SEEDING	ACRE	5	\$1,145.00
127	713	REINFORCED FILTER FABRIC BARRIER	LF	5,520	\$7,176.00
128	719	INLET PROTECTION BARRIER (STAGE 1, WITH FIBER ROLLS)	EACH	31	\$55.64
129	724	STABILIZED CONSTRUCTION ACCESS, TYPE 1 ROCK	SY	222	\$4,218.00
130	730	CONCRETE TRUCK WASHOUT STRUCTURES	LS	1	\$2,496.00
131	741	INLET PROTECTION BARRIER (FOR STAGES II INLETS, GRAVEL BAGS)	EACH	24	\$2,376.24
132	750	ROCK FILTER DAM (TYPE 3)	LF	80	\$2,800.00
133	HCFC D 2361	REINFORCED SLIT FENCE	LF	680	\$884.00
134	751 (DWGS)	SWPPP INSPECTION AND MAINTENANCE (MIN. BID - \$6,000/MONTH)	MONTH	11	\$5,148.00

Item No.	Spec. No.	Item Description	Unit Measure	Unit Quantity	Unit Price	Total in Figures
135	700 (PROJECT MANUAL)	TPDES GENERAL PERMIT NO. TXR 150000, NOTICE OF INTENT (NOI) APPLICATION FEES (CONTRACTOR'S NOI FEE & FORT BEND COUNTY'S NOI FEE, EACH FEE SHALL BE SET PRICE OF \$325.00)	EACH	2	\$338.00	\$676.00
SUB-TOTAL OF STORM WATER POLLUTION PREVENTION ITEMS						\$56,940.08

I. EXTRA WORK						
136	430	SEAL SLAB, CLASS D CONCRETE, 7" THICKNESS (MIN. BID \$25/SY)	SY	200	\$25.00	\$5,000.00
137	436	WELL POINTING SYSTEM (MIN. BID \$15/LF)	LF	500	\$15.00	\$7,500.00
138	552-6001	5-STRAND BARBED WIRE FENCE	LF	1,500	\$3.00	\$4,500.00
139	552-6002	5-STRAND SLICK WIRE FENCE	LF	1,000	\$5.00	\$5,000.00
140	552-6006	GALVANIZED TUBE GATES, TY 2 GATE	EA	2	\$1,500.00	\$3,000.00
141	559	CONSTRUCTION SAFETY FENCE	LF	1,000	\$3.36	\$3,360.00
142	0360 (SP 360)	MOWING PROJECT SITE	CYCLE	4	\$1,500.00	\$6,000.00
143	672	UNIFORM PEACE OFFICER (MINIMUM: \$25/HR)	HOURL	200	\$50.00	\$10,000.00
144	SS8006	ELECTRICAL ROSER RELOCATION FOR PROPERTY OWNER (CUSTOMER OWNED)-CONNECTION TO CENTERPOINT ENERGY ELECTRICAL SERVICE - SINGLE PHASE, 120 VOLT 3-WIRE ELECTRICAL SERVICES	LF	200	\$20.00	\$4,000.00
145	SS8006	ELECTRICAL ROSER RELOCATION FOR PROPERTY OWNER (CUSTOMER OWNED)-CONNECTION TO CENTERPOINT ENERGY ELECTRICAL SERVICE - THREE PHASE (COMMERCIAL CUSTOMER) ELECTRICAL SERVICES	LF	200	\$25.00	\$5,000.00
SUB-TOTAL EXTRA WORK ITEMS						\$53,360.00

James Construction Group, LLC						
A. SITE PREPARATION					\$403,763.15	
B. SUBGRADE AND PAVING					\$2,414,089.50	
C. STORM SEWER					\$1,278,736.04	
D. TRAFFIC CONTROL					\$152,502.79	
E. SIGNING AND PAVEMENT MARKING					\$29,386.41	
F. PERMANENT TRAFFIC SIGNALS (TXDOT SPECIFICATIONS)					\$71,385.00	
G. BRIDGE STRUCTURE (TXDOT SPECIFICATIONS)					\$1,226,309.69	
H. STORM WATER POLLUTION PREVENTION					\$56,940.08	
I. EXTRA WORK					\$53,360.00	
TOTAL BID PRICE (SUM OF ITEMS A THROUGH I)					\$5,686,472.66	

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

OFFICE USE ONLY CERTIFICATION OF FILING

Certificate Number:
2016-142921

Date Filed:
12/05/2016

Date Acknowledged:

1 Name of business entity filing form, and the city, state and country of the business entity's place of business.

Allgood Construction Company, Inc.
Richmond, TX United States

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.

Fort Bend County

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.

B17-038
Construction of Williams Way Blvd.


4	Name of Interested Party	City, State, Country (place of business)	Nature of interest (check applicable)	
			Controlling	Intermediary

5 Check only if there is NO Interested Party.



6 AFFIDAVIT

I swear, or affirm, under penalty of perjury, that the above disclosure is true and correct.



[Signature]

Signature of authorized agent of contracting business entity

AFFIX NOTARY STAMP / SEAL ABOVE

Sworn to and subscribed before me, by the said Sterling Moore, this the 13 day of December, 2016, to certify which, witness my hand and seal of office.

[Signature]

Signature of officer administering oath

Kelsie Moore

Printed name of officer administering oath

Accounting Manager

Title of officer administering oath