



April 12, 2017

Mr. Paul Smith
Ft. Bend County EMS
Email: Paul.Smith@fortbendcountytx.gov

Quote # 236

Mr. Smith,

Per your request we are quoting remounting and refurbishing your Frazer Type I 12' Generator Powered Module X-1160 (X-854/E-1618) onto a 2017 Dodge Ram 3500 6.7L diesel chassis (Dodge White PW7) (customer provided) with a LiquidSpring suspension system for Dodge Ram 3500. For your convenience all pricing has been itemized below.

Frazer Type I 12' Generator Powered Module X-1160 (X-854/E-1618)
2017 Dodge Ram 3500 6.7L diesel chassis (Dodge White PW7) (customer provided)
Note: Furnish & install 20 gallon transfer flow tank

LiquidSpring suspension system for Dodge Ram 3500 \$ 10,500.00
Note - tie in to stud in console instead of VSIM

Heat shielding for diesel chassis	\$ 1,500.00
Remount of Module (see Incl. Items below)	\$ 18,000.00
Chassis Exterior Upgrades	\$ -100.00
Chassis Interior Upgrades	\$ 1,200.00
Module Exterior Upgrades	\$ 22,125.00
Module Interior Upgrades	\$ 15,400.00
Buy Board Fee Contract #492-15	\$ 800.00
Total	\$ 69,425.00

Items included in above total:

Chassis Exterior Upgrades:

- | | |
|--|------------|
| 1 . Items included in remount fee: | \$ incl. |
| a) Credit for not installing Ranch Hand grille guard | \$ -250.00 |
| b) (2) Whelen M4 grille lights w/ clear lenses
<i>Layout: red, amber</i> | |
| c) (2) Whelen M4 intersects w/ clear lenses mounted on chassis fenders (no brackets) (like X-984) - make them straight, DO NOT follow curve of fender
<i>Layout: red, red</i> | |
| d) Furnish & install (2) through the bumper Cast aluminum speakers in lieu of (2) Whelen 315P speakers | \$ 550.00 |

e) Frazer aluminum rear window pass through plate

f) (2) Mega fuses with new wiring in engine compartment

g) New mounting rubber

h) New tie downs & spacers

i) Furnish & install Backup alarm

j) Mudflaps

k) Make old chassis road ready - customer will pick-up as soon as it is ready

1. Install rear mud flaps on chassis

2. Install rear BTT lights

3. Remove and reinstall compressor on chassis frame rail

4. Remove license plate on rear of module and keep w/ old chassis

l) Fuel with diesel to verify fuel flow

m) Issue temporary license plate

n) Wash Unit

o) Unit will be picked up by the customer

p) Route chassis exhaust to below the generator compartment

q) Credit for not striping new chassis

\$ -400.00

r) This unit DOES NOT need a state inspection

s) Retain factory wheel covers

Total \$ -100.00

Chassis Interior Upgrades

2 . Items included in remount fee:

\$ incl.

a) Furnish & install pinned powder coated aluminum four position console without the base

Note - Mount it as far back as possible

Slot 1 – MDT plate (extended) - no swivel (or holes) - with a genset fuel gauge on the bottom left corner

\$ 50.00

Slot 2 – Single switch panel

Layout: PRIMARY-SECONDARY-Blank - FLOOD/SPOT (3 position switch) - SIDE SCENE - SIDE SCENE - BLANK - INTERIOR LIGHT - START/STOP (Genset)

Note - Ensure Tomar emitter on front wall is activated with Siren #2 switch (no disable switch; factory switch located in electrical compartment)

Slot 3 – Radio plate 2398

Slot 4 – Furnish & install Whelen 295HFSC9 siren w/ mic on passenger's side of console slot 1

\$ 150.00

Note - DO NOT install Tap-2 (prep chassis for Tap-2)

Note - Ship loose additional siren in the electrical compartment

Note - Furnish & install RED TIR3 "COMP OPEN" and "DOOR OPEN" warning LED in addition to our standard LEDs on the driver's side of plate

\$ 150.00

3 . Ensure Cat 5 cables coming from Sierra wireless base in radio compartment is run to and left coiled at the front of the console

4 . Coil existing camera cables behind drivers seat, customer will reconnect these after delivery

\$ N/C

NOTE - MAKE SURE THE CABLES ARE COVERED DURING PAINT - Customer was concerned that paint got into the cable ends on the last remount

5 . Furnish & install arm rests on the console (discard existing)

\$ 200.00

6 . Furnish & install (1) large aluminum map holder on the rear of the console

\$ 200.00

7 . Gamber Johnson heavy-duty dual cup holder on the floor of the chassis in front of the console riser	\$	150.00
8 . Remove and reinstall Motorola 800mHz radio head in console slot 4 w/ mic on D/S of console slot 1	\$	300.00
a) Remove & reinstall speaker on rear wall of chassis cab - towards passenger's side (not centered like X-1015)		
b) Reconnect to base in electrical compartment		
Note - Wire battery hot		
Total	\$	1,200.00

Module Exterior Upgrades

9 . Items included in remount fee:	\$	incl.
a) Install new ignition & fail safe solenoids on electrical shelf		
b) Full electrical check		
c) Furnish & install (2) 4" round red LED lower B/T/T's and (2) 4" round lower clear back up lights		
d) New passthrough rubber boot		
e) Replace all door compartment bumpers		
f) Replace weather stripping		
g) New ribbed rubber in applicable compartments		
h) Replace existing halogen compartment lights w/ LED flex strip lighting		
(1) 43" LED flex light along the forward wall, next to the insert of the O2 compartment		
(1) 55" LED flex light along the ceiling, next to the insert of the long lower storage compartment		
(1) 12" LED flex light along the forward wall, next to the insert of the radio/storage compartment		
(1) LED flex light along the ceiling, next to the insert of the rear storage compartment		
(1) 36" LED flex light along the front wall lasco, next to the insert of the front I/O		
(1) LED flex light along the ceiling, next to the insert of the rear wall D/S storage compartment		
i) This unit needs to be weighed and a weight slip provided to the customer		
j) Verify front and rear wall skins have 10ga Black ground wire terminated to roof frame		
k) Furnish & install new fuel guards (discard old)		
l) Replace marker lights (discard)		
m) Install rear entry threshold		

n) Furnish & install Genset shutdown circuit w/ acknowledge switch at rear entry doors (discard existing buzzer kill switch in the electrical compartment)

o) Inner fenders

p) Frazer key fob

q) Zero clearance behind side main entry step well

r) Zero clearance inside lower front I/O compartment

10 . Strip, prime, and repaint 12' module Frazer white (BT 650 TOPCOAT) \$ 14,500.00

Note – Items sub-listed are included with paint unless stated other wise

a) Furnish & install painted corner caps on module

b) Replace compartment and entry door latches with new Eberhard latches

c) Furnish & install thresholds for Onan & A/C compartments

d) Furnish & install drip rails in the following locations (Discard old):

1. Side entry doors

2. Rear entry doors

e) Furnish & install gas shock on long lower storage compartment in new location (discard cables)

f) Furnish & install gas shock on rear storage compartment (discard cables)

g) Furnish & install side entry door gas shock w/ side entry door headknocker (discard existing) \$ 250.00

h) Install new side entry door grab rail (discard old)

i) Install new rear entry door grab rails (discard old)

j) Furnish and install O2 compartment vent

k) Install new O2 compartment insert threshold (discard old)

l) Remove & reinstall existing antenna's on module roof

m) Replace entry door windows with double pane windows

- n) Rear entry corner guards
 - o) Surface sand corrosion around inserts
 - p) Remove steel plates on exterior walls
 - q) Remove & reinstall back-up camera on rear wall
 - r) Remove & reinstall rear storage compartment door & rear wall D/S compartment door & panel w/ Cleveland latch
- Note:** doors should be painted and the panels timesaved

- s) Plate over 120VAC on front wall towards the P/S \$ 100.00
- t) Furnish & install new rear entry door grabbers (discard existing)
- u) Furnish & install Ford Style LED license plate light in non-standard location - **see Kasey** (discard existing)
- v) Remove & reinstall existing emergency & scene lighting
- 11 . Furnish & install new doors on the following (discard old): \$ incl.
 - a) O2 compartment
 - b) Radio compartment
 - c) Long lower storage compartment
 - e) Rear passenger's side entry door
 - f) Rear driver's side entry door
 - g) Side entry door
 - h) Generator compartment
 - i) Front I/O compartment
 - j) A/C compartment
 - k) Electrical compartment
 - m) Rear backboard compartment
 - n) A/C Exhaust vent
- 12 . Furnish & install new panels on the following new doors: \$ incl.
 - a) O2 compartment
 - b) Radio compartment
 - c) Long lower storage compartment
 - e) Rear passenger's side entry door
 - f) Rear driver's side entry door
 - g) Side entry door
 - h) Front I/O compartment
 - i) A/C compartment
 - j) Electrical compartment
 - l) Rear backboard compartment
- 13 . Furnish & install new hinges on the following doors (discard old): \$ incl.
 - a) O2 compartment
 - b) Radio compartment
 - c) Long lower storage compartment
 - e) Rear passenger's side entry door
 - f) Rear driver's side entry door
 - g) Side entry door
 - h) Generator compartment
 - i) Front I/O compartment
 - j) Electrical compartment
 - m) Rear backboard compartment
 - l) A/C compartment
- 14 . This unit will NOT be receiving Striping & Lettering \$ N/C
- 15 . Furnish and install the following decals:
 - a) Install CO stickers in three (3) locations
 - b) Install one (1) NO SMOKING sticker on dash

16 .	Furnish & install (3) 6" x 12" steel plates and make a magnetic decal for it on the front, driver's side & passenger's side walls, - paint the plate the same color as the module - deliver plate to striping and lettering once painted	\$	375.00
17 .	Furnish & install (8) Whelen M9 series red corner box lights with standard chrome flanges (NOT CONVERTER FLANGES) (ship existing corner box lights loose)	\$	2,400.00
18 .	Replace treadbrite at front, wheel wells, and rear corners with new, discard existing	\$	900.00
	a) Driver's & Passenger's side front corner panels		
	b) Passenger's side wheel well panel		
	c) Driver's side wheel well panel square filler guards		
	d) Driver side rear panel with (2) 4" round light cut outs		
	e) Passenger side rear panel with (2) 4" round light cut outs		
19 .	Furnish & install entire rear bumper (ship loose existing)	\$	700.00
	Note: Reinforce rear bumper step		
	a) Driver side bumper cap		
	b) Center step		
	c) Passenger side bumper cap		
	d) Driver & passenger side dock bumper		
	e) Center bumper strip		
20 .	Furnish & install new Meltric single 30A twist lock shore power receptacle on driver's side front corner w/ (2) pigtails shipped loose (discard existing)	\$	900.00
	Note - do NOT reconnect existing shore power ignition kill switch in electrical compartment		
21 .	Furnish & install (1) Shelf 20" ID from floor of O2 compartment (standard height)	\$	200.00
	a) Discard existing shelves		
22 .	Furnish & install 3 high "D" cylinder holder in the O2 compartment next to the laydown O2 - route O2 hose to accommodate 3 high "D" cylinder holder	\$	300.00
23 .	Furnish & install Lambda power supply	\$	1,500.00
		Total \$	22,125.00

Module Interior Upgrades:


24 .	Items included in remount fee:	\$	incl.
	a) Replace all non-skid material on threshold(s) with 3M non-skid material		
	b) Complete detail of module interior:		
	c) Air filter		
	d) Remove & reinstall male and female seatbelts at squad bench & CPR seat		
	e) Discard wall holder above the CPR seat		
25 .	Furnish & install Blue cushions - single CPR seat - Protek backrest and headrests at seated positions on squad bench (location 1 and 3) and CPR Seat	\$	1,350.00
26 .	Replace floor with Alucabond subfloor and Lonseal Loncoin II, Onyx, instead of standard flooring (12' unit) (discard existing)	\$	3,250.00
	Note: please remove antler & bar prior to remount drop-off		
	a) Remove & reinstall lay down O2 box w/ fridge plate		
	Note: please remove fridge prior to remount drop-off		
	b) Replace thresholds (discard existing)		
	c) Remove & reinstall O2 rollers		

27 .	Install customer provided Stryker PerformanceLOAD system	\$	2,000.00
	Note - Install additional plating in baseframe		
28 .	Furnish & install Blue Captain's chair with 4 pt. harness (no child safety seat)	\$	1,350.00
29 .	Furnish & install P/S front wall cabinet (discard existing)	\$	600.00
30 .	Furnish & install front I/O w/ (1) shelf for a 12' unit with tube at the bottom for Eberhard latches & reinforced Lexan doors (discard existing)	\$	1,500.00
	a) Ship loose portable suction on shelf in front I/O	\$	50.00
	b) Remove & reinstall drug box on P/S of front I/O	\$	100.00
31 .	Furnish & install 22 pocket acrylic organizer stacked above squad bench (was PD1) between positions 1 & 3. Part B above and part A below	\$	600.00
32 .	Discard squad bench cabinet & install corner covers	\$	100.00
33 .	Furnish & install 17 1/2" (HFD style) end rail at the forward end of squad bench	\$	150.00
34 .	Reframe squad bench opening for White trash can in the top opening at the head of the squad bench	\$	350.00
	a) Discard glove box/end-rail combo		
35 .	Furnish & install small Frazer acrylic organizer forward of the CPR seat (discard existing)	\$	250.00
36 .	Furnish & install large Frazer acrylic organizer to the rear of the CPR seat (discard existing)	\$	350.00
37 .	Plate over rear end of action wall cabinet	\$	150.00
	Note - Use at cabinet A/W Cut size 0.80" x 23 7/8" x 12 1/2"		
38 .	Furnish & install new countertop aft of the CPR seat	\$	250.00
	Note - discard cabinet aft of the CPR seat & install new A/C cladding		
39 .	Furnish & install (8) Grote LED fixtures NO retrofit plates (discard existing)	\$	3,000.00
	Note - Standard interior light switching:		
	Note - Wire interior HIGH circuit ignition hot		
	a) Driver's side front single LED on a 3 way switch to the HIGH setting		
	b) ON/OFF interior light switch at the console that controls the front driver's side interior LED only		
	c) ON/OFF interior light switch at the action wall that controls the front driver's interior LED only		
	d) HIGH/OFF/LOW interior light switch at the action wall that controls all but one of the interior LED's		
		Total	\$ 15,400.00

Terms and Conditions

- 1 . This quote is valid for 90 days.
- 2 . Please note, payment for the entire purchase is due upon receipt and acceptance of completed unit.
- 3 . Please make your purchase order out to Frazer, Ltd. (7219 Rampart Houston, TX 77081). Please email a copy of your purchase order and this quote to Adam Fischer at sales@frazerbilt.com.
- 4 . To minimize delays, customer provided items should be present prior to unit production start.
- 5 . Please remove your A/C prior to remount delivery at Frazer.
- 6 . Please remove your Onan generator prior to remount delivery at Frazer.
- 7 . Fair condition of module is assumed when quoting paint. Large or excessive dents, deep or excessive scratches and unforeseen body work will require a revision to the quoted paint price.

Best Regards,



Kasey Gillum
Sales Team Leader
Frazer, Ltd.

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

OFFICE USE ONLY CERTIFICATION OF FILING

1 Name of business entity filing form, and the city, state and country of the business entity's place of business.

Frazer, Ltd.
Houston, TX United States

Certificate Number:
2017-194713

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.

Fort Bend County

Date Filed:
04/19/2017

Date Acknowledged:

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.

13317
Remount of Ambulance w/ upgrades

4	Name of Interested Party	City, State, Country (place of business)	Nature of interest (check applicable)	
			Controlling	Intermediary

5 Check only if there is NO Interested Party.



6 AFFIDAVIT

I swear, or affirm, under penalty of perjury, that the above disclosure is true and correct.



Jerry D. Ward
Signature of authorized agent of contracting business entity

AFFIX NOTARY STAMP / SEAL ABOVE

Sworn to and subscribed before me, by the said Jerry D. Ward, this the 18th day of April, 2017, to certify which, witness my hand and seal of office.

Nicole Martinez
Signature of officer administering oath

Nicole Martinez
Printed name of officer administering oath

HR Manager / Notary
Title of officer administering oath