

THE STATE OF TEXAS §
 §
COUNTY OF FORT BEND §

**RESOLUTION AND ORDER DECREERING THE ACQUISITION OF
PROPERTY TO BE A PUBLIC NECESSITY AND AUTHORIZING THE
ACQUISITION AND PAYMENT OF COMPENSATION**

WHEREAS, on the ____ day of _____, 2017, at a regular meeting of the Commissioners Court of Fort Bend County, Texas, sitting as the governing body of Fort Bend County, upon motion of Commissioner _____, seconded by Commissioner _____, and upon record vote, passed ____ votes in favor ____ votes opposed:

RESOLUTION

RESOLVED THAT WHEREAS, the Commissioners Court has received and reviewed the plans for a public project known as the Sansbury Expansion Project, located from Williams Way to Grand Estates Drive, in Fort Bend County, Texas; and,

WHEREAS, Commissioners Court has determined that public necessity and convenience exists for the location, alignment, construction, operation, and maintenance, including appurtenant drainage and detention requirements, of a public project known as the Sansbury Expansion Project, located from Williams Way to Grand Estates Drive, in Fort Bend County, Texas, in accordance with said plans, alignment, and tract identifications which are made a part hereof as Exhibit A:

ORDER

NOW THEREFORE, IT IS ORDERED AND DECREED that the plans for the location, alignment, construction, operation, and maintenance, including appurtenant drainage and detention requirements, of the public project known as the Sansbury Expansion Project, located from Williams Way to Grand Estates Drive, in Fort Bend County, Texas, is approved.

IT IS FURTHER ORDERED AND DECREED that public necessity and convenience exist for the public project, known as the Sansbury Expansion Project, located from Williams Way to Grand Estates Drive, in Fort Bend County, Texas, and that the County Engineer be authorized and directed to obtain appraisals, surveys, title information and/or make official offers of specific

amount for the purchase of either easement or the fee simple interest in and to the tract(s) situated within such alignment as shown in Exhibit A; that the County Attorney be authorized and directed, and he is hereby authorized and directed to file or cause to be filed proceedings in eminent domain and to acquire thereby easement or fee simple interest for said purposes in the tract(s) which cannot be acquired as aforesaid by donation, dedication, or purchase.

IT IS FURTHER ORDERED AND DECREED that this Resolution and Order apply to any and all parcels of land that must be condemned for this project, that the County Judge, or designated representative be authorized and directed to sign any papers or agreements associated with closing the purchase(s); the County Attorney, County Clerk, County Auditor and County Treasurer be authorized and directed to perform any and all necessary acts within their respective spheres of official duties toward the final acquisition of the tract(s) of land, or interest(s) therein, together with the improvement if any, within the said public project known as the Sansbury Expansion Project, located from Williams Way to Grand Estates Drive, in Fort Bend County, Texas and the payment and compensation therefore.

PASSED AND APPROVED this ____ day of _____, 2017.

FORT BEND COUNTY

Robert E. Hebert, County Judge

ATTEST:

Laura Richard, County Clerk

EXHIBIT "A"

Page 1 of 3

PARCEL 1

DESCRIPTION OF A TRACT OF LAND CONTAINING
2.3121 ACRES (100,716 SQUARE FEET) SITUATED IN
THE JOSEPH KUYKENDAHL LEAGUE, A-49
FORT BEND COUNTY, TEXAS

Being a tract of land containing 2.3121 acres (100,716 square feet) situated in the Joseph Kuykendahl League, A-49, Fort Bend County, Texas, being a portion of Lot 5, J.W. Blakely Subdivision, a subdivision recorded in Volume Q, Page 554 of the Fort Bend County Deed Records and being out of and a part of a called 3.761-acre tract conveyed unto TD Phan Ltd. by deed recorded under County Clerk's File No. 2008088570 and being out of and a part of a called 4.0525-acre tract conveyed unto TDPhan, Ltd. by deed recorded under County Clerk's File No. 2007049506, both of the Official Public Record of Fort Bend County, Texas. Said 2.3121-acre tract being more particularly described by metes and bounds as follows:

Note: The bearings referenced herein are grid values, based on the Texas Coordinate System of 1983 (NAD83, 2011 Adjustment), South Central Zone. All coordinates shown herein are grid values. Multiply by a combined adjustment factor of 1.00013 to convert to surface values.

COMMENCING FOR REFERENCE at a point located in the existing southeasterly right-of-way line of Williams Way (120 feet wide, recorded in Volume 1059, Page 622 and Volume 2720, Page 362, both of the Deed Records of Fort Bend County, Texas and under County Clerk's File No. 8541747 of the Official Public Records of Fort Bend County, Texas) for the southwest corner of said 3.761-acre tract and for the northwest corner of Reserve "K" of the Retreat at Sovereign Shores, a subdivision of recorded under Plat Number 20070041, of the Plat Records of Fort Bend County, Texas, from which a found 1-inch iron pipe bears South 60° 32" East, a distance of 0.33 feet;

THENCE North 21° 57' 27" East with the existing southeasterly right-of-way line of said Williams Way and the northwesterly line of said 3.761-acre tract, a distance of 44.48 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set at the intersection of the southeasterly right-of-way line of said Williams Way and the proposed southeasterly right-of-way line of Sansbury Boulevard (width varies) for the southwesterly corner of the herein described tract and for the **POINT OF BEGINNING** having grid coordinates of X=3,011,509.93, and Y=13,764,826.14;

THENCE North 21° 57' 27" East continuing with the existing southeasterly right-of-way line of said Williams Way and the northwesterly line of said 3.761-acre tract, a distance 182.00 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set in the proposed northwesterly right-of-way line of said Sansbury Boulevard for the northwesterly corner of said herein described tract;

THENCE along the proposed northwesterly right-of-way line of said Sansbury Boulevard the following courses and distances:

1. South 23° 02' 33" East, a distance of 35.36 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates" for corner;
2. South 68° 02' 33" East, a distance of 239.69 feet to a set 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" for corner;
3. South 63° 05' 54" East, a distance of 100.00 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates" for corner, and being the beginning of a non-tangent curve to the left;
4. Easterly, with the arc of said non-tangent curve to the left having a radius of 1,140.00 feet and a central angle of 22° 04' 51" (chord bears South 83° 29' 49" East, a distance of 436.62 feet) at an arc length of 60.27 feet passing the northerly line of said 3.761-acre tract and the southerly line of said 4.0525-acre tract, continuing for a total arc length of 439.34 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set in the easterly line of said 4.0525-acre tract, the westerly line of the residue of a called 93.056-acre tract conveyed unto Lakes of Williams Ranch, Ltd. by deed recorded under County Clerk's File No. 2005100129 of the Official Public Records of Fort Bend County, Texas, for the northeasterly corner of herein described tract, said point being South 21° 45' 45" West, a distance of 90.39 feet from a found 1/2-inch iron rod located at the northeast corner of said 4.0525-acre tract;

THENCE South 21° 45' 45" West with the easterly line of said 4.0525-acre tract, the westerly line of the residue of said 93.056-acre tract, a distance of 132.33 feet to a set 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" in the proposed southeasterly right-of-way line of said Sansbury Boulevard for the southeasterly corner of herein described tract and for the beginning of a non-tangent curve to the right, said point being South 21° 45' 45" West, a distance of 14.01 feet from a found 5/8-inch iron rod located at the northeast corner of said 3.761-acre tract;

THENCE along the proposed southeasterly right-of-way line of said Sansbury Boulevard the following courses and distances:

1. Westerly, with the arc of said non-tangent curve to the right having a radius of 1,260.00 feet and a central angle of 23° 49' 40" (chord bears North 79° 57' 23" West, a distance of 520.23 feet) for an arc distance of 524.00 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set for a point of tangency;
2. North 68° 02' 33" West, a distance of 251.58 feet to a set 5/8-inch iron rod with cap stamped "Cobb Fendley & Associates" for corner;

3. South $66^{\circ} 57' 27''$ West, a distance of 35.36 feet to the **POINT OF BEGINNING** and containing 2.3121 acres (100,716 square feet).

Note: This metes and bounds description is referenced to a survey drawing prepared by Cobb, Fendley & Associates, Inc. of even date.

Cobb, Fendley & Associates, Inc.
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
Phone: 713-462-3242

Job No. 1711-006-01

April 12, 2017



A handwritten signature in black ink, appearing to be "KCS", written below the professional seal.

NOTES:

1. ALL BEARINGS AND COORDINATES SHOWN HEREIN ARE GRID VALUES, REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983, TEXAS, SOUTH CENTRAL ZONE NO. 4204, NAD 83 (2011) COORDINATES MAY BE BROUGHT TO SURFACE VALUES BY APPLYING A SURFACE ADJUSTMENT FACTOR OF 1.00013.
2. ALL VERTICAL DATUM REFERENCED HEREIN IS BASED ON NAVD83 VALUES. REFERENCE BENCHMARK IS NATIONAL GEODETIC SURVEY MONUMENT PID NO. 484730, LOCATED ON THE FRONT OF THE HISTORIC COURTHOUSE BUILDING IN THE CITY OF RICHMOND, TEXAS.
3. ALL FIELD INFORMATION SHOWN HEREON IS BASED ON AN "ON-THE-GROUND" SURVEY PERFORMED BY COBB, FENDLEY & ASSOCIATES, INC., DURING THE MONTHS OF APRIL AND MAY, 2015.
4. 5/8-INCH IRON RODS WITH YELLOW CAPS STAMPED "COBB FENDLEY & ASSOCIATES" SET AT ALL TRACT CORNERS UNLESS NOTED OTHERWISE.
5. ALL PARCELS ARE REFERENCED TO METES AND BOUNDS DESCRIPTIONS PREPARED BY COBB, FENDLEY & ASSOCIATES, INC. OF EVEN DATE.
6. THE WORD CERTIFY IS UNDERSTOOD TO BE AN EXPRESSION OF PROFESSIONAL JUDGMENT BY THE SURVEYOR, WHICH IS BASED ON HIS/HER BEST KNOWLEDGE, INFORMATION AND BELIEF.
7. SQUARE FOOTAGE AREA SHOWN HEREON IS FOR INFORMATION ONLY AND SURVEYOR DOES NOT CERTIFY ACCURACY OF SURVEY TO NEAREST SQUARE FOOT.

FLOODPLAIN INFORMATION

THE PROPERTY SHOWN HEREON (EITHER IN TOTAL OR A PORTION) IS LOCATED IN THE FOLLOWING ZONE(S) BASED ON THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP 48157C0265L, LAST REVISED APRIL 2, 2014:

SHADED ZONE X - AREAS OF 0.2% ANNUAL CHANCE FLOOD AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.

ZONE AE (FLOODWAY) - THE FLOODWAY IS THE CHANNEL OF A STREAM PLUS ANY ADJACENT FLOODPLAIN AREAS THAT MUST BE KEPT FREE OF ENCROACHMENT SO THAT THE 1% ANNUAL CHANCE FLOOD CAN BE CARRIED WITHOUT SUBSTANTIAL INCREASES IN FLOOD HEIGHTS.

ELEVATIONS WERE NOT OBTAINED ON THE SUBJECT TRACT TO DETERMINE THE FLOOD ZONES.

DETERMINATION OF THE FLOOD ZONE IS BASED ON THE GRAPHICAL DELINEATION OF THE ZONES AS DEPICTED ON THE FLOOD PLAIN MAPS.

IF THIS PROPERTY IS NOT WITHIN AN IDENTIFIED FLOOD HAZARD AREA, THIS INFORMATION DOES NOT IMPLY THAT THE PROPERTY AND/OR STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE. ON RARE OCCASIONS GREATER FLOODS CAN OCCUR AND FLOOD HEIGHTS MAY BE INCREASED BY MAN-MADE OR NATURAL CAUSES. THIS FLOODPLAIN INFORMATION SHALL NOT CREATE LIABILITY ON THE PART OF THE SURVEYOR.

AREA SUMMARY

PARCEL	EXISTING	OWNER	FILE NO./F.C. NO.	TAKING		REMAINING/CALC	
				TOTAL		LEFT	RIGHT
1	4,0525 (CALLED)	TD PHAN, LTD.	FILE NO. 2007049506	2,3121 AC. 100,716 SQ.FT.	0.3998 AC. 17,414 SQ.FT.	3.3590 AC.	N/A
	3.761 (CALLED)	TD PHAN, LTD.	FILE NO. 2008088570	1,8098 AC. 78,835 SQ.FT.		0.0379 AC.	1.8168 AC.


SURVEYOR'S CERTIFICATE

IN MY PROFESSIONAL OPINION, THIS PLAT REPRESENTS THE FACTS FOUND ON THE GROUND DURING THE COURSE OF A BOUNDARY SURVEY CONDUCTED UNDER MY SUPERVISION DURING THE MONTHS OF APRIL AND MAY, 2015 AND THAT THIS SURVEY SUBSTANTIALLY COMPLIES WITH THE CURRENT STANDARDS OF PRACTICE OF THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING.

WITNESS MY HAND AND SEAL THIS 12TH DAY OF APRIL, 2017, AT HOUSTON, TEXAS.

[Signature]

KYLE CARSON SUNDAY
REGISTERED PROFESSIONAL LAND SURVEYOR #5924



NO.	DESCRIPTION	DATE



TBPE Firm Registration No. 274
TBPLS Firm Registration No. 100487
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbhendley.com

FORT BEND COUNTY
MOBILITY PROJECTS

SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS

PARCEL 1

SCALE: HORIZ. 20' GRAPHIC	DATE: 03/28/2017	APP'D:	BY: 01 OF 04
VERT. 4'0" (1:12.7)	DATE: 03/28/2017	DATE: 03/28/2017	DATE: 03/28/2017
DATE: 03/28/2017	DATE: 03/28/2017	DATE: 03/28/2017	DATE: 03/28/2017

FND 5/8" I.R.
(CM)
EXISTING R.O.W.

FND 1/2" I.R.
(N49°01'E, 0.96')

120.00'

MANFORD BOULEVARD
(120' WIDE)

SOVEREIGN SHORES ESTATES
FILE NO. 2364B,
P.R.F.B.C.
FILE NO. 2002103700
P.R.F.B.C.

EXISTING R.O.W.
FND 5/8" I.R.
(CM)

LOT 1
BLOCK 5

EXISTING R.O.W.

WILLIAMS WAY
120' WIDE

VOL. 1059, PG. 622 D.R.F.B.C.
VOL. 2720, PG. 362 D.R.F.B.C.
FILE NO. 8541747 O.P.R.F.B.C.

JOSEPH KUYKENDAH
ABSTRACT NO. 49

0 20 40



N21°57'27"E 182.00'
EXISTING R.O.W.

N21°57'27"E 44.48'
EXISTING R.O.W.

TD PHAN, LTD.
4.0525 ACRES
FILE NO. 2007049506
O.P.R.F.B.C.

S 23°02'33" E 35.36'
S 68°02'33" E 239.69'
PROPOSED R.O.W.

PARCEL 1 =
2.3121 ACRES
(100,716 SQ.FT.)
OWNER: TDPHAN, LTD.

TD PHAN, LTD.
3.761 ACRES
FILE NO. 2008088570
O.P.R.F.B.C.

N 68°02'33" W 251.58'
PROPOSED R.O.W.

POB PARCEL 1
X = 3,011,509.93
Y = 13,764,826.14

RESERVE "K"
RETREAT AT
SOVEREIGN SHORES
FILE NO. 20070041
P.R.F.B.C.
POC PARCEL 1
FND 1" I.P.
(S60°32'E, 0.33')

MATCHLINE 1 OF 2

CobbFendley
TBP Firm Registration No. 274
TBP Plus Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbhendley.com

**FORT BEND COUNTY
MOBILITY PROJECTS**
SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS
PARCEL 1

SCALE: HORIZONTAL - 40'	DRAWN BY: JCS	CHECKED BY: JCS	SHEET #
DATE: 03/20/2017	APPROVED BY:		92 OF 9

TD PHAN, LTD.
4.0525 ACRES
FILE NO. 2007049506
O.P.R.F.B.C.

A=439.34'
R=1,140.00'
D=22°04'51"
CB=S 83°29'49" E
CH=436.62'

PARCEL 1 =

2.3121 ACRES
(100,716 SQ.FT.)
OWNER: TDPHAN, LTD.
TD PHAN, LTD.
3.761 ACRES
FILE NO. 2008088570
O.P.R.F.B.C.

JOSEPH KUYKENDAHL LEAGUE
ABSTRACT NO. 49


100' DRAINAGE EASEMENT
FORT BEND COUNTY
DRAINAGE DISTRICT
VOL. D.R.F.B.C. 516

PROPOSED
R.O.W.

A=524.00'
R=1,260.00'
D=23°49'40"
CB=N 79°57'23" W
CH=520.23'

MATCHLINE 1 OF 2

MATCHLINE 2 OF 2



CobbFendley

TBPE Firm Registration No. 274
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbhendley.com

FORT BEND COUNTY
MOBILITY PROJECTS

SANSBURY BOULEVARD

PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS
PARCEL 1

SCALE: HORIZ. 1" = 40'	DATE
DRAWN BY: [blank]	DATE: 03/20/2017
CHECKED BY: [blank]	DATE: [blank]
DESIGNED BY: [blank]	DATE: [blank]
IN CHARGE: [blank]	DATE: [blank]
DATE: 03/20/2017	DATE: [blank]

I R
(CM)

100.

A=439.34'
R=1,140.00'
D=22°04'51"
CB=S 83°29'49" E
CH=438.62'

PROPOSED R.O.W.

TD PHAN, LTD.
4.0525 ACRES
FILE NO. 2007049506
O.P.R.F.B.C.

TD PHAN, LTD.
3.761 ACRES
FILE NO. 2008088570
O.P.R.F.B.C.

A=524.00'
R=1,260.00'
D=23°49'40"
CB=N 79°57'23" W
CH=520.23'

JOSEPH KUYKENDAHLE LEAGUE
ABSTRACT NO. 49

PARCEL 1 =
2.3121 ACRES
(100, 716 SQ. FT.)
OWNER: TDPHAN, LTD.

MATCHLINE 2 OF 2

PROPOSED
R. O. W.

RESIDUE OF 93.056 ACRES
LAKES OF WILLIAMS RANCH, LTD.
FILE NO. 2005100129
O.P.F.R.B.C.

9.925 ACRES
FORT BEND COUNTY
DRAINAGE DISTRICT
FILE NO. 2010097931
O.P.R.F., B.C.

NO.	DESCRIPTION	DATE
-----	-------------	------



CobbFendley

1B/E Firm Registration No. 2/74
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | Fax 713.462.3262
www.cobbfindley.com

**FORT BEND COUNTY
MOBILITY PROJECTS**

SANSBURY BOULEVARD

**PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS
PARCEL 1**

SCALE: HORIZ: 1" = 40'	DSN: KCS	Hwy NO.
	Q: MCS	
	DSN: BM	SHEET NO.
DATE: 03/26/2017	APPD:	94.05 84.05

PARCEL 2A

DESCRIPTION OF A TRACT OF LAND CONTAINING
1.6375 ACRES (71,328 SQUARE FEET) SITUATED IN
THE JOSEPH KUYKENDAHL LEAGUE, A-49
FORT BEND COUNTY, TEXAS

Being a tract of land containing 1.6375 acres (71,328 square feet) situated in the Joseph Kuykendahl League, A-49, Fort Bend County, Texas, being a part of Lot 5 and Lot 6 of the J.W. Blakely subdivision, recorded under Volume Q, Page 554 of the Deed Records of Fort Bend County, Texas, and a part of a 33.5075-acre (Tract I) conveyed unto The Estates at Lakes of Williams Ranch, Ltd., recorded under County Clerk's File No. 2016134407 of the Official Public Records of Fort Bend County, Texas. Said 1.6375-acre tract being more particularly described by metes and bounds as follows:

Note: The bearings referenced herein are grid values based on the Texas Coordinate System of 1983 (NAD83, 2011 Adjustment), South Central Zone. All coordinates shown herein are grid values. Multiply by a combined adjustment factor of 1.00013 to convert to surface values.

COMMENCING FOR REFERENCE at a found 1/2-inch iron rod located at the northeast corner of a called 4.0525-acre tract conveyed unto TDPHAN, Ltd., by deed recorded under County Clerk's File No. 2007049506 of the Official Public Records of Fort Bend County, Texas, and being in the southwest property line of the residue of a called 63.107-acre tract conveyed unto Williams Way Partnership, Ltd., by deed recorded under County Clerk's File No. 9680818 of the Official Public Records of Fort Bend County, Texas;

THENCE South 21° 45' 45" West with the southeasterly property line of said 4.0525-acre tract and the westerly property line of the residue of said Williams Way Partnership, Ltd. tract, a distance of 59.68 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set in the proposed northwesterly right-of-way line of Sansbury Boulevard (width varies) for the northwesterly corner of herein described tract, for the beginning of a non-tangent curve to the left and **POINT OF BEGINNING**, having grid coordinates of X=3,012,348.39 and Y=13,762,806.61;

THENCE in a northeasterly direction, along the proposed northerly right-of-way line of said Sansbury Boulevard, same being the south property line of said residue of 63.107-acre tract, and the north line of said 33.5075-acre tract, with the arc of said non-tangent curve to the left having a radius of 2,060.00 feet and a central angle of 10° 09' 18" (chord bears North 76° 56' 23" East, a distance of 364.63 feet) for an arc distance of 365.11 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", for the northwest corner of a 2.2741-acre tract conveyed unto Fort Bend County M.U.D. No. 116, by deed recorded under County Clerk's File No. 2016130081 of the Official Public Records of Fort Bend County, Texas;

THENCE South $71^{\circ} 00' 45''$ East with the northeast property line of said 33.5075-acre tract, same being the southwest property line of said 2.2741-acre tract, a distance of 126.67 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", for corner;

THENCE South $28^{\circ} 16' 02''$ East continuing with the northeast property line of said 33.5075-acre tract, same being the southwest property line of said 2.2741-acre tract, a distance of 47.44 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", in the proposed southerly right-of-way line of said Sansbury Boulevard, for the easternmost corner of said tract herein described, and for the beginning of a non-tangent curve to the right;

THENCE along the proposed southerly right-of-way line of said Sansbury Boulevard, with the arc of said non-tangent curve to the right having a radius of 1,260.00 feet and a central angle of $26^{\circ} 30' 57''$ (chord bears South $74^{\circ} 52' 18''$ West, a distance of 577.93 feet) for an arc distance of 583.11 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set in the northwesterly line of the of said 33.5075-acre tract, and the southeasterly line of a called 3.761-acre tract conveyed unto TD PHAN, Ltd., by deed recorded under County Clerk's File No. 2008088570 of the Official Public Records of Fort Bend County, Texas, for the southwesterly corner of herein described tract;

THENCE North $21^{\circ} 45' 45''$ East with the northwesterly line of said 33.5075-acre tract, and the southeasterly line of said 3.761-acre tract, at a distance of 14.01 feet passing a 5/8-inch iron rod found for the northeasterly corner of said 3.761-acre tract, same being the southeasterly corner of said 4.0525-acre tract, continuing for a total distance of 163.05 feet to the **POINT OF BEGINNING** and containing 1.6375 acres (71,328 square feet).

Note: This metes and bounds description is referenced to a survey drawing prepared by Cobb, Fendley & Associates, Inc. of even date.

Cobb, Fendley & Associates, Inc.
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
Phone: 713-462-3242

Job No. 1711-006-01

April 18, 2017



NOTES:

1. ALL BEARINGS AND COORDINATES SHOWN HEREIN ARE GRID VALUES, REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983, TEXAS, SOUTH CENTRAL ZONE NO. 4204, NAD 83 (2011) COORDINATES MAY BE BROUGHT TO SURFACE VALUES BY APPLYING A SURFACE ADJUSTMENT FACTOR OF 1.00013.
2. ALL VERTICAL DATUM REFERENCED HEREIN IS BASED ON NAD83. ALL VERTICAL REFERENCE BENCHMARK IS NATIONAL GEODETIC SURVEY MONUMENT AND NO. 41120 LOCATED ON THE CORNER OF THE HISTORIC COURTHOUSE BUILDING IN THE CITY OF RICHMOND, TEXAS.
3. ALL FIELD INFORMATION SHOWN HEREON IS BASED ON AN "ON-THE-GROUND" SURVEY PERFORMED BY COBB, FENDLEY & ASSOCIATES, INC., DURING THE MONTHS OF APRIL AND MAY, 2015.
4. 5/8-INCH IRON RODS WITH YELLOW CAPS STAMPED "COBB FENDLEY & ASSOCIATES" SET AT ALL TRACT CORNERS UNLESS NOTED OTHERWISE.
5. ALL PARCELS ARE REFERENCED TO METES AND BOUNDS DESCRIPTIONS PREPARED BY COBB, FENDLEY & ASSOCIATES, INC. OF EVEN DATE.
6. THE WORD CERTIFY IS UNDERSTOOD TO BE AN EXPRESSION OF PROFESSIONAL JUDGMENT BY THE SURVEYOR, WHICH IS BASED ON HIS/HER BEST KNOWLEDGE, INFORMATION AND BELIEF.
7. SQUARE FOOTAGE AREA SHOWN HEREON IS FOR INFORMATION ONLY AND SURVEYOR DOES NOT CERTIFY ACCURACY OF SURVEY TO NEAREST SQUARE FOOT.

FLOODPLAIN INFORMATION

THE PROPERTY SHOWN HEREON (EITHER IN TOTAL OR A PORTION) IS LOCATED IN THE FOLLOWING ZONE (S) BASED ON THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP 48157C0265L, LAST REVISED APRIL 2, 2014:

SHADED ZONE X - AREAS OF 0.2% ANNUAL CHANCE FLOOD; AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH BRAKAGE AREAS LESS THAN 1 SQUARE MILE; FLOOD AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.

ZONE A6 (FLOODWAY) - THE FLOODWAY IS THE CHANNEL OF A STREAM PLUS ANY ADJACENT FLOODPLAIN AREAS THAT MUST BE KEPT FREE OF ENCROACHMENT SO THAT THE 1% ANNUAL CHANCE FLOOD CAN BE CARRIED WITHOUT SUBSTANTIAL INCREASES IN FLOOD HEIGHTS.

ELEVATIONS WERE NOT OBTAINED ON THE SUBJECT TRACT TO DETERMINE THE FLOOD ZONES.

DETERMINATION OF THE FLOOD ZONE IS BASED ON THE GRAPHICAL DELINEATION OF THE ZONES AS DEPICTED ON THE FLOOD PLAIN MAPS.

IF THIS PROPERTY IS NOT WITHIN AN IDENTIFIED FLOOD HAZARD AREA, THIS INFORMATION DOES NOT IMPLY THAT THE PROPERTY IS FREE OF FLOODING. THERE ARE OCCASIONS WHEN FLOODS OCCUR AND FLOOD HEIGHTS MAY BE INCREASED BY MAN-MADE OR NATURAL CAUSES. THIS FLOODPLAIN INFORMATION SHALL NOT CREATE LIABILITY ON THE PART OF THE SURVEYOR.

AREA SUMMARY

PARCEL	EXISTING	OWNER	FILE NO./F.C. NO.	TAKING	REMAINDER
2A	33.8075 AC TRACT B	THE ESTATES AT LAMAR, L.P.	FILE NO. 208634407	16376 AC 71,328 SQ. FT.	318700 AC.


SURVEYOR'S CERTIFICATE

IN MY PROFESSIONAL OPINION, THIS PLAT REPRESENTS THE FACTS FOUND ON THE GROUND DURING THE COURSE OF A BOUNDARY SURVEY CONDUCTED UNDER MY SUPERVISION DURING THE MONTHS OF APRIL AND MAY, 2015 AND THAT THIS SURVEY SUBSTANTIALLY COMPLIES WITH THE CURRENT STANDARDS OF PRACTICE OF THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING.

WITNESS MY HAND AND SEAL THIS 18TH DAY OF APRIL, 2017, AT HOUSTON, TEXAS.

[Signature]

KYLE CARSON SUNDAY
REGISTERED PROFESSIONAL LAND SURVEYOR #5924



CobbFendley


TSP# Firm Registration No. 274
TSP#S Firm Registration No. 100467
13430 Northwest Freeway Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbendley.com

FORT BEND COUNTY
MOBILITY PROJECTS

SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS

PARCEL 2A

NO.	DESCRIPTION	DATE
1	13430 NW Freeway Suite 1100	11/11/14
2	13430 NW Freeway Suite 1100	11/11/14
3	13430 NW Freeway Suite 1100	11/11/14
4	13430 NW Freeway Suite 1100	11/11/14
5	13430 NW Freeway Suite 1100	11/11/14
6	13430 NW Freeway Suite 1100	11/11/14
7	13430 NW Freeway Suite 1100	11/11/14
8	13430 NW Freeway Suite 1100	11/11/14
9	13430 NW Freeway Suite 1100	11/11/14
10	13430 NW Freeway Suite 1100	11/11/14

[illegible]

40' DRAINAGE EASEMENT
FORT BEND COUNTY
DRAINAGE DISTRICT
VOL. 314, PG. 61
D. R. F. B. C.

A=365.11'
R-2, 060.00'
D=10° 09' 18"
CB-N 76° 56' 23" E
CH=364.63'


PARCEL 2A =
1.6375 ACRES
(71, 328 SQ. FT.)
OWNER: THE ESTATES AT
LAKES OF WILLIAMS
RANCH, LTD.

149.29

PROPOSED R.O.W.

31.8700 ACRES (CAI C.) D=26° 30' 57"
RESIDUE OF 33.5075 ACRES (TRACT 1) CB=S 74° 52' 18 W
THE ESTATES AT CH=577.93'
LAKES OF WILLIAMS RANCH, LTD.
FILE NO. 2016134407
O.P.R.F.B.C.

JOSEPH KUYKENDAHLE LEAGUE
ABSTRACT No. 49

[illegible]

40' DRAINAGE EASEMENT
 FORT BEND COUNTY
 DRAINAGE DISTRICT
 VOL. 314, PG. 61
 D.R.F.B.C.

WILLIAMS WAY PARTNERSHIP, LTD.
 RESIDUE OF CALLED 63.107 ACRE
 FILE NO. 9680818
 O.P.R.F.B.C.

PROPOSED R.O.W.


MATCHLINE 2 OF 2

PARCEL 2A =
 1.6375 ACRES
 (71,328 SQ.FT.)
 OWNER: THE ESTATES AT
 LAKES OF WILLIAMS
 RANCH, LTD.

2.2741 ACRES
 FORT BEND COUNTY M.U.D. NO. 116
 FILE NO. 2016130081
 O.P.R.F.B.C.

4.0528 ACRES (CALC.)
 RESIDUE OF 4.6041 ACRES (TRACT 11)
 THE ESTATES AT
 LAKES OF WILLIAMS RANCH, LTD.
 FILE NO. 2016134407
 O.P.R.F.B.C.

PROPOSED R.O.W.



JOSEPH KUYKENDAHLE LEAGUE
 ABSTRACT NO. 49

NO.	DESCRIPTION	DATE

CobbFendley
TSPE Firm Registration No. 274
 TSPS Firm Registration No. 100467
 13430 Northwest Freeway, Suite 1100
 Houston, Texas 77040
 713.462.3242 | fax 713.462.3262
 www.cobbfendley.com

**FORT BEND COUNTY
 MOBILITY PROJECTS**

SANSBURY BOULEVARD

**PROPOSED RIGHT-OF-WAY
 FORT BEND COUNTY, TEXAS
 PARCEL 2A**

SCALE: HORIZ. 1" = 40'	DATE: 03/23/2017
DRAWN BY: JAP/UD	SHEET NO. 34 OF 84

PARCEL 6

**DESCRIPTION OF A TRACT OF LAND CONTAINING
0.4833 ACRES (21,054 SQUARE FEET) SITUATED IN
THE JOSEPH KUYKENDAHL LEAGUE, A-49
FORT BEND COUNTY, TEXAS**

Being a tract of land containing 0.4833 acres (21,054 square feet) situated in the Joseph Kuykendahl League, A-49, Fort Bend County, Texas, being a part of Lot 5 and Lot 6 of the J.W. Blakely subdivision, recorded under Volume Q, Page 554 of the Deed Records of Fort Bend County, Texas, and a part of a 2.2741-acre tract conveyed unto Fort Bend County M.U.D. No. 116, by deed recorded under County Clerk's File No. 2016130081 of the Official Public Records of Fort Bend County, Texas. Said 0.4833-acre tract being more particularly described by metes and bounds as follows:

Note: The bearings referenced herein are grid values based on the Texas Coordinate System of 1983 (NAD83, 2011 Adjustment), South Central Zone. All coordinates shown herein are grid values. Multiply by a combined adjustment factor of 1.00013 to convert to surface values.

COMMENCING FOR REFERENCE at a found 1/2-inch iron rod located at the northeast corner of a called 4.0525-acre tract conveyed unto TDPHAN, Ltd., by deed recorded under County Clerk's File No. 2007049506 of the Official Public Records of Fort Bend County, Texas, and being in the southwest property line of the residue of a called 63.107-acre tract conveyed unto Williams Way Partnership, Ltd., by deed recorded under County Clerk's File No. 9680818 of the Official Public Records of Fort Bend County, Texas;

THENCE South 21° 45' 45" West with the southeasterly property line of said 4.0525-acre tract and the westerly property line of the residue of said Williams Way Partnership, Ltd. tract, a distance of 59.68 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set in the proposed northwesterly right-of-way line of Sansbury Boulevard (width varies) for the northwesterly corner of a 33.5075-acre tract (Tract I) conveyed unto The Estates at Lakes of Williams Ranch, Ltd., by deed recorded under County Clerk's File No. 2016134407 of the Official Public Records of Fort Bend County, Texas, for the beginning of a non-tangent curve to the left;

THENCE in a northeasterly direction, with the proposed northerly right-of-way line of said Sansbury Boulevard, same being the south property line of said residue of 63.107-acre tract, and the north line of said 33.5075-acre tract, with the arc of said non-tangent curve to the left having a radius of 2,060.00 feet and a central angle of $10^{\circ} 09' 18''$ (chord bears North $76^{\circ} 56' 23''$ East, a distance of 364.63 feet) for an arc distance of 365.11 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", for the northwest corner of said 2.2741-acre tract, for the westernmost corner of said tract herein described and **POINT OF BEGINNING**, having grid coordinates of X=3,012,703.55 and Y=13,762,889.00;

THENCE continuing in a northeasterly direction, with the proposed northerly right-of-way line of said Sansbury Boulevard, same being the south property line of said residue of 63.107-acre tract, and the north line of said 2.2741-acre tract, and with said curve to the left having a radius of 2,060.00 feet and a central angle of $07^{\circ} 46' 01''$ (chord bears North $67^{\circ} 58' 44''$ East, a distance of 279.03 feet) for an arc distance of 279.25 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", for the northernmost corner of said 2.2741-acre tract, and for the westernmost corner of a 4.6041-acre tract (Tract II) conveyed unto The Estates at Lakes of Williams Ranch, Ltd., by deed recorded under County Clerk's File No. 2016134407 of the Official Public Records of Fort Bend County, Texas, and for the northernmost corner of said tract herein described;

THENCE South $12^{\circ} 57' 38''$ West, with the easterly property line of said 2.2741-acre tract and the westerly property line of said 4.6041-acre tract, a distance of 85.57 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", for corner;

THENCE South $28^{\circ} 16' 02''$ East, continuing with the common property line of said 2.2741-acre tract and said 4.6041-acre tract, a distance of 38.21 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", for corner in the proposed southerly right-of-way line of said Sansbury Boulevard, and the beginning of a non-tangent curve to the right;

THENCE with the proposed southerly right-of-way line of said Sansbury Boulevard, with the arc of said non-tangent curve to the right having a radius of 1,260.00 feet and a central angle of $06^{\circ} 09' 06''$ (chord bears South $58^{\circ} 32' 17''$ West, a distance of 135.28 feet) for an arc distance of 135.28 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set in the westerly property line of said 2.2741-acre tract, same being the easterly property line of said 33.5075-acre tract;

THENCE North $28^{\circ} 16' 02''$ West, continuing with the common property line between said 2.2741-acre tract and said 33.5075-acre tract, a distance of 47.44 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", for corner;

THENCE North 71° 00' 45" West, continuing with the common property line between said 2.2741-acre tract and said 33.5075-acre tract, a distance of 126.67 feet to the **POINT OF BEGINNING** and containing 0.4833 acres (21,054 square feet).

Note: This metes and bounds description is referenced to a survey drawing prepared by Cobb, Fendley & Associates, Inc. of even date.

Cobb, Fendley & Associates, Inc.
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
Phone: 713-462-3242

Job No. 1711-006-01

April 18, 2017



A handwritten signature in black ink, appearing to read "KCS", written over the bottom portion of the professional seal.

NOTES:

1. ALL BEARINGS AND COORDINATES SHOWN HEREIN ARE GRID VALUES REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983, TEXAS SOUTH CENTRAL ZONE NO. 4204, NAD 83 (2011) COORDINATES MAY BE BROUGHT TO SURFACE VALUES BY APPLYING A SURFACE ADJUSTMENT FACTOR OF 1.00013.
2. ALL VERTICAL DATUM REFERENCED HEREIN IS BASED ON NAVD83 VALUES. REFERENCE BENCHMARK IS NATIONAL GEODETIC SURVEY MONUMENT PID NO. 474730, LOCATED ON THE FRONT OF THE HISTORIC COURTHOUSE BUILDING IN THE CITY OF RICHMOND, TEXAS.
3. ALL FIELD INFORMATION SHOWN HEREON IS BASED ON AN "ON-THE-GROUND" SURVEY PERFORMED BY COBB, FENDLEY & ASSOCIATES, INC., DURING THE MONTHS OF APRIL AND MAY, 2015.
4. 5/8-INCH IRON RODS WITH YELLOW CAPS STAMPED "COBB FENDLEY & ASSOCIATES" SET AT ALL TRACT CORNERS UNLESS NOTED OTHERWISE.
5. ALL PARCELS ARE REFERENCED TO METES AND BOUNDS DESCRIPTIONS PREPARED BY COBB, FENDLEY & ASSOCIATES, INC. OF EVEN DATE.
6. THE WORD CERTIFY IS UNDERSTOOD TO BE AN EXPRESSION OF PROFESSIONAL JUDGMENT BY THE SURVEYOR, WHICH IS BASED ON HIS/HER BEST KNOWLEDGE, INFORMATION AND BELIEF.
7. SQUARE FOOTAGE AREA SHOWN HEREON IS FOR INFORMATION ONLY AND SURVEYOR DOES NOT CERTIFY ACCURACY OF SURVEY TO NEAREST SQUARE FOOT.

FLOODPLAIN INFORMATION

THE PROPERTY SHOWN HEREON (EITHER IN TOTAL OR A PORTION) IS LOCATED IN THE FOLLOWING ZONE(S) BASED ON THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP 48157C0265L, LAST REVISED APRIL 2, 2014:

SHADED ZONE X - AREAS OF 0.2% ANNUAL CHANCE FLOOD; AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.

ZONE AE (FLOODWAY) - THE FLOODWAY IS THE CHANNEL OF A STREAM PLUS ANY ADJACENT FLOODPLAIN AREAS THAT MUST BE KEPT FREE OF ENCROACHMENT SO THAT THE 1% ANNUAL CHANCE FLOOD CAN BE CARRIED WITHOUT SUBSTANTIAL INCREASES IN FLOOD HEIGHTS.

ELEVATIONS WERE NOT OBTAINED ON THE SUBJECT TRACT TO DETERMINE THE FLOOD ZONES

DETERMINATION OF THE FLOOD ZONE IS BASED ON THE GRAPHICAL DELINEATION OF THE ZONES AS DEPICTED ON THE FLOOD PLAIN MAPS.

IF THIS PROPERTY IS NOT WITHIN AN IDENTIFIED FLOOD HAZARD AREA, THIS INFORMATION DOES NOT IMPLY THAT THE PROPERTY AND/OR STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE. ON RARE OCCASIONS, GREATER FLOODS CAN OCCUR AND FLOOD HEIGHTS MAY BE INCREASED BY MAN-MADE OR NATURAL CAUSES. THIS FLOODPLAIN INFORMATION SHALL NOT CREATE LIABILITY ON THE PART OF THE SURVEYOR.

AREA SUMMARY


PARCEL	EXISTING	OWNER	FILE NO./F.E. NO.	TAKING	REMAINDER
6	2.2741 AC.	FORT BEND COUNTY M.U.D. NO. 116	FILE NO. 2016030081	0.4833 AC. 21054 SQ. FT.	1.7908 AC. (CALC.)

SURVEYOR'S CERTIFICATE

IN MY PROFESSIONAL OPINION, THIS PLAN REPRESENTS THE FACTS FOUND ON THE GROUND DURING THE COURSE OF A BOUNDARY SURVEY CONDUCTED UNDER MY SUPERVISION DURING THE MONTHS OF APRIL AND MAY, 2015 AND THAT THIS SURVEY SUBSTANTIALLY COMPLIES WITH THE CURRENT STANDARDS OF PRACTICE OF THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING.

WITNESS MY HAND AND SEAL THIS 18TH DAY OF APRIL, 2017, AT HOUSTON, TEXAS.

KYLE CARSON SUNDAY
REGISTERED PROFESSIONAL LAND SURVEYOR #5924



NO.	DESCRIPTION	DATE

CobbFendley
TBPE Firm Registration No. 276
TBPLS Firm Registration No. 100457


13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbrendley.com

FORT BEND COUNTY
MOBILITY PROJECTS

SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS

PARCEL 6

SCALE: HORIZ. 1" = 40'	DSM-AOS	APP. NO.
	ON-AOS	
	DATE REV	SHEET NO.
DATE: 03/30/2017	APPD:	OF 04



RESIDUE OF CALLED 63.107 AC.
WILLIAMSWAY PARTNERSHIP, LTD.
FILE NO. 9680818
O.P.R.F.B.C.

40 DRAINAGE EASEMENT
FORT BEND COUNTY
DRAINAGE DISTRICT
VOL. 314, PG. 61
D.R.F.B.C.

A=279.25'
R=2,060.00'
D=07°46'01"
CB=N 67°58'44" E
CH=279.03'

A=365.11'
R=2,060.00'
D=10°09'18"
CB=N 76°56'23" E
CH=364.63'

POB PARCEL 6
X=3,012,703.55
Y=13,762,889.00

MATCHLINE 2 OF 2

PROPOSED R.O.W.

PROPOSED R.O.W.

31.8700 ACRES (CALC.)
RESIDUE OF 33.5075 ACRES (TRACT I)
THE ESTATES AT
LAKES OF WILLIAMS RANCH, LTD.
FILE NO. 2016134407
O.P.R.F.B.C.

JOSEPH KUYKENDAHL LEAGUE
ABSTRACT No. 49



NO.	DESCRIPTION	DATE

CobbFendley
TBPE Firm Registration No. 274
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbendley.com

FORT BEND COUNTY
MOBILITY PROJECTS

SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS
PARCEL 6

SCALE: HORIZ. 1" = 40'	DSM: ACS	REV. NO.
	CR: ACS	
	DRN: BM	SHEET NO.
DATE: 03/30/2017	APPVD:	03 OF 84

MATCHLINE 1 OF 2

40' DRAINAGE EASEMENT
FORT BEND COUNTY
DRAINAGE DISTRICT
VOL. 314, PG. 61
D.R.F.B.C.

WILLIAMS WAY PARTNERSHIP, LTD.
RESIDUE OF CALLED 63.107 ACRE
FILE NO. 9680818
O.P.R.F.B.C.

PROPOSED R.O.W.

A=279.25'
R-2,060.00'
-D=0°46'01"
CB=N 67°58'44" E
CII=279.03'

N71°00'45"W
126.67'

MATCHLINE 2 OF 2

PARCEL 6 =
0.4833 ACRES
(21,054 SQ.FT.)
OWNER: FORT BEND
M.U.D. NO. 116

-N28°16'02"W 47.44'
S 28°16'02" E 38.21'

PROPOSED R.O.W.

A=135.28'
R-1,260.00'
D=06°09'06"
CB=S 58°32'17" W
CH=135.28'

4.0528 ACRES (CALC.)
RESIDUE OF 4.6041 ACRES (TRACT II)
THE ESTATES AT
LAKES OF WILLIAMS RANCH, LID.
FILE NO. 2016134407
O.P.R.F.B.C.

1.7908 ACRES (CALC)
RESIDUE OF 2.2741 ACRES
FORT BEND COUNTY M.U.D. NO. 116
FILE NO. 2016130081
O.P.R.F.B.C.

FORT BEND COUNTY DRAINAGE DISTRICT
FILE NO. 2016130975
O.P.R.F.B.C.

JOSEPH KUYKENDAHL LEAGUE
ABSTRACT No. 49

NO.	DESCRIPTION	DATE

CobbFendley
TBPE Firm Registration No. 274
TBPLS Firm Registration No. 100467

13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbendley.com

FORT BEND COUNTY
MOBILITY PROJECTS

SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS
PARCEL 6

SCALE: HORIZ. 1" = 40'	DSN: KCS	INVT: NO
	CS: KCS	
	DRN: BM	SHEET NO
DATE: 03/30/2017	APP'D:	86 OF 84

PARCEL 2B

DESCRIPTION OF A TRACT OF LAND CONTAINING
0.5513 ACRES (24,013 SQUARE FEET) SITUATED IN
THE JOSEPH KUYKENDAHL LEAGUE, A-49
FORT BEND COUNTY, TEXAS

Being a tract of land containing 0.5513 acres (24,013 square feet) situated in the Joseph Kuykendahl League, A-49, Fort Bend County, Texas, being a part of Lot 5 and Lot 6 of the J.W. Blakely subdivision, recorded under Volume Q, Page 554 of the Deed Records of Fort Bend County, Texas, and a part of a 4.6041-acre (Tract II) conveyed unto The Estates at Lakes of Williams Ranch, Ltd., recorded under County Clerk's File No. 2016134407 of the Official Public Records of Fort Bend County, Texas. Said 0.5513-acre tract being more particularly described by metes and bounds as follows:

Note: The bearings referenced herein are grid values based on the Texas Coordinate System of 1983 (NAD83, 2011 Adjustment), South Central Zone. All coordinates shown herein are grid values. Multiply by a combined adjustment factor of 1.00013 to convert to surface values.

COMMENCING FOR REFERENCE at a found 1/2-inch iron rod located at the northeast corner of a called 4.0525-acre tract conveyed unto TDPHAN, Ltd., by deed recorded under County Clerk's File No. 2007049506 of the Official Public Records of Fort Bend County, Texas, and being in the southwest property line of the residue of a called 63.107-acre tract conveyed unto Williams Way Partnership, Ltd., by deed recorded under County Clerk's File No. 9680818 of the Official Public Records of Fort Bend County, Texas;

THENCE South 21° 45' 45" West with the southeasterly property line of said 4.0525-acre tract and the westerly property line of the residue of said Williams Way Partnership, Ltd. tract, a distance of 59.68 feet to a set 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" in the northerly property line of a 33.5075-acre tract conveyed unto The Estates at Lakes of Williams Ranch, Ltd., by deed recorded under County Clerk's File No. 2016134407 of the Official Public Records of Fort Bend County, Texas, same being the proposed northerly right-of-way line of Sansbury Boulevard (width varies), and for the beginning of a non-tangent curve to the left;

THENCE in a northeasterly direction, with the proposed northerly right-of-way line of said Sansbury Boulevard, same being the south property line of said residue of 63.107-acre tract, and the north line of said 33.5075-acre tract, with the arc of said non-tangent curve to the left having a radius of 2,060.00 feet and a central angle of 17° 55' 18" (chord bears North 73° 03' 23" East, a distance of 641.73 feet), at an arc distance of 365.11 feet passing the westernmost corner of a 2.2741-acre tract conveyed unto Fort Bend County M.U.D. No. 116, by deed recorded under County Clerk's File No. 2016130081 of the Official Public Records of Fort Bend County, Texas, and continuing for a total arc distance of 644.36 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", for the northeast corner of said 2.2741-acre tract, for the westernmost corner of said tract herein described, and **POINT OF BEGINNING**, having grid coordinates of X= 3,012,962.19 and Y= 13,762,993.61;

THENCE in a northeasterly direction, continuing with the proposed northerly right-of-way line of said Sansbury Boulevard, same being the south property line of said residue of 63.107-acre tract, and the north line of said 4.6041-acre tract, with said curve to the left having a radius of 2,060.00 feet and a central angle of 12° 55' 32" (chord bears North 57° 37' 58" East, a distance of 463.74 feet), at an arc distance of 464.72 to a found 5/8-inch iron rod for the northernmost corner of said 4.6041-acre tract, and for the westernmost corner of Lakes of Williams Ranch, Section 1, a subdivision plat recorded under File No. 20060158 of the Plat Records of Fort Bend County, Texas;

THENCE with the proposed southerly right-of-way line of said Sansbury Boulevard, the following courses and distances:

- a. South 44° 42' 49" West, a distance of 300.96 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", for the beginning of a tangent curve to the right;
- b. Westerly with the arc of said tangent curve to the right having a radius of 1,260.00 feet and a central angle of 10° 44' 55" (chord bears South 50° 05' 17" West, a distance of 236.03 feet) for an arc distance of 236.37 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set in the westerly line of the of said 4.6041-acre tract, same being the easterly line of said 2.2741-acre tract, for the southernmost corner of said tract herein described;

THENCE North 28° 16' 02" West, with the easterly line of said 2.2741-acre tract and the westerly line of said 4.6041-acre tract, a distance of 38.21 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", for corner;

THENCE North 12° 57' 38" East with the westerly line of said 4.6041-acre tract and the easterly line of said 2.2741-acre tract, a distance of 85.57 feet to the **POINT OF BEGINNING** and containing 0.5513 acres (24,013 square feet).

Note: This metes and bounds description is referenced to a survey drawing prepared by Cobb, Fendley & Associates, Inc. of even date.

Cobb, Fendley & Associates, Inc.
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
Phone: 713-462-3242

Job No. 1711-006-01

April 18, 2017



NOTES:

1. ALL BEARINGS AND COORDINATES SHOWN HEREIN ARE GRID VALUES REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983. THE SURVEY WAS CONDUCTED IN 2015 AND 2017. COORDINATES MAY BE BROUGHT TO SURFACE VALUES BY APPLYING A SURFACE ADJUSTMENT FACTOR OF 1.00013.
2. ALL VERTICAL DATUM REFERENCED HEREIN IS BASED ON NAVD83 VALUES. REFERENCE BENCHMARK IS NATIONAL GEODETIC SURVEY MONUMENT PID NO. AW4730, LOCATED ON THE FRONT OF THE HISTORIC COURTHOUSE BUILDING IN THE CITY OF RICHMOND, TEXAS.
3. ALL FIELD INFORMATION SHOWN HEREON IS BASED ON AN "ON-THE-GROUND" SURVEY PERFORMED BY COBB, FENDLEY & ASSOCIATES, INC., DURING THE MONTHS OF APRIL AND MAY, 2015.
4. 5/8" INCH IRON RODS WITH YELLOW CAPS STAMPED "COBB FENDLEY & ASSOCIATES" SET AT ALL TRACT CORNERS UNLESS NOTED OTHERWISE.
5. ALL PARCELS ARE REFERENCED TO METES AND BOUNDS DESCRIPTIONS PREPARED BY COBB, FENDLEY & ASSOCIATES, INC. OF EVEN DATE.
6. THE WORD CERTIFY IS UNDERSTOOD TO BE AN EXPRESSION OF PROFESSIONAL JUDGMENT BY THE SURVEYOR, WHICH IS BASED ON HIS/HER BEST KNOWLEDGE, INFORMATION AND BELIEF.
7. SQUARE FOOTAGE AREA SHOWN HEREON IS FOR INFORMATION ONLY AND SURVEYOR DOES NOT CERTIFY ACCURACY OF SURVEY TO NEAREST SQUARE FOOT.

ELUCIDATE INFORMATION

THE PROPERTY SHOWN HEREON (EITHER IN TOTAL OR A PORTION) IS LOCATED IN THE FOLLOWING ZONE(S) BASED ON THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP 48151C0285L, LAST REVISED APRIL 2, 2014:

SHADED ZONE X - AREAS OF 0.2% ANNUAL CHANCE FLOOD; AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.

ZONE AE (FLOODWAY) - THE FLOODWAY IS THE CHANNEL OF A STREAM PLUS ANY ADJACENT FLOODPLAIN AREAS THAT MUST BE KEPT FREE OF ENCROACHMENT SO THAT THE 1% ANNUAL CHANCE FLOOD CAN BE CARRIED WITHOUT SUBSTANTIAL INCREASES IN FLOOD HEIGHTS.

ELEVATIONS WERE NOT OBTAINED ON THE SUBJECT TRACT TO DETERMINE THE FLOOD ZONES.

DETERMINATION OF THE FLOOD ZONE IS BASED ON THE GRAPHICAL DELINEATION OF THE ZONES AS DEPICTED ON THE FLOOD PLAIN MAPS.

IF THIS PROPERTY IS NOT WITHIN AN IDENTIFIED FLOOD HAZARD AREA, THIS INFORMATION DOES NOT IMPLY THAT THE PROPERTY AND/OR STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE. ON RARE OCCASIONS, GREATER FLOODS CAN OCCUR AND FLOOD HEIGHTS MAY BE INCREASED BY MAN-MADE OR NATURAL CAUSES. THIS FLOODPLAIN INFORMATION SHALL NOT CREATE LIABILITY ON THE PART OF THE SURVEYOR.

AREA SUMMARY

PARCEL	EXISTING	OWNER	FILE NO./F.C. NO.	TAKING	REMAINDER
2B	4.6041 AC (TRACT 3)	THE ESTATES AT LAKES OF WILLIAMS RANCH, LTD.	FILE NO. 2016134407	0.5513 AC 24.013 SQ. FT.	4.0528 AC.


SURVEYOR'S CERTIFICATE

IN MY PROFESSIONAL OPINION, THIS PLAT REPRESENTS THE FACTS FOUND ON THE GROUND DURING THE COURSE OF A BOUNDARY SURVEY CONDUCTED UNDER MY SUPERVISION DURING THE MONTHS OF APRIL AND MAY, 2015 AND THAT THIS SURVEY SUBSTANTIALLY COMPLETES AND MEETS THE CURRENT STANDARDS OF PRACTICE OF THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING.

WITNESS MY HAND AND SEAL THIS 18TH DAY OF APRIL, 2017, AT HOUSTON, TEXAS.

[Signature]

KYLE CARSON SUNDAY
REGISTERED PROFESSIONAL LAND SURVEYOR #5924




CobbFendley
Tape Firm Registration No. 274
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713-462-3242 | fax 713-462-3262
www.cobbhendley.com

FORT BEND COUNTY
MOBILITY PROJECTS

SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS


PARCEL 2B

NO.	DESCRIPTION	DATE
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		
63		
64		
65		
66		
67		
68		
69		
70		
71		
72		
73		
74		
75		
76		
77		
78		
79		
80		
81		
82		
83		
84		
85		
86		
87		
88		
89		
90		
91		
92		
93		
94		
95		
96		
97		
98		
99		
100		



NO.	DESCRIPTION	DATE

SCALE: HORIZ. 1" = 40'	DSM NO.	HWY NO.
	CC-A23	
	PRN BM	
	APP'VD	SHEET NO.
DATE: 03/20/2017		82 OF 85



CobbFendley

TBPE Firm Registration No. 274
 TBPE Firm Registration No. 100467
 13430 Northwest Freeway, Suite 1100
 Houston, Texas 77040
 713.462.3242 | fax 713.462.3262
www.cobbfindley.com

**FORT BEND COUNTY
MOBILITY PROJECTS**

SANSBURY BOULEVARD

**PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS**

PARCEL 2B

RESIDUE OF CALLED 63.07 AC.
WILLIAMS WAY PARTNERSHIP, LTD.
FILE NO. 9680818
O.P.R.F.B.C.

40' DRAINAGE EASEMENT
FORT BEND COUNTY
DRAINAGE DISTRICT
VOL. 314, PG. 61
D.R.F.B.C.

PROPOSED R.O.W.

365.11'
A=644.36'
R=2,060.00'
D=17°55'18"
CB-N 73°03'23" E
CH=641.13'

135.78'


PROPOSED R.O.W.

MATCHLINE 2 OF 3

MATCHLINE 1 OF 3

31.8700 ACRES (CALC.)
RESIDUE OF 33.5075 ACRES (TRACT 1)
THE ESTATES AT
LAKES OF WILLIAMS RANCH, LTD.
FILE NO. 2016134407
O.P.R.F.B.C.

JOSEPH KUYKENDAHLE LEAGUE
ABSTRACT NO. 49



NO.	DESCRIPTION	DATE

CobbHendley
TBP&S Firm Registration No. 274
TBP&S Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbenhendley.com

FORT BEND COUNTY
MOBILITY PROJECTS
SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS
PARCEL 2B

SCALE: 1"=40'	DSN: NCS	HWY: NO.
CR: KCS	DRW: BM	SHEET: NO.
DATE: 01/20/2007	APPROV:	23 OF 25

40' DRAINAGE EASEMENT
FORT BEND COUNTY
DRAINAGE DISTRICT
VOL. 314, PG. 61
D.R.F.B.C.

WILLIAMS WAY PARTNERSHIP, LTD.
RESIDUE OF CALLED 63.107 ACRE
FILE NO. 9680818
O.P.R.F.B.C.

PROPOSED R.O.W.

A=644.36'
R=2,060.00'
D=17°55'18"
CB=N 73°03'23" E
CH=641.73'

POB PARCEL 2B
X=3,012,962.19
Y=13,162,993.6'

PARCEL 2B =
0.5513 ACRE
(24,013 SQ.FT.)

OWNER: THE ESTATED AT
LAKES OF
WILLIAM RANCH, LTD.


PROPOSED R.O.W.

2.2741 ACRES
FORT BEND COUNTY M.J.D. NO.116
FILE NO. 201613008
O.P.R.F.B.C.

4.0528 ACRES (CALC.)
RESIDUE OF 4.6041 ACRES (TRACT II)
THE ESTATES AT
LAKES OF WILLIAMS RANCH, LTD.
FILE NO. 201613407
O.P.R.F.B.C.

A=236.37'
R=1,260.00'
D=10°42'55"
CB=S 50°05'17" W
CH=236.03'

A=464.72'
R=2,060.00'
D=12°55'32"
CB=N 57°37'58" E
CH=463.74'



MATCHLINE 2 OF 3

MATCHLINE 3 OF 3

JOSEPH KUYKENDAHLE LEAGUE
ABSTRACT NO.49

CobbFendley
TBP&S Firm Registration No. 274
TBP&S Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbhendley.com

FORT BEND COUNTY
MOBILITY PROJECTS

SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS
PARCEL 2B

NO.	DESCRIPTION	DATE
		</

PARCEL 2B =
0.5513 ACRE
(24,013 SQ.FT.)
OWNER: THE ESTATES AT
LAKES OF WILLIAM RANCH, LTD.

A=236.37'
R=1,260.00'
D=10°44'55"
CB=S 50°05'17" W
CH=236.03'

PROPOSED R.O.W.
S44° 42' 49" W 300.96'

300.96

LAKE OF WILLIAMS RA
SECTION 1
FILE NO. 20060158
P.R.F.B.C.

FND 5/8" I. R.
(CM)

4.0528 ACRES (CALC.)
RESIDUE OF 4.6041 ACRES (TRACT II)
THE ESTATES AT
LAKES OF WILLIAMS RANCH, LTD.
FILE NO. 201613407
O.P.R.F.B.C.

JOSEPH KUYKENDahl LEAGUE
ABSTRACT No. 49

NO.	DESCRIPTION	DATE

CobbFendley

THE Firm Registration No. 274
 TBPLS Firm Registration No. 100467
 13430 Northwest Freeway, Suite 1100
 Houston, Texas 77040
 713.462.3242 | fax 713.462.3262
www.cobbhendley.com

**FORT BEND COUNTY
 MOBILITY PROJECTS**

SANSBURY BOULEVARD

**PROPOSED RIGHT-OF-WAY
 FORT BEND COUNTY, TEXAS**

PARCEL 2B

SCALE: HORIZ. 1" = 40'	DSM KCS	HWM NO.
CC-KCS		
DRW BA		SHEET NO.
APPEND		85 OF 85

PARCEL 3

DESCRIPTION OF A TRACT OF LAND CONTAINING
1.9331 ACRES (84,206 SQUARE FEET) SITUATED IN
THE JOSEPH KUYKENDAHL LEAGUE, A-49
FORT BEND COUNTY, TEXAS

Being a tract of land containing 1.9331 acres (84,206 square feet) situated in the Joseph Kuykendahl League, A-49, Fort Bend County, Texas, being a part of Lot 5 and Lot 6 of the J.W. Blakely subdivision, recorded under Volume Q, Page 554 of the Deed Records of Fort Bend County, Texas, and a part of the residue of a called 63.107-acre tract conveyed unto Williams Way Partnership, Ltd., by deed recorded under County Clerk's File No. 9680818 of the Official Public Records of Fort Bend County, Texas. Said 1.9331-acre tract being more particularly described by metes and bounds as follows:

Note: The bearings referenced herein are grid values based on the Texas Coordinate System of 1983 (NAD83, 2011 Adjustment), South Central Zone. All coordinates shown herein are grid values. Multiply by a combined adjustment factor of 1.00013 to convert to surface values.

COMMENCING FOR REFERENCE at a found 1/2-inch iron rod located for the northeast corner of a called 4.0525-acre tract conveyed unto TDPHAN, Ltd., by deed recorded under County Clerk's File No. 2007049506 of the Official Public Records of Fort Bend County, Texas, for an angle point in the southerly line of the residue of said 63.107-acre tract,;

THENCE South 21° 45' 45" West with the east line of said 4.0525-acre tract and the west line of said residue of 63.107-acre tract, a distance of 59.68 feet to a point for the for the northwesterly corner of the residue of a called 93.056-acre tract as conveyed unto Lakes of Williams Ranch, Ltd., by deed recorded under County Clerk's File No. 2005100129 of the Official Public Records of Fort Bend County, Texas, and for the beginning of a non-tangent curve to the left from which a found 5/8-inch iron rod bears South 82° 01' West, a distance of 0.19 feet;

THENCE Northeasterly with the south line of the residue of said 63.107-acre tract, the north line of the residue of said 93.056-acre tract and said non-tangent curve to the left having a radius of 2,060.00 feet and a central angle of 13° 54' 27" (chord bears North 75° 03' 48" East, a distance of 498.80 feet) for an arc distance of 500.03 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set in the proposed northwesterly right-of-way line of Sansbury Boulevard (width varies) for the southwesterly corner of herein described tract, for a non-radial point of compound curvature to the left, and for the **POINT OF BEGINNING** having grid coordinates of X=3,012,830.27 and Y=13,762,935.16;

THENCE in a northeasterly direction with said non-radial curve to the left having a radius of 1,140.00 feet and a central angle of $14^{\circ} 29' 55''$ (chord bears North $51^{\circ} 57' 47''$ East, a distance of 287.71 feet) for an arc distance of 288.47 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", for a point of tangency;

THENCE North $44^{\circ} 42' 50''$ East, with the proposed northerly right-of-way line of Sansbury Boulevard, a distance of 643.58 feet to a set 5/8-inch iron rod with plastic cap stamped "Cobb Fendley & Associates", for corner in the southwest property line of Oakbend Medical Center Subdivision, a subdivision plat recorded under County Clerk's File No. 20080119 of the Plat Records of Fort Bend County, Texas, and for the northernmost corner of said tract herein described;

THENCE South $67^{\circ} 53' 24''$ East, with the northeasterly line of the residue of said 63.107-acre tract and the southwesterly line of said Oakbend Medical Center Subdivision, at a distance of 7.91 feet passing a 1/2-inch iron pipe found for the southerly corner of said Oakbend Medical Center Subdivision and for the westerly corner of the residue of a called 274.2319-acre tract as conveyed unto 274 Brazos, Ltd., by deed recorded under County Clerk's File No. 1999020603 of the Official Public Records of Fort Bend County, Texas, from which a found 5/8-inch iron rod bears North $29^{\circ} 49'$ West, a distance of 0.98 feet, continuing with the northeasterly line of the residue of said 63.107-acre tract and the southwesterly line of the residue of said 274.2319-acre tract for a total distance of 114.09 feet to a 1/2-inch iron pipe found for the easterly corner of the residue of said 63.107-acre tract, for an angle point in the southwesterly line of the residue of said 274.2319-acre tract and for an angle point in the northeasterly line of herein described tract;

THENCE South $21^{\circ} 56' 28''$ West continuing with the northeasterly line of the residue of said 63.107-acre tract and the southwesterly line of the residue of said 274.2319-acre tract, a distance of 67.46 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set in the proposed southeasterly right-of-way line of said Sansbury Boulevard and in the northwesterly line of Reserve "B" of Lakes of Williams Ranch, Section One, a subdivision of record recorded under Plat Number 20060158 of the Plat Records of Fort Bend County, Texas, for a corner in the southeasterly line of the residue of said 63.107-acre tract, for the southerly corner of the residue of said 274.2319-acre tract and for a corner in the southeasterly line of herein described tract;

THENCE along the proposed southeasterly right-of-way line of said Sansbury Boulevard the following courses and distances.

1. South $43^{\circ} 20' 32''$ West with the southeasterly line of the residue of said 63.107-acre tract and the northwesterly line of said Reserve "B", a distance of 43.33 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set for the beginning of a tangent curve to the right;
2. Southwesterly continuing with the southeasterly line of the residue of said 63.107-acre tract, the northwesterly line of said Reserve "B" and with the arc of said tangent curve to the right having a radius of 2,060.00 feet and a central angle of $24^{\circ} 46' 03''$ (chord bears South $55^{\circ} 43' 34''$ West, a distance of 883.57 feet) at an arc distance of 281.44 feet passing a 5/8-inch iron rod found for the westerly corner of said Reserve "B" and for the northeasterly corner of the residue of said 93.056-acre tract, continuing with the southeasterly line of the residue of said 63.107-acre tract and the northwesterly line of the residue of said 93.056-acre tract for a total arc distance of 890.49 feet to the **POINT OF BEGINNING** and containing 1.9331 acres (84,206 square feet).

Note: This metes and bounds description is referenced to a survey drawing prepared by Cobb, Fendley & Associates, Inc. of even date.

Cobb, Fendley & Associates, Inc.
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
Phone: 713-462-3242

Job No. 1711-006-01

April 12, 2017



A handwritten signature in black ink, appearing to read "KCS", written over the bottom portion of the professional seal.

NOTES:

1. ALL BEARINGS AND COORDINATES SHOWN HEREIN ARE GRID VALUES, REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983, TEXAS SOUTH CENTRAL ZONE NO. 4204, NAD 83 (2011) COORDINATES MAY BE BROUGHT TO SURFACE VALUES BY APPLYING A SURFACE ADJUSTMENT FACTOR OF 1.00013.
2. ALL VERTICAL DATUM REFERENCED HEREIN IS BASED ON NAVD83 VALUES. REFERENCE BENCHMARK IS NATIONAL GEODETIC SURVEY MONUMENT PID NO. AW4730, LOCATED ON THE FRONT OF THE HISTORIC COURTHOUSE BUILDING IN THE CITY OF RICHMOND, TEXAS.
3. ALL FIELD INFORMATION SHOWN HEREON IS BASED ON AN "ON-THE-GROUND" SURVEY PERFORMED BY COBB, FENDLEY & ASSOCIATES, INC., DURING THE MONTHS OF APRIL AND MAY, 2015.
4. 5/8-INCH IRON RODS WITH YELLOW CAPS STAMPED "COBB FENDLEY & ASSOCIATES" SET AT ALL TRACT CORNERS UNLESS NOTED OTHERWISE.
5. ALL PARCELS ARE REFERENCED TO METES AND BOUNDS DESCRIPTIONS PREPARED BY COBB, FENDLEY & ASSOCIATES, INC. OF EVEN DATE.
6. THE WORD CERTIFY IS UNDERSTOOD TO BE AN EXPRESSION OF PROFESSIONAL JUDGMENT BY THE SURVEYOR, WHICH IS BASED ON HIS/HER BEST KNOWLEDGE, INFORMATION AND BELIEF.
7. SQUARE FOOTAGE AREA SHOWN HEREON IS FOR INFORMATION ONLY AND SURVEYOR DOES NOT CERTIFY ACCURACY OF SURVEY TO NEAREST SQUARE FOOT.

FLOODPLAIN INFORMATION

THE PROPERTY SHOWN HEREON (EITHER IN TOTAL OR A PORTION) IS LOCATED IN THE FOLLOWING ZONE(S) BASED ON THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP 48157C0265L, LAST REVISED APRIL 2, 2014:

SHADE ZONE X- AREAS OF 0.2% ANNUAL CHANCE FLOOD; AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.

ZONE AE (FLOODWAY)- THE FLOODWAY IS THE CHANNEL OF A STREAM PLUS ANY ADJACENT FLOODPLAIN AREAS THAT MUST BE KEPT FREE OF ENCROACHMENT SO THAT THE 1% ANNUAL CHANCE FLOOD CAN BE CARRIED WITHOUT SUBSTANTIAL INCREASES IN FLOOD HEIGHTS.

ELEVATIONS WERE NOT OBTAINED ON THE SUBJECT TRACT TO DETERMINE THE FLOOD ZONES.

DETERMINATION OF THE FLOOD ZONE IS BASED ON THE GRAPHICAL DELINEATION OF THE ZONES AS DEPICTED ON THE FLOOD PLAIN MAPS.

IF THIS PROPERTY IS NOT WITHIN AN IDENTIFIED FLOOD HAZARD AREA, THIS INFORMATION DOES NOT IMPLY THAT THE PROPERTY AND/OR STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE. ON RARE OCCASIONS, GREATER FLOODS CAN OCCUR AND FLOOD HEIGHTS MAY BE INCREASED BY MAN-MADE OR NATURAL CAUSES. THIS FLOODPLAIN INFORMATION SHALL NOT CREATE LIABILITY ON THE PART OF THE SURVEYOR.

AREA SUMMARY


PARCEL	EXISTING	OWNER	FILE NO./F.C. NO.	TAKING	REMAINDER
3	23,553 AC. (CALCULATED)	WILLIAMS WAY PARTNERSHIP, LTD.	FILE NO. 9680818	18,331 AC. 84,208 SQ. FT.	21,620 AC.

SURVEYOR'S CERTIFICATE

IN MY PROFESSIONAL OPINION, THIS PLAT REPRESENTS THE FACTS FOUND ON THE GROUND DURING THE COURSE OF A BOUNDARY SURVEY CONDUCTED UNDER MY SUPERVISION DURING THE MONTHS OF APRIL AND MAY, 2015 AND THAT THIS SURVEY SUBSTANTIALLY COMPLETES WITH THE CURRENT STANDARDS OF PRACTICE OF THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING.

WITNESS MY HAND AND SEAL THIS 12TH DAY OF APRIL, 2017. AT HOUSTON, TEXAS.

[Signature]
KYLE CARSON SUNDAY
REGISTERED PROFESSIONAL LAND SURVEYOR #5924



NO.	DESCRIPTION	DATE

CobbFendley
T&E Firm Registration No. 274
T&E Firm Registration No. 109467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbhendley.com


**FORT BEND COUNTY
MOBILITY PROJECTS**

SANSBURY BOULEVARD

**PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS**

PARCEL 3

SCALE: HORIZ. 1" = 40'	DATE: 03/20/2017	APPROV: [Signature]	DATE: 03/20/2017
DRAWN BY: [Signature]	CHECKED BY: [Signature]	DATE: 03/20/2017	DATE: 03/20/2017
SHEET: 1	OF: 1	DATE: 03/20/2017	DATE: 03/20/2017



NO.	DESCRIPTION	DATE

CobbFendley
 TSPE Firm Registration No. 274
 TBPLS Firm Registration No. 100467
 13430 Northwest Freeway, Suite 1100
 Houston, Texas 77040
 713.462.3242 | Fax 713.462.3262
 www.cobbendley.com

FORT BEND COUNTY MOBILITY PROJECTS	PARCEL 3
SANSBURY BOULEVARD	
PROPOSED RIGHT-OF-WAY FORT BEND COUNTY, TEXAS	
SCALE: HORIZ. 1" = 40'	VERT. 1" = 20'
DATE: 03/20/2017	APPROVED: [Signature]
	SHEET 1 OF 2

RESIDUE OF 93.056 ACRES
 LAKES OF WILLIAMS RANCH, LTD.
 FILE NO. 2005100129
 O.P.R.F.B.C.

**JOSEPH KUYKENDAHL LEAGUE
 ABSTRACT NO. 49**

TD PHAN, LTD.
 4.0525 ACRES
 FILE NO. 2007049506
 O.P.R.F.B.C.

A=288.47'
 R=1,140.00'
 D=14° 29' 55"
 CB=N 51° 57' 47" E
 CH=287.71'

WILLIAMS WAY PARTNERSHIP, LTD.
 RESIDUE OF CALLED 63.107 ACRE
 FILE NO. 9680818
 O.P.R.F.B.C.

MATCHLINE 1 OF 2

N44° 42' 50" E 643.58'
 PROPOSED R.O.W.


PARCEL 3 =
 1.9331 ACRE
 (84,206 SQ.FT.)
 OWNER: WILLIAMS WAY
 PARTNERSHIP, LTD.

PROPOSED R.O.W.
 A=890.49'
 R=2,060.00'
 D=24° 46' 03"
 CB=S 55° 43' 34" W
 CH=883.57'

RESIDUE OF 93.056 ACRES
 LAKES OF WILLIAMS RANCH, LTD.
 FILE NO. 2005100129
 O.P.F.R.B.C.

JOSEPH KUYKENDAHL LEAGUE
 ABSTRACT NO. 49

MATCHLINE 2 OF 3



NO.	DESCRIPTION	DATE

CobbFendley
 TBPE Firm Registration No. 274
 TBPLS Firm Registration No. 100467
 13430 Northwest Freeway, Suite 1100
 Houston, Texas 77040
 713.462.3242 | fax 713.462.3262
 www.cobbfindley.com

**FORT BEND COUNTY
 MOBILITY PROJECTS**

**SANSBURY BOULEVARD
 PROPOSED RIGHT-OF-WAY
 FORT BEND COUNTY, TEXAS**

PARCEL 3

SCALE: HORIZ. 1" = 40'	DATE: 03/20/2017	DATE: 03/20/2017
DESIGN: KCS	DATE: 03/20/2017	DATE: 03/20/2017
CHECK: KCS	DATE: 03/20/2017	DATE: 03/20/2017
DRAWN BY: KCS	DATE: 03/20/2017	DATE: 03/20/2017
APPROVED: KCS	DATE: 03/20/2017	DATE: 03/20/2017
SHEET: 3	DATE: 03/20/2017	DATE: 03/20/2017
OF 3	DATE: 03/20/2017	DATE: 03/20/2017

WILLIAMS WAY PARTNERSHIP, LTD.
RESIDUE OF CALLED 63.107 ACRE
FILE NO. 9680818
O.P.R.F.B.C.

N44° 42' 50" E 643.58'
PROPOSED R.O.W.

PARCEL 3 =
1.9331 ACRE
(84,206 SQ.FT.)
OWNER: WILLIAMS WAY
PARTNERSHIP, LTD.

MATCHLINE 2 OF 3


MATCHLINE 3 OF 3

RESIDUE OF 93.056 ACRES
LAKES OF WILLIAMS RANCH,
FILE NO. 2005100129
O.P.F.R.B.C.

FND 5/8" I.R. (CM)
PROPOSED R.O.W. 281.44'
RESERVE "B"
A=890.49'
R=2,060.00'
D=24° 46' 03"
CB=S 55° 43' 34" W
CH=883.57'

LOT 7
LOT 6
LOT 8
LAKES OF WILLIAMS RANCH
SECTION 1
FILE NO. 20060158
P.R.F.B.C.

JOSEPH KUYKENDAHL LEAGUE
ABSTRACT NO. 49



NO.	DESCRIPTION	DATE

CobbFendley
TBPET Firm Registration No. 274
TBPUS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbfindley.com

**FORT BEND COUNTY
MOBILITY PROJECTS**
SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS
PARCEL 3

SCALE: 1"=40'	ESK: KCS	HWY: 1
CHK: KCS	DATE: 03/20/2017	SHEET 04 OF 04
DATE: 03/20/2017	APPROVED:	

WILLIAMS WAY PARTNERSHIP, LTD.
RESIDUE OF CALLED 63.107 ACRE
FILE NO. 9680818

O.P.R.F.B.C. N44° 42' 50" E 643.58' O.P.R.F.B.C.
OAKBEND MEDICAL CENTER SUBDIVISION
FILE NO. 20080119

PROPOSED R.O.W.

FND 1 1/2" I.P. (CM)
FND 5/8" I.R.
(N29° 49' W, 0.98')

MATCHLINE 3 OF 3

PARCEL 3 =
1.9331 ACRE
(84,206 SQ.FT.)
OWNER: WILLIAMS WAY
PARTNERSHIP, LTD.

274 BRAZOS, LTD.
RESIDUE OF
CALLED 274.2319 ACRE
FILE NO. 1999020603
O.P.R.F.B.C.

106.18'
567° 53' 24" E
114.09' I.P.
FND 1 1/2" I.P. (CM)

PROPOSED R.O.W.

281.44' D
A=890.49'
R=2,060.00'
D=24° 46' 03"
CB=S 55° 43' 34" W
CH=883.57'

LAKES OF WILLIAMS RANCH
SECTION 1
FILE NO. 20060158
P.R.F.B.C.
RESERVE "B"


PROPOSED R.O.W.

S43° 20' 32" W
43.33'

S21° 56' 28" W
521.67' D

LOT 3
LOT 4
LOT 5
LOT 6

JOSEPH KUYKENDAHL LEAGUE
ABSTRACT NO. 49



NO.	DESCRIPTION	DATE

CobbFendley
TBPE Firm Registration No. 274
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbhendley.com

FORT BEND COUNTY MOBILITY PROJECTS
SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY FORT BEND COUNTY, TEXAS
PARCEL 3
SCALE: 1"=40'
DATE: 03/20/2017
BY: JVB
CHECKED: JVB
DATE: 03/20/2017
SHEET
OF 05

PARCEL 4

DESCRIPTION OF A TRACT OF LAND CONTAINING
0.0293 ACRE (1,276 SQUARE FEET) SITUATED IN
THE JOSEPH KUYKENDAHL LEAGUE, A-49
FORT BEND COUNTY, TEXAS

Being a tract of land containing 0.0293 acre (1,276 square feet) situated in the Joseph Kuykendahl League, A-49, Fort Bend County, Texas, being a part of Lot 5 and Lot 6 of the J.W. Blakely subdivision, recorded under Volume Q, Page 554 of the Deed Records of Fort Bend County, Texas, and part of Oakbend Medical Center Subdivision as recorded under County Clerk's File No. 20080119 of the Plat Records of Fort Bend County, Texas, and also being a part of a called 16.642-acre tract as conveyed unto Oakbend Medical Center by deed recorded under County Clerk's File No. 2008028394 of the Official Public Records of Fort Bend County, Texas. Said 0.0293-acre tract being more particularly described by metes and bounds as follows:

Note: The bearings referenced herein are grid values based on the Texas Coordinate System of 1983 (NAD83, 2011 Adjustment), South Central Zone. All coordinates shown herein are grid values. Multiply by a combined adjustment factor of 1.00013 to convert to surface values.

COMMENCING FOR REFERENCE at a 1/2-inch iron pipe found for an angle point in the southwesterly line of the residue of a called 274.2319-acre tract as conveyed unto 274 Brazos, Ltd., by deed recorded under County Clerk's File No. 1999020603 of the Official Public Records of Fort Bend County, Texas, and for the easterly corner of the residue of a called 63.107-acre tract as conveyed unto Williams Way Partnership, Ltd., by deed recorded under County Clerk's File No. 9680818 of the Official Public Records of Fort Bend County, Texas;

THENCE North 67° 53' 24" West with the southwesterly line of the residue of said 274.2319-acre tract and the northeasterly line of the residue of said 63.107-acre tract, a distance of 106.18 feet to a 1/2-inch iron pipe found for the southerly corner of said Oakbend Medical Center Subdivision, for the westerly corner of the residue of said 274.2319-acre tract, for the southerly corner of herein described tract and for the **POINT OF BEGINNING** having grid coordinates of X=3,013,516.91 and Y=13,763,566.72, from which a found 5/8-inch iron rod bears North 29° 49" West, a distance of 0.98 feet;

THENCE North 67° 53' 24" West with the southwesterly line of said Oakbend Medical Center Subdivision and northeasterly line of the residue of said 63.107-acre tract, a distance of 7.91 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set in the proposed northwesterly right-of-way line of Sansbury Boulevard (width varies) for the westerly corner of the herein described tract;

THENCE North $44^{\circ} 42' 50''$ East with the proposed northwesterly right-of-way line of said Sansbury Boulevard, a distance of 30.05 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set for the beginning of tangent curve to the right;

THENCE Northeasterly continuing with the proposed northwesterly right-of-way line of said Sansbury Boulevard and with said tangent curve to the right having a radius of 2,060.00 feet and a central angle of $04^{\circ} 30' 23''$ (chord bears North $46^{\circ} 58' 01''$ East, a distance of 161.98 feet) for an arc distance of 162.02 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" for the point of tangency;

THENCE North $49^{\circ} 13' 13''$ East, continuing with the proposed northwesterly right-of-way line of said Sansbury Boulevard, a distance of 105.75 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set in the southeasterly line of said Oakbend Medical Center Subdivision and the northwesterly line of the residue of said 274.2319-acre tract for the easterly corner of herein described tract and for the beginning of a non-tangent curve to the left;

THENCE Southwesterly with the southeasterly line of said Oakbend Medical Center Subdivision, the northwesterly line of the residue of said 274.2319-acre tract and with said non-tangent curve to the left having a radius of 2,060.00 feet and a central angle of $04^{\circ} 05' 37''$ (chord bears South $47^{\circ} 10' 24''$ West, a distance of 147.15 feet) for an arc distance of 147.18 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set for the point of tangency;


THENCE South $45^{\circ} 07' 36''$ West continuing with the southeasterly line of said Oakbend Medical Center Subdivision and the northwesterly of the residue of said 274.2319-acre tract, a distance of 147.28 feet to the **POINT OF BEGINNING** and containing 0.0293 acre (1,276 square feet).

Note: This metes and bounds description is referenced to a survey drawing prepared by Cobb, Fendley & Associates, Inc. of even date.

Cobb, Fendley & Associates, Inc.
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
Phone: 713-462-3242

Job No. 1711-006-01

April 12, 2017



A handwritten signature in black ink, appearing to read "K. Sunday", written over the bottom portion of the professional seal.

NOTES:

1. ALL BEARINGS AND COORDINATES SHOWN HEREIN ARE GRID VALUES, REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983. TEXAS SOUTH CENTRAL ZONE NO. 42904, NAD 83 (2011) COORDINATES MAY BE BROUGHT TO SURFACE VALUES BY APPLYING A SURFACE ADJUSTMENT FACTOR OF 1.00013.
2. ALL VERTICAL DATUM REFERENCED HEREIN IS BASED ON NAVD88 VALUES. REFERENCE BENCHMARK IS NATIONAL GEODETIC SURVEY MONUMENT PID NO. AM4730, LOCATED ON THE FRONT OF THE HISTORIC COURTHOUSE BUILDING IN THE CITY OF RICHMOND, TEXAS.
3. ALL FIELD INFORMATION SHOWN HEREON IS BASED ON AN "ON-THE-GROUND" SURVEY PERFORMED BY COBB, FENDLEY & ASSOCIATES, INC., DURING THE MONTHS OF APRIL AND MAY, 2015.
4. 5/8-INCH IRON RODS WITH YELLOW CAPS STAMPED "COBB FENDLEY & ASSOCIATES" SET AT ALL TRACT CORNERS UNLESS NOTED OTHERWISE.
5. ALL PARCELS ARE REFERENCED TO METES AND BOUNDS DESCRIPTIONS PREPARED BY COBB, FENDLEY & ASSOCIATES, INC. OF EVEN DATE.
6. THE WORD CERTIFY IS UNDERSTOOD TO BE AN EXPRESSION OF PROFESSIONAL JUDGMENT BY THE SURVEYOR, WHICH IS BASED ON HIS/HER BEST KNOWLEDGE, INFORMATION AND BELIEF.
7. SQUARE FOOTAGE AREA SHOWN HEREON IS FOR INFORMATION ONLY AND SURVEYOR DOES NOT CERTIFY ACCURACY OF SURVEY TO NEAREST SQUARE FOOT.

AREA SUMMARY

PARCEL	EXISTING	OWNER	FILE NO./F.C. NO.	TAKING	REMAINDER
4	16,642 AC. (CALLED)	OMBEBO MEDICAL CENTER	F.B.S. NO. 2008028394	0.0293 AC. (2.76 SQ. FT.)	16,613

FLOODPLAIN INFORMATION

THE PROPERTY SHOWN HEREON (EITHER IN TOTAL OR A PORTION) IS LOCATED IN THE FOLLOWING ZONE(S) BASED ON THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP 4815702065L, LAST REVISED APRIL 2, 2014:

SHADED ZONE X - AREAS OF 0.2% ANNUAL CHANCE FLOOD AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.

ZONE AE (FLOODWAY) - THE FLOODWAY IS THE CHANNEL OF A STREAM PLUS ANY ADJACENT FLOODPLAIN AREAS THAT MUST BE KEPT FREE OF ENCROACHMENT SO THAT THE 1% ANNUAL CHANCE FLOOD CAN BE CARRIED WITHOUT SUBSTANTIAL INCREASES IN FLOOD HEIGHTS.

ELEVATIONS WERE NOT OBTAINED ON THE SUBJECT TRACT TO DETERMINE THE FLOOD ZONES.

DETERMINATION OF THE FLOOD ZONE IS BASED ON THE GRAPHICAL DELINEATION OF THE ZONES AS DEPICTED ON THE FLOOD PLAIN MAPS.

IF THIS PROPERTY IS NOT WITHIN AN IDENTIFIED FLOOD HAZARD AREA, THIS INFORMATION DOES NOT IMPLY THAT THE PROPERTY AND/OR STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE ON RARE OCCASIONS. GREATER FLOODS CAN OCCUR AND FLOOD HEIGHTS MAY BE INCREASED BY MAN-MADE OR NATURAL CAUSES. THIS FLOODPLAIN INFORMATION SHALL NOT CREATE LIABILITY ON THE PART OF THE SURVEYOR.


SURVEYOR'S CERTIFICATE

IN MY PROFESSIONAL OPINION, THIS PLAT REPRESENTS THE FACTS FOUND ON THE GROUND DURING THE COURSE OF A BOUNDARY SURVEY CONDUCTED UNDER MY SUPERVISION DURING THE MONTHS OF APRIL AND MAY, 2015 AND THAT THIS SURVEY SUBSTANTIALLY COMPLETES WITH THE CURRENT STANDARDS OF PRACTICE OF THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING.

WITNESS MY HAND AND SEAL THIS 12TH DAY OF APRIL, 2017, AT HOUSTON, TEXAS.

[Signature]

KYLE CARSON SUNDAY
REGISTERED PROFESSIONAL LAND SURVEYOR - 5924



CobbFendley

TYPE Firm Registration No. 274
TBRUS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbhendley.com

**FORT BEND COUNTY
MOBILITY PROJECTS**

SANSBURY BOULEVARD

**PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS**

PARCEL 4

NO.	DESCRIPTION	DATE
1	SCALE: HORIZ. 1" = 40'	DATE: 03/30/2017
2	DATE: 03/30/2017	1 OF 2

OAKBEND MEDICAL CENTER
 CALLED 16.642 ACRES
 FILE NO. 2008028394
 O.P.R.F.B.C.

PARCEL 4 =
O.0293 ACRES
(1,276 SQ.FT.)
OWNER: OAKBEND
MEDICAL CENTER

OAKBEND MEDICAL
 CENTER SUBDIVISION
 FILE NO. 20080119
 P.R.F.B.C.

WILLIAMS WAY PARTNERSHIP, LTD.
 RESIDUE OF CALLED 63.107 ACRE
 FILE NO. 9680818
 O.P.R.F.B.C.

N67°53'24"W 7.91'
 N44°42'50"E 30.05'
 S45°07'36"W 147.28'
 POB PARCEL 4
 FND 1/2" I.P. (CM)
 FND 5/8" I.R.
 (N29°49'W, 0.98')
 X=3,013,516.91
 Y=13,763,566.72

A=162.02'
 R=2,060.00'
 D=04°30'23"
 CB=N 46°58'01" E
 CH=161.98'


N49°13'13"E 105.75'
 A=147.18'
 R=2,060.00'
 D=04°05'37"
 CB=S 47°10'24" W
 CH=147.15'

274 BRAZOS, LTD.
 RESIDUE OF
 CALLED 274.2319 ACRE
 FILE NO. 1999020603
 O.P.R.F.B.C.

POC PARCEL 4
 FND 1/2" I.P.

LAKE OF WILLIAMS RANCH
 SECTION 1
 FILE NO. 20060158
 P.R.F.B.C.

PROPOSED R.O.W.



NOL		DESCRIPTION		DATE	

TYPE Firm Registration No. 274
 TBPUS Firm Registration No. 100467
 13430 Northwest Freeway, Suite 1100
 Houston, Texas 77040
 713.462.3242 | fax 713.462.3262
 www.cobbfindley.com

FORT BEND COUNTY
MOBILITY PROJECTS

SANSBURY BOULEVARD

PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS
PARCEL 4

SCALE	HORIZ. 1" = 40'	VERT. 1" = 40'	DATE
DATE	03/20/2017	APPRO	02 OF 22

PARCEL 5

DESCRIPTION OF A TRACT OF LAND CONTAINING
1.0929 ACRES (47,608 SQUARE FEET) SITUATED IN
THE JOSEPH KUYKENDAHL LEAGUE, A-49
FORT BEND COUNTY, TEXAS

Being a tract of land containing 1.0929 acres (47,608 square feet) situated in the Joseph Kuykendahl League, A-49, Fort Bend County, Texas, being a part of Lot 5 and Lot 6 of the J.W. Blakely subdivision, recorded under Volume Q, Page 554 of the Deed Records of Fort Bend County, Texas, and part of the residue of a called 274.2319-acre tract as conveyed unto 274 Brazos, Ltd., by deed recorded under County Clerk's File No. 1999020603 of the Official Public Records of Fort Bend County, Texas. Said 1.0929-acre tract being more particularly described by metes and bounds as follows:

Note: The bearings and coordinates referenced herein are grid values, based on the Texas Coordinate System of 1983 (NAD83, 2011 Adjustment), South Central Zone No. 4204. Multiply coordinates by a combined adjustment factor of 1.00013 to convert to surface values.

BEGINNING at a found 1/2-inch iron pipe for an angle point in the southwesterly line of the residue of said 274.2319-acre tract, for the easterly corner of the residue of a called 63.107-acre tract as conveyed unto Williams Way Partnership, Ltd., by deed recorded under County Clerk's File No. 9680818 of the Official Public Records of Fort Bend County, Texas, and for an angle point in the southwesterly line of herein described tract having grid coordinates of X=3,013,615.27 and Y=13,763,526.76;

THENCE North 67° 53' 24" West with the southwesterly line of the residue of said 274.2319-acre tract and the northeasterly line of the residue of said 63.107-acre tract, a distance of 106.18 feet to a found 1/2-inch iron pipe for the southerly corner of Oakbend Medical Center Subdivision as recorded under County Clerk's File No. 20080119 of the Plat Records of Fort Bend County, Texas, for the westerly corner of the residue of said 274.2319-acre tract and for the northwesterly corner of herein described tract, from which a found 5/8-inch iron rod bears North 29° 49" West, a distance of 0.98 feet;

THENCE North 45° 07' 36" East, with the northwesterly line of the residue of said 274.2319-acre tract and the southeasterly line of said Oakbend Medical Center Subdivision, a distance of 147.28 feet to a point for the beginning of a tangent curve to the right from which a found 5/8-inch iron rod bears South 39° 47' 00" West, a distance of 0.31 feet;

THENCE Northeasterly continuing with the northwesterly line of the residue of said 274.2319-acre tract, the southeasterly line of said Oakbend Medical Center Subdivision and with said tangent curve to the right having a radius of 2,060.00 feet and a central angle of $07^{\circ} 38' 53''$ (chord bears North $48^{\circ} 57' 02''$ East, a distance of 274.77 feet) at an arc distance of 147.13 feet passing a found 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" at the intersection with the proposed northwesterly right-of-way line of Sansbury Boulevard (width varies), and continuing with the northwesterly line of the residue of said 274.2139-acre tract and with said curve to the right for a total arc length of 274.98 feet to a point located in the existing southwesterly right-of-way line of Grand Estates Drive (100 feet wide, recorded under County Clerk's File No. 20060158 of the Official Public Records of Fort Bend County, Texas) for the northerly corner of herein described tract, from which a found 5/8-inch iron rod bears South $80^{\circ} 56''$ East, a distance of 0.39 feet;

THENCE South $37^{\circ} 10' 34''$ East, with the southwesterly right-of-way line of said Grand Estates Drive, a distance of 120.00 feet to a found 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" in the proposed southeasterly right-of-way line of said Sansbury Boulevard, in the southeasterly line of the residue of said 274.2319-acre tract and the northwesterly line of Reserve "B" of Lakes of Williams Ranch, Sec. 1 as recorded under County Clerk's File No. 20060158 of the Plat Records of Fort Bend County, Texas, for the easterly corner of herein described tract and for the beginning of a non-tangent curve to the left;

THENCE Southwesterly with the proposed southeasterly right-of-way line of said Sansbury Boulevard, the southeasterly line of the residue of said 274.2319-acre tract, the northwesterly line of said Reserve "B" and with said non-tangent curve to the left having a radius of 1,940.00 feet and a central angle of $09^{\circ} 25' 46''$ (chord bears South $48^{\circ} 03' 25''$ West, a distance of 318.92 feet) for an arc length of 319.28 feet to a 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" set for a point of tangency;

THENCE South $43^{\circ} 20' 32''$ West, continuing with the proposed southeasterly right-of-way line of said Sansbury Boulevard, the southeasterly line of the residue of said 274.2319-acre tract and the northwesterly line of said Reserve "B", a distance of 107.42 feet to a found 5/8-inch iron rod with yellow cap stamped "Cobb Fendley & Associates" for a corner in the southeasterly line of the residue of said 63.107-acre tract, for the southerly corner of the residue of said 274.2319-acre tract and for the southerly corner of herein described tract;


THENCE North 21° 56' 28" East with the southwesterly line of the residue of said 274.2319-acre tract and the southeasterly line of the residue of said 63.107-acre tract, a distance of 67.46 feet to the **POINT OF BEGINNING** and containing 1.0929 acres (47,608 square feet).

Note: This metes and bounds description is referenced to a survey drawing prepared by Cobb, Fendley & Associates, Inc. of even date.

Cobb, Fendley & Associates, Inc.
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
Phone: 713-462-3242

Job No. 1711-006-01

April 12, 2017



A handwritten signature in black ink, appearing to read "K. Sunday", written over the bottom portion of the professional seal.

NOTES:

1. ALL BEARINGS AND COORDINATES SHOWN HEREIN ARE GRID VALUES REFERENCED TO THE TEXAS COORDINATE SYSTEM OF 1983. THE SURVEY WAS CONDUCTED IN 2015 AND 2016. COORDINATES MAY BE BROUGHT TO SURFACE VALUES BY APPLYING A SURFACE ADJUSTMENT FACTOR OF 1.00013.
2. ALL VERTICAL DATUM REFERENCED HEREIN IS BASED ON NAVD83 VALUES. REFERENCE BENCHMARK IS NATIONAL GEODETIC SURVEY MONUMENT PID NO. AMAT730, LOCATED ON THE FRONT OF THE HISTORIC COURTHOUSE BUILDING IN THE CITY OF RICHMOND, TEXAS.
3. ALL FIELD INFORMATION SHOWN HEREON IS BASED ON AN "ON-THE-GROUND" SURVEY PERFORMED BY COBB, FENDLEY & ASSOCIATES, INC., DURING THE MONTHS OF APRIL AND MAY, 2015.
4. 5/8-INCH IRON RODS WITH YELLOW CAPS STAMPED "COBB FENDLEY & ASSOCIATES" SET AT ALL TRACT CORNERS UNLESS NOTED OTHERWISE.
5. ALL PARCELS ARE REFERENCED TO METES AND BOUNDS DESCRIPTIONS PREPARED BY COBB, FENDLEY & ASSOCIATES, INC. OF EVEN DATE.
6. THE WORD CERTIFY IS UNDERSTOOD TO BE AN EXPRESSION OF PROFESSIONAL JUDGMENT BY THE SURVEYOR, WHICH IS BASED ON HIS/HER BEST KNOWLEDGE, INFORMATION AND BELIEF.
7. SQUARE FOOTAGE AREA SHOWN HEREON IS FOR INFORMATION ONLY AND SURVEYOR DOES NOT CERTIFY ACCURACY OF SURVEY TO NEAREST SQUARE FOOT.

AREA SUMMARY

PARCEL	EXISTING	OWNER	FILE NO./F.C. NO.	TAKING	REMARKS
5	1.0929 AC (CALCULATED)	274 BRAZOS, LTD.	FILE NO. 1999020603	1.0929 AC 47,808 SQ. FT.	NONE

FLOODPLAIN INFORMATION

THE PROPERTY SHOWN HEREON (EITHER IN TOTAL OR A PORTION) IS LOCATED IN THE FOLLOWING ZONE(S) BASED ON THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP 48151C0265L, LAST REVISED APRIL 2, 2014:

SHADED ZONE X - AREAS OF 0.2% ANNUAL CHANCE FLOOD AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN ONE MILE; AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.

ZONE AE (FLOODWAY) - THE FLOODWAY IS THE CHANNEL OF A STREAM PLUS ANY ADJACENT FLOODPLAIN AREAS THAT MUST BE KEPT FREE OF ENCROACHMENT SO THAT THE 1% ANNUAL CHANCE FLOOD CAN BE CARRIED WITHOUT SUBSTANTIAL INCREASES IN FLOOD HEIGHTS.

ELEVATIONS WERE NOT OBTAINED ON THE SUBJECT TRACT TO DETERMINE THE FLOOD ZONES.

DETERMINATION OF THE FLOOD ZONE IS BASED ON THE GRAPHICAL DELINEATION OF THE ZONES AS DEPICTED ON THE FLOOD PLAIN MAPS.

IF THIS PROPERTY IS NOT WITHIN AN IDENTIFIED FLOOD HAZARD AREA, THIS INFORMATION DOES NOT IMPLY THAT THE PROPERTY AND/OR STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE, ON RARE OCCASIONS, GREATER FLOODS CAN OCCUR AND FLOOD HEIGHTS MAY BE INCREASED BY MAN-MADE OR NATURAL CAUSES. THIS FLOODPLAIN INFORMATION SHALL NOT CREATE LIABILITY ON THE PART OF THE SURVEYOR.


SURVEYOR'S CERTIFICATE

IN MY PROFESSIONAL OPINION, THIS PLAT REPRESENTS THE FACTS FOUND ON THE GROUND DURING THE COURSE OF A BOUNDARY SURVEY CONDUCTED UNDER MY SUPERVISION DURING THE MONTHS OF APRIL AND MAY, 2015 AND THAT THIS SURVEY SUBSTANTIALLY COMPLIES WITH THE CURRENT STANDARDS OF PRACTICE OF THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING.

WITNESS MY HAND AND SEAL THIS 12TH DAY OF APRIL, 2017, AT HOUSTON, TEXAS.

[Signature]

KYLE CARSON SUNDAY
REGISTERED PROFESSIONAL LAND SURVEYOR #5924



NO.	DESCRIPTION	DATE
-----	-------------	------

CobbFendley
TBBE Firm Registration No. 274
TBBE Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.5242 | fax 713.462.3262
www.cobbhendley.com

**FORT BEND COUNTY
MOBILITY PROJECTS**

**SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS**

PARCEL 5

SCALE: HERE TO - 4"	DATE: 04/20/2017	APP'D:	1 OF 3
---------------------	------------------	--------	--------

JOSEPH KUYKENDAHLE LEAGUE ABSTRACT NO. 49

OAKBEND MEDICAL
CENTER

OAKBEND MEDICAL CENTER
CALLED 16.642 AC.
FILE NO. 2008028394
SUBDIVISION
P.R.F.B.C. FILE NO. 20080119

FND 1 1/2" I.P. (CM)
FND 5/8" I.R.
(N29° 49' 00" W, 0.98')

O.P.R.F.B.C.

FND 5/8" I.R.
(S39° 47' 00" W, 0.31')

A=274.98'
R=2,060.00'
D=07° 38' 53"
CB=N 48° 57' 02" E
CH=274.77'

N45° 07' 36" E 147.28'

L=147.13'

PARCEL 5 =
1.0929 ACRE
(47,608 SQ.FT.)
OWNER: 274 BRAZOS LTD.

WILLIAMS WAY PARTNERSHIP, LTD.
RESIDUE OF CALLED 63.107 ACRE.
O.P.R.F.B.C. FILE NO. 9680818

POB PARCEL 5
FND 1 1/2" I.P. (CM)
X=3,013,615.27
Y=13,763,526.76

274 BRAZOS, LTD.
RESIDUE OF
CALLED 274.2319 ACRE
FILE NO. 1999020603
O.P.R.F.B.C.

RESERVE "B"
LAKES OF WILLIAMS
RANCH SEC. 1
FILE NO. 20060158
P.R.F.B.C.
PROPOSED R.O.W.
A=319.28'
R=1,940.00'
D=09° 25' 46"
CB=S 48° 03' 25" W
CH=318.92'

LOT 5
LOT 4
LOT 3
LOT 2
BLOCK 1

MATCHLINE 1 OF 1



NO.	DESCRIPTION	DATE

CobbFendley
TYPE Firm Registration No. 274
TBPLS Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbhendley.com

**FORT BEND COUNTY
MOBILITY PROJECTS**
SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS

SCALE: HORIZONTAL - 40'	DRAWN BY	CHECKED BY	DATE

PARCEL 5

OAKBEND MEDICAL
CENTER
SUBDIVISION
FILE NO. 20080119
P.R.F.B.C.

OAKBEND MEDICAL CENTER
CALLED 16.642 ACRES
FILE NO. 2008028394
O.P.R.F.B.C.

A=274.98'
R=2,060.00'
D=07°38'53"
CB=N 48°57'02" E
CH=274.77'

FND 5/8" I.R.
(S80°56'E,
0.39')

GRAND ESTATES DRIVE
(100' WIDE)
FILE NO. 20060158
O.P.R.F.B.C.

JOSEPH KUYKENDAHL
LEAGUE
ABSTRACT NO. 49

MATCHLINE 1 OF 1

PARCEL 5 =
1.0929 ACRE
(47,608 SQ.FT.)
OWNER: 274 BRAZOS LTD.

274 BRAZOS, LTD.
RESIDUE OF
CALLED 274.2319 ACRE
FILE NO. 1999020603
O.P.R.F.B.C.

A=319.28' PROPOSED R.O.W.
R=1,940.00'
D=09°25'46"
CB=S 48°03'25" W
CH=318.92'

LAKE OF WILLIAMS RANCH
SEC. 1
FILE NO. 20060158
P.R.F.B.C.

EXISTING R.O.W.
S37°10'34"E 120.00'

SANSBURY
BOULEVARD
(120' WIDE)
FILE NO. 20060158
O.P.R.F.B.C.

N54°57'29"E
139.71'
FND 5/8" I.R.
(CM)
EXISTING
R.O.W.

EXISTING R.O.W.
GRAND ESTATES
DRIVE
(VARIABLE
WIDTH)



CobbFendley

TAPE Firm Registration No. 100467
13430 Northwest Freeway, Suite 1100
Houston, Texas 77040
713.462.3242 | fax 713.462.3262
www.cobbendley.com

FORT BEND COUNTY
MOBILITY PROJECTS
SANSBURY BOULEVARD
PROPOSED RIGHT-OF-WAY
FORT BEND COUNTY, TEXAS


PARCEL 5

SCALE: HORIZ. 1" = 40'	DATE: 11/02/2015
DESIGN: []	APPD: []
CHECKS: []	SHEET NO. 3 OF 3
DATE: 11/02/2015	APPD: []

Sansbury Blvd.

Project # 13111

Limits:
From: East ROW line of Williams Way Blvd.
To: West ROW line of Grand Estates Dr.



Railroad Blvd

Google earth

200 ft




Sansbury Blvd.

Project # 13111

Limits:

From: East ROW line of Williams Way Blvd.
To: West ROW line of Grand Estates Dr.



Google earth

12/20/2009 1:25:15

Sansbury Blvd.

Project # 13111

Limits:

From: East ROW line of Williams Way Blvd.
To: West ROW line of Grand Estates Dr.



Google earth

200 ft

Grand Estates Dr

