

**Modification/Change Order No. 2**

Bid Number:

PO #: 195193

Fort Bend County Drainage District

EWP – Oyster Creek Channel Bank Stabilization Phase I

Fort Bend County, Texas

April 6, 2021

<b>CHANGE ORDER/MODIFICATION NO. 1</b>		Effective Date:		Page 1 of 2	
Contract: PO 195193		Dated: 12/16/2019		Project: EWP –Oyster Creek Channel Bank Stabilization Phase I	
Issued By (Contracting Local Organization): Fort Bend County			Issued To (Contractor): Shirley and Sons		
TYPE OF MODIFICATION ( <i>check appropriate box below</i> )					
<input checked="" type="checkbox"/> CHANGE ORDER: Issued pursuant to Article 14.4 the changes set forth below are made by this modification.					
Contract Price		\$3,296,222.56		PERFORMANCE TIME: none	
Net Increase in Contract Price:		\$ 174,895.00			
REVISED Contract Price:		\$3,471,117.56			
ATTACHMENTS ( <i>If none, so state.</i> ):					
This modification is hereby made a part of the contract. Except as provided herein, all terms and conditions of the original contract (as revised) remain unchanged and in full force and effect.					
<b>CONTRACTOR'S RELEASE OF CLAIMS</b> In consideration of the modification agreed to herein as complete equitable adjustment for the Contractors proposal, dated 4-1-2021, the Contractor hereby releases Fort Bend County from any and all liability under this contract for further equitable adjustments attributable to such facts or circumstances concerning the added work for the above added work, including all impacts to the work, overhead and profit.					
Recommended By:(print or type name/title of signer)  Thomas P. Beach, PE M&E Consultants <i>Thomas P. Beach</i>					
<b>Important Note:</b> Contractor IS required to sign this document and return two (2) copies to the issuing office.					
CONTRACTOR (print or type name/title of signer)  <i>Donald Shirley President</i>			Sponsors/Contracting Local Organization Adam Wright <i>Adam Wright</i> Fort Bend County Drainage District		
SIGNATURE (person authorized to sign)  <i>[Signature]</i>		DATE  4-5-21		SIGNATURE (County Judge)   DATE	

Modification/Change Order No.2  
Fort Bend County Drainage District  
EWP – Oyster Creek Phase I Channel Bank Stabilization  
Fort Bend County, Texas  
April 6, 2021  
Contract No: PO 195193

#### DESCRIPTION OF MODIFICATION/CHANGE ORDER

Pursuant to General Condition, Article 14.4, the contract shall be modified as following.

The Contractor shall furnish all material, equipment, and labor to install 150 pieces of 8" x 30' x .322 wall thickness steel pipe in the bellies of the sheet pile web. The contractor shall furnish 2 -6" angle iron for each pipe and weld the angle to the sheet pile and the installed 8" pipe. Each pipe pile shall be capped the concrete to create a watertight seal.

Compensation shall be in accordance with the applicable added items below. Contractor Quality Control shall be accomplished in accordance with Construction Specification 94 for the added work.

#### Changes to the Bid Schedule:

Add

Item


No.	Work or Material	Spec.	Quantity	Units	Unit Price	Amount
22	Added Pipe Piles	81	1	LS	\$XXX	\$ 174,895.00

Contract price increase - \$ 174,895.00

Contract Performance time: - no change

#### CONTRACTOR'S STATEMENT OF RELEASE

In consideration of the modification agreed to herein as complete equitable adjustment for the Contractors proposal, dated 4-1-2021, the Contractor hereby releases Fort Bend County from any and all liability under this contract for further equitable adjustments attributable to such facts or circumstances concerning the added work for the above added work, including all impacts to the work, overhead and profit.



P.O. Box 429 • Cleveland, Texas 77328-0429  
15705 FM 787 West • Cleveland, Texas 77327  
HOUSTON LINE: (713) 222-7881 • PHONE: (281) 592-9254 • FAX: (281) 592-9543

April 1, 2021

Oyster Creek Phase 1 Mod 2

Attn: Tom Beach

We are pleased to submit this proposal for furnishing and driving approximately 150 pieces of 8"x30'x.322" wall pipe in between the belly's of the sheet pile. Also included is welding two pieces of angle iron from the pipe to the sheet pile and filling the top of the pipe with concrete.

**Total Price \$174,895.00**

Any questions please call.

A handwritten signature in blue ink, appearing to read "Ronald R. Shirley", is written over the printed name.

Ronald R. Shirley