

Justice Center Program Description

Lower Level Spaces

Isolated Holding Cells for Males, Females and Juveniles w/ Control Room
Secured vehicle Sallyport
Bailiff Security Control Room, Offices, Squad Room, Locker Rooms and Break Room
Mail Room
Janitorial and Maintenance Storage/Supply Rooms

1st Floor Spaces

Building Security
2 District or CCL Courtrooms, 1 Associate Courtroom, w/ Chambers & Support Spaces
Jury Assembly for 736 spaces
County Clerk
District Clerk
Cafeteria w/ Deli

2nd Floor Spaces

4 District or CCL Courtrooms, 2 Associate Courtrooms, w/ Chambers & Support Spaces
Law Library
District Attorney

3rd Floor Spaces

6 District or CCL Courtrooms, 2 Associate Courtrooms, w/ Chambers & Support Spaces
2 Shelled Courtrooms w/ Chambers and Support Spaces
Grand Jury Meeting Space w/ Support Spaces



May 27, 2009

Mr. Don Brady, Director
Fort Bend County Facilities Management and Planning
1402 Band Road
Rosenburg, Texas 77471

Re: Fort Bend County Justice Center
Rosenburg, Texas

Dear Mr. Brady,


Attached, please find our Final GMP pricing for providing construction services for the new Fort Bend County Justice Center, connector tunnel to the jail, and related site improvements. Our GMP is based on the Final GMP documents, dated March 30, 2009 as provided by PGAL Architects.

Included in this revised submission is our updated GMP pricing incorporating subcontractor pricing and changes from the Permit Set documents. We have also included a list of alternates and VE options, a list of documents on which we based our GMP pricing, a list of allowances, a detailed set of qualification and clarifications, and a project schedule.

JE Dunn is honored to be a participant in the process to deliver the new justice center for Fort Bend County and looks forward to discussing the details of this document with you.

Upon review of this information, should you have any questions or comments, please feel free to contact me.

Sincerely,


Joseph Kummer
Assistant Vice President

CC: Dan Bernhard
Bruce Crocombe
Doug Combes
David Andrews

ATLANTA

AUSTIN

CHARLOTTE

COLORADO SPRING

DALLAS

DENVER

DES MOINES

FORT WORTH

HOUSTON

KANSAS CITY

MINNEAPOLIS

NASHVILLE

ORLANDO

PORTLAND

**GUARANTEED MAXIMUM PRICE
CHANGE ORDER**
for
PROJECT NO. SOQ#08-078
FORT BEND COUNTY COURTS FACILITY

TO: Fort Bend County Commissioners Court
301 Jackson St., Suite 719
Richmond, Texas 77469
Attn: Robert Hebert, PH.D., County Judge
Facsimile Number: (281) 341-8609

Gentlemen:

In accordance with Article 4.1 of the Construction Management Agreement dated August 26, 2008, Project No. SOQ#08-078, Fort Bend County Courts Facility, the undersigned offers to provide all services, labor and material to perform in accordance with Contract Documents construction of the Project described in the Final GMP Documents prepared by PGAL in accordance with Exhibit D and the Construction Management Agreement, for a Guaranteed Maximum Price of \$58,485,991.

The undersigned guarantees the material completion of the Work on or before the Date of Material Completion which shall be 670 Calendar days from the execution of this document, receipt of all required permits and a full Notice to Proceed.

The undersigned guarantees the final completion of the Work on or before the Date of Final Completion which shall be 60 calendar days following the date of Material Completion.

The Guaranteed Maximum Price of \$58,485,991 is comprised of the following components:

1.	Estimated Cost of the Work	\$52,068,052
2.	Construction Manager's Contingency (includes Construction and Design Contingency)	\$1,000,000
3.	Construction Manager's Fee	\$1,322,925
4.	Construction Manager's Maximum Construction Overhead Costs	\$4,095,014
	TOTAL (Guaranteed Maximum Price)	\$58,485,991

This proposed GMP Change Order is based on the Final GMP Document Submittal and the revisions thereto by Construction Document Change Orders, entered into prior to the date of this proposal, in accordance with the assumptions stated in Exhibit D and the Construction Management Agreement.

The proposed GMP Change Order is based on the preparation by the Architect and addition to the Construction Management Agreement by Construction Document Change Order of Construction Documents embodying revisions of the Final GMP Document Submittal described in Exhibit D which lists the most recent drawings, specifications, and other documents which describe the proposed revisions.

The Estimated Cost of the Work includes the allowances listed in Exhibit E and each allowance notes whether the allowance covers furnish and delivery or furnish, delivery and installation. The Estimated Cost of the Work (but not the

Construction Manager's Contingency or Fee) is subject to increase to the extent Actual Cost for the Work covered by allowances exceeds the amount set forth in Exhibit E.

The GMP Estimate Summary and Detail is attached as Exhibit A.

Alternates and VE Options Accepted by the Owner and incorporated in this agreement is attached as Exhibit B.

A Construction Budget is attached as Exhibit C.

The list of Permit Set Documents as issued by the Architect is attached as Exhibit D.

The list of Allowances included in the GMP is attached as Exhibit E.

The GMP is based upon Qualifications, Clarifications and Exclusions as listed in Exhibit F.

A Design Completion Schedule is attached as Exhibit G.

A Project Progress Schedule is attached as Exhibit H.

The Project Staff Plan is attached as Exhibit I.

The General Conditions Breakdown is attached as Exhibit J.

A Shop Drawing Approval Schedule is attached as Exhibit K.

The concurrence of the Architect to Exhibits G and K is attached as Exhibit L.

The RFIs upon which the GMP is based are attached as Exhibit M.

The Constructability Review which is not a part of this agreement or the GMP pricing is attached as Exhibit N.

Each of Exhibits A through M are part of this Proposed GMP Change Order and are incorporated herein by reference.

The Dates of Material and Final Completion and the Guaranteed Maximum Price are subject to adjustment in the manner provided by the Construction Management Agreement.

This offer is submitted as the proposed GMP Change Order pursuant to Article 4.1 of the Construction Management Agreement. The terms of the Construction Management Agreement are incorporated herein by reference.

The undersigned agrees that this proposed GMP Change Order, together with the Notice of Acceptance, shall constitute an amendment to the Construction Management Agreement for the performance by the undersigned of the Work for the above-stated compensation in accordance with the Project Progress Schedule and within the time specified for the Dates of Substantial and Final Completion in accordance with the Contract Documents and shall constitute an amendment to the Construction Management Agreement by Change Order, if approved and agreed upon by the Owner.

We have visited the Site and familiarized ourselves with the conditions under which the Work described in the Contract Documents is to be performed and correlated our observations with the requirements of the Contract Documents, including the requirements set forth in Exhibit D.

DATED: May 27, 2009.


RECOMMENDED FOR OWNER'S ACCEPTANCE:

DAVID L. ANDREWS
Supervising Architect – Pierce Goodwin Alexander & Linville


By: 

Douglas R. Combes
Sr. Vice President

Construction Manager – JE Dunn South Central, Inc.

By:  *JE Dunn*


Donald G. Brady
Director, Fort Bend County Facilities Management and Planning



APPROVED:

Owner
County of Fort Bend Commissioners Court



BY:  *June 2, 2009*
Robert E. Hebert, County Judge

ATTEST

BY: 
Dianne Wilson, County Clerk

Date: 6-2-09

AUDITOR'S CERTIFICATE

I hereby certify that funds are available in an amount not to exceed \$ 58,485,991, plus
\$ _____ in Reimbursable Expenses, to accomplish and pay the obligation of Fort Bend County in the
foregoing matter.


Robert Ed Sturdivant, County Auditor

Ft. Bend County Justice Center



FINAL GMP
May 26, 2009

Table of Contents

GMP Change Order	Tab 1
Estimate Detail (Exhibit A) Summary of Costs Summary of Changes Revisions to Parking Garage Credit	Tab 2
Alternates and VE Options (Exhibit B)	Tab 3
Budget Format (Exhibit C)	Tab 4
Document List (Exhibit D)	Tab 5
List of Allowances (Exhibit E)	Tab 6
Qualifications and Clarifications (Exhibit F)	Tab 7
Design Completion Schedule (Exhibit G)	Tab 8
Project Schedule (Exhibit H)	Tab 9
Staff Plan (Exhibit I)	Tab 10
GC Breakdown (Exhibit J)	Tab 11
Shop Drawing Schedule (Exhibit K)	Tab 12
Architect's Concurrence (Exhibit L)	Tab 13
RFI Log (Exhibit M) 2/12/09 RFI Log (#1-160) Email correspondence between PGAL and JE Dunn (53 Pages) Bid Package – Site Fixtures (19 pages)	Tab 14
Constructability Review (Exhibit N) Civil, Structural and Arch. Review Architectural Review MEP Review	Tab 15

Project: Fort Bend County Justice Center
 City: Richmond, TX

Exhibit A
Estimate Detail

5/27/09

CostCode	Description	Sub Name	Final GMP total	Comments
01000	General Conditions	GC	4,095,014	
01099	Cleanup	JE Dunn Self-Perform	713,963	
02220	Selective Demolition	JE Dunn Self-Perform	10,570	
02250	Crib/Shtpls/Underpinning	Schnabel	885,630	
02300	Earthwork	Schramme	1,254,342	
02360	Soil Treatment	Bugtime	5,955	
02399	Traffic Control	JE Dunn Self-Perform	39,926	
02399	Erosion Control	Environmental Allies	21,195	
02500	Site Utilities	Schramme	638,633	
02740	Asphalt	Hayden	27,421	
02760	Pavement Marking	Rows and Rows	8,035	
02820	Fences & Gates	Astro Fence	97,524	
02900	Landscaping	Pampered Lawns	267,038	
02999	Tunnel Sod at existing Jail	Pampered Lawns	3,217	
03300	Cast-In-Place Concrete	JE Dunn Self-Perform	9,134,074	
03400	Precast Concrete	Not Applicable	0	
03999	Hoisting for Tunnel work	JE Dunn Self-Perform	203,000	
04200	Unit Masonry	Lucia	3,204,600	
05099	Steel Erection	Empire	768,491	
05100	Struct Mtl Framing	Sanco LTD / Southern	1,590,971	
05700	Ornamental Metal	Hoffa Inc.	56,580	
06199	Misc-Rough Carpentry	JE Dunn Self-Perform	625,427	
06220	SubC-Millwork	Howard McKinney	3,312,524	
07100	Waterproofing	Chamberlin	1,069,832	
07255	Spray Fireproofing	Fireproof Contractors	277,243	
07500	Membrane Roofing	Chamberlin	1,338,016	
08100	SubC-Mtl Door Supl (& Frames)	American Door/Versatrack	924,071	
08330	Coiling Doors	Holiday Door	34,626	
08400	Glass & Glazing	Admiral	766,582	
08600	Skylights	United Skys	153,086	
09200	Lath & Plaster	Baker Triangle	16,680	
09250	Gypsum Drywall	Baker	2,233,922	
09300	Tile	Sigma	266,993	
09399	Stone Countertops	Commercial Stone Group	240,061	
09400	Terrazzo	National Terrazzo	182,379	

Project: **Fort Bend County Justice Center**
 City: **Richmond, TX**

Exhibit A
Estimate Detail

5/27/09

CostCode	Description	Sub Name	Final GMP total	Comments
09510	Acoustical Ceiling	Applied Finishes	479,366	
09650	Resilient Flooring	Architectural Floors	839,615	
09670	Polished Concrete	API	28,164	
09699	Access Flooring	Allied Interiors	55,789	
09900	Painting&Wall Cvr	R&M	515,143	
10160	Toilet Compartments	PBJ Specialties	21,950	
10199	Specialties Installation	JE Dunn Self-Perform	17,678	
10199	Tower Clock	Verdin Company	20,115	
10200	Louvers & Vents	Nystrom	13,380	
10350	Flagpoles	Kronberg's	6,755	
10440	Interior Signs	Intex United	231,880	
10500	Lockers	Longhorn	8,016	
10520	Fire Prot. Specialties	PBJ Specialties	13,821	
10538	Canopies	Avadek	57,716	
10670	Stair Nosings	Specialized Building Systems	25,060	
10800	Toilet and Bath Accessories	PBJ Specialties	47,266	
	Electronic Projection Screens	PBJ Specialties	62,730	
11161	Dock Levelers	Overhead Door	5,100	
11190	Detention Equipment	CCC Group Inc.	867,300	
11400	Food Service Equipment	Preferred Food Service	102,560	
12510	Blinds and Shades	Windo-Shade	14,835	
13199	Electronic Security	Metroplex Control Systems	1,698,366	
13199	Dome Structure	McCarthy	265,000	
14200	Elevators	Schindler	1,194,457	
14999	Wheelchair Lifts	Home Elevator	304,062	
15300	Fire Protection	SAFE / Standard	652,297	
15400	Plumbing	Kilgore	1,423,630	
15500	HVAC	Graves	5,556,869	
16000	Electrical	E3	5,673,579	
16199	Telecom	ieSmartSystems	585,425	
30200	Design Contingency		500,000	
35000	CM Contingency		500,000	
	Addendum 1 Allowance for Various Subs		218,000	

Project: Fort Bend County Justice Center
 City: Richmond, TX

Exhibit A
Estimate Detail

5/27/09

CostCode	Description	Sub Name	Final GMP total	Comments
	Subguard/Sub Bonds @ 1.25%		595,541	As a cost of the work, this includes a lump sum amount based on 1.25% for Subguard in lieu of approximately 1.5% for sub bonds. Bond Costs removed from above line items.
	Additional Preconstruction Costs		93,978	As a cost of the work, this includes 3 months of additional preconstruction for period beyond 2/20/09 Draft GMP for additional estimating costs.
			<u>Sub-Totals</u> 57,163,066	
			Fee 1,629,147	
			Deduct CM fee on JE Dunn Self-Perform work -306,222	
			<u>58,485,991</u>	

58,485,991

**Fort Bend County Justice Center
Final GMP**

5/27/09

2/20/09 Draft GMP - Total Costs including Site, Courthouse, Tunnel and Garage for 1/5/09 Documents Owner Alternates incorporated into the 3/30/09 Documents: Alt # 3 - Landscaping and Hardscape Sidewalks to North Side of Ring Road Alt # 4 - Provide Concrete Parking area at North Side of Ring Road	\$57,939,652	
JE Dunn Alternates incorporated into the 3/30/09 Documents: Alt # 6 - Trees and Lawns within Right of Way of Ring Road	\$88,190	Alternate included in Final GMP Documents with Changes to scope noted below
	\$196,320	Alternate included in Final GMP Documents with Changes to scope noted below
	\$0	Deleted by Owner during 5/1/09 review of Final GMP Draft
JE Dunn Value Engineering incorporated into 3/30/09 Documents: Delete Epoxy grout for tile except at Cafeteria and Basement Level Showers	\$0	Deleted by Owner during 5/1/09 review of Final GMP Draft
Eliminate Cooling Tower Basin Heaters Delete requirement to center Sprinkler Heads	(\$10,609)	
Delete Parking Garage and associated work	(\$56,516)	VE pricing adjusted below for Courtrooms and Lobby
USG Eclipse with USG DX grid in lieu of Armstrong Cirrus with Armstrong Prelude XL grid Change Elevators # 1 & 2 from Traction to Hydraulic Install Semi-Recessed Sprinkler Heads in lieu of Concealed Heads at certain areas Paint Central Plant Chilled Water Piping Allow 2" Thermax sheet exterior Duct Insulation in lieu of Phenolic Allow Blanket Wrap Insulation at lateral Roof Drains in lieu of "hard" Insulation	(\$2,630,574)	Pricing adjusted below based on scope meeting with Owner's D/B Garage contractor
	(\$50,100)	
	(\$77,050)	
	(\$10,000)	VE pricing adjusted below based on scope
	\$6,200	
	(\$70,000)	
	(\$16,000)	
	\$55,309,513	Total Costs for 2/20/09 GMP based on submitted costs
3/30/09 Final GMP - Scope Changes between 2/20/09 GMP and 3/30/09 Documents Increase CM & Design Contingency each from \$200K to \$500K each Additional Scope for Garage per 4/7/09 Spreadsheet Add 4th Level Garage Security not included in 4/7/09 Spreadsheet 3 months of additional Pre-Construction costs from Draft GMP to Final GMP Earthwork and Utilities North Side of Ring Road Changes North Side of Garage Changes Natural Gas Line & Meter at Courthouse Site Natural Gas Line at Existing Jail/Tunnel	\$600,000	Per Owner Request
	\$135,468	
	\$24,701	
	\$93,978	
	\$21,726	
	\$4,794	
	\$6,688	
	\$20,000	Allowance for Gas Line, Demo and Rework to surface Landscape & Hardscape - Gas line routing is not shown

**Fort Bend County Justice Center
Final GMP**

5/27/09

Temp Pump for Sanitary Sewer tie-in at Ransom Road	\$21,730	
Garage Pad Fill - Cut from Basement and compacted by Others	(\$19,030)	
Stabilized Fill at Retaining Wall Footings	\$0	Deleted by Architect per 5/8/09 Email
Piping from French Drain piping to Base Drain W'proofing connectors and sump pumps	\$14,214	
Delete temporary detour road and use Ring Road for detour during tunnel work at Ransom Rd	(\$50,000)	Offered as VE to Owner on 5/14/09
Erosion Control		
North Side of Ring Road Changes	\$1,520	
Pavement Markings	\$60	
Landscaping & Irrigation		
Changes per Plans	\$25,009	
North Side of Ring Road Changes	\$9,689	
North Side of Ring Road Changes - Site Furnishings	(\$3,140)	
Relocate Trees as Noted	\$0	Trees to be relocated by Owner as discussed during 5/1/09 review of Final GMP Draft
Irrigation at the South, West and North sides of the Garage	\$5,640	Not shown on plans - Discussed during 5/26/09 review of Final GMP
Cast-In-Place Concrete		
Changes per Plans - Structural	\$11,770	
Site Concrete changes including added sandblasting	\$7,650	
Site Concrete - Added sidewalks and paving North of Ring Road	\$39,284	
Relocation of Historical Marker at Exist. Jail (including new concrete pad)	\$5,000	Allowance
Demo & Exp Joints - Ground Level at Tunnel Connection to Exist. Jail	\$8,900	
Allowance for 24 each Pipe Bollards	\$16,800	Not shown on plans - Discussed during 5/1/09 review of Final GMP Draft
Masonry		
Elevator & Mech Room Changes	\$19,400	
Basement Level Changes	\$23,000	
Basement Level Changes - Type Q CMU wall changed back to Type P CMU wall	(\$18,250)	Per Architect direction during 5/1/09 review of Final GMP Draft, excluding metal studs or drywall previously required at Type P.
Anchor Spec Changes	\$47,000	
Structural Steel Fabrication & Erection		
Changes per Plans	\$13,320	
Rough Carpentry		
Window Rough Opening blocking	\$52,632	
Add Plywood behind added Zodiac wainscot	\$7,958	
Add Plywood behind Courtroom Monitors	\$3,468	
Courtroom Platforms	\$112,136	Remove from Millwork

**Fort Bend County Justice Center
Final GMP**

5/27/09

Millwork		
Courtroom Platforms		
Sculpture Cabinet (Not Detailed)		
Flat paneling vs Raised paneling in Courtrooms		
Wood Door Casing Changes		
Security Desk and Entry Screening Changes		
Lobby Columns wainscot changed from wood paneling to Zodiaq		
Lobby Information Desk Changes		
Jury Assembly - Added Door and Window Casings; Workstation Upgrades		
Courtrooms - Added wood treads and veneered risers at platforms		
Waterproofing		
Bentonite added at Structural changes	\$5,916	
North Side of Ring Road Changes - Caulking	\$1,275	
Additional SAF Details	\$15,300	
Added Base Drain to the waterproofing system at the Basement and Tunnel Walls	\$44,343	
Additional Security Sealants	\$24,480	
Fireproofing & Spray Insulation		
Added Spray Insulation to Basement Walls around Conditioned Space	\$55,802	
Color of Spray Insulation at Ceiling and Walls in Basement - Black vs. Tan	\$0	Tan approved by Architect during 5/1/09 review of Final GMP Draft
Roofing		
Roofing at parapet walls carried from roof to coping flashing	\$33,915	Not shown but needed - Not included in 2/20/09 Draft GMP
5 Year Roof and Wall Bond	\$66,606	
Change Roofing sub to attain 5 Year Roof and Wall Bond	\$70,167	
HM Doors & Frames, Wood Doors, Hardware - Furnish and Install	\$24,812	
Plan Changes	(\$1,662)	
Overhead Doors		
Glass & Glazing		
Added Door Glass	\$47,170	
Plaster		
Deleted Ext Plaster at backside of Clock Tower	(\$9,695)	
Drywall		
Misc Plan Changes	\$32,246	
Tile		
Lath & Scratch Coat at Walls	\$0	Deleted by Architect during 5/1/09 review of Final GMP Draft

**Fort Bend County Justice Center
Final GMP**

5/27/09

Restrooms Changes - Cut tile base changed to Cove Base; Accents and Patterns added	\$34,937	
Quarry Tile base added at Cafeteria	\$1,675	
Material type changed at walls behind Judge's Bench	\$10,934	
Stone & Solid Surface Countertops		
Lobby Columns wainscot changed from wood paneling to Zodiac	\$53,054	
Change S2 - Zodiac Vela Brown to Silestone Coffee Brown	(\$17,916)	Includes changing lobby column wainscoting
S2 for Courtroom Tops changed to ST1 - Zodiac Vela Brown to Zodiac Rosso Verona	\$11,973	
Acoustical		
Plan Changes	(\$24,255)	
Acoustical Wall Panels in Courtrooms	\$171,195	Moved from Painting
Resilient Flooring		
Add Floor Patterns to MCT	\$6,273	
Misc Flooring Changes	\$22,012	
Painting - Plan Changes	\$15,300	
Acoustical Wall Panels in Courtrooms	(\$171,195)	Moved to Acoustical
Access Floor - Added Jury Assembly Room	\$1,893	
Specialties		
Lockers - Added	\$516	
Fire Extinguishers and Cabinets	\$3,583	
Updated requirements for Toilet Accessories	\$2,346	
Added Electronic Projection Screens	\$89,531	Includes structural supports not yet designed
Kynar finish on Architectural Louvers	\$2,000	Added by Architect per 5/12/09 Email
Change flagpole sub and include signed and sealed calc's to meet 110 mph wind loading	\$1,090	
Change surface mounted exterior stair nosings to cast-in-place	\$2,275	
Detention Equipment		
Plan Changes	\$15,504	
Steel Plate Detention Walls at Holding Cells	\$9,690	Not specified but needed - Not included in 2/20/09 Draft GMP
Detention Glass changes	\$7,600	
Food Service Equipment	(\$22,552)	
Electronic Security		
Misc Changes	(\$18,147)	
Delete Plenum rated cable	(\$13,462)	Added Conduit noted below in Electrical
Add Endura/Pelco IP Based Security System	\$262,204	
Security system equipment and upgrades at Exist Jail for tie-in to Tunnel	\$27,319	
Elevators & Escalators		
Add control of Elevators 3, 5, 6, 7 & 8 from Security Control Room	\$24,490	
Change Escalator steps from 24" to 40" width	\$17,940	

**Fort Bend County Justice Center
Final GMP**

5/27/09

Change Vertical Platform Lifts from hydraulic drive to screw drive system

(\$24,701) Change approved by Architect per 5/12/09 Email

Fire Sprinkler	
Concealed Heads only at Jury Assembly and Courtrooms	\$3,213
Plumbing	
Misc Changes	\$19,309
HVAC	
Ductwork Changes at Basement	\$40,024
Ductwork Changes throughout the Building	\$33,854
Grilles, Damper and Fans Changes throughout the Building	\$32,794
Insulation Changes	\$4,080
Roof Piping Changes	\$10,200
York Equipment Changes VE	\$0
Test & Balance	Engineers rejected the VE Proposal Work to be contracted by the Owner as per 5/1/09 review of Final GMP Draft

Electrical

Conduit for Electronic Security system	\$76,646
One-Line Diagram Changes including adding Bussman Power Module Switches	\$50,222
Site Lighting Changes including SP & SR Fixtures + SQ Bollards	\$109,889
Lighting Changes throughout the Building	\$37,689
Power Changes throughout the Building	\$18,507
Courtroom Changes including power for added Projection Screens	\$28,858
IT/Comm Rm Changes including Starline Busway and Added Bus Power units	\$24,061
Fire Alarm System Changes	\$13,791
Raceways and associated work for all systems tied to the Tunnel from the Exist. Jail	\$50,000
Judges' Chambers Intercom System	\$20,000

Telecom

Added Equipment Cabinets	\$11,319
Change Cable from Panduit to Belden	\$15,009
Patch Panel Inserts and other changed materials to Belden	\$33,719
Added Fiber Management Trough	\$10,440
Additional Comm Rm UPS Systems	\$20,400
Tunnel and Tunnel to Existing Jail Telecom not yet shown	\$10,000

MEP

Constructability Review Allowance	\$0
Foundation and Structural Steel Supports for Cooling Towers and other Equipment	\$38,415

Per WPM Sketch dated 5/7/09 and subsequent emails with PGAL

**Fort Bend County Justice Center
Final GMP**

5/27/09

4/20/09 Addendum # 1 Structural & Architectural Added Elevator Hoist Beams and Guide Rail supports Additional Steel Grating and Misc Lobby Ceiling Changes Waterproof Roof Pedestals w/SST flashing wrap around pipe columns Added "Skirt" at Metal Roof (A7.79) Other Structural & Architectural Changes not noted above Elevator Pit depth changes & Additional concrete beams Overhead Doors - Deleted 14 each Int. Fire Doors Fire Sprinkler - Add additional Heads at Lobby	\$218,000 ALLOWANCE
HVAC	
Electrical	
Smoke Evac System in Basement	\$60,098
Site Telecom Conduit Changes	\$1,543
Delete OH Fire Doors	(\$2,970)
Smoke Evac System in Basement	\$7,882
5/21/09 Email from PGAL - Change Spec 0271500-2.1.A.1 & 0271500-2.2.B.1	(\$20,000) Allowance
5/21/09 Email from PGAL regarding City of Richmond Public Works & Engineering Comments Earthwork & Utilities changes Paving changes	\$105,000 Allowance \$21,930
Sub-Total Scope Changes between 2/20/09 GMP and 3/30/09 Documents	\$3,052,980
Sub-Total Costs for 3/30/09 GMP Documents \$58,362,493	
Net General Conditions and Fee Adjustments \$123,498	
Total Costs for 3/30/09 GMP Documents \$58,485,991	

\$8,177 Separate piping and valving not included; This is not indicated in the Documents as being required to satisfy code.

Fort Bend County Justice Center
 Revisions to JE Dunn Parking Garage credit based on Garage Contractor's Scope

4/7/09

Security	Wiring from Courthouse to Garage	\$72,320
	Wiring and Equipment in the Garage	IN ABV
Telecomm	Garage contractor must have rough-in/conduit within the Garage	By Garage GC
Fire Sprinkler	Pull wire and connect to Garage contractor elevator controller	\$6,240
	Fire line from Central Plant to Garage	\$12,500
Electrical	Garage contractor to provide gph needs for verification of CH pump size	By Garage GC
	Conduits for Power, Fire Alarm, Security and Telecom from Courthouse to Garage	\$14,408
	Power and Fire Alarm wiring from Courthouse to Garage	IN ABV
	Tie-In Main power, Emergency power and Fire Alarm panels at Garage	IN ABV
	Remove temporary power service at Garage	IN ABV
	Temporary electric panel and service	By Garage GC
Sitework	Garage contractor to provide all rough-in, wiring and equipment for power, lighting and fire alarm	By Garage GC
	Garage contractor to verify equipment and loads conform with Courthouse design	By Garage GC
	Changes reflected on Final GMP drawings will be reflected in the Final GMP	N/A
Signage	Removal of casting beds for tilt-up by Garage contractor	By Garage GC
Touch Up	Interior and Exterior (If applicable - No Ext. signage for Garage shown on Courthouse drawings)	By Garage GC
	Paint Touch-Up upon turnover to County at Courthouse completion	5,000
	Final Clean / Pressure Wash upon turnover to County at Courthouse completion	25,000
		<u>135,468</u>
		(2,630,574)
		(2,495,106)

Sub-Total
 JE Dunn 2/20/09 GMP Deduct for Parking Garage
Total Deduct for Parking Garage

*** This is based upon our best understanding of information provided during the 4/1/09 Coordination Meeting.
 A preliminary civil plan was available but no other Garage design drawings were provided for review.

Exhibit B

Value Engineering and Alternates Accepted by Owner and included in GMP Pricing

Accepted Owner Requested Alternates

Alt # 3 - Landscaping and Hardscape Sidewalks to North Side of Ring Road

Alt # 4 - Provide Concrete Parking area at North Side of Ring Road

Accepted JE Dunn Alternates

None

Accepted JE Dunn Value Engineering

Eliminate Cooling Tower Basin Heaters

Delete requirement to center Sprinkler Heads

Delete Parking Garage and associated work

USG Eclipse with USG DX grid in lieu of Armstrong Cirrus with Armstrong Prelude XL grid

Change Elevators # 1 & 2 from Traction to Hydraulic

Install Semi-Recessed Sprinkler Heads in lieu of Concealed Heads at certain areas

Paint only Central Plant Chilled Water Piping

Allow 2" Thermax sheet exterior Duct Insulation in lieu of Phenolic

Allow Blanket Wrap Insulation at lateral Roof Drains in lieu of "hard" Insulation

EXHIBIT C
BUDGET FORMAT

GMP				
Division	Name	Units	Unit Cost	Cost
01	General Requirements			\$ 1,621,484
02	Site Work			\$ 3,259,486
03	Concrete			\$ 9,337,074
04	Masonry			\$ 3,204,600
05	Metals			\$ 2,416,042
06	Woods & Plastics			\$ 3,937,951
07	Thermal / Moisture Prot.			\$ 2,685,091
08	Doors & Windows			\$ 1,878,365
09	Finishes			\$ 4,858,112
10	Specialties			\$ 463,637
11	Equipment			\$ 1,037,690
12	Furnishings			\$ 14,835
13	Special Construction			\$ 265,000
14	Conveying System			\$ 1,498,519
15	Mechanical			\$ 7,632,796
16	Electrical			\$ 5,673,579
17	Security Electronics & Communications			\$ 2,283,791
	General Conditions			\$ 4,095,014
	Construction Contingency			\$ 500,000
	Fee			\$ 1,322,925
	Design Contingency			\$ 500,000
Total Construction			Final GMP	\$58,485,991
Owner's Disbursements	Preconstruction Agreement			\$ 156,630
Subtotal				\$58,642,621
Total Project				

Exhibit D

Contract Documents

1. Drawings as prepared by Pierce Goodwin Alexander & Linville (PGAL) (Architect) listed below.
2. Specifications as prepared by Pierce Goodwin Alexander & Linville (PGAL) (Architect), Volumes I and II, dated 3/30/09.
3. Signage and Graphics Program and Message Schedule as prepared by The Douglas Group and transmitted by Pierce Goodwin Alexander & Linville (PGAL) (Architect) dated 01/05/09.
4. JE Dunn Proposal Addendum No. 1 dated 01/15/09.
5. JE Dunn Proposal Addendum No. 2 dated 01/21/09.
6. JE Dunn Proposal Addendum No. 3 dated 01/27/09.

<u>Page</u>	<u>Description</u>	<u>Date</u>
<u>Volume I</u>		
	Cover Page	3/30/09
A0.01	Sheet Index	3/30/09
C1.10	Overall Site Layout	3/30/09
C1.20	Construction Notes	12/08/08
C1.30	Existing Survey	12/08/08
C2.10	Site Layout Plan	3/30/09
C2.12	Horizontal Control Plan	3/30/09
C2.20	Clearing and Grubbing Plan	3/30/09
C2.30	Demolition Plan	3/30/09
C2.40	Site Grading Plan	3/30/09
C2.42	Enlarged Grading and Drainage Plan Main Entrance	3/30/09
C2.44	Enlarged Site and Grading Plans	3/30/09
C2.46	Enlarged Flag Pole Area Site & Grading Plans	3/30/09
C2.48	Enlarged North Parking Plan	3/30/09
C2.50	Drainage Area Map Proposed Conditions	3/30/09
C2.52	Storm Drain Data Table	12/08/08
C2.60	Site Utility Plan	3/30/09
C2.62	Plan & Profile Ransom Road Sanitary Sewers	3/30/09
C2.64	Plan & Profile Ransom Road Water Lines	12/08/08
C2.66	Plan & Profile Ransom Road Sanitary Sewer & Truck Dock Forcemain	3/30/09
C2.68	Communications Plan	12/08/08
C2.70	Tunnel Plan & Profile	3/30/09
C2.71	Plan & Profile Ransom Road Sanitary Sewer	3/30/09
C2.72	Tunnel/Access Demolition Plan	3/30/09
C2.74	Tunnel/Access Improvement Plan	12/08/08
C2.80	Storm Water Pollution Prevention Plan	3/30/09
C2.82	Storm Water Pollution Prevention Details	12/08/08
C2.90	Concrete Pavement Joint Layout	3/30/09
C3.10	Site Details	3/30/09
C3.21	City of Richmond Detail R-1	12/08/08
C3.22	City of Richmond Detail R-2	12/08/08
C3.23	City of Richmond Detail R-3	12/08/08
C3.24	City of Richmond Detail R-4	12/08/08
C3.25	City of Richmond Detail R-5	12/08/08
C3.26	City of Richmond Detail R-6	12/08/08
C3.27	City of Richmond Detail R-7	12/08/08
C5.00	Overall Retaining Wall Layout	12/08/08
C5.01	Retaining Wall A Plan & Profile	12/08/08
C5.02	Retaining Wall A Typical Section	12/08/08
C5.03	Retaining Wall B Plan & Profile Sheet 1 of 2	12/08/08
C5.04	Retaining Wall B Plan & Profile Sheet 2 of 2	12/08/08
C5.05	Retaining Wall B Typical Section	12/08/08
C5.06	Retaining Wall C Plan & Profile Sheet 1 of 2	12/08/08

Exhibit D

Contract Documents

Page	Description	Date
C5.07	Retaining Wall C Plan & Profile Sheet 2 of 2	12/08/08
C5.08	Retaining Wall C Typical Section	12/08/08
C5.09	Retaining Wall D Plan & Profile	12/08/08
C5.10	Retaining Wall D Typical Section	12/08/08
C5.11	Misc. Details Sheet 1 of 3	12/08/08
C5.12	Misc. Details Sheet 2 of 3	12/08/08
C5.13	Misc. Details Sheet 3 of 3	12/08/08
C5.14	Misc. Details Sheet 3 of 3	3/30/09
C6.00	Ransom Road Detour Plan	12/08/08
L1.00	Landscape Site Plan	3/30/09
L2.00	Planting Plan	3/30/09
L2.01	Planting Plan	3/30/09
L2.02	Planting Plan	3/30/09
L3.00	Irrigation Mainline Plan	3/30/09
L3.01	Irrigation Plan	3/30/09
L3.02	Irrigation Plan	3/30/09
L3.03	Irrigation Plan	3/30/09
L4.00	Planting Details	3/30/09
L5.00	Irrigation Details	12/08/08
S1.00	General Notes	3/30/09
S1.01	General Notes	3/30/09
S2.00	Tunnel Level Plan	1/5/09
S2.00A	Tunnel Level Plan A	3/30/09
S2.00B	Tunnel Level Plan B	3/30/09
S2.01	Basement Plan/Foundation	3/30/09
S2.01A	Basement Plan/Foundation "A"	3/30/09
S2.01B	Basement Plan/Foundation "B"	3/30/09
S2.01C	Basement Plan/Foundation "C"	3/30/09
S2.02	Level 1 Framing Plan	1/5/09
S2.02A	Level 1 Framing Plan "A"	3/30/09
S2.02B	Level 1 Framing Plan "B"	3/30/09
S2.02C	Level 1 Framing Plan "C"	3/30/09
S2.02D	Central Plant Level 1/Foundation Plan	3/30/09
S2.03	Level 2 Framing Plan	1/5/09
S2.03A	Level 2 Framing Plan "A"	3/30/09
S2.03B	Level 2 Framing Plan "B"	3/30/09
S2.03C	Level 2 Framing Plan "C"	3/30/09
S2.03D	Central Plant Roof Plan	3/30/09
S2.04	Level 3 Framing Plan	1/5/09
S2.04A	Level 3 Framing Plan "A"	3/30/09
S2.04B	Level 3 Framing Plan "B"	3/30/09
S2.05	Roof Level	3/30/09
S2.05A	Roof Level "A"	3/30/09
S2.05B	Roof Level "B"	3/30/09
S2.06	Metal Roof Level	1/5/09
S2.06A	Metal Roof Level "A"	3/30/09
S2.06B	Metal Roof Level "B"	3/30/09
S2.06D	Clock Tower Plans	3/30/09
S3.00	Typical Foundation Details	3/30/09
S3.01	Typical Foundation Details	1/5/09
S3.02	Typical Foundation Details	1/5/09
S3.03	Typical Foundation Details	1/5/09
S3.04	Typical Concrete Details	1/5/09
S3.05	Typical Concrete Details	1/5/09
S3.06	Post Tensioning Details	1/5/09

Exhibit D

Contract Documents

Page	Description	Date
S3.07	Post Tensioning Details	3/30/09
S3.09	Typical Steel Details	3/30/09
S3.10	Brace Elevations and Notes	3/30/09
S3.11	Brick and CMU Details	3/30/09
S3.12	Building Elevations Steel and CMU Lintels	3/30/09
S3.13	Exterior Building Sections	3/30/09
S4.01	Foundation Details and Level One Details	3/30/09
S4.02	Foundation Details and Level One Details	3/30/09
S4.03	Foundation Details and Level One Details	3/30/09
S4.04	Floor Level Details	3/30/09
S4.10	Framing Details	3/30/09
S4.11	Framing Details	3/30/09
S4.12	Framing Details	3/30/09
S5.00	Column Schedule and Details	3/30/09
S5.01	Column Schedule and Details	1/5/09
S5.10	Beam Schedule	3/30/09
S5.11	Beam Schedule	3/30/09
S5.12	Beam Schedule	3/30/09
S5.20	Post Tensioned Schedule	3/30/09
S5.21	Post Tensioned Schedule	3/30/09
S5.22	Post Tensioned Schedule	1/5/09
SG0.00	Garage 3D View	1/5/09
SG2.01	Garage Level 1 and Foundation Plan	3/30/09
SG2.02	Garage Level 2 Framing Plan	3/30/09
SG2.02A	Garage level 2 Framing Plan – Alternate #2	3/30/09
SG2.03	Garage Level 3 Framing Plan	3/30/09
SG2.03A	Garage Level 3 Framing Plan – Alternate #2	3/30/09
SG2.04	Garage Level 4 Framing Plan	3/30/09
SG2.04A	Garage Level 4 Framing Plan – Alternate #2	3/30/09
SG2.05	Garage Roof Level Framing	3/30/09
SG3.08	Typical Details	1/5/09
SG4.01	Concrete Details	3/30/09
SG4.02	Concrete Details	3/30/09
SG4.03	Concrete Details	3/30/09
SG5.01	Column Schedules	1/5/09
SG5.02	Beam Schedule	3/30/09
SG6.00	Garage Sections	3/30/09
SG6.01	Garage Sections	3/30/09
SG6.02	Garage Sections	1/5/09
SG6.03	Garage Sections	1/5/09
A0.02	Symbols, Abbreviations & General Information	3/30/09
A0.03	ADA Mounting Standard	12/08/08
A0.04	Exit Analysis	3/30/09
A0.10	Partition Types	3/30/09
A0.20	Finish Schedule	3/30/09
A0.21	Finish Schedule	3/30/09
A0.22	Finish Schedule	3/30/09
A0.23	Finish Legend	3/30/09
A0.30	Door Schedule	3/30/09
A0.31	Door Schedule	3/30/09
A0.32	Door Schedule	3/30/09
A0.33	Door & Window Types	1/5/09
A0.34	Door Details	3/30/09
A0.35	Door & Window Details	3/30/09
A0.36	Window Details	3/30/09

Exhibit D

Contract Documents

Page	Description	Date
A0.37	Window Details	3/30/09
A0.38	Window Details	3/30/09
A1.01	Site Plan	3/30/09
A1.02	Site Details	12/08/08
A1.03	Entrance Enlarge Floor Plan and Exterior Details	3/30/09
A1.04	Exterior Ramp & Stairs	3/30/09
A1.05	Judges Ramp & Stairs	3/30/09
A1.06	Enlarged Canopy Floor Plan	12/08/08
A1.07	Canopy Elevations & Details	3/30/09
A2.00	Lower Level Floor Plan	3/30/09
A2.00A	Lower Level Floor Plan "A"	3/30/09
A2.00B	Lower Level Floor Plan "B"	3/30/09
A2.01	Level 1 Floor Plan	3/30/09
A2.01A	Level 1 Floor Plan "A"	3/30/09
A2.01B	Level 1 Floor Plan "B"	3/30/09
A2.02	Level 2 Floor Plan	3/30/09
A2.02A	Level 2 Floor Plan "A"	3/30/09
A2.02B	Level 2 Floor Plan "B"	3/30/09
A2.03	Level 3 Floor Plan	3/30/09
A2.03A	Level 3 Floor Plan "A"	3/30/09
A2.03B	Level 3 Floor Plan "B"	3/30/09
A2.03B ALT.	Level 3 Alternate Floor Plan "B"	12/08/08
A2.04	Lower Roof Floor Plan	3/30/09
A2.04A	Lower Roof Plan "A"	3/30/09
A2.04B	Lower Roof Plan "B"	3/30/09
A2.05	Roof Plan	12/08/08
A2.05A	Roof Plan "A"	12/08/08
A2.05B	Roof Plan "B"	12/08/08
A2.06	Tunnel Level Floor Plan	3/30/09
A3.00	Lower Level Reflected Ceiling Plan	3/30/09
A3.00A	Lower Level Reflected Ceiling Plan "A"	3/30/09
A3.00B	Lower Level Reflected Ceiling Plan "B"	3/30/09
A3.01	Level 1 Reflected Ceiling Plan	3/30/09
A3.01A	Level 1 Reflected Ceiling Plan "A"	3/30/09
A3.01B	Level 1 Reflected Ceiling Plan "B"	3/30/09
A3.02	Level 2 Reflected Ceiling Plan	3/30/09
A3.02A	Level 2 Reflected Ceiling Plan "A"	3/30/09
A3.02B	Level 2 Reflected Ceiling Plan "B"	3/30/09
A3.03	Level 3 Reflected Ceiling Plan	12/08/08
A3.03A	Level 3 Reflected Ceiling Plan "A"	3/30/09
A3.03B	Level 3 Reflected Ceiling Plan "B"	3/30/09
A3.03B ALT.	Level 3 Alternate Reflected Ceiling Plan "B"	12/08/08
A3.04	Tunnel Reflected Ceiling Plan	3/30/09
A3.11	Typical Courtrooms/Jury Assembly Reflected Ceiling Plans	1/5/09
A3.12	Lobby Reflected Ceiling Plan	3/30/09
A3.20	Ceiling Details	3/30/09
A4.01	Central Plant Floor Plan & Elevations	3/30/09
A4.02	Enlarged Floor Plans	12/08/08
A4.03	Enlarged Floor Plans	3/30/09
A4.04	Enlarged Floor Plans	3/30/09
A4.05	Enlarged Stair Plans	3/30/09
A4.06	Enlarged Stair Plans	3/30/09
A4.07	Enlarged Stair Sections	3/30/09
A4.08	Enlarged Stair Sections	3/30/09
A4.09	Stair Details	12/08/08

Exhibit D

Contract Documents

<u>Page</u>	<u>Description</u>	<u>Date</u>
A4.10	Stair Details	3/30/09
A4.11	Enlarged Elevator Plans	3/30/09
A5.00	Plan Details	3/30/09
A5.01	Plan Details	3/30/09
A6.00	North & South Elevations	3/30/09
A6.01	East & West Elevations	12/08/08
A6.02	Exterior Partial Elevations	3/30/09
A6.03	Control Joint Elevations	3/30/09
A6.30	Tunnel Section, Tunnel Stair Sections	3/30/09
A6.70	Section Details	3/30/09
A7.50	Wall Sections & Enlarged Elevations	3/30/09
A7.51	Wall Sections & Enlarged Elevations	3/30/09
A7.52	Wall Sections & Enlarged Elevations	3/30/09
A7.53	Wall Sections & Enlarged Elevations	3/30/09
A7.54	Wall Sections & Enlarged Elevations	12/08/08
A7.55	Wall Sections & Enlarged Elevations	1/5/09
A7.56	Wall Sections & Enlarged Elevations	3/30/09
A7.57	Wall Sections & Enlarged Elevations	3/30/09
A7.58	Wall Sections & Enlarged Elevations	3/30/09
A7.59	Wall Sections & Details	3/30/09
A7.60	Enlarged Sections	3/30/09
A7.61	Wall Sections & Enlarged Elevations	3/30/09
A7.62	Wall Sections & Enlarged Elevations	1/5/09
A7.63	Chase Sections	3/30/09
A7.75	Wall Sections Details	3/30/09
A7.76	Wall Sections Details	3/30/09
A7.77	Wall Sections Details	3/30/09
A7.78	Wall Sections Details	3/30/09
A7.79	Roof Details	12/08/08
A7.80	Roof Details	3/30/09
A7.90	Manufacturer's Typical Waterproofing Details	12/08/08
A8.00	Interior Elevations	3/30/09
A8.01	Jury Assembly Interior Elevation	3/30/09
A8.02	Level 1 Corridor Interior Elevation	3/30/09
A8.03	Level 2 Corridor Interior Elevation	3/30/09
A8.04	Level 3 Corridor Interior Elevation	3/30/09
A8.04A	Level 3 Corridor Interior Elevation	3/30/09
A8.04B	Level 1, 2, & 3 Lobby Interior Elevation	3/30/09
A8.05	Interior Elevations	3/30/09
A8.10	Interior Elevations	3/30/09
A8.11	Interior Elevations	3/30/09
A8.50	Interior & Millwork Details	3/30/09
A8.51	Interior & Millwork Details	3/30/09
A8.52	Interior & Millwork Details	3/30/09
A8.53	Interior & Millwork Details	3/30/09
AG2.01	Ground Level Garage Floor Plan	12/08/08
AG2.02	Second Level Garage Floor Plan	12/08/08
AG2.03	Roof Level Garage Floor Plan	12/08/08
AG2.03 ALT.	Third Level Garage Floor Plan	12/08/08
AG2.04 ALT.	Roof Level Garage Floor Plan	12/08/08
AG5.00	Enlarged Stair Plan	12/08/08
AG6.00	Garage Exterior Elevations	12/08/08
AG6.00 ALT.	Garage Exterior Elevations	12/08/08
AG6.01	Garage Exterior Elevations	12/08/08
AG7.00	Garage Wall Sections	12/08/08

Exhibit D

Contract Documents

<u>Page</u>	<u>Description</u>	<u>Date</u>
AG7.01	Garage Wall Sections	12/08/08
AG7.02	Garage Building Sections	12/08/08
 <u>Volume 2</u>		
	Cover Page	3/30/09
A0.01	Sheet Index	3/30/09
M0.01	Mechanical Symbols and Abbreviations	3/30/09
M2.00A	Mechanical Plan – Basement Area “A”	3/30/09
M2.00B	Mechanical Plan – Basement Area “B”	3/30/09
M2.01A	Mechanical Plan – First Floor Area “A”	1/5/09
M2.01B	Mechanical Plan – First Floor Area “B”	3/30/09
M2.02A	Mechanical Plan – Second Floor Area “A”	3/30/09
M2.02B	Mechanical Plan – Second Floor Area “B”	3/30/09
M2.03A	Mechanical Plan – Third Floor Area “A”	3/30/09
M2.03B	Mechanical Plan – Third Floor Area “B”	3/30/09
M2.04A	Mechanical Plan – Roof Area “A”	3/30/09
M2.04B	Mechanical Plan – Roof Area “B”	3/30/09
M3.01	Mechanical Central Plant Plan	3/30/09
M3.02	Mechanical Partial Plan Tunnel	3/30/09
M4.01	Central Plant Piping Diagram	3/30/09
M4.02	Chilled Water Piping Diagram	3/30/09
M4.03	Chilled Water Piping Diagram	3/30/09
M4.04	Air Riser Diagrams	1/5/09
M4.05	Air Riser Diagrams	3/30/09
M5.01	Mechanical Schedules	3/30/09
M5.02	Mechanical Schedules	3/30/09
M6.01	Mechanical Details	3/30/09
M6.02	Mechanical Details	3/30/09
M6.03	Mechanical Details	3/30/09
M6.04	Mechanical Details	1/5/09
E0.01	Electrical Legend and Abbreviations	1/5/09
E1.00	Site Plan	3/30/09
EL2.00A	Electrical Lighting Plan-Basement Floor - Area “A”	3/30/09
EL2.00B	Electrical Lighting Plan-Basement Floor - Area “B”	3/30/09
EL2.01A	Electrical Lighting Plan-1 st Floor - Area “A”	3/30/09
EL2.01B	Electrical Lighting Plan—1 st Floor - Area “B”	3/30/09
EL2.02A	Electrical Lighting Plan-2 nd Floor – Area “A”	3/30/09
EL2.02B	Electrical Lighting Plan-2 nd Floor - Area “B”	3/30/09
EL2.03A	Electrical Lighting Plan – 3 rd Floor – “Area “A”	3/30/09
EL2.03B	Electrical Lighting Plan—3 rd Floor –Area “B”	3/30/09
EL2.04A	Electrical Lighting Plan – Roof and Penthouse – Area “A”	3/30/09
EL2.04B	Electrical Lighting Plan – Roof and Penthouse – Area “B”	3/30/09
EP2.00A	Electrical Power Plan – Basement Floor – Area “A”	3/30/09
EP2.00B	Electrical Power Plan – Basement Floor – Area “B”	3/30/09
EP2.01A	Electrical Power Plan – 1 st Floor – Area “A”	3/30/09
EP2.01B	Electrical Power Plan – 1 st Floor – Area “B”	3/30/09
EP2.02A	Electrical Power Plan – 2 nd Floor – Area “A”	3/30/09
EP2.02B	Electrical Power Plan – 2 nd Floor – Area “B”	3/30/09
EP2.03A	Electrical Power Plan – 3 rd Floor – Area “A”	3/30/09
EP2.03B	Electrical Power Plan – 3 rd Floor – Area “B”	3/30/09
EP2.04A	Electrical Power Plan – Roof and Penthouse – Area “A”	3/30/09
EP2.04B	Electrical Power Plan – Roof and Penthouse – Area “B”	3/30/09
E3.01	Electrical Partial Plans	3/30/09
E3.02	Electrical Partial Plan Tunnel	3/30/09
E3.03	Electrical Parking Garage Plan	1/5/09

Exhibit D

Contract Documents

<u>Page</u>	<u>Description</u>	<u>Date</u>
E3.04	Electrical Parking Garage Details	1/5/09
E3.05	Electrical Partial Plans Typical Courtroom Power	3/30/09
E3.06	Electrical Partial Plans Typical Courtroom Power	3/30/09
E3.07	Electrical Partial Plans Typical Courtroom Lighting	3/30/09
E3.08	Electrical Partial Plans Typical Courtroom Lighting	1/5/09
E3.09	Electrical Partial Plans Main IT/Security Room Power	3/30/09
E3.10	Electrical Partial Plans Kitchen Power	1/5/09
E4.01	Electrical One Line Diagram	3/30/09
E4.02	Electrical One Line Diagram	3/30/09
E4.03	Electrical One Line Diagram	3/30/09
E5.01	Electrical Power Riser Diagram	3/30/09
E5.02	Electrical Fire Alarm Riser Diagram	3/30/09
E6.01	Electrical Schedules	3/30/09
E6.02	Electrical Panel Schedules	3/30/09
E6.03	Electrical Panel Schedules	3/30/09
E6.04	Electrical Panel Schedules	3/30/09
E6.05	Electrical Panel Schedules	1/5/09
E6.06	Electrical Panel Schedules	1/5/09
E6.07	Electrical Panel Schedules	3/30/09
E6.08	Electrical Panel Schedules	3/30/09
E6.09	Electrical Panel Schedules	3/30/09
E6.10	Electrical Panel Schedules	3/30/09
E6.11	Electrical Panel Schedules	3/30/09
E7.01	Electrical Details	3/30/09
E7.02	Electrical Details	1/5/09
E7.03	Electrical Details	3/30/09
E7.04	Electrical Details	3/30/09
E7.05	Electrical Details	3/30/09
E8.01	Site Lighting Calculations	1/5/09
P0.01	Plumbing Legend and Abbreviations	1/5/09
P2.00A	Plumbing Plan – Basement Floor – Area “A”	3/30/09
P2.00B	Plumbing Plan – Basement Floor – Area “B”	3/30/09
P2.01A	Plumbing Plan – 1 st Floor – Area “A”	3/30/09
P2.01B	Plumbing Plan – 1 st Floor – Area “B”	3/30/09
P2.02A	Plumbing Plan – 2 nd Floor – Area “A”	1/5/09
P2.02B	Plumbing Plan – 2 nd Floor – Area “B”	1/5/09
P2.03A	Plumbing Plan – 3 rd Floor – Area “A”	1/5/09
P2.03B	Plumbing Plan – 3 rd Floor – Area “B”	1/5/09
P2.04A	Plumbing Plan – Roof and Penthouse – Area “A”	1/5/09
P2.04B	Electrical Power Plan – Roof and Penthouse – Area “B”	1/5/09
P3.01	Plumbing Central Plant Plan	3/30/09
P3.02	Plumbing Partial Plan Tunnel	1/5/09
P3.03	Plumbing Parking Garage Plans	3/30/09
P3.04	Plumbing Parking Garage Plans	3/30/09
P4.00	Plumbing Schedules	1/5/09
P4.01	Plumbing Schedules	3/30/09
P5.00	Plumbing Details	1/5/09
P5.01	Plumbing Details	1/5/09
P5.02	Plumbing Details	1/5/09
P6.00	Plumbing Riser Diagram	1/5/09
P6.01	Plumbing Riser Diagram	1/5/09
ES0.00	Symbol Sheet	3/30/09
ES0.01	Site Plan	3/30/09
ES2.00A	Lower Level Floor Plan “A”	3/30/09
ES2.00B	Lower Level Floor Plan “B”	3/30/09

Exhibit D

Contract Documents

Page	Description	Date
ES2.01A	Level 1 Floor Plan "A"	3/30/09
ES2.01B	Level 1 Floor Plan "B"	3/30/09
ES2.02A	Level 2 Floor Plan "A"	3/30/09
ES2.02B	Level 2 Floor Plan "B"	3/30/09
ES2.03A	Level 3 Floor Plan "A"	3/30/09
ES2.03B	Level 3 Floor Plan "B"	3/30/09
ES2.04A	Lower Roof Plan "A"	3/30/09
ES2.04B	Lower Roof Plan "B"	3/30/09
ES2.06	Tunnel Level Floor Plan	3/30/09
ESG2.01	Garage 1 st Level Floor Plan	3/30/09
ESG2.02	Garage 2 nd Level Floor Plan	3/30/09
ESG2.03	Garage 3 rd Level Floor Plan	3/30/09
ESG2.04	ALT Garage 4 th Level Floor Plan	3/30/09
ES3.00	Enlarged Scale Floor Plans	3/30/09
ES3.01	Enlarged Scale Floor Plans	3/30/09
ES4.01	Detail Sheet	3/30/09
ES4.02	Detail Sheet	3/30/09
ES5.01	Video Surveillance System Diagram	3/30/09
ES5.02	Electronic Security System Block Diagram	3/30/09
ES5.03	Access Control System Diagram	3/30/09
T0.01	Communications Legend, Abbrev. & Symbols	3/30/09
T2.00	Communications Lower Floor Plan	3/30/09
T2.01	Communications First Floor Plan	3/30/09
T2.01A	Communications Enlarged First Floor Plan	3/30/09
T2.01B	Communications Enlarged First Floor Plan	3/30/09
T2.01C	Communications Enlarged First Floor Plan	3/30/09
T2.02	Communications Second Floor Plan	3/30/09
T2.02A	Communications Enlarged Second Floor Plan	3/30/09
T2.02B	Communications Enlarged Second Floor Plan	3/30/09
T2.02C	Communications Enlarged Second Floor Plan	12/08/08
T2.03	Communications Third Floor Plan	3/30/09
T2.03A	Communications Enlarged Third Floor Plan	3/30/09
T2.03B	Communications Enlarged Third Floor Plan	3/30/09
T2.03C	Communications Enlarged Third Floor Plan	3/30/09
T3.01	Communications Enlarged Floor TR & MER Rooms	3/30/09
T3.01.1	Communications Enlarged Floor TR & MER Rooms	3/30/09
T4.01	Communications Outlet Elevations & Details	3/30/09
T5.01	Communications Single Line & Riser Diagrams	3/30/09
FS1.1	Foodservice Equipment Plan	3/30/09
FS1.2	Foodservice Plumbing Mechanical Plan	1/5/09
FS1.3	Foodservice Electrical Plan	1/5/09
FS2.1	Foodservice Equipment Elevations	3/30/09
FS3.1	Foodservice Equipment Details	1/5/09
EG1.00	Justice Center/County Jail Site Plan	1/5/09
EG2.00	Justice Center Lower Level	1/5/09
EG2.01	Justice Center Floor 1	1/5/09
EG2.02	Justice Center Floor 2	1/5/09
EG2.03	Justice Center Floor 3	1/5/09
EG2.04	Justice Center Floor 4 (Roof)	1/5/09
EG2.06	Justice Center County Jail Tunnel Lower Level	12/08/08
EG2.07	County Jail Tunnel Grade	12/08/08
EGG2.01	Justice Center Garage Level 1 (Blue)	12/08/08
EGG2.02	Justice Center Garage Level 2 (Red)	12/08/08
EGG2.03	Justice Center Garage Level 3 (Green)	12/08/08
EGG2.04	Justice Center Garage Level 4 (Purple) (Roof)	12/08/08

Exhibit D

Contract Documents

Page	Description	Date
D1.00	Detention: Symbols, Terms Index	3/30/09
D1.01	Detention: Anchorage Details Setting Diagrams	3/30/09
D2.00	Lower Level Floor Plan	1/5/09
D2.00A	Lower Level Floor Plan	3/30/09
D2.00B	Lower Level Floor Plan	3/30/09
D2.00C	Lower Level Floor Plan	1/5/09
D2.01	Level 1 Floor Plan	12/08/08
D2.02	Level 2 Floor Plan	12/08/08
D2.03	Level 3 Floor Plan	12/08/08
D2.06	Detention Tunnel Floor Plans	3/30/09
D3.00	Detention: Door, Frame, WDW Elevations	3/30/09
D3.01	Detention: Details 1-19	12/08/08
D3.02	Detention: Details 20-38	12/08/08
D3.03	Detention: Details 39-57	12/08/08
D3.04	Detention: Details 58-78	12/08/08
D3.05	Detention: Details 79-99	12/08/08
D4.00	Detention: Furniture/Accessories	3/30/09

END OF CONTRACT DOCUMENTS LIST

FORT BEND COUNTY JUSTICE CENTER
Richmond, Texas
LIST OF ALLOWANCES
May 26, 2009

All allowances are included as lump sum allowances including Material, Labor, Installation, Storage, and Freight unless noted otherwise. The allowances carried are as follows:

a. Monument Sign Foundations	\$ 9,000
b. Sign EXT.07 Foundations	\$ 10,500
c. Gas Line relocation at Tunnel (Including Landscape & Hardscape Demo & Rework	\$ 20,000
d. Hydro-excavation of utilities along Ransom Road.	\$ 9,000
e. Cab Finishes for Elevators 1 and 2	\$ 60,000
f. Relocation of Historical Marker at Existing Jail	\$ 5,000
g. 24 each Pipe Bollards	\$ 16,800
h. Raceways and associated work for all systems tied to the Tunnel from Exist. Jail	\$ 50,000
i. Tunnel and Tunnel to Existing Jail Telecom not yet shown	\$ 10,000
j. Structural & Architectural changes included in Addendum 1, as noted in the Summary of Changes included in Exhibit A	\$218,000
k. Judges' Chambers Intercom System complete	\$ 20,000
l. Sculpture Cabinet at Lobby Level 1	\$ 5,200
m. Change Spec 271500 to Belden IBDN System 3600 & Belden Datatwist 3613 cable (in lieu of Belden System 4800 LX & Belden Gigaflex 4813LX cable)	\$ (20,000)
n. City of Richmond Public Works and Engineering Comments for earthwork and utilities per PGAL email dated 5/21/09	\$105,000

FORT BEND COUNTY JUSTICE CENTER
Richmond, Texas

LIST OF QUALIFICATIONS AND CLARIFICATIONS
May 26, 2009

General Project Information

The Final GMP estimate is based on the following:

- 0.1 Construction Documents and RFI's attached to this GMP as Exhibits D & M.
- 0.2 Project consists of a new three story Justice Center plus basement level, detached Central Plant and new Tunnel from the existing Jail Building to the Justice Center.
- 0.3 Allowances are listed in Exhibit E.
- 0.4 Our price is based on working hours between 7 a.m. to 7 p.m. Monday thru Friday, with Saturdays being a make-up day for weather. Concrete pours and other work may require early morning or late evening hours beyond the normal hours. We will work with the Owner to keep them informed of work occurring before and after normal working hours.
- 0.5 With regards to the handicapped accessibility requirement of the Federal Fair Housing Act and other relevant provision of Texas Law, JE Dunn South Central, Inc. specifically excludes the responsibility to ascertain that the contract documents are in accordance with laws, codes, statutes, etc., and exclude any costs related to the lack of design compliance with the contract documents.
- 0.6 Our price is based on JE Dunn South Central, Inc. carrying a contractor controlled insurance program (CCIP) and providing insurance per our CCIP standard requirements.
- 0.7 Wind loads on S1.00 are assumed to be for the structure only. Wind loads and design pressure criteria for specific work is included, as defined within each specification.
- 0.8 We have included Subguard on subcontractors and material suppliers at a lump sum amount of \$595,541 equaling approximately 1.25% of their contract value in lieu of individual subcontractor bonds at approximately 1.5%.
- 0.9 We will notify the Owner and the Architect of any code compliance issues actually found as they are recognized.
- 0.10 The GMP includes several categories of work that JE Dunn will be self-performing on a lump sum basis in accordance with the Agreement.

Our pricing excludes the following:

- 0.11 Provisions for air rights.
- 0.12 The responsibility for the documents to meet local, state, and federal codes (except for specific specifications requiring the contractor/subcontractor to submit an engineered design).
- 0.13 The cost for building permit expeditor.
- 0.14 Costs for and obtaining temporary and permanent utility easements.



0.15 Preconstruction costs included in Exhibit A of the Construction Management Agreement have not been included in the GMP and it is assumed any remaining balance of unpaid Preconstruction costs will be paid in full separate from this GMP. We have included 3 months of additional Preconstruction Costs (\$93,978) for the time between our 2/20/09 Draft GMP and the anticipated start date of Early June 2009, based upon the work involved with pricing the new documents.

1. **GENERAL CONDITIONS**

- 1.1 This GMP pricing is valid until June 5, 2009 after which the pricing will need to be confirmed in order to be valid.
- 1.2 We anticipate the project taking 22 months to complete. This requires that building permits, construction documents and the notice to proceed are issued when required to allow the work to start as shown in our construction schedule on a continuous basis.
- 1.3 This GMP assumes JE Dunn will have use of all areas north of Ring Road between the new Tax Assessor's office and the existing Precinct One offices for use in material laydown, office and storage trailers, excavation stockpile, etc.
- 1.4 This GMP assumes JE Dunn will be allowed use of the access road west of the tunnel (adjoining the existing jail), a portion of the existing jail parking lot and the west entrance area of the existing jail during construction of the tunnel south of Ransom Road to facilitate excavation equipment, concrete trucks and placement, scaffolding for the above-grade connectors and other required staging. Use of this road will not be needed for the entire 22 month construction duration; The timing and duration of this use will be coordinated with the Owner.
- 1.5 The Guaranteed Maximum Price is for the total project only. Individual line item amounts are not guaranteed and may increase or decrease within the overall GMP as the project progresses.
- 1.6 We have included a design contingency of \$500,000 to be used to cover the cost impact of scope or other changes required due to incomplete, erroneous or uncoordinated documents. The GMP does not include other funds or provisions to address these issues and the total scope and cost of the project will need to be maintained in order to maintain the GMP.
- 1.7 The GMP includes a construction contingency of \$500,000 to be utilized by the Construction Manager with the Owner's approval for construction related issues as needed during the construction process. Issues for which this contingency may be used include, but are not limited to: expediting, temporary protection, overtime, shiftwork, scope gaps, subcontractor failures, low estimates, weather protection, escalation, cost overruns and other circumstances that may arise or that may not be quantifiable prior to creation of the GMP. This contingency is not intended to be used for changes in the scope of the work or to cover errors or omissions in the construction documents. Any contingency remaining at the conclusion of the project will be treated as savings and returned to the Owner in accordance with the contract.

- 1.8 We exclude redesign costs for Value Engineering. All accepted Value Engineering, Alternates or other changes shall be fully coordinated and incorporated into the For Construction documents by the Design Team.
- 1.9 All provisions requiring compensation from the Construction Manager to the Designers are excluded. The GMP assumes that CAD files for all contract documents will be provided to the Contractor and Subcontractors free of cost upon notice to proceed. It has been agreed that Subcontractors will sign the Architect's Release Agreement to obtain these files.
- 1.10 No Owner Furnished-Contractor Installed equipment is indicated or included. Also excluded is any installation of materials or work which may be supplied by vendors employed directly by the Owner.
- 1.11 Schedules of value shall be submitted for billing purposes only and shall not be used as a basis for change orders.
- 1.12 The GMP assumes the design team has coordinated the design to allow for proper fit and access for all work.
- 1.13 The GMP includes overhead coordination for construction incorporating Mechanical, Plumbing, HVAC and Electrical work on a single set of coordination drawings. These drawings will also indicate major architectural and structural features and access doors. The overhead coordination drawings shall be reviewed in an overhead coordination meeting which shall be attended by the general contractor, the MEP subcontractors, the Architect, the Engineer and the Owner. At the conclusion of the meeting all parties shall approve the overhead coordination drawings. Coordination drawings will incorporate the specified ceiling heights and required clearances to the extent practical. Other procedures for overhead coordination included in the documents are excluded.
- 1.14 The GMP includes temporary provisions in accordance with Section 01 50 00 only as applicable for JE Dunn use.
- 1.15 The GMP relies upon the plans and specifications as a complete and coordinated design. As construction manager, we have indicated any inconsistencies we discovered in the clarifications and/or constructability review comments. We rely on specifications to indicate type and quality of materials and drawings to indicate locations and quantities. In case of conflicts, the following precedence is assumed – Qualifications & Clarifications, CM at Risk Agreement dated 9/4/08, Specifications, Drawings. Specific details and enlarged plans supersede general plans. When specifications describe items that do not appear on the drawings these items are hereby excluded as inapplicable. References to intent and similar provisions shifting design responsibility are excluded as we are only able to ascertain the designer's intent to the extent it is reflected on clear coordinated documents.
- 1.16 The GMP includes corrections that have been made on the plans, specifications and addendums due to constructability comments but does not include provisions based upon constructability comments not yet corrected in the documents. Responses on the constructability review itself are considered for reference only as they would be impossible to adequately coordinate and communicate to all subcontractors and suppliers without corrected documents.



- 1.17 The GMP assumes that the Architect and Consultants have reviewed and found acceptable all of the listed manufacturers and or products included in the specifications and the documents have been coordinated to reflect any of these items.
- 1.18 All on-site testing will be paid for by the Owner, except those items specifically listed in Specification 014529-1.7G. All expedited cylinder breaks required to expedite the project shall be paid for by the Owner. Contractor shall be responsible for retesting costs due to fault of contractor for failure of initial tests. Contractor shall provide factory or historical materials testing as specified in the specific specification sections for particular products. All inspections or monitoring by special inspectors, geotechnical engineer and any other agencies shall be paid for by the Owner as specified in Specification 014529-1.4.A.
- 1.19 Colors selections shall be made prior to the project start. Color approvals shall be made upon receipt of all pertinent submittals, with the exterior approvals separate from the interior approvals.
- 1.20 RFI's responses shall be received within a reasonable time unless the schedule requires an expedited response. Normally this will be 3 days.
- 1.21 All submittal approval times shall be 14 calendar days beginning on the date sent by Contractor to Architect and ending on the date received back by Contractor from Architect. Contractor and Architect agree to expedite shipment of submittals to achieve this time frame. Architect, Consultants' & Owner's review shall be incorporated into one returned submittal by the Architect. Contractor and Architect shall work together to prioritize these so submittal times can be expedited or extended as needed.
- 1.22 The GMP assumes punchlists and partial occupancy will be performed by area to facilitate orderly inspection, turnover and occupancy of the project. The GMP is based on a 22 month construction schedule from notice to proceed to (substantial) material completion. This schedule will begin once the GMP is approved, For Construction documents are received, building permits are in place and a notice to proceed is received allowing construction to commence.
- 1.23 The GMP assumes the recommendations included in the Geotechnical Report have been evaluated and incorporated into the specifications to the extent appropriate by the Engineer.
- 1.24 Surveys, as required by the specifications, shall be submitted to Architect for review and recording by others.
- 1.25 The Garage is excluded. The Garage Contractor will partially excavate the basement level to an elevation no lower than 77.0 in any area, to utilize soils for the Garage pad. Any work associated with the Garage that will be performed by JE Dunn is defined in Exhibit A. The Coordination of the Garage design with the design for work included in this GMP shall be the responsibility of the Design/Build Garage Contractor and PGAL (and their consultants and engineers).

2. DEMOLITION

Our pricing excludes the following

- 2.1 Asbestos or hazardous materials removal.
- 2.2 Salvage for reuse or storage any demolished materials or plants/trees.
- 2.3 LEED Documentation of material disposal.
- 2.4 New or reworked precast panels at the connection between the Tunnel and the Existing Jail. It is assumed that the panels are sufficiently designed and installed to be cut for the new door opening and frame without rework or replacement of the existing precast panels or skin elements.

3. **SITWORK**

Our pricing includes the following:

- 3.1 We have assumed that all excavations are suitable to use as structural and non-structural backfill. The specifications for the earthwork call for overexcavation & imported select fill and do not coincide with the geotechnical report which states that the onsite excavations can be used for backfill. We have included no overexcavation, import of select fill or stabilized sand.
- 3.2 We have assumed that the water table is at an elevation approximately 35 - 40 feet below existing grade based upon the geotechnical report. As a result we have assumed no groundwater dewatering or other subsurface systems will be required.
- 3.3 Water filled plastic traffic barriers will be used in lieu of concrete barriers.
- 3.4 Hydro-excavation to expose utilities in right of way at Ransom Road is included for utilities indicated in the Documents.
- 3.5 Shoring systems for the tunnel excavation will, in whole or in part, remain in place permanently. The shoring systems is a soldier pile and lagging system; The entire system will remain in place after construction, except the (approx.) top 4' of the piles will be removed.
- 3.6 The french drains at the Tunnel and Basement will be connected at approximately every 20' to the bentonite base drain system. The french drains for the tunnel will be connected to the sump pumps located at each end and at the midpoint of the tunnel. The french drain system for the Basement will be connected to the duplex pumps shown on Sheet P3.01. It is assumed that the design of the pumps is sufficient to provide proper drainage for these french drain systems and all other systems connected to the pumps.

Our pricing excludes the following:

- 3.7 The Storm drainage Trunk line south of Ring Road is by others. The GMP assumes this trunk line installation shall be completed prior to JE Dunn beginning mass excavation of the building basement areas or coordinated with JE Dunn to not impact the work. The curb inlets along and adjacent to either side of Ring Road are by others.
- 3.8 Permanent Dewatering systems.

- 3.9 Shoring or earth retention systems around the building basement walls (we have included shoring for portions of the tunnel excavation).
- 3.10 Imported select fill; GMP pricing assumes suitable back fill material for grading, walls, foundations, slabs and all other areas shall be available from on-site excavations as per the Soils Report.
- 3.11 Lime and/or cement stabilized fill material at any areas except under the paving areas as shown. We have not included stabilized fill at any other foundations or slabs based upon reusing suitable backfill material from onsite excavations.
- 3.12 Contaminated soil excavation and haul off.
- 3.13 Removal of unsuitable soils or rock, and any other structures or utilities unless specifically identified in the documents.
- 3.14 Sidewalk at either side of the perimeter of Ring Road (noted to be by others).
- 3.15 Dumpster enclosures as none are shown.
- 3.16 Tap fees to be paid by Owner.
- 3.17 Site retaining walls subdrainage, underslab subdrainage, landscaping subdrainage or plaza deck subdrainage as none is shown in the drawings.
- 3.18 Termite treatment under the garage, tunnel and entry.
- 3.19 Water meter on the fire line.
- 3.20 Temporary Detour Road for work affecting Ransom Road. Ring Road shall be used as a temporary detour road.
- 3.21 Engineering and costs for a new traffic plan associated with using Ring Road as the temporary detour road.

4. **LANDSCAPING**

Our pricing includes the following:

- 4.1 Existing soil to be used for topsoil.

Our pricing excludes the following:

- 4.2 Trees and Lawns within the Right of Way of Ring Road. This includes all landscaping and irrigation between the sidewalks and Ring Road and along the west side of the existing detention pond.
- 4.3 Relocation of trees shall be by others.

5. **CONCRETE WORK**

Our pricing includes the following:

- 5.1 Allowance for Monument Sign Foundation of \$9,000 (2 EA at \$4,500.)
- 5.2 Allowance for sign type EXT.07 foundation of \$10,500 (7 EA at \$1,500.)

- 5.3 Allowance of \$5,000 for relocation of and new pad for the Historical Marker approximately located at the corner of Ransom Road and the west driveway adjacent to the existing Jail building.
- 5.4 Pan slab soffits shall have a Class "D" finish, except at areas exposed to public view which shall receive a Class "C" finish.
- 5.5 All vertical wall surfaces will have a class "B" finish.
- 5.6 PT system for the building shall be an encapsulated system.
- 5.7 Reference Detail 7, 7A/S3.07 and the associated notes - Beam 2 & 4 shall be designed to be self-supporting so as not to require backshoring. Formwork for these beams shall be stripped and shored based on the same requirements as other portions of the elevated slabs. Beam 3 (Pour strip) shall be a Non PT beam as shown on 3/S3.07.

Our pricing excludes the following:

- 5.7 Precast Stairs at front entry plaza. We have included the plaza and steps as cast-in-place.
- 5.8 Concrete Testing by Owner.

6. MASONRY

Our pricing includes the following:

- 6.1 Water-repellant mortar admixture at CMU specified to receive integral water repellent.
- 6.2 CMU walls in the basement noted as Type P shall be changed back to Type Q as shown on the 1/05/09 Permit Documents, except the metal studs and drywall at the Type Q partitions are not included.

Our pricing excludes the following:

- 6.3 Masonry Sealer – This spec duplicates Water Repellants specified in Division 7 (which is included in our GMP).

7. STRUCTURAL STEEL/STEEL FABRICATIONS

Our pricing includes the following:

- 7.1 Cast-in-place exterior stair nosings at locations shown to receive nosings. Interior nosings shall be integral with the metal pan stairs.

Our pricing excludes the following:

- 7.2 AISC or City of Houston certifications for fabricators or erectors. No proposals were received from subs or vendors with these certifications.

8. **ORNAMENTAL METAL**

Our pricing includes the following

- 8.1 24 each Pipe bollards as an Allowance of \$16,800.

9. **ROUGH CARPENTRY**

Our pricing includes the following:

- 9.1 Blocking as shown.
9.2 All plywood backing as shown.
9.3 Blocking behind the courtroom monitors that is not shown.

10. **FINISH CARPENTRY**

Our pricing includes the following:

- 10.1 All cabinets and countertops that have not been labeled as wood, stone or solid surface were priced as plastic laminate.
10.2 The millwork sculptured cabinet at the 1st Lobby level is included as an Allowance of \$5,200.

11. **ARCHITECTURAL WOODWORK**

Our pricing includes the following:

- 11.1 Judges benches were priced with bullet resistant material directly in front of the Judge's bench at the section parallel to the courtroom only (approx. 4'-5" length).

12. **BUILDING INSULATION**

Our pricing includes the following:

- 12.1 K-13 Sprayed insulation at the underside of the Level 1 courthouse slabs and beams (above unoccupied space) and the walls in the basement adjacent to conditioned spaces, as shown. Tan color is included.

13. **WATERPROOFING**

Our pricing includes the following:

- 13.1 40 mil self-adhered asphalt flashing as specified in Specification 042000. Specification 071311 SAF is not included, as this specification conflicts with 042000.
- 13.2 Silicone exterior caulking at shelf angles and control joints of cast stone.
- 13.3 Base drain system for bentonite waterproofing is included. Solid piping and sump pumps that would tie-in to this system are not designed or shown and are not included in the GMP.

Our pricing excludes:

- 13.4 Flood testing of bentonite waterproofing as this is not recommended by the manufacturer.
- 13.5 Caulking of cast stone-cast stone joints not associated with an exterior opening or control joint, per RFI response.
- 13.6 Site and exterior concrete sealants shall be 2 part, self-leveling urethane in lieu of specified non-sag silicone sealants, as previously agreed upon.

14. **ROOFING**

Exclusions:

- 14.1 Roof Hatches or roof access ladders – none shown.

15. **FIREPROOFING**

16. **HOLLOW METAL DOORS AND FRAMES**

17. **WOOD DOORS**

18. **COILING DOORS**

Our pricing includes the following:

- 18.1 Segmented view lites on the service doors at the Central Plant.

19. **FINISH HARDWARE**

Our pricing includes the following:

- 19.1 Specification 0871000 – 2.1.A.1 This specification pertains to Building Codes and Accessibility Statutes, of which the ability to comply with this specification depends upon the hardware selected by the Architect for all affected openings.

20. **GLASS, GLAZING, STOREFRONT, AND SKYLIGHTS**

Our pricing includes the following:

- 20.1 A skylight system by United Sky, proposed equal to the mfr's listed in the specifications.
- 20.2 Skylight dimensions and configurations are based on the structural drawings. We could find no dimensions for these on the Architectural drawings.
- 20.3 Segmented glass barrel vaults in lieu of bent glass per the RFI response.
- 20.4 Standard color two coat Kynar finish on all skylights. Non Exotic/ Non Metallic color to be selected.
- 20.5 A Pyrolytic Low E coating on skylight glass in the absence of any Low E performance data or product reference.
- 20.6 Vistawall storefront system in manufacturer's standard colors/finish.
- 20.7 1 (one) operable window at the south side of Level 2 for access to the adjacent lower roof.

21. **DRYWALL**

Our pricing includes the following:

- 21.1 Moisture resistant gypsum board as backer for ceramic tile at restrooms and Cementitious backer board at Basement Level shower walls.

22. **CERAMIC & STONE TILE & TOPS**

Our pricing includes the following:

- 22.1 Epoxy grout at all tile.
- 22.2 Threshold at doors are priced as a marble threshold.
- 22.3 Crack suppression membrane at all floor tile.
- 22.4 S2 Solid Surface specified on Sheet A0.23 is included as Silestone Coffee Brown.
- 22.5 ST1 Stone specified on Sheet A0.23 is included as Zodiaq Rosso Verona.

Our pricing excludes the following:

- 22.6 Responsibility for slip resistance of tile. The products are specified by the Architect and it is understood that the Architect has verified the selected products will meet the appropriate requirements.
- 22.7 Grout sealer not included since epoxy grout is included per 22.1 above.
- 22.8 Lath and scratch coat at wall tile.

23. **ACOUSTICAL CEILINGS**

24. **TERRAZZO FLOORS**

Our pricing includes the following:

- 24.1 We have assumed a design with 4 colors. We will work with the Architect to achieve an acceptable and workable pattern/design.

25. **RESILIENT TILE & BASE**

Our pricing includes the following:

- 25.1 MCT tile flooring per the finish schedule.
25.2 4" high rubber base per the finish schedule.

26. **CARPET AND FLOORING**

27. **PAINTING AND WALL FINISHES**

Our pricing excludes the following:

- 27.1 Field Painting MEP equipment or piping, except as noted under Section 40 of these Qualifications and Clarifications.
27.2 Responsibility for slip resistance of floor sealers. The Architect shall confirm products specified for concrete sealer and finish coat (Section 097950-3.2C) meet slip resistance requirements.

28. **SPECIAL WALL SURFACING**

29. **TOILET PARTITIONS**

Our pricing includes the following:

- 29.1 Pricing is based on all toilet partitions to be floor mounted per Note TA-09/A4.03, not ceiling hung per Spec section 102113-1 Section 1.2A.1. Specification was not changed in the Final GMP documents

30. **SIGNAGE**

Our pricing excludes the following:

- 30.1 DVD players or CPU units for the LCD monitors because the documents are not clear on who is to furnish these items.

31. **TOILET AND BATH ACCESSORIES**

32. **DETENTION EQUIPMENT**

33. **LOUVERS AND VENTS**

Our pricing includes the following:

- 33.1 Louvers to have a Kynar finish per the documents.

34. **ACCESS FLOOR**

Our pricing includes the following:

- 34.1 Carpet tiles to be furnished and installed by flooring subcontractor as opposed to being provided by access flooring subcontractor.
- 34.2 Responsibility for slip resistance of access flooring. The products are specified by the Architect and it is understood that the Architect has verified the selected products will meet the appropriate requirements.
- 34.3 TecCrete access flooring in lieu of ConCore by Tate Access Floors.

35. **EXTERIOR CLOCK**

36. **FLAGPOLES**

Our pricing includes the following:

- 36.1 Flagpoles are have a 30' exposure designed to meet 110 mph wind load.

37. **HORIZONTAL LOUVER BLINDS**

38. **ELEVATORS**

Our pricing includes the following:

- 38.1 A \$60,000 interior upgrade allowance (total) for elevators 1 and 2. All other cabs are standard finish.
- 38.2 Schindler requires accelerated payment (example: 35% of \$1,194,457 with order submittal). This GMP assumes the Owner will make this payment to JE Dunn who will in turn make payment to Schindler. This payment shall be for Engineering. Materials will not be billed until they are on-site.
- 38.3 Vertical platform lifts will utilize manufacturer's ACME standard screw drive power system in lieu of the specified hydraulic drive system.

Our pricing excludes the following:

- 38.4 Requirements, certifications or required inspection from the Texas Department of Licensing and Regulation approval per Rule 68.31 for wheelchair lifts. RFI responses indicate that it's anticipated that TDLR will waive any requirements not addressed or contrary to the specifications.

39. **FIRE PROTECTION**

Our pricing includes the following:

- 39.1 Fire Extinguisher types, labels and locations shall be as specified and shown by the Architect, in order to satisfy code requirements.

Our pricing excludes the following:

- 39.2 Painting of fire sprinkler piping and labeling beyond that required by NFPA #13.
- 39.3 Factory Mutual requirements.
- 39.4 FM-200 Systems.
- 39.5 Any sprinkler under the roof canopy.
- 39.6 Galvanized pipe on the sprinkler pre-action and dry systems.
- 39.7 Separate piping and valves for sprinkler heads at the Lobby, whereby Fire Doors were deleted.

40. **HVAC**

Our pricing includes the following:

- 40.1 Roof pipe supports to be per 5/M6.03 with bottom of pipe/duct at 24" above roof. This conflicts with Note 8 on M2.04 A&B.
- 40.2 Cooling Tower foundation and supports per Walter P. Moore design dated 5/7/09, transmitted by PGAL via Email.

Our pricing excludes the following:

- 40.3 Test and Balance shall be contracted by the Owner.
- 40.4 Painting of any piping, insulation or ductwork except finish paint of chilled water piping inside the Central Plant and primer coat on all other chilled water piping.
- 40.5 Heat tracing on any piping, exposed or otherwise.
- 40.6 Galvanic Protection on any piping.
- 40.7 Additional structural changes to the building frame in order to support equipment and piping.
- 40.8 Architectural louver fronting or backing the dampers above the catwalk and as indicated by note 2 on Drawings M2.04 A and B. (We do have architectural louvers on the Roof side of the Note 1 openings)
- 40.9 Commissioning.

41. **PLUMBING**

- 41.1 Additional structural changes to the building frame in order to support equipment and piping.

42. **ELECTRICAL**

Our pricing includes the following:

- 42.1 MC Cable is used in areas allowed by code.
- 42.2 An Allowance of \$50,000 is included for Conduits, raceways and all associated work necessary to run these systems from the Tunnel to the required locations within the Existing Jail. This work is not designed.
- 42.3 An Allowance of \$20,000 is included for the Judges' Chambers Intercom System.

Our pricing excludes the following:

- 42.2 Additional structural changes to the building frame in order to support equipment and piping.
- 42.3 Insect control fan referenced on E3.10, note 6. None found in the drawings. Final GMP documents have not deleted the E3.10 note.
- 42.4 Sound masking systems as none are shown.
- 42.5 Costs for permanent transformers and other Utilities provided equipment, if any.

43. **AUDIO VISUAL SYSTEMS**

Our pricing includes the following:

43.1 Projection screens in the Courtrooms as shown.

Our pricing excludes the following:

43.2 All tack boards, chalkboards, monitors, audio systems and other work shown but not specified. This work is assumed to be by Owner's vendors/subcontractors if required.

44. **TECHNOLOGY ENGINEERING SYSTEMS**

Our pricing includes the following:

44.1 Typical work area outlets will be as noted on T0.01 with 2 cable drops (one phone and one data). This note on T0.01 references back to Detail 6/T4.01, which shows two data and one phone outlet. We have 2 drops and outlets per the note on T0.01 and similar to 10/T4.01 with a phone vs. blank outlet.

Our pricing excludes the following:

44.2 Networking equipment, workstation devices, computers, terminals, telephones and similar equipment.

44.3 Innerduct as all coax and fiber optic cabling will have armored shielding.

44.4 4" Conduits shown on the Electrical "E" & Communications "T" drawings from the property lines to MER 10044 are assumed to be empty with pull strings for wiring and connections to be by others.

44.5 Any work or materials for the tunnel, garage, central plant, or site not shown. We have included no wiring or connections to or within the existing jail, if required.

44.6 New equipment at the existing Jail to support the systems shown for the Tunnel.

45. **SECURITY**

End of Qualifications and Clarifications

Exhibit G


Design Completion Schedule Assuming a 6/1/09 NTP

Issuance of Final Addendum to Construction Documents	4/20/09
Submission of final Constructability/Design Review Comments	5/8/09
Design modifications due to Constructability/Design Review Comments	6/15/09
Issuance of final signage/graphics design	6/15/09
Initiation of 3 rd Party Structural Peer Review (upon NTP)	6/1/09*
Completion of 3 rd Party Structural Peer Review	6/29/09
Design Modifications due to 3 rd party Peer Review (if required)	7/27/09

Act ID	Description	Dur. 5d/Wk	Early Start	Early Finish
1280	Construction Start / Notice to Proceed	0	01JUN09 *	
1710	Total Construction Duration - CAL. DAYS	670 *	01JUN09	01APR11
1770	Material (Substantial) Completion	0		01APR11
1775	Final Completion	0		31MAY11

Sitetework				
Act ID	Description	Dur. 5d/Wk	Early Start	Early Finish
1500	Mobilization	10	01JUN09	12JUN09
1720	CLEAR AND GRUB	5	15JUN09	19JUN09
1730	ESTABLISH BENCHMARKS	5	22JUN09	26JUN09
1735	MASS EXCAVATION	20	29JUN09	27JUL09
1736	SITE RETAINING WALLS	60	21JUL09	13OCT09
1740	ROUGH GRADING	60	04AUG09	27OCT09
1750	SITE UTILITIES	50	01SEP09	10NOV09
1760	PAVING BASE	40	17JUN10	12AUG10
1780	PAVING	40	16JUL10	10SEP10
1790	STRIPING	10	13SEP10	24SEP10
1800	FINE GRADING	10	13SEP10	24SEP10
1810	IRRIGATION	30	27SEP10	05NOV10
1820	LANDSCAPING	30	08NOV10	21DEC10
1840	SITE SIGNAGE	10	22DEC10	05JAN11

Foundations				
Act ID	Description	Dur. 5d/Wk	Early Start	Early Finish
2000	EXCAVATE TUNNEL (UNDER BUILDING)	5	28JUL09	03AUG09
2040	SPREAD FOOTINGS	40	28JUL09	22SEP09
2070	DRILL PIERS	20	28JUL09	24AUG09
2005	TUNNEL SLAB	5	04AUG09	10AUG09
2050	GRADE BEAMS	40	04AUG09	29SEP09
2100	COLUMNS BASEMENT TO FIRST FLOOR	40	04AUG09	29SEP09



Early bar
 Progress bar
 Critical bar
 Summary bar
 Start milestone point
 Finish milestone point

JE Dunn Construction
Fort Bend County Justice Center, Richmond, TX
EXHIBIT H - CONSTRUCTION SCHEDULE

Act ID	Description	Dur. 5d/Wk	Early Start	Early Finish
5000	Form Pour A 3.1	5	28OCT09	03NOV09
5010	Form Pour B 3.2	5	04NOV09	10NOV09
5030	Rebar/Sleeves Pour A 3.1	5	04NOV09	10NOV09
5020	Form Pour C 3.3	5	11NOV09	17NOV09
5040	Rebar/Sleeves Pour B 3.2	5	11NOV09	17NOV09
5060	Pour/Columns Pour A 3.1	5	11NOV09	17NOV09
5050	Rebar/Sleeves Pour C 3.3	5	18NOV09	24NOV09
5070	Pour/Columns Pour B 3.2	5	18NOV09	24NOV09
5080	Pour/Columns Pour C 3.3	5	25NOV09	03DEC09
5090	Remove Basement Reshores West	10	04DEC09	17DEC09
West Roof				
6000	Form Pour A Roof/4.1	5	18NOV09	24NOV09
6010	Form Pour B Roof 4.2	5	25NOV09	03DEC09
6030	Rebar/Sleeves Pour A Roof 4.1	5	25NOV09	03DEC09
6020	Form Pour C Roof 4.3	5	04DEC09	10DEC09
6040	Rebar/Sleeves Pour B Roof 4.2	5	04DEC09	10DEC09
6060	Pour/Columns Pour A Roof 4.1	5	04DEC09	10DEC09
6050	Rebar/Sleeves Pour C Roof 4.3	5	11DEC09	17DEC09
6070	Pour/Columns Pour B Roof 4.2	5	11DEC09	17DEC09
6080	Pour/Columns Pour C Roof 4.3	5	18DEC09	28DEC09
6090	Remove 1st Floor Reshores - West Half	10	29DEC09	12JAN10
6100	Remove all West Shoring	20	29DEC09	26JAN10
East 1st Floor				
4500	Form Pour D 1.4	5	11DEC09	17DEC09
4510	Form Pour E 1.5	5	18DEC09	28DEC09
4530	Rebar/Sleeves Pour D 1.4	5	18DEC09	28DEC09
4540	Rebar/Sleeves Pour E 1.5	5	29DEC09	05JAN10
4560	Pour/Columns Pour D 1.4	5	29DEC09	05JAN10
4570	Pour/Columns Pour E 1.5	5	06JAN10	12JAN10
4580	Pour Pour Strip	5	10MAR10	16MAR10
East 2nd Floor				

JE Dunn Construction
Fort Bend County Justice Center, Richmond, TX
EXHIBIT H - CONSTRUCTION SCHEDULE

Start date 01JUN09
 Finish date 31MAY11
 Data date 01JUN09
 Run date 19MAY09
 Page number 3A
 Page count 14A
 © Primavera Systems, Inc.

PR03-Fortbend C...

Act ID	Description	Dur. 5d/Wk	Early Start	Early Finish
5500	Form Pour D 2.4	5	06JAN10	12JAN10
5510	Form Pour E 2.5	5	13JAN10	19JAN10
5530	Rebar/Sleeves Pour D 2.4	5	13JAN10	19JAN10
5540	Rebar/Sleeves Pour E 2.5	5	20JAN10	26JAN10
5560	Pour/Columns Pour D 2.4	5	20JAN10	26JAN10
5570	Pour/Columns Pour E 2.5	5	27JAN10	02FEB10
5580	Pour Pour Strip	5	31MAR10	06APR10
East 3rd Floor				
6500	Form Pour D 3.4	5	27JAN10	02FEB10
6510	Form Pour E 3.5	5	03FEB10	09FEB10
6530	Rebar/Sleeves Pour D 3.4	5	03FEB10	09FEB10
6540	Rebar/Sleeves Pour E 3.5	5	10FEB10	16FEB10
6560	Pour/Columns Pour D 3.4	5	10FEB10	16FEB10
6570	Pour/Columns Pour E 3.5	5	17FEB10	23FEB10
6590	Remove Basement Reshores - East Half	10	24FEB10	09MAR10
6580	Pour Pour Strip	5	21APR10	27APR10
East Roof				
7500	Form Pour D Roof /4.4	5	17FEB10	23FEB10
7510	Form Pour E Roof / 4.5	5	24FEB10	02MAR10
7530	Rebar/Sleeves Pour D Roof / 4.4	5	24FEB10	02MAR10
7540	Rebar/Sleeves Pour E Roof / 4.5	5	03MAR10	09MAR10
7560	Pour/Columns Pour D Roof / 4.4	5	03MAR10	09MAR10
7570	Pour/Columns Pour E Roof / 4.5	5	10MAR10	16MAR10
7580	Remove All East Shoring	20	17MAR10	13APR10
7590	Remove 1st Floor Reshores - East Half	10	17MAR10	30MAR10
Enclosure				
West Roof				
9540	Roof Blocking	20	29DEC09	26JAN10
9550	Temp Roof	7	29DEC09	07JAN10
9560	Roof Insulation	40	13JAN10	09MAR10
9570	Roofing	40	27JAN10	23MAR10
East Roof				

JE Dunn Construction
Fort Bend County Justice Center, Richmond, TX
EXHIBIT H - CONSTRUCTION SCHEDULE

Start date 01JUN09
 Finish date 31MAY11
 Data date 01JUN09
 Run date 19MAY09
 Page number 4A
 Page count 14A
 © Primavera Systems, Inc.

PR03-Fortbend C...

Act ID	Description	Dur. 5d/Wk	Early Start	Early Finish
9700	Roof Blocking	20	10MAR10	06APR10
9710	Temp Roof	7	17MAR10	25MAR10
9720	Roof Insulation	40	24MAR10	18MAY10
9730	Roofing	40	07APR10	02JUN10
West Elevation				
2140	Block Backup	30	11DEC09	26JAN10
2150	Dampproofing	30	29DEC09	09FEB10
2160	Masonry	40	13JAN10	09MAR10
2170	Glazing	35	27JAN10	16MAR10
South Elevation				
8000	Block Backup	30	06JAN10	16FEB10
8010	Dampproofing	30	20JAN10	02MAR10
8020	Masonry	40	03FEB10	30MAR10
8030	Glazing	35	24FEB10	13APR10
North Elevation				
9000	Block Backup	30	27JAN10	09MAR10
9010	Dampproofing	30	10FEB10	23MAR10
9020	Masonry	40	24FEB10	20APR10
9030	Glazing	35	10MAR10	27APR10
9040	West Building Dry	0		27APR10
East Elevation				
9500	Block Backup	30	17MAR10	27APR10
9510	Dampproofing	30	31MAR10	11MAY10
9520	Masonry	40	14APR10	09JUN10
9530	Glazing	35	28APR10	16JUN10
9580	East Building Dry	0		16JUN10

Interior				
Basement				
10000	BEGIN INTERIOR WORK	0	18DEC09	
10010	LAYOUT WALLS	5	18DEC09	28DEC09
10020	INSTALL CEILING TRACK	3	29DEC09	31DEC09
10030	INSTALL BLOCK WALLS & FRAMES	15	29DEC09	19JAN10

Start date 01JUN09
 Finish date 31MAY11
 Data date 01JUN09
 Run date 19MAY09
 Page number 5A
 Page count 14A
 © Primavera Systems, Inc.

PR03-Fortbend C...
 JE Dunn Construction
 Fort Bend County Justice Center, Richmond, TX
 EXHIBIT H - CONSTRUCTION SCHEDULE

Legend:

- Early bar
- Progress bar
- Critical bar
- Summary bar
- Start milestone point
- Finish milestone point

Act ID	Description	Dur. 5d/Wk	Early Start	Early Finish
10040	INSTALL DUCTWORK	15	04JAN10	22JAN10
10050	INSTALL OH MEP	20	20JAN10	16FEB10
10060	FRAME WALLS	15	03FEB10	23FEB10
10080	WALL ROUGH IN	15	10FEB10	02MAR10
10070	INSTALL FRAMES	5	17FEB10	23FEB10
10090	WALL INSPECTION	1	03MAR10	03MAR10
10100	ROCK WALLS	15	28APR10	18MAY10
10110	FRAME HARD CEILINGS	3	05MAY10	07MAY10
10120	ROUGH IN CEILINGS	5	10MAY10	14MAY10
10130	ROCK CEILINGS	5	17MAY10	21MAY10
10140	TAPE AND FINISH WALLS	10	24MAY10	07JUN10
10150	PAINT WALLS AND CEILINGS	6	08JUN10	15JUN10
10160	CEILING GRID	5	16JUN10	22JUN10
10180	INSTALL SPECIALTIES	10	16JUN10	29JUN10
10190	START UP AHU'S	15	17JUN10	08JUL10
10200	DROP DIFFUSERS, LIGHTS, HEADS	5	23JUN10	29JUN10
10210	OH INSPECTION	1	30JUN10	30JUN10
10250	DROP TILE	3	01JUL10	06JUL10
10170	INSTALL FINISH CARP.	10	09JUL10	22JUL10
10260	TEST AND BALANCE	10	09JUL10	22JUL10
10220	HARD FLOORING	10	23JUL10	05AUG10
10230	DOORS AND HARDWARE	10	23JUL10	05AUG10
10240	TRIM OUT MEP	10	23JUL10	05AUG10
10270	INSTALL CARPET	5	06AUG10	12AUG10
10280	FINAL PAINT WALLS	3	13AUG10	17AUG10
10290	FINAL PAINT DOORS AND FRAMES	2	18AUG10	19AUG10
10300	PRE PUNCH	15	20AUG10	10SEP10
10310	ARCH/OWNER PUNCH	1	13SEP10	13SEP10
10320	CORRECT PUNCH ITEMS	10	14SEP10	27SEP10
10330	FINAL CLEAN	5	28SEP10	04OCT10

1st Floor West Side

Start date 01JUN09
 Finish date 31MAY11
 Data date 01JUN09
 Run date 19MAY09
 Page number 6A
 Page count 14A
 © Primavera Systems, Inc.

PR03-Fortbend C...
 JE Dunn Construction
 Fort Bend County Justice Center, Richmond, TX
 EXHIBIT H - CONSTRUCTION SCHEDULE

Legend:
 [Pattern] Early bar
 [Pattern] Progress bar
 [Pattern] Critical bar
 [Pattern] Summary bar
 [Symbol] Start milestone point
 [Symbol] Finish milestone point

Act ID	Description	Dur. 5d/Wk	Early Start	Early Finish
11000	BEGIN INTERIOR WORK	0	13JAN10	
11010	LAYOUT WALLS	5	13JAN10	19JAN10
11020	INSTALL CEILING TRACK	3	20JAN10	22JAN10
11030	INSTALL BLOCK WALLS & FRAMES	15	20JAN10	09FEB10
11040	INSTALL DUCTWORK	15	25JAN10	12FEB10
11050	INSTALL OH MEP	20	10FEB10	09MAR10
11060	FRAME WALLS	15	24FEB10	16MAR10
11080	WALL ROUGH IN	15	03MAR10	23MAR10
11070	INSTALL FRAMES	5	10MAR10	16MAR10
11090	WALL INSPECTION	3	24MAR10	26MAR10
11100	ROCK WALLS	15	19MAY10	09JUN10
11110	FRAME HARD CEILINGS	10	26MAY10	09JUN10
11120	ROUGH IN CEILINGS	5	10JUN10	16JUN10
11130	ROCK CEILINGS	5	17JUN10	23JUN10
11140	TAPE AND FINISH WALLS	10	24JUN10	08JUL10
11150	PAINT WALLS AND CEILINGS	6	09JUL10	16JUL10
11160	CEILING GRID	5	19JUL10	23JUL10
11180	INSTALL SPECIALTIES	10	19JUL10	30JUL10
11190	START UP AHU'S	15	19JUL10	06AUG10
11200	DROP DIFFUSERS, LIGHTS, HEADS	8	26JUL10	04AUG10
11210	OH INSPECTION	1	05AUG10	05AUG10
11170	INSTALL FINISH CARP.	25	09AUG10	13SEP10
11250	DROP TILE	5	09AUG10	13AUG10
11260	TEST AND BALANCE	10	16AUG10	27AUG10
11220	HARD FLOORING / TERRAZZO	30	14SEP10	25OCT10
11230	DOORS AND HARDWARE	10	14SEP10	27SEP10
11240	TRIM OUT MEP	10	14SEP10	27SEP10
11270	INSTALL CARPET	7	26OCT10	03NOV10
11280	FINAL PAINT WALLS	5	04NOV10	10NOV10
11290	FINAL PAINT DOORS AND FRAMES	3	11NOV10	15NOV10
11300	PRE PUNCH	15	16NOV10	08DEC10

Start date 01JUN09

Finish date 31MAY11

Data date 01JUN09

Run date 19MAY09

Page number 7A

Page count 14A

© Primavera Systems, Inc.

PR03-Fortbend C...

JE Dunn Construction

Fort Bend County Justice Center, Richmond, TX

EXHIBIT H - CONSTRUCTION SCHEDULE

Legend:

- Early bar
- Progress bar
- Critical bar
- Summary bar
- Start milestone point
- Finish milestone point

Act ID	Description	Dur. 5d/Wk	Early Start	Early Finish
11310	ARCH/OWNER PUNCH	1	09DEC10	09DEC10
11320	CORRECT PUNCH ITEMS	10	10DEC10	23DEC10
11330	FINAL CLEAN	5	27DEC10	31DEC10

Act ID	Description	Dur. 5d/Wk	Early Start	Early Finish
1st Floor East Side				
12000	BEGIN INTERIOR WORK	0	31MAR10	
12010	LAYOUT WALLS	5	31MAR10	06APR10
12020	INSTALL CEILING TRACK	3	07APR10	09APR10
12030	INSTALL BLOCK WALLS & FRAMES	15	07APR10	27APR10
12040	INSTALL DUCTWORK	15	12APR10	30APR10
12050	INSTALL OH MEP	20	28APR10	25MAY10
12060	FRAME WALLS	15	12MAY10	02JUN10
12080	WALL ROUGH IN	15	19MAY10	09JUN10
12070	INSTALL FRAMES	5	26MAY10	02JUN10
12090	WALL INSPECTION	1	10JUN10	10JUN10
12100	ROCK WALLS	15	17JUN10	08JUL10
12110	FRAME HARD CEILINGS	10	24JUN10	08JUL10
12120	ROUGH IN CEILINGS	5	09JUL10	15JUL10
12130	ROCK CEILINGS	5	16JUL10	22JUL10
12140	TAPE AND FINISH WALLS	10	23JUL10	05AUG10
12150	PAINT WALLS AND CEILINGS	6	06AUG10	13AUG10
12160	CEILING GRID	5	16AUG10	20AUG10
12180	INSTALL SPECIALTIES	10	16AUG10	27AUG10
12190	START UP AHU'S	15	16AUG10	03SEP10
12200	DROP DIFFUSERS, LIGHTS, HEADS	7	23AUG10	31AUG10
12210	OH INSPECTION	1	01SEP10	01SEP10
12170	INSTALL FINISH CARP.	15	07SEP10	27SEP10
12250	DROP TILE	5	07SEP10	13SEP10
12260	TEST AND BALANCE	10	14SEP10	27SEP10
12220	HARD FLOORING	10	28SEP10	11OCT10
12230	DOORS AND HARDWARE	10	28SEP10	11OCT10
12240	TRIM OUT MEP	10	28SEP10	11OCT10

- ◇ BEGIN INTERIOR WORK
- ▣ LAYOUT WALLS
- ▣ INSTALL CEILING TRACK
- ▣ INSTALL BLOCK WALLS & FRAMES
- ▣ INSTALL DUCTWORK
- ▣ INSTALL OH MEP
- ▣ FRAME WALLS
- ▣ WALL ROUGH IN
- ▣ INSTALL FRAMES
- | WALL INSPECTION
- ▣ ROCK WALLS
- ▣ FRAME HARD CEILINGS
- ▣ ROUGH IN CEILINGS
- ▣ ROCK CEILINGS
- ▣ TAPE AND FINISH WALLS
- ▣ PAINT WALLS AND CEILINGS
- ▣ CEILING GRID
- ▣ INSTALL SPECIALTIES
- ▣ START UP AHU'S
- ▣ DROP DIFFUSERS, LIGHTS, HEADS
- | OH INSPECTION
- ▣ INSTALL FINISH CARP.
- ▣ DROP TILE
- ▣ TEST AND BALANCE
- ▣ HARD FLOORING
- ▣ DOORS AND HARDWARE
- ▣ TRIM OUT MEP

Start date	01JUN09
Finish date	31MAY11
Data date	01JUN09
Run date	19MAY09
Page number	8A
Page count	14A
© Primavera Systems, Inc.	

PR03-Fortbend C...

JE Dunn Construction
Fort Bend County Justice Center, Richmond, TX
EXHIBIT H - CONSTRUCTION SCHEDULE

▣	Early bar
▣	Progress bar
▣	Critical bar
▣	Summary bar
◇	Start milestone point
◇	Finish milestone point

Act ID	Description	Dur. 5d/Wk	Early Start	Early Finish	2009	2010	2011
12270	INSTALL CARPET	7	04NOV10	12NOV10			INSTALL CARPET
12280	FINAL PAINT WALLS	5	15NOV10	19NOV10			FINAL PAINT WALLS
12290	FINAL PAINT DOORS AND FRAMES	3	22NOV10	24NOV10			FINAL PAINT DOORS AND FRAMES
12300	PRE PUNCH	15	09DEC10	30DEC10			PRE PUNCH
12310	ARCH/OWNER PUNCH	1	31DEC10	31DEC10			ARCH/OWNER PUNCH
12320	CORRECT PUNCH ITEMS	10	03JAN11	14JAN11			CORRECT PUNCH ITEMS
12330	FINAL CLEAN	5	17JAN11	21JAN11			FINAL CLEAN
2nd Floor West Side							
13000	BEGIN INTERIOR WORK	0	07APR10				BEGIN INTERIOR WORK
13010	LAYOUT WALLS	5	07APR10	13APR10			LAYOUT WALLS
13020	INSTALL CEILING TRACK	3	14APR10	16APR10			INSTALL CEILING TRACK
13030	INSTALL BLOCK WALLS & FRAMES	15	14APR10	04MAY10			INSTALL BLOCK WALLS & FRAMES
13040	INSTALL DUCTWORK	15	19APR10	07MAY10			INSTALL DUCTWORK
13050	INSTALL OH MEP	20	05MAY10	02JUN10			INSTALL OH MEP
13060	FRAME WALLS	15	19MAY10	09JUN10			FRAME WALLS
13080	WALL ROUGH IN	15	26MAY10	16JUN10			WALL ROUGH IN
13070	INSTALL FRAMES	5	03JUN10	09JUN10			INSTALL FRAMES
13090	WALL INSPECTION	1	17JUN10	17JUN10			WALL INSPECTION
13100	ROCK WALLS	15	18JUN10	09JUL10			ROCK WALLS
13110	FRAME HARD CEILINGS	10	25JUN10	09JUL10			FRAME HARD CEILINGS
13120	ROUGH IN CEILINGS	5	12JUL10	16JUL10			ROUGH IN CEILINGS
13130	ROCK CEILINGS	5	19JUL10	23JUL10			ROCK CEILINGS
13140	TAPE AND FINISH WALLS	10	26JUL10	06AUG10			TAPE AND FINISH WALLS
13150	PAINT WALLS AND CEILINGS	6	09AUG10	16AUG10			PAINT WALLS AND CEILINGS
13160	CEILING GRID	5	17AUG10	23AUG10			CEILING GRID
13180	INSTALL SPECIALTIES	10	17AUG10	30AUG10			INSTALL SPECIALTIES
13190	START UP AHU'S	15	17AUG10	07SEP10			START UP AHU'S
13200	DROP DIFFUSERS, LIGHTS, HEADS	8	24AUG10	02SEP10			DROP DIFFUSERS, LIGHTS, HEADS
13210	OH INSPECTION	1	03SEP10	03SEP10			OH INSPECTION
13250	DROP TILE	5	08SEP10	14SEP10			DROP TILE
13170	INSTALL FINISH CARP.	25	14SEP10	18OCT10			INSTALL FINISH CARP.

Early bar
 Progress bar
 Critical bar
 Summary bar
 Start milestone point
 Finish milestone point

Start date 01JUN09
 Finish date 31MAY11
 Data date 01JUN09
 Run date 19MAY09
 Page number 9A
 Page count 14A
 © Primavera Systems, Inc.

PR03-Fortbend C...

JE Dunn Construction
 Fort Bend County Justice Center, Richmond, TX
 EXHIBIT H - CONSTRUCTION SCHEDULE

Act ID	Description	Dur. 5c/Wk	Early Start	Early Finish
15150	PAINT WALLS AND CEILINGS	6	07SEP10	14SEP10
15160	CEILING GRID	5	15SEP10	21SEP10
15180	INSTALL SPECIALTIES	10	15SEP10	28SEP10
15190	START UP AHU'S	15	15SEP10	05OCT10
15200	DROP DIFFUSERS, LIGHTS, HEADS	8	22SEP10	01OCT10
15210	OH INSPECTION	1	04OCT10	04OCT10
15250	DROP TILE	5	06OCT10	12OCT10
15260	TEST AND BALANCE	10	13OCT10	26OCT10
15170	INSTALL FINISH CARP.	30	26OCT10	08DEC10
15220	HARD FLOORING	10	09DEC10	22DEC10
15230	DOORS AND HARDWARE	10	09DEC10	22DEC10
15240	TRIM OUT MEP	10	09DEC10	22DEC10
15270	INSTALL CARPET	7	23DEC10	03JAN11
15280	FINAL PAINT WALLS	5	04JAN11	10JAN11
15290	FINAL PAINT DOORS AND FRAMES	3	11JAN11	13JAN11
15300	PRE PUNCH	15	14JAN11	03FEB11
15310	ARCH/OWNER PUNCH	1	04FEB11	04FEB11
15320	CORRECT PUNCH ITEMS	10	07FEB11	18FEB11
15330	FINAL CLEAN	5	21FEB11	25FEB11
3rd Floor East Side				
16000	BEGIN INTERIOR WORK	0	26MAY10	
16010	LAYOUT WALLS	5	26MAY10	02JUN10
16020	INSTALL CEILING TRACK	3	03JUN10	07JUN10
16030	INSTALL BLOCK WALLS & FRAMES	15	03JUN10	23JUN10
16040	INSTALL DUCTWORK	15	08JUN10	28JUN10
16050	INSTALL OH MEP	20	24JUN10	22JUL10
16060	FRAME WALLS	15	09JUL10	29JUL10
16080	WALL ROUGH IN	15	16JUL10	05AUG10
16070	INSTALL FRAMES	5	23JUL10	29JUL10
16090	WALL INSPECTION	1	06AUG10	06AUG10
16100	ROCK WALLS	15	09AUG10	27AUG10

Start date 01JUN09

Finish date 31MAY11

Data date 01JUN09

Run date 19MAY09

Page number 12A

Page count 14A

© Primavera Systems, Inc.

PR03-Fortbend C...

JE Dunn Construction

Fort Bend County Justice Center, Richmond, TX

EXHIBIT H - CONSTRUCTION SCHEDULE

Legend:

- Early bar
- Progress bar
- Critical bar
- Summary bar
- Start milestone point
- Finish milestone point

Act ID	Description	Dur. 5d/Wk	Early Start	Early Finish
16110	FRAME HARD CEILINGS	10	16AUG10	27AUG10
16120	ROUGH IN CEILINGS	5	30AUG10	03SEP10
16130	ROCK CEILINGS	5	07SEP10	13SEP10
16140	TAPE AND FINISH WALLS	10	14SEP10	27SEP10
16150	PAINT WALLS AND CEILINGS	6	28SEP10	05OCT10
16160	CEILING GRID	5	06OCT10	12OCT10
16180	INSTALL SPECIALTIES	10	06OCT10	19OCT10
16190	START UP AHU'S	15	06OCT10	26OCT10
16200	DROP DIFFUSERS, LIGHTS, HEADS	7	13OCT10	21OCT10
16210	OH INSPECTION	1	22OCT10	22OCT10
16250	DROP TILE	5	27OCT10	02NOV10
16260	TEST AND BALANCE	10	03NOV10	16NOV10
16170	INSTALL FINISH CARP.	30	23NOV10	06JAN11
16220	HARD FLOORING	10	07JAN11	20JAN11
16230	DOORS AND HARDWARE	10	07JAN11	20JAN11
16240	TRIM OUT MEP	10	07JAN11	20JAN11
16270	INSTALL CARPET	7	21JAN11	31JAN11
16280	FINAL PAINT WALLS	5	01FEB11	07FEB11
16290	FINAL PAINT DOORS AND FRAMES	3	08FEB11	10FEB11
16300	PRE PUNCH	15	11FEB11	03MAR11
16310	ARCH/OWNER PUNCH	1	04MAR11	04MAR11
16320	CORRECT PUNCH ITEMS	20	07MAR11	01APR11
16340	MATERIAL (SUBSTANTIAL) COMPLETION	0		01APR11
16330	FINAL CLEAN / FINAL PUNCH	42	04APR11	31MAY11
16350	FINAL COMPLETION	0		31MAY11

Elevators & Escalators	
17000	Install Elevators
17010	Install Escalators

GARAGE (BY OTHERS)	
17000	Install Elevators
17010	Install Escalators

Start date	01JUN09
Finish date	31MAY11
Data date	01JUN09
Run date	19MAY09
Page number	13A
Page count	14A
© Primavera Systems, Inc.	

PR03-Fortbend C...

JE Dunn Construction
 Fort Bend County Justice Center, Richmond, TX
 EXHIBIT H - CONSTRUCTION SCHEDULE

	Early bar
	Progress bar
	Critical bar
	Summary bar
	Start milestone point
	Finish milestone point

3153810		TOTAL \$1,871,457		10320		Estimating Rate (more than 1 year) Thru 6-09		Estimating Rate Through 6-10	
Job Title	% of time on Job	rate/week	Comm Equip	Rate (less than 1 year) Thru 6-09	Rate (more than 1 year) Thru 6-09	Rate Through 6-10	Estimating Rate Through 6-10	Charge to jobs	Estimating Rate Through 6-10
Supervision	5.00%	4295	220	4800	4,130	4295	4295	4800	4,130
General Superintendent	105.00%	3338	4620	3705	3,210	3338	3338	3705	3,210
Senior Superintendent	105.00%	2673	4620	2987	2,570	2673	2673	2987	2,570
Superintendent	0.00%	1872	0	2040	1,800	1872	1872	2040	1,800
Assistant Superintendent	0.60%	1622	0	1760	1,560	1622	1622	1760	1,560
Superintendent Trainee	105.00%	4285	4620	3927	3,420	4285	4285	3927	3,420
Sr Project Manager	0.00%	2766	0	3052	2,660	2766	2766	3052	2,660
Project Manager	105.00%	2059	4620	2204	1,980	2059	2059	2204	1,980
Assistant Project Manager	20.00%	1581	0	1720	1,520	1581	1581	1720	1,520
Field Engineer & Rodman	10.00%	1872	880	2080	1,800	1872	1872	2080	1,800
Quality Assurance	0.00%	1280	0	1400	1,240	1280	1280	1400	1,240
Administrative Assistant	0.00%	1185	0	1240	1,160	1185	1185	1240	1,160
Senior Project Coordinator	0.00%	3453	0	3840	3,320	3453	3453	3840	3,320
Project Coordinator	0.00%	2496	0	2800	2,400	2496	2496	2800	2,400
Senior Estimator	0.00%	1789	0	1960	1,720	1789	1789	1960	1,720
Estimator	0.00%	5408	0	5200	5,200	5408	5408	5200	5,200
Assistant Estimator	0.00%	1581	0	1720	1,520	1581	1581	1720	1,520
Commissioning	100.00%	2538	4400	2800	2,440	2538	2538	2800	2,440
Safety Engineer	0.00%	2538	220	2800	2,440	2538	2538	2800	2,440
Scheduler	0.00%	4285	1320	4800	4,120	4285	4285	4800	4,120
Engineer Services (NET 200)	30.00%		1320						
Project Executives (Office)	30.00%		1320						
LABOR TOTAL		21,476		205,920		21,476		205,920	
LABOR UNIT		5 WK		100 WK		5 WK		100 WK	
LABOR TOTAL		333,840		333,840		333,840		333,840	
LABOR UNIT		100 WK		100 WK		100 WK		100 WK	
LABOR TOTAL		267,280		267,280		267,280		267,280	
LABOR UNIT		0 WK		0 WK		0 WK		0 WK	
LABOR TOTAL		428,480		428,480		428,480		428,480	
LABOR UNIT		100 WK		100 WK		100 WK		100 WK	
LABOR TOTAL		2,766		2,766		2,766		2,766	
LABOR UNIT		0 WK		0 WK		0 WK		0 WK	
LABOR TOTAL		205,920		205,920		205,920		205,920	
LABOR UNIT		100 WK		100 WK		100 WK		100 WK	
LABOR TOTAL		80,621		80,621		80,621		80,621	
LABOR UNIT		34 WK		34 WK		34 WK		34 WK	
LABOR TOTAL		35,568		35,568		35,568		35,568	
LABOR UNIT		19 WK		19 WK		19 WK		19 WK	
LABOR TOTAL		135,408		135,408		135,408		135,408	
LABOR UNIT		105 WK		105 WK		105 WK		105 WK	
LABOR TOTAL		1,414		1,414		1,414		1,414	
LABOR UNIT		0 WK		0 WK		0 WK		0 WK	
LABOR TOTAL		1,165		1,165		1,165		1,165	
LABOR UNIT		0 WK		0 WK		0 WK		0 WK	
LABOR TOTAL		3,453		3,453		3,453		3,453	
LABOR UNIT		0 LS		0 LS		0 LS		0 LS	
LABOR TOTAL		2,496		2,496		2,496		2,496	
LABOR UNIT		0 WK		0 WK		0 WK		0 WK	
LABOR TOTAL		1,769		1,769		1,769		1,769	
LABOR UNIT		0 WK		0 WK		0 WK		0 WK	
LABOR TOTAL		5,408		5,408		5,408		5,408	
LABOR UNIT		0 WK		0 WK		0 WK		0 WK	
LABOR TOTAL		150,176		150,176		150,176		150,176	
LABOR UNIT		95 WK		95 WK		95 WK		95 WK	
LABOR TOTAL		12,688		12,688		12,688		12,688	
LABOR UNIT		5 WK		5 WK		5 WK		5 WK	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		1320		1320		1320		1320	
LABOR TOTAL		4285		4285		4285		4285	
LABOR UNIT		1320		1320		1320		1320	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT		195,980		195,980		195,980		195,980	
LABOR TOTAL		195,980		195,980		195,980		195,980	
LABOR UNIT									

Exhibit I

Code	Description	QTY	Unit	Rate	Amount	Rate	Amount	Rate	Amount	
01230	Barricade/Guardrails	1	LS	0	0	0	0	0	0.00%	
01231	Temp. Ladders & Stairs	1	EA	0	0	0	0	0	0.00%	
01233	Overhead Protection	1	EA	0	0	0	0	0	0.00%	
01234	Temp. Dry Sheet	1	LS	0	0	0	0	0	0.00%	
01235	General Safety & Maintenance	1	LS	18,450	18,450	0	0	0	0.04%	
01240	Office Janitorial	22	MO	0	0	440	9,680	0	0.02%	
01241	Dumpster	0	EA	450	0	0	0	0	0.00%	
01242	Street Cleaning	1	LS	0	0	0	0	0	0.00%	
01243	Daily Clean Up	95.26	WK	0	0	0	0	0	0.00%	
012431	Final Clean Up Building	279,011	SF	0	0	0	0	0	0.00%	
012431	Final Clean Up - Garage	1	SF	0	0	0.97	0	0	0.00%	
012431	Job Meetings and Ceremony Expense	1	ls	0	0	10,000	10,000	0	0.02%	
01260	Partnering Sessions	1	LS	0	0	5,000	5,000	0	0.01%	
01299	Misc.-Temp. Facilities	1	LS	0	0	0	0	0	0.00%	
Personnel Hoisting										
01310	Hoist Personnel Freight Rental	22	MO	0	0	0	0	0	0.00%	
01311	Base Construction	0	LS	0	0	0	0	0	0.00%	
01310	Crane Rental	22	MO	0	0	0	0	0	0.00%	
01311	Base Construction	0	LS	0	0	0	0	0	0.00%	
01313	Gates Platforms Brackets	0	EA	0	0	0	0	0	0.00%	
01315	Hoist Up Down	0	LF	0	0	0	0	0	0.00%	
01315	Crane Up Down	0	LF	0	0	0	0	0	0.00%	
01316	Hoist-Oper.	95.26	WK	0	0	0	0	0	0.00%	
01318	Crane-Oper.	22	MO	0	0	0	0	0	0.00%	
01399	Misc.-Hoisting (Pers./Matl.)	1	LS	0	0	0	0	0	0.00%	
Temporary Utilities										
01401	Telephone Service (4 lines)	22	MO	0	600	13,200	0	0	0.03%	
01402	Phone Hook up (4 lines)	1	LS	0	1,000	1,000	0	0	0.00%	
01402	Water Billings	22	MO	0	75	1,650	0	0	0.00%	
01403	Gas Utility Billings	22	MO	0	0	0	0	0	0.00%	
01404	Electricity Billings - Field Offices Only	279,011	SF	0	\$ 0.13	35,208	0	0	0.07%	
01404	Electricity Billings	22	MO	0	0	0	0	0	0.00%	
01404	Electricity Billings	22	MO	0	0	0	0	0	0.00%	
01405	Temp. Util. Services	1	LS	0	4,000	4,000	0	0	0.01%	
01406	Temp. HVAC/Filters	1	LS	0	0	0	0	0	0.00%	
01499	Misc.-Temp. Utilities	1	LS	0	0	0	0	0	0.00%	
Equipment Rental										
01501	Small Equip. Rental	1	LS	0	28,500	28,500	0	0	0.06%	
01502	Warehouse Del. Trucks	22	LS	0	0	0	0	0	0.00%	
01503	Pickup Trucks	22	MO	0	0	0	0	0	0.00%	
01503	Pickup Trucks	22	MO	0	0	0	0	0	0.00%	

Exhibit I

01503	Fuel Oil Gas Pickup Trucks	24	MO	0	150	3,600	0	0	0	3,600	0	0.01%
01504	1 or 2 Ton Trucks (Flatbed)	22	MO	0	0	0	0	0	0	0	0	0.00%
01505	Boom Truck	22	MO	0	0	0	0	0	0	0	0	0.00%
01506	Radio's/Repeater/Cell Phone	1	LS	0	19580	19,580	0	0	0	19,580	0	0.04%
01599	Misc.-Equip. Rental	1	LS	0	0	0	0	0	0	0	0	0.00%
Permits, Bonds & Insurance												
01601.01	Permits	1	LS	0	0	0	0	0	0	0	0	0.22%
01602.1	Bldrs. Risk/DIC Insurance	1	LS	0	0	0	0	0	0	0	0	1.01%
01613	Wind Premium	0	LS	0	0	0	0	0	0	0	0	0.00%
01615.01	Flood Premium	0	LS	0	0	0	0	0	0	0	0	0.00%
01616	Terrorist	1	LS	0	0	0	0	0	0	0	0	0.00%
01617	OCP Insurance	1	LS	0	0	0	0	0	0	0	0	0.00%
01618	AGC Dues	1	LS	0	5795	5,795	0	0	0	0	0	0.01%
01699	Liability Insurances	1	LS	0	0	0	0	0	0	0	0	1.18%
	P & P Bond	1	LS	0	0	0	0	0	0	0	0	0.82%
	Laber Burden on Field	0	\$\$	0	0.8000	0	0	0	0	0	0	0
	Total				1,869,306	287,029	1,919,064	4,075,400	4075399.896			
521,550					1,869,306	287,029	1,919,064	4,075,400				7.86%
					cost	51,700,000						

2,401,825
4.65%

Exhibit I

ite	Through		
	6-11		
	4467		
	3472		
	2780		
	1947		
	1687		
	3699		
	2877		
	2142		
	1644		
	1947		
	1341		
	1471		
	1211		
	3591		
	2596		
	1860		
	5624		
	1644		
	2639		
	2639		
	4456		
		% of gc	
		0.53%	
		8.19%	
		6.56%	
		0.00%	
		0.00%	
		10.51%	
		0.00%	
		5.05%	
		1.98%	
		0.87%	
		3.32%	
		0.00%	
		0.00%	
		0.00%	
		0.00%	
		0.00%	
		0.00%	
		0.00%	
		3.68%	
		0.31%	

Exhibit I

1.81%
3.05%
0.00%
0.00%
0.00%
0.00%
0.74%
0.12%
3.91%
0.40%
0.00%
0.00%
0.04%
0.11%
0.00%
0.05%
0.00%

0.73%

0.11%

0.54%
0.00%
0.00%
0.07%
0.12%
0.51%
0.08%
0.00%
0.54%
0.00%
0.01%
0.16%
0.00%
0.00%
0.00%
0.00%
0.43%
0.01%
0.17%
0.00%
0.00%
0.12%
0.12%
0.00%

Exhibit I

0.00%
0.00%
0.00%
0.00%
0.45%
0.24%
0.00%
0.00%
0.00%
0.00%
0.00%
0.25%
0.12%
0.00%

0.00%
0.00%
0.00%
0.00%
0.00%
0.00%
0.00%
0.00%
0.00%
0.00%
0.00%

0.32%
0.02%
0.04%
0.00%
0.86%
0.00%
0.00%
0.10%
0.00%
0.00%

0.70%
0.00%
0.00%
0.00%

Exhibit I

0.09%
0.00%
0.00%
0.48%
0.00%

2.81%
12.80%
0.00%
0.00%
0.00%
0.14%
14.93%
10.38%

99.72%

**Exhibit J
PROJECT COST MATRIX**

In each of the spaces marked with an "x", excluding Cost of the Work, enter the total monthly amount for that item, the unit measure and the number of units involved

Project No.

Office Expense	Total Quantity	Unit	Monthly Rate				TOTAL
			In Pre-Const. Services	In Construction Services	Cost of Work	By Others	
CM Field Office, Furniture & Furnishings	22	MO		\$1,907.41			\$41,963.00
Office Supplies - Preconst.	2		\$495.00				\$990.00
Office Supplies	22	MO		\$1,000.00			\$22,000.00
Field Office Equipment & Maintenance (Temporary Fence)	22	MO		\$1,843.38			\$40,554.40
Owner/Arch Office, Equip & Utilities for all Trailers only	22	MO		\$2,375.37			\$52,258.10
Jobsite Radios/Beepers	22	MO		\$890.00			\$19,580.00
Copy Machine & Maintenance - Preconst.	2	MO	\$2,209.00				\$4,418.00
Copy Machine & Maintenance	22	MO		\$300.00			\$6,600.00
Computers, Usage, Software & Maintenance - Pre			with precon labor				\$0.00
Computers, Usage, Software & Maintenance (network)	22	MO		\$1,143.18			\$25,150.00
Fax Machine & Service	22	MO		\$12.50			\$275.00
Field Office Telephone	22	MO		\$645.45			\$14,200.00
Long Distance - Preconst.	2		\$275.00				\$550.00
Long Distance				with telephone			\$0.00
Office Janitorial	22	MO		\$440.00			\$9,680.00
Postage & Expressage - Preconst.	2	MO	\$137.50				\$275.00
Postage & Expressage	22	MO		\$750.00			\$16,500.00
Plans & Specifications (6 sets per bid pkg.)	22	MO		\$1,363.64			\$30,000.00
Scheduling Expenses	22	MO		\$576.73			\$12,688.00
Construction Photos & Supplies	22	MO		\$150.00			\$3,300.00
Job Travel	22	MO		\$366.27			\$8,058.00
Job Meetings & Ceremony Expense	22	MO		\$454.55			\$10,000.00
Partnering Sessions	22	MO		\$227.27			\$5,000.00
Construction Trade Training Program	22	MO		\$263.41			\$5,795.00
Record Drawings	22	MO		\$295.45			\$6,500.00
Advertising (for bids)					x		\$0.00
Messenger/Runner/Courier					x		\$0.00
Audit				\$0.00			\$0.00
Records Storage				\$0.00			\$0.00
Public Information Program				\$0.00			\$0.00



Testing, Inspection & Quality Control			In Pre-Const. Services	In Construction Services	Cost of Work	By Others	TOTAL
Testing Laboratory Services						x	\$0.00
Soils Testing & Inspection						x	\$0.00
Concrete Testing & Inspections						x	\$0.00
QC/QA Manager	22	MO		\$1,616.73			\$35,568.00
Taxes/Insurance/Fees			In Pre-Const. Services	In Construction Services	Cost of Work	By Others	TOTAL
Building Permits	22	MO		\$5,211.36			\$114,650.00
Special Permits, Licenses, Fees (not required per City)				\$0.00			\$0.00
Utility Connection Permits (not available from City)				\$0.00			\$0.00
Operational Permits						x	\$0.00
Easements						x	\$0.00
Impact Fees (not available from City)				\$0.00			\$0.00
Worker's Compensation Insurance				included with labor			\$0.00
Builder's Risk Insurance	22	MO		\$23,706.82			\$521,550.00
Insurance Deductibles				\$0.00			\$0.00
Owner's Protective Insurance				Need limit requirements			\$0.00
Liability & Property Insurance for Project	22	MO		\$27,657.95			\$608,475.00
Miscellaneous Insurance				\$0.00			\$0.00
Sales, Use and Gross Receipts Taxes				Exempt			\$0.00
Performance & Payment Bonds	22	MO		\$19,232.05			\$423,105.00
Construction Management Labor			In Pre-Const. Services	In Construction Services	Cost of Work	By Others	TOTAL
Payroll Tax Fringes			included in labor	included in labor			\$0.00
Worker's Compensation Insurance			included in labor	included in labor			\$0.00
Pre-const. Management Labor	2	MO	\$28,209.17				\$56,418.34
Const. Management Labor	22	MO		\$41,454.53			\$911,999.60
Safety Officer	22	MO		\$6,917.09			\$152,176.00
General Conditions Labor	22	MO		\$38,079.73			\$837,754.00
Fees			In Pre-Const. Services	In Construction Services	Cost of Work	By Others	TOTAL
CM Fees (Separately proposed)							\$0.00
Legal Fees				\$0.00			\$0.00
Construction Equipment & Tools			In Pre-Const. Services	In Construction Services	Cost of Work	By Others	TOTAL
Levels and Transits	22	MO		\$1,295.45			\$28,500.00
Field Engineer	7.85	MO		\$10,270.17			\$80,620.80
Layout Crew				with Field Engineer			\$0.00
Engineering Equipment				with levels and transits			\$0.00
Engineering Supplies	7.85	MO		\$636.94			\$5,000.00
Layout/Batter boards					x		\$0.00
Licensed Survey Layout	22	MO		\$227.27			\$5,000.00
Site Surveys & Soils Reports						x	\$0.00

EXHIBIT J
WAGE RATES AND LABOR COST

SCHEDULE OF STAFF RATES FOR 2008/2009

Should services be required of any of the below listed staff positions, JE Dunn South Central will be reimbursed at the corresponding rate:

Project Executive	\$120.00 per hour
Director of Preconstruction Services	\$120.00 per hour
Chief Estimator	\$103.00 per hour
Senior Estimator	\$ 96.00 per hour
Estimator	\$ 70.00 per hour
Estimator Trainee	\$ 49.00 per hour
Administrative Assistant	\$ 35.00 per hour
Senior Project Manager	\$ 99.00 per hour
Project Manager	\$ 77.00 per hour
Assistant Project Manager	\$ 56.00 per hour
Field/Office Engineer	\$ 43.00 per hour
MEP/BIM Personnel	\$ 70.00 per hour
Senior Project Coordinator	\$ 39.00 per hour
Project Coordinator	\$ 31.00 per hour
Commissioning	\$130.00 per hour
Safety Engineers	\$ 43.00 per hour
Quality Assurance Personnel	\$ 52.00 per hour
General Superintendent	\$120.00 per hour
Senior Superintendent	\$ 93.00 per hour
Superintendent	\$ 75.00 per hour
Assistant Superintendent	\$ 51.00 per hour
Superintendent Trainee/Foreman	\$ 44.00 per hour

The above rates include wages, taxes, fringe benefits, vacation, training and DPE, and are good from June 1, 2008, through June 30, 2009, and will be escalated four percent (4%) annually.

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Test Reports	01815 - Testing, Adjusting, and Balancing (TAB) Of Mechanical Systems 1.3A	1.3A	Test Reports: 1. Submit test report forms for review minimum 90 days prior to requesting final review by A/E. 2. Furnish six individually bond copies of test data. Neatly type and arrange data. Include with the data the date tested, personnel present, weather conditions, nameplate record of test instrument and list all measurements taken, both prior to and after any corrections are made to the system. Record all failures and corrective action taken to remedy incorrect situation. 3. A/E will retain one copy. Remaining copies will be returned for inclusion in operation and maintenance manuals. Refer to section 15052. 4) Submit draft copies of report for review prior to final acceptance of project. Provide final copies for A/E and for inclusion in operating and maintenance manuals.	5	14	7	5/30/2010	7/2/2010
Drawings	01815 - Testing, Adjusting, and Balancing (TAB) Of Mechanical Systems 1.3B	1.3B	Including a set of reduced drawings with air outlets and equipment identified to correspond with data sheets and including thermostat locations.	5	14	7	6/15/2010	7/18/2010
Qualification Data	024119 - Selective Structure Demolition 1.4A	1.4A	Qualification Data: For Demolition Firm	5	14	7		6/1/2009
Submittal Schedule	024119 - Selective Structure Demolition 1.4B	1.4B	Schedule of Selective Demolition Activities: Indicate the following: 1. Detailed sequence of selective demolition and removal of work, with starting and ending dates for each activity. Ensure owner's and other tenants' on-site operations are uninterrupted. 2. Interruption of utility services. Indicate how long utility services will be interrupted. 3. Coordination for shutoff, capping, and continuation of utility services.	5	14	7		6/1/2009
Inventory Submittal	024119 - Selective Structure Demolition 1.4C	1.4C	Inventory: After selective demolition is complete, submit a list of items that have been removed and salvaged.	5	14	7		6/1/2009
Design Calculations	031000 - Concrete Formwork 1.6A	1.6A	Design Calculations: Submit for record calculations of all concrete formwork and the shoring plan sealed by a registered engineer in the state where the project is located.	5	14	7	6/6/2009	7/2/2009
Drawings	031000 - Concrete Formwork 1.6B	1.6B	Formwork Drawings: Formwork Drawings, prepared under the supervision and sealed by a registered professional engineer in the state where the project is located, shall be submitted for Owners record and shall be reviewed by the Engineer for conformance to structural layout only. Such shop drawings shall indicate types of materials, sizes, lengths, connection details, design allowance for construction loads, anchors form ties, shores, braces, construction joints, reveals, camber, openings, formwork coatings and all other pertinent information.	5	14	7	6/6/2009	7/2/2009
Drawings	031000 - Concrete Formwork 1.6C	1.6C	Plan Form Drawings: The Contractor shall submit plan shop drawings for Engineer's review and approval. Approval will be for coatings and all other pertinent information.	5	14	7	6/6/2009	7/2/2009
Plan	031000 - Concrete Formwork 1.6D	1.6D	Shoring Plan: Submit drawings to indicate the number of levels of shoring, proposed time and sequence of formwork and shore removal, minimum concrete strength for stripping of forms and shore removal, assumed construction loads, amount and layout of shores (specify whether backshores or reshores), and length of time shores are to be left in place. This plan shall be strictly followed by the Contractor. Shoring plans are to be submitted for Owner's record only and will not be reviewed or returned.	5	14	7	6/6/2009	7/2/2009
Shop Drawings	032000 - Concrete Reinforcement 1.5A	1.5A	Shop Drawings: Submit shop drawings for all reinforcing steel and related accessories for the Engineer's approval. Shop drawings shall show arrangement and layout, bending and assembly diagrams, bar schedules, stirrup spacing, splicing and laps of bars and shall be prepared in accordance with CSI Standards. Submit details for steel templates that are to be used when placing dowels for columns, pilings, or pilasters out of foundation elements or for placing anchor bolts for structural steel members.	5	14	7	6/6/2009	7/2/2009
Certificates	032000 - Concrete Reinforcement 1.5B	1.5B	Mill Certificates: Submit mill certificates for all reinforcement signed by Contractor and producer for record.	5	14	7	6/6/2009	7/2/2009
Product Data	032000 - Concrete Reinforcement 1.5C	1.5C	Product Data: Submit manufacturer's product data with application and installation instructions for proprietary materials and items, including mechanical splices, rowel bar substitute systems, and dowel bar sleeves.	5	14	7	6/6/2009	7/2/2009
Technical Reports	032000 - Concrete Reinforcement 1.5D	1.5D	Technical Reports: Submit technical reports of approval from ICCBO for mechanical splice and dowel bar substitute systems.	5	14	7	6/6/2009	7/2/2009
Product Data	033000 - Cast-In-Place Concrete 1.7A	1.7A	Product Data: Submit manufacturer's product data with application and installation instructions for proprietary materials and items, including admixtures, patching compounds, epoxies, grouts, waterstops, joint systems, curing compounds, dry-shake finish materials, hardeners, sealers and others as requested by Architect/Engineer.	5	14	7	6/6/2009	7/2/2009
Samples	033000 - Cast-In-Place Concrete 1.7B	1.7B	Samples: Submit samples of materials specified if requested by Architect/Engineer, including names, sources and descriptions.	5	14	7	6/6/2009	7/2/2009
Mix Designs	033000 - Cast-In-Place Concrete 1.7C	1.7C	Mix Designs: Submit mix designs and the Concrete Mix Design Submittal Form located at the back of this specification section for each class of concrete that is to be provided for the project as specified herein. Submit the Qualifying test data that supports each mix design as required herein. For any concrete mix that contains fly ash, submit evidence of satisfactory performance of the mix on past projects using the same percentage level of fly ash replacement with identical sources of materials.	5	14	7	6/6/2009	7/2/2009
Certificates	033000 - Cast-In-Place Concrete 1.7D	1.7D	Material and Mill Certificates: Provide material and mill certificates as specified herein and in the Testing Laboratory section of the Specifications. The Manufacturer and contractor shall sign the material and mill certificates certifying that each material item complies with specified requirements. Provide certification from admixture manufacturers that chloride ion content complies with specified requirements.	5	14	7	6/6/2009	7/2/2009
Drawings	033000 - Cast-In-Place Concrete 1.7E	1.7E	Construction Joints: Submit drawings of proposed construction joint locations in concrete for slab on grade, foundations, and walls. Submit any additional or changed reinforcing that is required at construction joints that differs from that shown on the drawings.	5	14	7	6/6/2009	7/2/2009

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/7/09 NTP)**

Item	Description	Quantity	Start Date	End Date	Notes
Records	033800 - Post - Tensioned Concrete	7	6/6/2009	7/2/2009	<p>Stressing Records: The contractor shall provide the appropriate cooperation and access to the Owner's Testing Laboratory to allow them to measure, record, and clearly report the following information. In the absence of a Testing Laboratory representative, the post-tensioning installer shall measure, record, report and submit the information described below. Submit records to the Architect/Engineer for approval within 24 hours after stressing.</p> <ol style="list-style-type: none"> 1. Floor, pour and tendon identification numbers. For walls, indicate wall location. 2. Calculated elongation and actual measured elongation for each jacking point, and totals for each tendon. 3. Stressing ram number, initial and final gauge load reading during stressing for each tendon. 4. Date of stressing operation and signature of the Contractor's stressing personnel and inspector witnessing the operation. 5. Range of allowable elongations for jacking force or a measure of the deviation of the measured elongations from the calculated elongations. Deviations that do not comply with the specified tolerances shall be noted for the Architect/Engineer to review. 6. Obvious irregularities or stress loss during anchoring procedures. 7. Required and actual concrete strength at time of jacking.
Record Drawings	033800 - Post - Tensioned Concrete	7	6/6/2009	7/2/2009	<p>Record Drawings: The Contractor shall provide record drawings to the Owner, in care of the Architect/Engineer, of any approved changes from the contract documents. Form of record drawings may be legible marked-up prints of contract drawings, or separate drawings of same Scale.</p> <p>Review: 1. After review, shop drawings/field-placing drawings and data shall not be changed nor shall construction operations be deviated from, unless resubmitted under a cover letter delineating such change and reapproved. 2. Review of details and construction operations will not relieve the Contractor of his responsibility for completing the work successfully in accordance with the contract drawings and specifications.</p> <p>Product Data: For each type of product indicated.</p> <p>Shop Drawings: For the following: 1. Masonry Units: Show sizes, profiles, coursing, and locations of special shapes. 2. Reinforcing Steel: Detail bending and placement of unit masonry reinforcing bars. Comply with ACI318, "Details and Detailing of Concrete Reinforcement" Show elevations of reinforced walls. 3. Fabricated Flashing: Detail corner units, end-dam units, and other special applications.</p>
Submittal	033800 - Post - Tensioned Concrete	7	6/6/2009	7/2/2009	<p>Samples for Initial Selection: For the following: 1. Colored mortar. 2. Weep holes/vents Samples for Verification: For each type and color of the following: 1. Face brick, in the form of strips of five (5) or more bricks. 2. Burnished-face concrete masonry units (CMU) 3. Pigmented mortar. Make Samples using same sand and mortar ingredients to be used on project.</p>
Product Data	0420000 - Unit Masonry	30	6/13/2009	8/1/2009	<p>Qualifications Data: For testing agency. List of Materials Used in Constructing Mockups: List generic product names together with manufacturer's, manufacturer's product names, model numbers, lot numbers, batch numbers, source of supply, and other information as required to identify materials used. Include mix proportions for mortar and grout and source of aggregates. 1. Submittals for information only. Neither receipt of list nor approval of mockup constitutes approval or deviations from the Contract Documents unless such deviations are specifically brought to the attention of Architect and approved in writing. Material Certificates: Include statements of material properties indicating compliance with requirements including compliance with standards and type designations within standards. Provide for each type and size of the following: 1. Masonry units. a. Include material test reports substantiating compliance with requirements. b. For masonry units used in structural masonry, include data and calculations establishing average net-area compressive strength of units. 2. Cementitious materials. Include brand, type, and name of manufacturer. 3. Preblended, dry mortar mixes. Include description of type and proportions of ingredients. 4. Grout mixes. Include description of type and proportions of ingredients. 5. Reinforcing bars. 6. Joint reinforcement. 7. Adaptors, ties, and special accessories.</p>
Shop Drawings	0420000 - Unit Masonry	30	6/13/2009	8/1/2009	
Samples	0420000 - Unit Masonry	30	6/13/2009	8/1/2009	
Samples	0420000 - Unit Masonry	30	6/13/2009	8/1/2009	
Qualifications Data	0420000 - Unit Masonry	30	6/13/2009	8/1/2009	
Mockup - List of Materials	0420000 - Unit Masonry	30	6/13/2009	8/1/2009	
Material Certificates	0420000 - Unit Masonry	30	6/13/2009	8/1/2009	

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Item	Code	Description	Quantity	Start Date	End Date
Mix Designs	0420000 - Unit Masonry	1.6H 1.6I 1.6J 1.5A Mix Designs: For each type of mortar and grout. Include description of type and proportions of ingredients. 1. Include test reports, per ASTM C 780, for mortar mixes required to comply with property specification. 2. Include test reports, per ASTM C 1019, for grout mixes required to comply with compressive strength requirement. Statement of Compressive Strength of Masonry: For each combination of masonry unit type and mortar type, provide statement of average net-area compressive strength of masonry units, mortar type, and resulting net-area compressive strength of masonry determined according to Tables 1 and 2 in ACI 530.1/ASCE 6/TMS 602. Cold-Weather Procedures: Detailed description of methods, materials, and equipment to be used to comply with cold-weather requirements Product Data: 1. Manufacturer's specifications and other data needed to prove compliance with specified requirements. 2. Manufacturer's installation instructions.	5	6/29/2009	8/1/2009
Statement	0420000 - Unit Masonry	1.6I	5	6/29/2009	8/1/2009
Procedures	0420000 - Unit Masonry	1.6J	5	6/29/2009	8/1/2009
Product Data	047210 - Cast Stone	1.5A	5	8/31/2009	11/18/2009
Samples	047210 - Cast Stone	1.5B	5	8/31/2009	11/18/2009
Shop Drawings	047210 - Cast Stone	1.5C	5	8/31/2009	11/18/2009
Design Details	047210 - Cast Stone	1.5D	5	8/31/2009	11/18/2009
Product Data	050510 - Tamper-Proof Metal Fasteners	1.5B	5	10/16/2009	11/18/2009
Samples	050510 - Tamper-Proof Metal Fasteners	1.5C	5	10/16/2009	11/18/2009
Product Data	051200 - Structural Steel Framing	1.6A	5	7/1/2009	10/18/2009

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Item	Description	Quantity	Start Date	End Date	Days
Shop Drawings	051200 - Structural Steel Framing : 1.6B	14	7/11/2009	10/18/2009	90
Calculations	051200 - Structural Steel Framing : 6C	5	7/11/2009	10/18/2009	90
Surveys	051200 - Structural Steel Framing : 6D	5	7/11/2009	10/18/2009	90
Test Reports	051200 - Structural Steel Framing : 6E	5	7/11/2009	10/18/2009	90
Qualifications Data	051200 - Structural Steel Framing : 6F	5	7/11/2009	10/18/2009	90
Substitutions	051200 - Structural Steel Framing : 6G	5	7/11/2009	10/18/2009	90

1. Definitions:

- a. Shop Drawings: Drawings of the individual structural steel shipping pieces that are to be produced in the fabrication shop.
 - b. Erection Drawings: Field-installation or member-placement drawings that are prepared by the Fabricator to show the location and attachment of the individual shipping pieces.
 - c. Erection-Bracing Drawings: Drawings that are prepared by the Erector to illustrate the sequence of erection, any requirements for temporary supports and the requirements for raising, bolting, and/or welding. These drawings are in addition to and separate from the Erection Drawings.
 2. Shop Drawings: Submit for review and approval shop drawings prepared under the supervision of and sealed by, for connection design only, a professional engineer licensed in the state where the project is located, including complete details and schedules for fabrication and assembly of structural steel members. In lieu of placing a seal on the shop drawings, the licensed professional engineer responsible for the design of the connections may submit a letter that is sealed attesting that the connection design engineer has reviewed the shop drawings and that the connections shown on the shop drawings conform to the design by the engineer. The Engineer reserves the right to reject all shop drawings not complying with the above requirements. Structural steel shop drawings shall include the following minimum information:
 - a. Include details of cuts, connections, camber, holes, and other pertinent data.
 - b. Indicate details of cuts, connections, camber, holes, and show size, length, and type of each weld. Indicate type, size, and length of bolts, distinguishing between shop and field bolts. Identify the type of high-strength bolted connection (slip-critical, direct-tension, or bearing connections). Holes, flange cuts, slots and openings shall be made as required by the structural drawings, all of which shall be properly located by means of templates.
 - c. Provide setting drawings, templates, and directions for installation of anchor bolts and other anchorages to be installed by others.
 3. Erection Drawings: Submit for review and approval complete erection drawings showing field-installation and member-placing instructions for locating and attaching the individual shipping pieces.
 4. Erection-Bracing Drawings: Submit for record purposes only complete erection-bracing drawings to illustrate the sequence of erection, any requirements for temporary supports and the requirements for raising, bolting, and/or welding.
 5. Preliminary Connection Review with Steel Fabricator: The fabricator shall submit for information as specified in Part 2-Connections. The Engineer reserves the right to reject all shop drawings submitted without complete design calculations.
- Surveys:**
1. Initial Survey: Submit report of discrepancies noted during the initial survey. Submit proposed measures to correct or compensate for these discrepancies.
 2. Final Survey: Submit a report certifying compliance with specified tolerances.
- Test Reports:** Submit copies of reports of tests conducted on all material and on shop and field bolted and welded connections. Include date on type(s) of tests conducted and test results. See **Qualification Data**.
1. Submit qualification data for firms and persons specified in Article 1.04 "Qualifications" to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
 2. Submit Welding Procedure Specifications (WPS) in accordance with ANSI/A AWS D.1 for all welded joints. Submit test reports showing successful passage of qualification tests for all non-pipe qualified WPSs.
 3. Provide certification that welders to be employed in work have satisfactorily passed AWS **Substitution Tests** as specified in section 1.05-B.1.
- Substitutions:**
1. Substitutions for the member sizes, types(s) of steel connection details or any other modifications proposed by the Contractor will be considered by the Architect/Engineer only under the following conditions:
 - a. That the request has been made and accepted prior to the submission of shop drawings. All substitutions shall be clearly marked and indicated on the shop drawings as a substitute.
 - b. That there is a substantial cost advantage or time advantage to the Owner; or that the proposed revision is necessary to obtain the required materials or methods at the proper times to accomplish the work in the time scheduled.
 - c. That sufficient sketches, engineering calculations, and other data have been submitted to facilitate checking by the Architect/Engineer, including cost reductions or savings in time to complete the work.
- (If, in no case, shall such revision result in additional cost to the Owner.)*

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Product Certification:	052123 - Steel Roof Decking	1.6A	Product Certification:	Submit manufacturer's specifications and installation instructions for each type of deck specified. Also submit a certificate of product compliance with SDI Standards as specified.	7/1/2009	5	14	90	10/18/2009
Shop Drawings	052123 - Steel Roof Decking	1.6B	Shop Drawings:	Submit detailed shop drawings showing type of deck, complete layout, attachment details, closures, edge strips, supplementary framing, and all other accessories. The shop drawings shall be sealed by the same registered professional engineer who seals the calculations.	7/1/2009	5	14	90	10/18/2009
Calculations	052123 - Steel Roof Decking	1.6C	Calculations:	The steel deck manufacturer shall submit design calculations sealed by a registered professional engineer in the state where the project is located verifying compliance with the specifications for all load and span conditions shown on the drawings. Calculations that show the deck attachment procedure and pattern meets the specified design criteria shall also be submitted.	7/1/2009	5	14	90	10/18/2009
Insurance Certification	052123 - Steel Roof Decking	1.6D	Insurance Certification:	Assist Architect and Owner in preparation and submittal of roof installation acceptance certification as may be necessary in connection with fire, windstorm, and extended coverage insurance.	7/1/2009	5	14	90	10/18/2009
Welding Certificate	052123 - Steel Roof Decking	1.6E	Welding Certificates:	Submit Copies of certificates for welding procedures and personnel.	7/1/2009	5	14	90	10/18/2009
Product Data	052123 - Steel Roof Decking	1.5A	Product Data:	For each type of cold-formed metal framing product and accessory indicated.	7/1/2009	5	14	90	10/18/2009
Shop Drawings	052123 - Steel Roof Decking	1.5B	Shop Drawings:	Show layout, spacings, sizes, thicknesses, and types of cold-formed metal framing; fabrication; and fastening and anchorage details, including mechanical fasteners. Show reinforcing channels, opening framing, supplemental framing, strapping, bracing, bridging, splices, accessories, connection details, and attachment to adjoining work.	7/1/2009	5	14	90	10/18/2009
Product Data	055000 - Metal Fabrications	1.4A	Product Data:	1. For cold-formed metal framing indicated to comply with design loads, include structural analysis data signed and sealed by the qualified professional engineer responsible for their preparation. 2. For the following: 1. Paint products.	7/2/2009	5	14	120	11/18/2009
Shop Drawings	055000 - Metal Fabrications	1.4B	Shop Drawings:	Detail fabrication and erection of each metal fabrication indicated. Include plans, elevations, sections, and details of metal fabrications and their connections. Show anchorage and accessory items.	7/2/2009	5	14	120	11/18/2009
Welding Certificate	055000 - Metal Fabrications	1.4C	Welding Certificates:	Copies of certificates for welding procedures and personnel. Demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.	7/2/2009	5	14	120	11/18/2009
Qualifications Data	055000 - Metal Fabrications	1.4D	Qualifications Data:	For firms and persons specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.	7/2/2009	5	14	120	11/18/2009
Product Data	055100 - Metal Stairs	1.5A	Product Data:	For metal stairs and the following: 1. Prefilled metal-pan stair treads. 2. Nonslip aggregates and nonslip-aggregate finishes.	7/2/2009	5	14	120	11/18/2009
Shop Drawings	055100 - Metal Stairs	1.5B	Shop Drawings:	Show fabrication and installation details for metal stairs. Include plans, elevations, sections, and details of metal stairs and their connections. Show anchorage and accessory items. Provide templates for anchors and bolts specified for installation under other Sections.	7/2/2009	5	14	120	11/18/2009
Welding Certificate	055100 - Metal Stairs	1.5C	Welding Certificates:	Copies of certificates for welding procedures and personnel. Demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.	7/2/2009	5	14	120	11/18/2009
Qualifications Data	055100 - Metal Stairs	1.5D	Qualifications Data:	For firms and persons specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.	7/2/2009	5	14	120	11/18/2009
Product Data	055210 - Pipe and Tune Railings	1.5A	Product Data:	For the following: 1. Manufacturer's product lines of mechanically connected railings. 2. Grout, anchoring cement, and paint products.	7/2/2009	5	14	120	11/18/2009
Shop Drawings	055210 - Pipe and Tune Railings	1.5B	Shop Drawings:	Include plans, elevations, sections, details, and attachments to other work. 1. For installed products indicated to comply with design loads, include structural analysis data signed and sealed by the qualified professional engineer responsible for their preparation.	7/2/2009	5	14	120	11/18/2009
Samples	055210 - Pipe and Tune Railings	1.5C	Samples for Initial Selection:	For products involving selection of color, texture, or design, including mechanical finishes on stainless steel.	7/2/2009	5	14	120	11/18/2009
Samples	055210 - Pipe and Tune Railings	1.5D	Samples for Verification:	For each type of exposed finish required. 1. Sections of each distinctly different linear railing member, including handrails, top rails, posts, and balusters. 2. Elftons and brackets.	7/2/2009	5	14	120	11/18/2009
Mill Certificates	055210 - Pipe and Tune Railings	1.5E	Mill Certificates:	Signed by manufacturers of stainless-steel products certifying that products furnished comply with requirements.	7/2/2009	5	14	120	11/18/2009
Welding Certificate	055210 - Pipe and Tune Railings	1.5F	Welding Certificates		7/2/2009	5	14	120	11/18/2009
Qualifications Data	055210 - Pipe and Tune Railings	1.5G	Qualifications Data:	For professional engineer and testing agency.	7/2/2009	5	14	120	11/18/2009
Product Test Reports	055210 - Pipe and Tune Railings	1.5H	Product Test Reports:	Based on evaluation of comprehensive tests performed by a qualified testing agency, according to ASTM E 894 and ASTM E 935	7/2/2009	5	14	120	11/18/2009

Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)

Product Data	061000 - Rough Carpentry	1.5A	11/22/2009	5	14	7	12/18/2009
Product Data	061000 - Rough Carpentry	1.5A	11/22/2009	5	14	7	12/18/2009
Research/Evaluation Report	061000 - Rough Carpentry	1.5B	11/22/2009	5	14	7	12/18/2009
Product Data	061600 - Sheathing	1.4A	11/22/2009	5	14	7	12/18/2009
Research/Evaluation Report	061600 - Sheathing	1.4B	11/22/2009	5	14	7	12/18/2009
Product Data	064100 - Interior Architectural Woodwork	1.4A	1/29/2010	5	14	90	5/18/2010
Product Data	064100 - Interior Architectural Woodwork	1.4B	1/29/2010	5	14	90	5/18/2010
Shop Drawings	064100 - Interior Architectural Woodwork	1.4C	1/29/2010	5	14	90	5/18/2010
Samples	064100 - Interior Architectural Woodwork	1.4D	1/29/2010	5	14	90	5/18/2010
Samples for Verification	064100 - Interior Architectural Woodwork	1.4E	1/29/2010	5	14	90	5/18/2010

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Product Certification:	Product Certificates:	For each type of product, signed by product manufacturer.	1/29/2010	5	14	90	5/18/2010
064100 - Interior Architectural Woodwork	1.4F	Woodwork Quality Standard Compliance Certificates: AWI Quality Certification Program certificates.	1/29/2010	5	14	90	5/18/2010
064100 - Interior Architectural Woodwork	1.4G	Qualification Data: For Fabricator.	1/29/2010	5	14	90	5/18/2010
064100 - Interior Architectural Woodwork	1.4H	Product Data: Submit data on fire retardant treatment materials and application instructions by item and location when specified in this Section.	1/29/2010	5	14	90	5/18/2010
064216 - Wood Panels	1.4A	Shop Drawings: Indicate materials, surface graining elevations of sheet paneling, fastening methods, joining methods, and interruptions to other work, to minimum scale of 1-1/2 inch to 1 ft. Include plan of panel number sequencing.	1/29/2010	5	14	90	5/18/2010
064216 - Wood Panels	1.4B	1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Indicate type of preservative used and net amount of preservative retained. Include Samples:	1/29/2010	5	14	90	5/18/2010
064216 - Wood Panels	1.4C	1. Submit two samples of finished paneling, 8 x 10 inch in size illustrating wood grain and specified finish. Include three unique samples indicating representative wood features from front, back and middle of veneer flitch.	1/29/2010	5	14	90	5/18/2010
064216 - Wood Panels	1.4D	2. Submit two samples of wood trim, 12 inches long.	1/29/2010	5	14	90	5/18/2010
071150 - Bituminous Dampproofing	1.4A	Product Data: Submit copy of fabricator's letter of certification from AWI.	6/15/2009	5	14	14	7/18/2009
071300 - Below Grade Waterproofing	1.5A	1. Manufacturer's specifications and other data needed to prove compliance with specified requirements.	6/15/2009	5	14	14	7/18/2009
071300 - Below Grade Waterproofing	1.5B	2. Manufacturer's installation instructions.	6/15/2009	5	14	14	7/18/2009
071300 - Below Grade Waterproofing	1.5C	Submit manufacturer's technical product data, installation instructions, and recommendations for each waterproofing material required. Include data substantiating that materials comply with requirements.	6/15/2009	5	14	14	7/18/2009
071311 - Self-Adhering Sheet Waterproofing	1.5A	Manufacturer's certification that applicator is approved by manufacturer.	6/15/2009	5	14	14	7/18/2009
071311 - Self-Adhering Sheet Waterproofing	1.5B	Submit a sample warranty identifying the terms and conditions stated in warranty.	6/15/2009	5	14	14	7/18/2009
071311 - Self-Adhering Sheet Waterproofing	1.5C	Product Data: Include manufacturer's written instructions for evaluating, preparing, and treating substrate, technical data, and tested physical and performance properties of waterproofing.	6/15/2009	5	14	14	7/18/2009
071311 - Self-Adhering Sheet Waterproofing	1.5D	Shop Drawings: Show locations and extent of waterproofing. Include details for substrate joints and cracks, sheet flashings, penetrations, inside and outside corners, tie-ins with adjoining waterproofing, and other termination conditions.	6/15/2009	5	14	14	7/18/2009
071311 - Self-Adhering Sheet Waterproofing	1.5E	Samples: For the following products:	6/15/2009	5	14	14	7/18/2009
071311 - Self-Adhering Sheet Waterproofing	1.5F	1. 12-by-12-inch square of waterproofing and flashing sheet.	6/15/2009	5	14	14	7/18/2009
071900 - Water Repellants	1.4A	Installer Certificates: Signed by manufacturers certifying that installers comply with requirements.	6/15/2009	5	14	14	7/18/2009
071900 - Water Repellants	1.4B	Product Test Reports: From a qualified independent testing agency indicating and interpreting test results of waterproofing for compliance with requirements, based on comprehensive testing of current waterproofing formulations.	6/15/2009	5	14	14	7/18/2009
071900 - Water Repellants	1.4C	Sample Warranty: Copy of special waterproofing manufacturer's warranty stating obligations, remedies, limitations, and exclusions before starting waterproofing.	6/15/2009	5	14	14	7/18/2009
071900 - Water Repellants	1.4D	Product Data: Provide details of product description, tests performed, limitations to coating, and chemical properties, including percentage of solids.	6/15/2009	5	14	14	7/18/2009
071900 - Water Repellants	1.4E	Manufacturer's Installation Instructions: Indicate special procedures and conditions requiring special attention; cautionary procedures required during application.	6/15/2009	5	14	14	7/18/2009
071900 - Water Repellants	1.4F	Manufacturer's Certificate: Certify that Products meet or exceed specified requirements.	6/8/2009	5	14	21	7/18/2009
072100 - Building Insulation	1.4A	Product Data: For each type of product indicated.	6/8/2009	5	14	21	7/18/2009
072100 - Building Insulation	1.4B	Samples for Verification: Full-size units for each type of exposed insulation indicated.	6/8/2009	5	14	21	7/18/2009
072100 - Building Insulation	1.4C	Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for insulation products.	6/8/2009	5	14	21	7/18/2009
072100 - Building Insulation	1.4D	Research/Evaluation Reports: For plastic insulation.	6/8/2009	5	14	21	7/18/2009
074130 - Exterior Metal Wall Panels	1.5A	Product Data: Include manufacturer's product specifications, standard details, certified product test results, and general recommendations, as applicable to materials and finishes for each component and for total panel assemblies.	8/31/2009	5	14	90	12/18/2009
074130 - Exterior Metal Wall Panels	1.5B	Shop Drawings: Show layouts of panels, details of corner conditions, joints, panel profiles, supports, anchorages, trim, flashings, closures, and special details. Distinguish between factory and field-assembled work.	8/31/2009	5	14	90	12/18/2009
074130 - Exterior Metal Wall Panels	1.5C	Samples for Verification: Provide sample panels 12 inches (300 mm) long by actual panel width, in the profile, style, color, and texture indicated. Include clips, caps, battens, fasteners, closures, and other exposed panel accessories.	8/31/2009	5	14	90	12/18/2009

**Exhibit K
Shop Drawing/Submital Schedule (Based on 6/1/09 NTP)**

Item	Item Description	Item Code	Item Category	Item Sub-Category	Item Unit	Item Quantity	Item Date	Item Description	Item Date	Item Quantity	Item Date		
Qualifications Data	074130 - Exterior Metal Wall Panels	1.5D						Qualification Data: For firms and persons specified in the "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.	8/31/2009	5	14	90	12/18/2009
Product Test Reports	074130 - Exterior Metal Wall Panels	1.5E						Product Test Reports: Indicate compliance of manufactured wall panel assemblies and materials with performance and other requirements based on comprehensive testing of current products.	8/31/2009	5	14	90	12/18/2009
Product Data	075520 - SBS-Modified Bituminous Membrane Roofing	1.5A						Product Data: For each type of roofing product specified. Include data substantiating that materials comply with requirements.	8/31/2009	5	14	90	12/18/2009
Shop Drawings	075520 - SBS-Modified Bituminous Membrane Roofing	1.5B						Shop Drawings: Include plans, sections, details, and attachments to other work, for the following: 1. Base flashings, caps, and membrane terminations. 2. Tapered insulation, including slopes. 3. Crickets, saddles, and tapered slope struts, including slopes.	8/31/2009	5	14	90	12/18/2009
Samples for Verification	075520 - SBS-Modified Bituminous Membrane Roofing	1.5C						Samples for Verification: Of the following products: 1. 12-by-12-inch (300-by-300-mm) square of modified bituminous, granule surfaced cap sheets, of color specified. 2. 12-by-12-inch (300-by-300-mm) square of roofing insulation. 3. 12-by-12-inch (300-by-300-mm) square of walkway pads. 4. Six (6) insulation fasteners of each type, length, and finish.	8/31/2009	5	14	90	12/18/2009
Installer Certificates	075520 - SBS-Modified Bituminous Membrane Roofing	1.5D						Installer Certificates: Signed by roofing system manufacturer certifying that Installer is approved, authorized, or licensed by manufacturer to install specified roofing system and is eligible to receive the standard roofing manufacturer's warranty.	8/31/2009	5	14	90	12/18/2009
Manufacturer Certificates	075520 - SBS-Modified Bituminous Membrane Roofing	1.5E						Manufacturer Certificates: Signed by roofing system manufacturer certifying that the roofing system complies with requirements specified in the "Performance Requirements" Article. Upon request, submit evidence of complying with requirements.	8/31/2009	5	14	90	12/18/2009
Qualifications Data	075520 - SBS-Modified Bituminous Membrane Roofing	1.5F						Qualification Data: For firms and persons specified to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.	8/31/2009	5	14	90	12/18/2009
Product Test Reports	075520 - SBS-Modified Bituminous Membrane Roofing	1.5G						Product Test Reports: Based on evaluation of tests performed by manufacturer and witnessed by a qualified independent testing agency, indicate compliance of components of roofing system with requirements based on comprehensive testing of current product compositions. 1. Indicate compliance of bulk roofing asphalt materials delivered to Project with requirements. Include quantity and statistical and descriptive data for each product. Submit certificate with each load before it is used. 2. Include continuous log showing time and temperature for each load of bulk bitumen, indicating date obtained from manufacturer, where held, and how transported before final heating and application on roof.	8/31/2009	5	14	90	12/18/2009
Research/Evaluation Report	075520 - SBS-Modified Bituminous Membrane Roofing	1.5H						Research/Evaluation Report: Evidence of roofing system's compliance with building code in effect for Project from a model code organization acceptable to authorities having jurisdiction.	8/31/2009	5	14	90	12/18/2009
Maintenance Data	075520 - SBS-Modified Bituminous Membrane Roofing	1.5I						Maintenance Data: For roofing system to include in the maintenance manuals specified in Division 01.	8/31/2009	5	14	90	12/18/2009
Warranty	075520 - SBS-Modified Bituminous Membrane Roofing	1.5J						Warranty: Sample copy of standard roofing manufacturer's warranty stating obligations, remedies, limitations, and exclusions of warranty.	8/31/2009	5	14	90	12/18/2009
Inspection Reports	075520 - SBS-Modified Bituminous Membrane Roofing	1.5K						Inspection Report: Copy of roofing system manufacturer's inspection report of completed roof installation.	8/31/2009	5	14	90	12/18/2009
Product Data	076100 - Prefinished Metal Roofing	1.5A						Product Data: For each type of product indicated. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each manufactured product and accessory.	8/31/2009	5	14	90	12/18/2009
Shop Drawings	076100 - Prefinished Metal Roofing	1.5B						Shop Drawings: Show fabrication and installation layouts of metal roofing, including plans, elevations, expansion joint locations, and keyed details. Distinguish between shop and field-assembled work. Include the following: 1. Details for forming metal roofing, including seams and dimensions. 2. Details for joining and securing metal roofing, including layout of fasteners, cleats, clips, and other attachments. 3. Details of termination points and assemblies, including fixed points. 4. Details of expansion joints, including showing direction of expansion and contraction. 5. Details of roof penetrations. 6. Details of edge conditions, including eaves, ridges, valleys, rakes, crickets, and counterflashings. 7. Details of special conditions. 8. Details of connections to adjoining work. 9. Detail the following accessory items, at a scale of not less than 1-1/2 inches per 12 inches (1:10):	8/31/2009	5	14	90	12/18/2009
Calculations	076100 - Prefinished Metal Roofing	1.5C						Calculations: 1. Engineering calculations defining cladding loads on all roof areas based on specified building codes, allowable clip loads and required number of fasteners to secure the panel clips to the designated substructure. 2. Uplift loads on clip fasteners with full recognition of any forces and eccentric clip loading. Calculate holding strength of fasteners in accordance with submitted test data provided by fastener manufacturer based on length of embedment and properties of materials.	8/31/2009	5	14	90	12/18/2009

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Item	Description	Quantity	Start Date	End Date	Notes
Samples	076100 - Prefinished Metal Roofing	14	8/31/2009	12/18/2009	<p>Samples:</p> <ol style="list-style-type: none"> Color charts or samples from the manufacturer's standard line of Kynar 500 or Hylar 5000 finishes for Architect's selection. One (1) foot long sample of coated panel, including clips and fasteners.
Certification	076100 - Prefinished Metal Roofing	5	8/31/2009	12/18/2009	<p>Certifications:</p> <ol style="list-style-type: none"> Letter of certification from manufacturer that installer is in compliance and meets specified requirements. Letter of certification from manufacturer that panels have been produced in accordance with strictest applicable standards to ensure quality. Certified test results by a recognized testing laboratory or manufacturer's laboratory (witnessed by a professional engineer) in accordance with specified performance test methods for each panel system.
Test Reports	076100 - Prefinished Metal Roofing	5	8/31/2009	12/18/2009	<p>Testing Reports: Showing metal panels have been tested in accordance with specified performance testing requirements.</p>
Warranty	076100 - Prefinished Metal Roofing	5	8/31/2009	12/18/2009	<p>Warranty: Manufacturer's warranty as specified.</p>
Manufacturer's Acknowledgement Letter	076200 - Sheet Metal Flashing and Trim	5	8/31/2009	12/18/2009	<p>Manufacturer's Acknowledgement Letter: Follow Division 01 Section "Submittal Procedures".</p>
Product Data	076200 - Sheet Metal Flashing and Trim	5	8/31/2009	12/18/2009	<p>Product Data: For each type of product indicated. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.</p>
Shop Drawings	076200 - Sheet Metal Flashing and Trim	5	8/31/2009	12/18/2009	<p>Shop Drawings: Show layouts of sheet metal flashing and trim, including plans and elevations. Distinguish between shop and field-assembled work. Include the following: 1. Identify material, thickness, weight, and finish for each item and location in project. 2. Details for forming sheet metal flashing and trim, including profiles, shapes, seams, and dimensions. 3. Details for fastening, joining, supporting, and anchoring sheet metal flashing and trim, including fasteners, clips, cleats, and attachments to adjoining work. 4. Details of expansion-joint covers, including showing direction of expansion and contraction.</p>
Samples for Initial Selection	076200 - Sheet Metal Flashing and Trim	5	8/31/2009	12/18/2009	<p>Samples for Initial Selection: For each type of sheet metal flashing and trim indicated with factory-applied color finishes.</p>
Samples for Verification	076200 - Sheet Metal Flashing and Trim	5	8/31/2009	12/18/2009	<p>Samples for Verification: For each type of exposed finish required, prepared on Samples of size indicated below:</p> <ol style="list-style-type: none"> Include similar Samples of trim and accessories involving color selection and other attachments. Sheet Metal Flashing: 12 inches long. Include fasteners, cleats, clips, closures, and other attachments. Trim: 12 inches long. Include fasteners and other exposed accessories. Accessories: Full-size Sample.
Product Data	078120 - Cementitious Sprayed Fire-Resistive Materials	5	10/30/2009	12/18/2009	<p>Product Data: For each fire-resistive product specified.</p>
Shop Drawings	078120 - Cementitious Sprayed Fire-Resistive Materials	5	10/30/2009	12/18/2009	<p>Shop Drawings: Structural framing plans indicating the following:</p> <ol style="list-style-type: none"> Locations and types of surface preparations required before applying sprayed fire-resistive material. Extent of sprayed fire-resistive material for each construction and fire-resistance rating, including the following: <ol style="list-style-type: none"> Applicable fire-resistive design designations of a qualified testing and inspecting agency acceptable to authorities having jurisdiction. Minimum thicknesses needed to achieve required fire-resistance ratings of structural components and assemblies. Designation of restrained and unrestrained conditions based on definitions in ASTM E 119, Appendix X3 as determined by a qualified professional engineer.
Installer Certificates	078120 - Cementitious Sprayed Fire-Resistive Materials	5	10/30/2009	12/18/2009	<p>Installer Certificates: Signed by manufacturer certifying that installers comply with specified requirements.</p>
Qualifications Data	078120 - Cementitious Sprayed Fire-Resistive Materials	5	10/30/2009	12/18/2009	<p>Qualification Data: For firms and persons specified in "Quality Assurance" Article 10 demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.</p>
Compatibility and Adhesion Test Reports	078120 - Cementitious Sprayed Fire-Resistive Materials	5	10/30/2009	12/18/2009	<p>Compatibility and Adhesion Test Reports: For primers and other coatings applied to structural steel. Provide reports from a qualified independent testing and inspecting agency engaged by Contractor. Confirm that primers and coatings proposed for application in shop or field are compatible with fire-resistive material. Instruct laboratory to determine compatibility according to requirements specified in "Quality Assurance" Article.</p>
Product Data	078160 - Intumescent Fireproofing	5	10/30/2009	12/18/2009	<p>Product Data: Manufacturer's data sheets on each product to be used, including:</p> <ol style="list-style-type: none"> UL Design Listings for specific applications required. Storage and handling requirements and recommendations. Field application manual.
Samples	078160 - Intumescent Fireproofing	5	10/30/2009	12/18/2009	<p>Samples: Two (2) sets of samples representing anticipated texture and finish.</p>

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Item	Item Description	Quantity	Unit	Start Date	End Date	Notes
083326 - Overhead Colling Grilles	1.6C	60	14	5	3/31/2010	5/18/2010
083326 - Overhead Colling Grilles	1.6D	60	14	5	3/31/2010	6/18/2010
083326 - Overhead Colling Grilles	1.6E	60	14	5	3/31/2010	6/18/2010
084113 - Aluminum-Framed Entrances and Storefronts	1.5A	90	14	5	10/1/2009	1/18/2010
084113 - Aluminum-Framed Entrances and Storefronts	1.5B	90	14	5	10/1/2009	1/18/2010
084113 - Aluminum-Framed Entrances and Storefronts	1.5C	90	14	5	10/1/2009	1/18/2010
084113 - Aluminum-Framed Entrances and Storefronts	1.5D	90	14	5	10/1/2009	1/18/2010
084113 - Aluminum-Framed Entrances and Storefronts	1.5E	90	14	5	10/1/2009	1/18/2010
084412 - Glazed Aluminum Curtain Wall	1.5A	90	14	5	10/1/2009	1/18/2010
084412 - Glazed Aluminum Curtain Wall	1.5B	90	14	5	10/1/2009	1/18/2010
084412 - Glazed Aluminum Curtain Wall	1.5C	90	14	5	10/1/2009	1/18/2010
084412 - Glazed Aluminum Curtain Wall	1.5D	90	14	5	10/1/2009	1/18/2010
086200 - Unit Skylights	1.6A	90	14	5	8/31/2009	12/18/2009
086200 - Unit Skylights	1.6B	90	14	5	8/31/2009	12/18/2009
086200 - Unit Skylights	1.6C	90	14	5	8/31/2009	12/18/2009
086200 - Unit Skylights	1.6D	90	14	5	8/31/2009	12/18/2009
086200 - Unit Skylights	1.6E	90	14	5	8/31/2009	12/18/2009
087100 - Door Hardware	1.4A	90	14	5	3/1/2010	6/18/2010

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Coordination	087100 - Door Hardware	1.4B	Coordinate hardware with doors, frames, and related work to ensure proper size thickness, hand, function, and finish of hardware. If requested by Architect, submit one sample of each type of exposed hardware unit, finished as required, and tagged with full description for coordination with schedule. Submit data and schedule at earliest possible date, particularly where acceptance of schedule must precede fabrication of other work (e.g. hollow metal frames) that is critical to the Project construction schedule. 1. Type, style, function, size and finish of each hardware item 2. Name and manufacturer of each item. 3. Fastenings and other pertinent information. 4. Hardware set location cross-referenced to both Drawing floor plan and door schedule indications. 5. Explanation of all abbreviations, symbols, and codes in schedule. 6. Mounting locations for hardware. 7. Door and frame sizes and materials.	5	14	90	6/18/2010
Coordination	087100 - Door Hardware	1.4C	Coordinate keying instructions, and keying information. Deliver keys and key control box to Owner in person and obtain receipt (No Exceptions).	5	14	90	6/18/2010
Product Data	087700 - Door and Window Accessories	1.4A	Product Data: Manufacturer's technical data sheets on each product to be used, including: 1. Preparation instructions and recommendations. 2. Storage and handling requirements and recommendations. 3. Installation methods.	5	14	90	12/18/2009
Certificate of Compliance	087700 - Door and Window Accessories	1.4B	Certificate of Compliance: Product certificate from the accessory manufacturer certifying that the applicable products being supplied comply with specified requirements and that the products have been tested by Underwriters' Laboratories (UL) and Warnock Hersey International (WHI), and National Fire Protection Association (NFPA) as specified.	5	14	90	12/18/2009
Shop Drawings	087700 - Door and Window Accessories	1.4C	Shop Drawings: Provide details showing installation in doors of types appropriate for the project. Show clouds, reinforcement required and other door and frame preparation.	5	14	90	12/18/2009
Selection Samples	087700 - Door and Window Accessories	1.4D	Selection Samples: For each finish product specified, two complete sets of color chips representing manufacturer's full range of available colors and patterns.	5	14	90	12/18/2009
Verification Sample	087700 - Door and Window Accessories	1.4E	Verification Samples: For each finish product specified, two samples, minimum size 12 inches (300 mm) square, representing actual product, color, and patterns.	5	14	90	12/18/2009
Product Data	088000 - Glazing	1.5A	Product Data: For each glass product and glazing material indicated. Samples: For the following products, in the form of 12-inch square Samples for glass and of 12-inch long Samples for sealants. Install sealant Samples between two strips of material representative in color of the adjoining framing system. Samples: For the following products, in the form of 12-inch square Samples. 1. For each color (except black) of exposed glazing sealant indicated. 2. Window tint film.	5	14	90	12/18/2009
Samples	088000 - Glazing	1.5B		5	14	90	12/18/2009
Samples	088000 - Glazing	1.5C		5	14	90	12/18/2009
Glazing Schedule	088000 - Glazing	1.5D	Glazing Schedule: Use same designations indicated on Drawings for glazed openings in preparing a schedule listing glass types and thicknesses for each size opening and location.	5	14	90	12/18/2009
Product Certification	088000 - Glazing	1.5E	Product Certificates: Signed by manufacturers of glass and glazing products certifying that products furnished comply with requirements.	5	14	90	12/18/2009
Preconstruction Adhesion and Compatibility Test Reports	088000 - Glazing	1.5F	Qualification Data: For installers.	5	14	90	12/18/2009
Product Test Reports	088000 - Glazing	1.5G	Preconstruction Adhesion and Compatibility Test Report: From glazing sealant manufacturer indicating glazing sealants were tested for adhesion to glass and glazing channel substrates and for compatibility with glass and other glazing materials.	5	14	90	12/18/2009
Warranty	088000 - Glazing	1.5H	Product Test Reports: For each of the following types of glazing products: 1. Glazing sealants. 2. Glazing gaskets.	5	14	90	12/18/2009
Shop Drawings	089500 - Translucent Glazing Systems	1.5A	Warranties: As specified in this Section. Shop Drawings: Submit one (1) full size set re-producible and two (2) full size copies of shop drawings plans, elevations, and section as required to fully describe the skylight construction for the Architect's approval prior to starting fabrication.	5	14	90	12/18/2009
Calculations	089500 - Translucent Glazing Systems	1.5B	Submit structural calculations prepared in accordance with the Aluminum Association's Specifications for Aluminum Structures (SAS30) by a professional engineer qualified in the design of self-supporting skylights and licensed in the State of Texas.	5	14	90	12/18/2009
Test Reports	089500 - Translucent Glazing Systems	1.5C	Submit test reports from an independent recognized testing laboratory, or a full size system sample, showing the skylight system has been designed to allow the glazing material to expand and contract in both the X and Y axis.	5	14	90	12/18/2009
Samples	089500 - Translucent Glazing Systems	1.5D	Submit two 12 inch square samples of the glazing material.	5	14	90	12/18/2009
Samples	089500 - Translucent Glazing Systems	1.5E	Submit one 12 inch long snap-on cap.	5	14	90	12/18/2009
Product Data	092400 - Portland Cement Plaster	1.4A	Product Data: For each type of product installed.	5	14	30	12/18/2009
Shop Drawings	092400 - Portland Cement Plaster	1.4B	Shop Drawings: Show locations and installation of control and expansion joints including plans, elevations, sections, details of components, and attachments to other work.	5	14	30	12/18/2009

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

1.4C	092400 - Portland Cement Plaster	1.4C	Samples for Initial Selection: For each type of factory-prepared finish coat indicated	10/30/2009	5	14	30	12/18/2009
1.4D	092400 - Portland Cement Plaster	1.4D	Samples for Verification: For each type of factory-prepared, colored, or textured finish coat indicated: 12 by 12 inches (305 by 305 mm), and prepared on rigid backing.	10/30/2009	5	14	30	12/18/2009
1.4A	092900 - Glass Fiber Reinforced Gypsum Fabrications (GFRG)	1.4A	Product Data: Manufacturer's data sheets on each product to be used, including dimensions, finishes, storage and handling requirements and recommendations, and installation recommendations.	10/30/2009	5	14	30	12/18/2009
1.4B	092900 - Glass Fiber Reinforced Gypsum Fabrications (GFRG)	1.4B	Shop Drawings: Showing plans, sections, details, joint treatment, reinforcing fastening devices, and relation to adjacent construction.	10/30/2009	5	14	30	12/18/2009
1.4C	092900 - Glass Fiber Reinforced Gypsum Fabrications (GFRG)	1.4C	Samples: For each finish specified, three (3) 6 inch x 6 inch flat samples for color and finish selection.	11/22/2009	5	14	7	12/18/2009
1.4A	092905 - Gypsum Board Shaft-Wall Assemblies	1.4A	Product Data: For each type of product indicated.	11/22/2009	5	14	7	12/18/2009
1.5A	093000 - Tiling	1.5A	Product Data: For each type of product indicated.	3/31/2010	5	14	60	6/18/2010
1.5B	093000 - Tiling	1.5B	Shop Drawings: Show locations of each type of tile and tile pattern. Show widths, details, and locations of expansion, contraction, control, and isolation joints in tile substrates and finished tile surfaces.	3/31/2010	5	14	60	6/18/2010
1.5C	093000 - Tiling	1.5C	Master Grade Certificates: For each shipment, type, and composition of tile, signed by tile manufacturer and installer.	3/31/2010	5	14	60	6/18/2010
1.5D	093000 - Tiling	1.5D	Product Certificates: For each type of product, signed by product manufacturer.	3/31/2010	5	14	60	6/18/2010
1.5E	093000 - Tiling	1.5E	Qualification Data: For Installer.	3/31/2010	5	14	60	6/18/2010
1.5F	093000 - Tiling	1.5F	Material Test Reports: For each tile-setting and -grouting product.	3/31/2010	5	14	60	6/18/2010
1.4A	093800 - Dimension Stone Tile	1.4A	Product Data: Submit manufacturer's product data and installation instructions for each material and product used.	3/1/2010	5	14	90	6/18/2010
1.4B	093800 - Dimension Stone Tile	1.4B	Samples: Submit two representative samples of each material specified indicating visual characteristics and finish. Include range samples if variation of finish is anticipated.	3/1/2010	5	14	90	6/18/2010
1.4A	094010 - Cementitious Terrazzo	1.4A	Product Data: For each type of terrazzo and accessory indicated.	3/1/2010	5	14	90	6/18/2010
1.4B	094010 - Cementitious Terrazzo	1.4B	Shop Drawings: Include terrazzo fabrication and installation requirements. Include plans, elevations, sections, component details, and attachments to other work. Show layout of the following: 1. Divider and control and expansion-joint strips. 2. Base and border strips. 3. Abrasive strips. 4. Stair treads, risers, and landings. 5. Terrazzo patterns.	3/1/2010	5	14	90	6/18/2010
1.4C	094010 - Cementitious Terrazzo	1.4C	Samples for Initial Selection: NTMA color plates showing the full range of colors and patterns available for each terrazzo type indicated.	3/1/2010	5	14	90	6/18/2010
1.4D	094010 - Cementitious Terrazzo	1.4D	Samples for Verification: For each type, material, color, and pattern of terrazzo and accessory required showing the full range of color, texture, and pattern variations expected. Label each terrazzo sample to identify matrix color and aggregate types, sizes, and proportions. Prepare samples of same thickness and from same material to be used for the work in size indicated below: 1. Terrazzo: 6-inch(150-mm-) square samples. 2. Accessories: 6-inch(150-mm-) long samples of each exposed stop item required.	3/1/2010	5	14	90	6/18/2010
1.4E	094010 - Cementitious Terrazzo	1.4E	Qualification Data: For Installer.	3/1/2010	5	14	90	6/18/2010
1.4F	094010 - Cementitious Terrazzo	1.4F	Material Certificates: For each terrazzo type, signed by manufacturer's	3/1/2010	5	14	90	6/18/2010
1.4G	094010 - Cementitious Terrazzo	1.4G	Maintenance Data: For each terrazzo type to include in maintenance manuals.	3/1/2010	5	14	90	6/18/2010
1.4A	095123 - Acoustical Lay-In Ceiling	1.4A	Product Data: For each type of product indicated.	2/28/2010	5	14	60	5/18/2010
1.4B	095123 - Acoustical Lay-In Ceiling	1.4B	Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, based on input from installers of the items involved: 1. Ceiling suspension system members. 2. Method of attaching hangers to building structure. 3. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings. 4. Minimum Drawing Scale: 1/4 inch = 1 foot.	2/28/2010	5	14	60	5/18/2010
1.4C	095123 - Acoustical Lay-In Ceiling	1.4C	Samples for Initial Selection: For components with factory-applied color finishes, and color. Manufacturer's specifications and other data needed to prove compliance with specified requirements. Manufacturer's installation instructions.	2/28/2010	5	14	60	5/18/2010
1.4D	095123 - Acoustical Lay-In Ceiling	1.4D	Samples: 1. 12 inch x 12 inch sample of each ceiling panel. 2. 12 inch long sample of each type and actual accessories.	2/28/2010	5	14	60	5/18/2010
1.4E	095123 - Acoustical Lay-In Ceiling	1.4E	Research/Evaluation Report: For each acoustical panel (ceiling and components and anchor and fastener type).	2/28/2010	5	14	60	5/18/2010
1.4F	095123 - Acoustical Lay-In Ceiling	1.4F	Maintenance Data: For finishes to include in maintenance manuals.	2/28/2010	5	14	60	5/18/2010
1.4A	096530 - Resilient Wall Base and Accessories	1.4A	Product Data: For each type of product indicated.	2/28/2010	5	14	60	5/18/2010

**Exhibit K
Shop Drawing/Submital Schedule (Based on 6/1/09 NTP)**

Item	Item Description	Item Code	Quantity	Unit	Start Date	End Date
Samples for Initial Selection	096530 - Resilient Wall Base and Accessories	1-4B	5	14	60	5/18/2010
Samples for Verification	096530 - Resilient Wall Base and Accessories	1-4C	5	14	60	5/18/2010
Product Data	096813 - Carpet Tile	1-4A	5	14	60	5/18/2010
Samples	096813 - Carpet Tile	1-4B	5	14	60	5/18/2010
Shop Drawings	096813 - Carpet Tile	1-4C	5	14	60	5/18/2010
Certification	096813 - Carpet Tile	1-4D	5	14	60	5/18/2010
Detail Sheets	096900 - Access Flooring	1-9A	5	14	60	5/18/2010
Test Reports	096900 - Access Flooring	1-9B	5	14	60	5/18/2010
Submittals for Information	096900 - Access Flooring	1-9C	5	14	60	5/18/2010
Manufacturer's Installation Instructions	096900 - Access Flooring	1-10A	5	14	60	5/18/2010
Manufacturer's Owner Manual	096900 - Access Flooring	1-10B	5	14	60	5/18/2010
Product Data	097750 - Fiber Reinforced Plastic Panels (FRP)	1-4A	5	14	60	5/18/2010
Samples	097750 - Fiber Reinforced Plastic Panels (FRP)	1-4B	5	14	60	5/18/2010
Installation Instructions	097750 - Fiber Reinforced Plastic Panels (FRP)	1-4C	5	14	60	5/18/2010
Product Data	097950 - Concrete Floor Sealer and Finish	1-4A	5	14	60	5/18/2010
Product Data	098410 - Acoustical Wall Panels	1-4A	5	14	90	5/18/2010
Shop Drawings	098410 - Acoustical Wall Panels	1-4B	5	14	90	5/18/2010
Samples	098410 - Acoustical Wall Panels	1-4C	5	14	90	5/18/2010
Informational Submittals	098410 - Acoustical Wall Panels	1-4D	5	14	90	5/18/2010
Closeout Submittals	098410 - Acoustical Wall Panels	1-4E	5	14	90	5/18/2010
Material List	099000 - Painting and Staining	1-5A	5	14	14	5/18/2010

**Exhibit K
Shop Drawing/Submital Schedule (Based on 6/1/08 NTP)**

Item	Description	Quantity	Start Date	End Date	Notes
Samples	099000 - Painting and Staining	14	4/15/2010	5/18/2010	<p>Samples: Submit full range of colors, patterns, textures and finishes available for selection, including the following:</p> <ol style="list-style-type: none"> Color Chips: Provide complete duplicate sets of color chips for color selection. Small Applied Samples: Provide pieces of actual material on which paint will occur with minimum dry mil thickness of specified paint. Provide painted 12 inch x 12 inch actual gypsum wallboard samples with approved textures for Architect's approval. Approved samples will become standard for which all work will be judged. Sheen Samples: Provide full range of varying sheens when sheens are controllable by intermix. <p>Installed Samples: Provide large size samples for approval. Approved samples may be left in place as part of the work.</p> <p>One room and/or area, as selected by the Architect, shall be painted with materials specified or accepted and applied directly from container, unthinned. After acceptance by Architect, room and/or area shall be standard of quality of entire project.</p> <p>Certifications: 1. Furnish a letter certifying that materials submitted are truly equivalent or better than those called out in the finish schedule. 2. Furnish certification by the manufacturer that products supplied comply with local regulations controlling use of volatile organic compounds (VOCs).</p> <p>Product Data: Include manufacturer's technical bulletins on each product. Sample of manufacturer's limited warranty and warranty application procedures.</p> <p>Product Data: 1. Manufacturer's literature, including schedules, charts, and illustrations to indicate the performance, fabrication, procedures, product variations, and accessories. 2. Air flow and water entrainment performance test results. 3. Material types and thickness.</p>
Installed Samples	099000 - Painting and Staining	14	4/15/2010	5/18/2010	
Installed Samples	099000 - Painting and Staining	14	4/15/2010	5/18/2010	
Certification	099000 - Painting and Staining	14	4/15/2010	5/18/2010	
Product Data	099653 - Electrometric Coating	30	3/30/2010	5/18/2010	
Product Data	099653 - Electrometric Coating	30	3/30/2010	5/18/2010	
Product Data	102000 - Louvers and Vents	120	8/1/2009	12/18/2009	
Shop Drawings	102000 - Louvers and Vents	120	8/1/2009	12/18/2009	
Samples	102000 - Louvers and Vents	14	8/1/2009	12/18/2009	
Product Data	102113 - Toilet Compartments	90	3/31/2010	7/18/2010	
Shop Drawings	102113 - Toilet Compartments	90	3/31/2010	7/18/2010	
Samples for Initial Selection	102113 - Toilet Compartments	14	3/31/2010	7/18/2010	
Samples for Verification	102113 - Toilet Compartments	14	3/31/2010	7/18/2010	
Product Data	102410 - Louvered Screen Wall	120	3/1/2010	7/18/2010	
Shop Drawings	102410 - Louvered Screen Wall	120	3/1/2010	7/18/2010	
product Data	102813 - Toilet Accessories	60	4/30/2010	7/18/2010	
Samples	102813 - Toilet Accessories	60	4/30/2010	7/18/2010	
Product Schedule	102813 - Toilet Accessories	60	4/30/2010	7/18/2010	
Maintenance Data	102813 - Toilet Accessories	60	4/30/2010	7/18/2010	
Product Data	103500 - Flagpoles	60	4/30/2010	7/18/2010	
Shop Drawings	103500 - Flagpoles	60	4/30/2010	7/18/2010	

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Schedule	104000 - Identifying Devices	5.1	A detailed graphic timeline schedule by phases of production and installation is to be submitted by the successful bidder at the same time as final bid quote submittals.	3/1/2010	5	14	120	7/18/2010
Samples	104000 - Identifying Devices	5.2	<p>Samples Submit (4) 8" x 10" samples of each color and finish of exposed materials and accessories, or final material substrate to be used in the project. Match the following paint colors using Matthews/Grip Gard acrylic polyurethane paint with a semi-gloss finish. They are as follows: P-1, PMS 0000 (Color). P-2, Brand (Color). P-3, Brand (Color). Submit one (1) Digital Print control sample of the following for the Graphic Designer's approval before beginning final production: Use final approved artwork for sample. Sign Type EXT 03! EXT 06 1 EXT 0! Description 000000 000000 000000 000000 Submit one (1) vinyl control sample of the following for the Graphic Designer's approval before beginning final production: V-1, Brand (Color). V-2, Brand (Color). V-3, Brand (Color). December 8, 2008 Pennt Set These samples shall become the property of the Graphic Designer for use in checking quality levels of workmanship at the time of final on-site punch reviews. Submit one (1) control sample of the following for the Graphic Designer's approval before beginning final production: Sign Type Description These samples shall become the property of the Graphic Designer.</p>	3/1/2010	5	14	120	7/18/2010
Shop Drawings	104000 - Identifying Devices	5.3	<p>Shop Drawings Submit one (1) reproducible copy of shop drawings in ledger font (11" x 17"), for the manufacturing, fabrication and erection of signs and graphic work at large scale. Show jointage, anchorage, accessory items, and finishes. A. Acceptance of shop drawings does not in any way change the documents. Documents may only be changed in writing. B. The Signage Contractor is responsible for reviewing shop drawings for conformance with the documents and notifying, in writing, the Graphic Designer of any variation from the documents. C. It is the Signage Contractor's responsibility to generate all such shop drawings without use of the Graphic Designer's electronic contract documents and files, to demonstrate the complete understanding of the work to be completed. D. Changes to the shop drawings are to be made by the Signage Contractor as directed by the Graphic Designer.</p>	3/1/2010	5	14	120	7/18/2010
Copy Layouts	104000 - Identifying Devices	5.4	<p>Copy Layouts Copy layouts are to be provided for each sign type. Submit full-scale drawings of typical sign faces showing copy layout. Half-scale drawings will be sufficient for sign faces 40" x 40" and larger. For multiple-message sign types, a typical of each variation to the original layout should be provided.</p>	3/1/2010	5	14	120	7/18/2010
Manufacturer's Data	104000 - Identifying Devices	5.5	<p>Manufacturer's Data Submit one (1) copy of the manufacturer's printed specifications, anchorage details and installation, and maintenance instructions for products to be used in the fabrication of signs and graphics work.</p>	3/1/2010	5	14	120	7/18/2010
Product Data	105050 - Metal Lockers	1.4A	<p>Product Data: Submit manufacturer's product data and installation instructions. Include product data on hardware, filler panels, tops, and other accessory items specified.</p>	3/1/2010	5	14	120	7/18/2010
Samples	105050 - Metal Lockers	1.4B	<p>Samples: Submit three (3) 6 inch x 6 inch samples of each required metal finish and color, on the same metal which will be used in the finished lockers.</p>	3/1/2010	5	14	120	7/18/2010
Maintenance Instructions	105050 - Metal Lockers	1.4C	<p>Maintenance Instructions: Instructions for cleaning lockers and for adjusting, repairing, and replacing locker doors and latching mechanisms.</p>	3/1/2010	5	14	120	7/18/2010

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Schedule	111900 - Detention Equipment	1.4C			6/14/2009	5	14	60	9/1/2009
			<p>Schedules (General): Schedules and/or templates on all materials and equipment of this Section shall be submitted for approval. They shall clearly indicate each item's location, size, type of materials, construction, finishes, spacing of anchors and joinery details with adjacent work.</p> <p>1. Security Hardware Schedule: The DEC shall provide a complete Security Door/Hardware Schedule. This submittal shall include ALL openings provided under this section. The DEC shall cross-reference their hardware set numbers with the hardware set numbers used within the Contract Documents. The submittal shall include cut sheets of all products included therein.</p> <p>2. Security Glass Schedule: The DEC shall provide a complete Security Glass Schedule. This submittal shall include ALL openings provided under this section. The DEC shall cross-reference the glass types with those used within the Contract Documents. The submittal shall include cut sheets of all products included therein. Product Data: Submit manufacturer's printed technical product data and catalog sheets indicating product characteristics, performance and limiting criteria.</p> <p>3. Keying Schedule: The DEC shall provide a preliminary keying schedule for ALL openings provided under this section. The DEC shall attend a meeting with the Design Team and user to review the Hardware Schedule and the proposed keying. (See section 11192 Locks/Hardware).</p> <p>Templates: Upon receipt of the approved security hardware schedule, the DEC shall promptly provide the security hardware templates to the security hollow metal manufacturer, the CM/CMGC, the Consultant, the ESS, or others requiring said information, for those entities' use in designing and installing their equipment and systems. The DEC shall extensively check the templates and shall certify their accuracy.</p> <p>Product Data: Submit manufacturer's printed technical product data and catalog sheets indicating product characteristics, performance and limiting criteria.</p>						
Templates	111900 - Detention Equipment	1.4D			6/14/2009	5	14	60	9/1/2009
Product Data	111900 - Detention Equipment	1.4E			6/14/2009	5	14	60	9/1/2009
Fire Labels	111900 - Detention Equipment	1.4F			6/14/2009	5	14	60	9/1/2009
			<p>Fire Labels: The DEC shall review the fire rated openings within the scope of this contract and identify any openings that cannot be fire labeled and the reasons why they cannot. If the designer furnishes the name of an approved manufacturer who can supply the fire labeled openings in question, the DEC shall be required to furnish the openings with fire labels at no additional cost. However, if label openings are not available as designed, the designer shall either authorize the necessary changes in opening design, hardware, glass or other features which will bring the openings into compliance or drop the fire labeling requirement on openings in question. Manufacturing the openings "Label Construction" without factory applied fire labels shall not be acceptable unless requested by the Consultant in writing.</p>						
Samples	111900 - Detention Equipment	1.4G			6/14/2009	5	14	60	9/1/2009
			<p>Samples: Upon request of the Architect or Consultant, provide samples of any item specified herein for final approval/review. In each case where the sample is requested, the sample shall accurately reflect the item to be used in the project in every way and shall be of sufficient size and quality to allow judgment to be made as to its compliance with the requirements herein and the intent of the security design criteria.</p>						
Product Data	111910 - Detention Hollow Metal	1.5B			6/14/2009	5	14	60	9/1/2009
Shop Drawings	111910 - Detention Hollow Metal	1.5C			6/14/2009	5	14	60	9/1/2009
Coordinator Drawings	111910 - Detention Hollow Metal	1.5D			6/14/2009	5	14	60	9/1/2009
			<p>Product Data: Include construction details, material descriptions, core descriptions, label compliance, fire-resistance rating, and finishes for each type of detention door and frame specified.</p> <p>Shop Drawings: For detention doors and frames. Include conditions at openings, details of construction, dimensions of profiles, and details of joints and connections. Show anchorage and accessories. Identify each detention door and frame using same reference numbers for openings as those on Drawings.</p> <p>Coordinator Drawings: Drawings of each opening, including detention door and frame, drawn to scale and coordinating detention door hardware. Show the following: 1. Locations, dimensions, and profiles of detention door hardware reinforcements. 2. Locations and installation details of detention door hardware. 3. Elevations of each detention door design type showing dimensions, locations of detention door hardware, and preparations for power, signal, and electrified control systems. 4. Details of each detention frame type.</p> <p>Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for detention doors and frames.</p> <p>Test Reports: Security hollow metal manufacturers not listed herein shall submit independent testing laboratory report certifying the following minimum performances: 1. Approved manufacturers listed herein shall submit these certificates of compliance with their approval drawings. 2. All test reports shall include details of test samples and details or photographs of the testing apparatus. The test samples shall be retained at the manufacturer's facilities for possible inspection through the warranty period. a. Thickness: ± 1/16" Provide samples of factory finishes or samples of special construction as requested by the Architect or Consultant.</p>						
Product Test Reports	111910 - Detention Hollow Metal	1.5E			6/14/2009	5	14	60	9/1/2009
Test Reports	111910 - Detention Hollow Metal	1.5E2			6/14/2009	5	14	60	9/1/2009
Samples	111910 - Detention Hollow Metal	1.5F			6/14/2009	5	14	60	9/1/2009

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Product Data	111920 - Security Locks and Hardware	1.5A	Product Data: Submit Manufacturer's technical product data for each item of finish hardware. Show compliance with requirements, and include instructions for installation and for maintenance of operating parts and finish.	5	14	90	4/18/2010
Samples	111920 - Security Locks and Hardware	1.5B	1. Submit one actual unit of each piece of finish hardware, tagged with full description for coordination with the Schedule. If Samples conform to the Contract Documents, they will be returned for inclusion in the Project. 2. Submit Samples of each metal finish on an actual piece of the metal specified. Shop Drawings a. Wiring Diagrams: Detail power, signal, and control wiring and differentiate between manufacturer-installed and field-installed wiring for electrified detention door hardware. Include the following: 1) System schematic. 2) Point-to-point wiring diagram, including location of connections. 3) Riser diagram. 4) Elevation of each detention door. 2. Provide template to door/frame manufacturer after contract and hardware schedule are approved. Hardware Schedule 1. Contractor shall prepare and submit a working schedule of finish hardware for Associate's review. This schedule shall list all items of finish hardware that are to be furnished. The format of the finish hardware schedule shall be "vertical type". Group all items of finish hardware so as to correspond to their areas of use and be readily identifiable. 2. Show required hardware and accessories for each door using door numbers indicated on Drawings. 3. List all other items required and the location in the building. 4. Establish degree of opening for doors with overhead holder, closer, etc., include on hardware schedule. 5. The schedule shall be checked and approved by the Contractor prior to submittal to Associate.	5	14	90	4/18/2010
Shop Drawings	111920 - Security Locks and Hardware	1.5C	1. Submit Shop Drawings showing quality, type, and location of security hardware. a. Wiring Diagrams: Detail power, signal, and control wiring and differentiate between manufacturer-installed and field-installed wiring for electrified detention door hardware. Include the following: 1) System schematic. 2) Point-to-point wiring diagram, including location of connections. 3) Riser diagram. 4) Elevation of each detention door. 2. Provide template to door/frame manufacturer after contract and hardware schedule are approved. Hardware Schedule 1. Contractor shall prepare and submit a working schedule of finish hardware for Associate's review. This schedule shall list all items of finish hardware that are to be furnished. The format of the finish hardware schedule shall be "vertical type". Group all items of finish hardware so as to correspond to their areas of use and be readily identifiable. 2. Show required hardware and accessories for each door using door numbers indicated on Drawings. 3. List all other items required and the location in the building. 4. Establish degree of opening for doors with overhead holder, closer, etc., include on hardware schedule. 5. The schedule shall be checked and approved by the Contractor prior to submittal to Associate.	5	14	90	4/18/2010
Hardware Schedule	111920 - Security Locks and Hardware	1.5D	1. Submit Shop Drawings showing quality, type, and location of security hardware. a. Wiring Diagrams: Detail power, signal, and control wiring and differentiate between manufacturer-installed and field-installed wiring for electrified detention door hardware. Include the following: 1) System schematic. 2) Point-to-point wiring diagram, including location of connections. 3) Riser diagram. 2. Provide template to door/frame manufacturer after contract and hardware schedule are approved. Hardware Schedule 1. Contractor shall prepare and submit a working schedule of finish hardware for Associate's review. This schedule shall list all items of finish hardware that are to be furnished. The format of the finish hardware schedule shall be "vertical type". Group all items of finish hardware so as to correspond to their areas of use and be readily identifiable. 2. Show required hardware and accessories for each door using door numbers indicated on Drawings. 3. List all other items required and the location in the building. 4. Establish degree of opening for doors with overhead holder, closer, etc., include on hardware schedule. 5. The schedule shall be checked and approved by the Contractor prior to submittal to Associate.	5	14	90	4/18/2010
Product Data	111930 - Detention Locking Devices	1.5A	Product Data: Submit Manufacturer's technical product data for each item of finish hardware. Show compliance with requirements, and include instructions for installation and for maintenance of operating parts and finish.	5	14	90	4/18/2010
Samples	111930 - Detention Locking Devices	1.5B	1. Submit one actual unit of each piece of finish hardware, tagged with full description for coordination with the Schedule. If Samples conform to the Contract Documents, they will be returned for inclusion in the Project. 2. Submit Samples of each metal finish on an actual piece of the metal specified. Shop Drawings 1. Submit Shop Drawings showing quality, type, and location of security hardware. a. Wiring Diagrams: Detail power, signal, and control wiring and differentiate between manufacturer-installed and field-installed wiring for electrified detention door hardware. Include the following: 1) System schematic. 2) Point-to-point wiring diagram, including location of connections. 3) Riser diagram. 4) Elevation of each detention door. 2. Provide template to door/frame manufacturer after contract and hardware schedule are complete and acceptable. 3. Provide information to the DFC for Device Coordination Drawings. Operation/Maintenance Manuals 1. Operation Manual covering parts, maintenance, and operation. Refer to Division 1 for submittal procedure. Product Certificates: For each type of electrified detention door hardware, signed by product manufacturer. 1. Certify that detention door hardware approved for use on types and sizes of labeled fire doors complies with listed fire door assemblies.	5	14	90	4/18/2010
Shop Drawings	111930 - Detention Locking Devices	1.5C	1. Submit Shop Drawings showing quality, type, and location of security hardware. a. Wiring Diagrams: Detail power, signal, and control wiring and differentiate between manufacturer-installed and field-installed wiring for electrified detention door hardware. Include the following: 1) System schematic. 2) Point-to-point wiring diagram, including location of connections. 3) Riser diagram. 4) Elevation of each detention door. 2. Provide template to door/frame manufacturer after contract and hardware schedule are complete and acceptable. 3. Provide information to the DFC for Device Coordination Drawings. Operation/Maintenance Manuals 1. Operation Manual covering parts, maintenance, and operation. Refer to Division 1 for submittal procedure. Product Certificates: For each type of electrified detention door hardware, signed by product manufacturer. 1. Certify that detention door hardware approved for use on types and sizes of labeled fire doors complies with listed fire door assemblies.	5	14	90	4/18/2010
Operation/Maintenance manuals	111930 - Detention Locking Devices	1.5D	1. Submit Shop Drawings showing quality, type, and location of security hardware. a. Wiring Diagrams: Detail power, signal, and control wiring and differentiate between manufacturer-installed and field-installed wiring for electrified detention door hardware. Include the following: 1) System schematic. 2) Point-to-point wiring diagram, including location of connections. 3) Riser diagram. 4) Elevation of each detention door. 2. Provide template to door/frame manufacturer after contract and hardware schedule are complete and acceptable. 3. Provide information to the DFC for Device Coordination Drawings. Operation/Maintenance Manuals 1. Operation Manual covering parts, maintenance, and operation. Refer to Division 1 for submittal procedure. Product Certificates: For each type of electrified detention door hardware, signed by product manufacturer. 1. Certify that detention door hardware approved for use on types and sizes of labeled fire doors complies with listed fire door assemblies.	5	14	90	4/18/2010
Product Certification	111930 - Detention Locking Devices	1.5E	1. Certify that detention door hardware approved for use on types and sizes of labeled fire doors complies with listed fire door assemblies.	5	14	90	4/18/2010
Product Data	111970 - Security Ceiling Systems	1.4A	Product Data: For each type of product indicated. Coordination Drawings: Reflected ceiling plans drawn to scale and coordinating penetrations and ceiling-mounted items. Show the following: 1. Joint pattern. 2. Security ceiling system suspension assembly members. 3. Method of attaching hangers to building structure. 4. Ceiling-mounted items including light fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings. 5. Minimum Drawing Scale: 1/4" inch = 1 foot (1:48).	5	14	90	4/18/2010
Coordination Drawings	111970 - Security Ceiling Systems	1.4B	Product Data: For each type of product indicated. Coordination Drawings: Reflected ceiling plans drawn to scale and coordinating penetrations and ceiling-mounted items. Show the following: 1. Joint pattern. 2. Security ceiling system suspension assembly members. 3. Method of attaching hangers to building structure. 4. Ceiling-mounted items including light fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings. 5. Minimum Drawing Scale: 1/4" inch = 1 foot (1:48).	5	14	90	4/18/2010

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Samples for Verification	1.11970 - Security Ceiling Systems	1.4C	12/30/2009	5	14	90	4/18/2010
Welding Certificate	1.11970 - Security Ceiling Systems	1.4D	12/30/2009	5	14	90	4/18/2010
Qualifications Data	1.11970 - Security Ceiling Systems	1.4E	12/30/2009	5	14	90	4/18/2010
Product Test Reports	1.11970 - Security Ceiling Systems	1.4F	12/30/2009	5	14	90	4/18/2010
Research/Evaluation Report	1.11970 - Security Ceiling Systems	1.4G	12/30/2009	5	14	90	4/18/2010
Informational Submittals	1.11970 - Security Ceiling Systems	1.4H	12/30/2009	5	14	90	4/18/2010
Special Requirements (General)	1.14000 - Foodservice Equipment	1.7A	4/1/2010	5	14	120	8/18/2010
	1.14000 - Foodservice Equipment	1.7B	4/1/2010	5	14	120	8/18/2010
Preliminary Submittals	1.14000 - Foodservice Equipment	1.7C	4/1/2010	5	14	120	8/18/2010
Brochure Format	1.14000 - Foodservice Equipment	1.7D	4/1/2010	5	14	120	8/18/2010
Shop Drawings	1.14000 - Foodservice Equipment	1.7E	4/1/2010	5	14	120	8/18/2010
Shop Drawings	1.14000 - Foodservice Equipment	1.7F	4/1/2010	5	14	120	8/18/2010
Regular Submittal	1.14000 - Foodservice Equipment	1.7G	4/1/2010	5	14	120	8/18/2010

Samples for Verification: For the following, prepared on Samples of size indicated below:

1. Security Ceiling Panel Units: Full cross section by 12 inches(300 mm) long for each type
2. Perimeter Supports, Closures, Exposed Molding: 12-inch(300-mm-) long Samples of each type.
3. Suspension System: 12-inch(300-mm-) long Samples.

Welding Certificates

Qualification Data:

1. Manufacturer: Company specializing and regularly engaged in the domestic manufacture of metal plank security ceilings with a minimum of five years experience in the manufacture of correctional ceiling systems.
2. Installer: Company specializing in the installation of metal plank security ceilings, approved by the manufacturer, and having a minimum of three (3) years experience in the installation of correctional ceiling systems.

Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for each security ceiling system.

Research Evaluation Reports: For security ceiling system.

Other Informational Submittals:

1. Examination reports documenting inspection of substrates, areas, and conditions.
2. Anchor inspection reports documenting inspections of built-in and cast-in anchors.
3. Field quality-control reports documenting inspections of installed products.
4. Field quality-control certification.

The following are in addition to any general requirements given elsewhere in the documents All drawings and other submittals indicate Wornell Design Group as foodservice consultant.

Submit two copies of the "buy-out" equipment brochure, one Sepia (reverse reading) and one print of all roughing-in and fabrication shop drawings to the General Contractor within four weeks after award of contract, Notice to Proceed or Issuance of Letter of Intent. Partial submittals will not be accepted or processed. 1. Include information listed in Article 19, Verification and Coordination of Project Data. 2. Electronically produced submittals: include to (2) copies on 3.5" D. floppy disks in AutoCAD Release 14.

1. Front and rear protective cover with labeled project name. 2. Brochure index: Indicate functional Area/Room number, item number, quantity, description and manufacturer. 3. A separate fly sheet for each component or item of equipment, indicating: item number, name, quantity, manufacturer, optional equipment, modifications, special instructions and utility requirements. An item of equipment or assembly containing more than one buyout sub-assembly or component shall have the secondary item listed in parenthesis beside the primary item name. For example: Serving Counter (hot food well). 4. Catalog specification sheet and manufacturer's drawings. 5. Certification letter of equipment listing or classification by Underwriters' Laboratories, inc. or other recognized testing facility.

Shop Drawings (rough-in Drawings): 1. Separate drawing sheets: same size as Contract Drawings (Contract Drawings are not to be traced or reproduced.) 2. 1/4" scale drawings of fixed/movable Foodservice Equipment and pre-fabricated Cold Storage Assemblies with itemized schedules. 3. Special Conditions Drawings, sizing and locating the following conditions: a. Slab depressions, cores, sleeves or block-outs (cold storage assemblies, drain trenches, piping, etc.) b. concrete platforms, c. Pip sleeves, d. Blocking grounds or anchor plates required on walls for equipment support/attachment. 4. Electrical rough-in drawings. 5. Plumbing/mechanical rough-in drawings. 6. Required information: a. All fixed and movable Foodservice Equipment shown on Contract Drawings. b. All prefabricated Cold Storage Assemblies shown on Contract Drawings. c. All general - use and convenience utilities or services indicated on Contract Drawings, including those required by or connected to equipment or devices not in this section. d. All rough-in drawings: Fully dimensioned from engineering benchmark or finished room: surface to point of stub-up through floor and stub-up.

Shop Drawings (manufacturer's and Fabricators): 1. Sheet size: identical to contract drawings, drawn or plotted at 3/4" scale for plan view and elevations; 1-1/2" scale for sections and construction details. 2. Included information: item number, name and quantity. 3. Construction details, sections and elevations to reflect requirements of the Specifications and Drawings. 4. Indicate adjacent walls, columns, and equipment. 5. Indicate plumbing and electrical schematic drawings for equipment such as: fabricated fixtures with single electrical or plumbing connection. 6. Mechanical or electrical operating components or products integrated into a fabricated fixture: ventilation and service access required or recommended by the manufacturer, including panel size and location to permit easy lubrication, adjacent or replacement of all moving parts.

1. After the return of one copy of the preliminary submittal, resubmit for approval. 2. Follow routine procedures specified elsewhere or as directed. 3. All data and material: thoroughly reviewed for compliance by Contractor prior to submittal. Foodservice Consultant's repetitive reviewing time (more than twice) incurred due to the Contractor's failure to comply with the requirements of this Article may be invoiced to the this Contractor at Consultant's standard hourly rates.

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Item	Description	Quantity	Unit	Start Date	End Date
Submittal Information	1.3800 - Electronic Security General Requirements	1.5H		9/1/2009	1/18/2010
Submittal Review	1.3800 - Electronic Security General Requirements	1.5J		9/1/2009	1/18/2010
Product Data	1.3800 - Electronic Security General Requirements	1.5J		9/1/2009	1/18/2010
Transient Surge Protection: Section 1.3800	1.3800 - Electronic Security General Requirements	1.5K		9/1/2009	1/18/2010
Project Data	1.3820 - Intercom and Paging System	1.4A.1		9/1/2009	1/18/2010
Shop Drawings	1.3820 - Intercom and Paging System	1.4A.2		9/1/2009	1/18/2010
Product Data	1.3820 - Intercom and Paging System	1.4A.3		9/1/2009	1/18/2010
Calculations	1.3820 - Intercom and Paging System	1.4A.4		9/1/2009	1/18/2010
Testing	1.3820 - Intercom and Paging System	1.4A.5		9/1/2009	1/18/2010
Project Data	1.3830 - Cabinets and Enclosures	1.4A.1		9/1/2009	1/18/2010
Shop Drawings	1.3830 - Cabinets and Enclosures	1.4A.2		9/1/2009	1/18/2010
Product Data	1.3830 - Cabinets and Enclosures	1.4A.3		9/1/2009	1/18/2010
Testing	1.3830 - Cabinets and Enclosures	1.4A.4		9/1/2009	1/18/2010
Project Data	1.3832 - Electronic Control System	1.4A.1		9/1/2009	1/18/2010

Provide information required for complete review of each item in one submittal. When individual sections of specifications require more than one item for review, such as shop drawings, product data, samples, and related items, submissions shall include all specified information delivered at one time.

1. Incomplete or partial submittals will not be reviewed by the Engineer.
 2. Extra copies of submittals will not be marked or returned, except at the expense of the Contractor.
 3. Duplicate copies of incomplete or partial submittals, or extra copies of submittals, will be discarded after 15 calendar days unless Contractor makes arrangement for return, at Contractor's expense.
 4. Submittals not requested specifically may be returned to Contractor without review.
 5. Review of submittals shall be limited to two (2) submissions. The Engineer shall be compensated for additional reviews. In such an event, a change order to the General Construction Contract will be executed for compensation of the Engineer. The change order shall be executed prior to additional reviews.
Project Data: Electronic Systems General Requirements: Section 1.3800.
 1. System Integrator personnel qualifications: (Project Manager, Project Engineer, On-site Supervising Technician).
 2. List of all manufacturers and equipment suppliers.
 3. Submittal schedule: Schedule shall be submitted within 30 days of Notice to Proceed and shall include time and duration for product data by group, shop drawings by group, touch screen demonstration station, and testing procedures.
 4. Functional block diagram of complete integrated system with references to all related sub-system drawings.
 5. Floor plans indicating device locations and cable assignments/groupings. Submission of these plans indicates that the contractor has coordinated the placement of all devices with architectural plans, and coordinated raceway requirements with all related trades.
 6. Drawings indicating complete conduit and raceway systems.
 7. Spare parts inventory with quantity, description and source listed.
Shop Drawings: Complete installation drawings including system diagrams and terminal provisions, and connection details.
Product Data: Submit material specifications and installation data for products specified herein.
Testing: Test reports of fiber optic cable installation.
Project Data: Description of system operation indicating purpose and capabilities of each component of system with functional system diagram indicating all interlaces to other systems. Description shall include, and call attention to, all variances from the contract documents.
Shop drawings: Complete installation drawings including system diagrams and terminal point to terminal point wiring diagrams or schedules.
Product data: Technical data sheets and specifications for each and every component.
Calculations: Amplifier sizing
Testing: Test reports of fiber optic cable installation.
Project data: Layouts of all electronic rooms equipment including floor plans and wall elevations. NEC required working clearances shall be identified.
Shop drawings: Assembly drawings of each control console arrangement including plan view, elevations, and sections.
Product data: Technical data sheets and specifications for each component.
Test results: Cabinet and enclosure temperatures.
Project data: Description of system operation indicating purpose and capabilities of each component of system with functional system diagram indicating all interlaces to other systems. Description shall include, and call attention to, all variances from the contract documents. Sample of each maintenance report.

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Certification	1.4A.2	Electronic Control System	1.4A.2	9/1/2009	5	14	120
Electronic Files	1.4A	13833 - Touch Screen Control and Management System	1.4A	9/1/2009	5	14	120
Project Data	1.4B.1	13833 - Touch Screen Control and Management System	1.4B.1	9/1/2009	5	14	120
Shop Drawings	1.4B.2	13833 - Touch Screen Control and Management System	1.4B.2	9/1/2009	5	14	120
Shop Drawings	1.4C.1	13833 - Touch Screen Presentation and Display System	1.4C.1	9/1/2009	5	14	120
Demonstration	1.4C.2	13833 - Touch Screen Presentation and Display System	1.4C.2	9/1/2009	5	14	120
Submittal Review	1.4C.3	13833 - Touch Screen Presentation and Display System	1.4C.3	9/1/2009	5	14	120

Certification: Submit written certification that control wiring and locking system consoles and panels have been coordinated with security hardware. (Section 11191). No submittal review will be conducted until receipt of certification. Certification letter shall read as follows:
 "(Manufacturer/Supplier name) has reviewed all electrical characteristics and control wiring requirements of all electric operated security devices, i.e., electric locks, position switches, door operators to be installed in this project and has incorporated all modifications and revisions required to provide a completely coordinated and functional control system."
 3. Shop drawings: Complete installation drawings including system diagrams and terminal point to terminal point wiring diagrams or schedules
 4. Product data: Technical data sheets and specifications for each component.
 5. ~~Test data: Test reports of fire, panic, reliable installation.~~

Electronic files of the electronic systems floor plans will be made available to the electronic system integrator upon request for the purpose of development of touch screen maps and other submittal requirements. Payment of an administrative charge of \$250.00 for the electronic files is required. The fee covers the labor and shipping costs associated with binding the drawings, writing to CD-RW and verification.

Project data: Description of system operation indicating purpose and capabilities of each component of system with functional system diagram indicating all interfaces to other systems. Description shall include, and call attention to, all variances from the contract documents.

Shop drawings: Complete installation drawings including system diagrams and terminal point to terminal point wiring diagrams.

Shop drawings:
 a. Full size layout of each graphic map.
 b. List of system integrator suggested modifications to graphic maps.
 c. Design of custom control stations.
 d. Theory of Operation describing all functional operations of the system.

Demonstration: Two operating touch screen stations shall be provided for the purpose of review of the presentation and display system. The stations shall be networked in order to demonstrate task group management features. Each function of the system shall be emulated via function keys.

a. Upon preliminary approval of the graphic maps, the Electronic Systems Integrator shall fabricate and program two networked touch screen control stations with all maps, icons, and functions as required by these contract documents.
 b. Engineer Demonstration: The Electronic Systems Integrator shall set up the stations at the offices of the Engineer and demonstrate the operational capabilities. The stations shall remain at the offices of the Engineer for a minimum period of four weeks. At the end of the review period, the Engineer will provide the Electronic Systems Integrator with a listing of modifications and/or adjustments deemed appropriate for the proper operation of the unit.
 c. Upon completion of the Engineer review, the Electronic Systems Integrator shall remove the unit from the offices of the Engineer and make all modifications and/or adjustments listed by the Engineer. If re-submittal is required, the Electronic Systems Integrator shall send updated software with instructions for loading and making operational or install updated software as necessary to allow review of revised operation.
 d. Owner Review: Upon completion of the modifications and/or adjustments listed by the engineer, the Electronic Systems Integrator shall set up the station at the offices of the Owner and demonstrate the operational capabilities. The stations shall remain at the offices of the Owner for a review period of 30 days. At the end of the review period, the Engineer will provide the Electronic Systems Integrator with a listing of modifications and/or adjustments deemed appropriate for the proper operation of the unit.
 e. Upon completion of the Owner review, the contractor shall make all modifications and/or adjustments listed by the Engineer and update the demonstration stations with software and hardware as required. If resubmittal is required, the Electronic Systems Integrator shall install updated software as necessary to allow review of revised operation. The demonstration stations shall remain at the offices of the Owner.

Completion of the submittal review for this portion of the work shall not be construed as an approval of the presentation system. Modifications and adjustments shall be provided after installation and field testing on site.

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Product Data	13930 - Wet-Pipe Fire Sprinkler Systems	1.5B	Product Data: Submit data on sprinklers, valves, and specialties, including manufacturers catalog information. Submit performance ratings, rough-in details, weights, support requirements and piping connections.	10/30/2009	5	14	30	12/18/2009
Design Data	13930 - Wet-Pipe Fire Sprinkler Systems	1.5C	Design Data: Submit shop drawings, product data, and hydraulic calculations to Authority Having Jurisdiction for approval, prior to submittal to A/E. Submit proof of approval to A/E.	10/30/2009	5	14	30	12/18/2009
Manufacturer's Certificate	13930 - Wet-Pipe Fire Sprinkler Systems	1.5D	Manufacturer's Certificate: Certify that Products meet or exceed specified requirements.	10/30/2009	5	14	30	12/18/2009
Shop Drawings	13890 - FM 200 Agent Extinguishing System	1.7A	Submit shop drawings and hydraulic calculations to the authority jurisdiction for approval prior to submittal to A/E. Submit proof of approval to A/E with calculations and shop drawings.	11/29/2009	5	14	90	3/18/2010
Data	13890 - FM 200 Agent Extinguishing System	1.7B	Include data for each pipe of equipment comprising the system including cylinders, manifolds, control panel, and nozzles. Include product data and design calculations bearing stamp of approval of authority having jurisdiction. Include calculations that verify system pressure, nozzle flow rate, orifice code numbers, piping pressure losses, component flow data and pipe sizes.	11/29/2009	5	14	90	3/18/2010
Manufacturer's Certificate	13890 - FM 200 Agent Extinguishing System	1.7C	Include manufacturer's certificate that system meets or exceeds specified requirements and NFPA 2001.	11/29/2009	5	14	90	3/18/2010
Welders Certificates	13890 - FM 200 Agent Extinguishing System	1.7D	Include welder's certificate of compliance with ASME SEC 9.	11/29/2009	5	14	90	3/18/2010
Installation Instructions	13890 - FM 200 Agent Extinguishing System	1.7E	Include manufacturer's installation instructions.	11/29/2009	5	14	90	3/18/2010
Product Data	142100 - Gearless Traction Elevator	1.6A	Product Data: Submit manufacturer's product data for each system proposed for use. Include the following: 1. Signal and operating fixtures, operating panels and indicators. 2. Cab design, dimensions and layout. 3. Hoistway-door and frame details. 4. Electrical characteristics and connection requirements. 5. Expected heat dissipation of elevator equipment in control room space and machine space (BTU). 6. Color selection chart for Cab and Entrances. Shop Drawings: Submit approval layout drawings. Include the following: 1. Car, guide rails, buffers and other components in hoistway. 2. Maximum rail bracket spacing. 3. Maximum loads imposed on guide rails requiring load transfer to building structure. 4. Clearances and travel of car. 5. Clear inside hoistway and pit dimensions. 6. Location and sizes of access doors, hoistway entrances and frames.	8/2/2009	5	14	150	1/18/2010
Shop Drawings	142100 - Gearless Traction Elevator	1.6B	Operations and Maintenance Manuals: Provide manufacturer's standard operations and maintenance manual.	8/2/2009	5	14	150	1/18/2010
Keys	142100 - Gearless Traction Elevator	1.6D	Keys: Furnish four (4) keys.	8/2/2009	5	14	150	1/18/2010
Product Data	142423 - Hydraulic Passenger Elevator	1.6A	Product Data: Submit manufacturer's product data for each system proposed for use. Include the following: 1. Signal and operating fixtures, operating panels and indicators. 2. Cab design, dimensions and layout. 3. Hoistway-door, and frame details. 4. Electrical characteristics and connection requirements. 5. Expected heat dissipation of elevator equipment in control room space (BTU). Shop Drawings: Submit approval layout drawings. Include the following: 1. Signal and operating fixtures, operating panels and indicators. 2. Car, guide rails, buffers and other components in hoistway. 3. Maximum rail bracket spacing. 4. Maximum loads imposed on guide rails requiring load transfer to building structure. 5. Loads on hoisting beams. 6. Clearances and travel of car. 7. Clear inside hoistway and pit dimensions. 8. Location and sizes of access doors, hoistway entrances and frames.	8/2/2009	5	14	150	1/18/2010
Shop Drawings	142423 - Hydraulic Passenger Elevator	1.6B	Operations and Maintenance Manuals: Provide manufacturer's standard operations and maintenance manual.	8/2/2009	5	14	150	1/18/2010
Keys	142423 - Hydraulic Passenger Elevator	1.6D	Keys: Furnish four (4) keys.	8/2/2009	5	14	150	1/18/2010
Product Data	143100 - Escalators	1.6A	Product Data: Submit manufacturer's product data, installation instructions, and maintenance recommendations for each material proposed for use.	8/2/2009	5	14	150	1/18/2010
Shop Drawings	143100 - Escalators	1.6B	Shop Drawings: Submit shop drawings for approval prior to fabrication. Include detailed plans, sections, elevations and large scale details indicating escalator system and relationship with adjacent construction. Include electrical characteristics and ventilation requirements.	8/2/2009	5	14	150	1/18/2010
Keys	143100 - Escalators	1.6C	Keys: Furnish four (4) keys to restart units.	8/2/2009	5	14	150	1/18/2010

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Item	Item Description	Item Code	Product Data	Shop Drawing	Product Data	Shop Drawing	Product Data	Shop Drawing	Product Data	Shop Drawing	Product Data
Product Data	144200 - Vertical Platform Lift	1.4A	Product Data: 1. Complete list of all items proposed to be furnished and installed under this Section. 2. Manufacturer's specifications, catalog cuts, and other data to demonstrate compliance with specified requirements. 3. Manufacturer's installation instructions. 4. Manufacturer's operation and maintenance manuals. 5. Shop Drawings: 1. Drawings showing dimensions including plans, elevations, and sections to show equipment locations, and locations of all items including supporting structure and clearances required. 2. Provide load and reaction drawings by the lift manufacturer and detailed on drawings. 3. Indicate all rough-in and wiring requirements. 4. Provide adequate size samples of all items with colors and finishes for Architect's selection. 5. Certification: Load ratings and safety factors certification by a professional engineer registered in the State of Texas. 6. Access Doors: Furnish product data and shop drawings. Indicate detailed dimensions. (i.e. Dark Blue) 7. Where similar items of equipment are utilized, include separate data sheet for each item, individually identified as to function.	144200 - Vertical Platform Lift	8/2/2009	5	14	150	1/18/2010		
Shop Drawings	144200 - Vertical Platform Lift	1.4B		144200 - Vertical Platform Lift	8/2/2009	5	14	150	1/18/2010		
Samples	144200 - Vertical Platform Lift	1.4C		144200 - Vertical Platform Lift	8/2/2009	5	14	150	1/18/2010		
Certification	144200 - Vertical Platform Lift	1.4D		144200 - Vertical Platform Lift	8/2/2009	5	14	150	1/18/2010		
Submittals for Information	15050 - Mechanical General Requirements	1.6A		15050 - Mechanical General Requirements	11/15/2009	5	14	14	12/18/2009		
Product Data	15055 - Motors	1.4A		15055 - Motors	9/30/2009	5	14	60	12/18/2009		
Data	15055 - Motors	1.4B		15055 - Motors	9/30/2009	5	14	60	12/18/2009		
Operation and Maintenance Manuals	15055 - Motors	1.4C		15055 - Motors	9/30/2009	5	14	60	12/18/2009		
Product Data	15060 - Hangers and Supports	1.5A		15060 - Hangers and Supports	11/15/2009	5	14	14	12/18/2009		
Product Data	15070 - Vibration Isolation	1.4A		15070 - Vibration Isolation	11/15/2009	5	14	14	12/18/2009		
Drawings Schedule	15070 - Vibration Isolation	1.4B		15070 - Vibration Isolation	11/15/2009	5	14	14	12/18/2009		
Schedule	15075 - Mechanical Identification	1.4A		15075 - Mechanical Identification	11/15/2009	5	14	14	12/18/2009		
Product Data	15075 - Mechanical Identification	1.4B		15075 - Mechanical Identification	11/15/2009	5	14	14	12/18/2009		
Product Data	15075 - Mechanical Identification	1.4C		15075 - Mechanical Identification	11/15/2009	5	14	14	12/18/2009		
Schedule	15075 - Mechanical Identification	1.4D		15075 - Mechanical Identification	11/15/2009	5	14	14	12/18/2009		
Installation Instructions	15075 - Mechanical Identification	1.4E		15075 - Mechanical Identification	11/15/2009	5	14	14	12/18/2009		
Product Data	15081 - Ductwork Insulation	1.4A		15081 - Ductwork Insulation	11/15/2009	5	14	14	12/18/2009		
Product Data	15081 - Ductwork Insulation	1.4B		15081 - Ductwork Insulation	11/15/2009	5	14	14	12/18/2009		
Product Data	15082 - Equipment Insulation	1.4A		15082 - Equipment Insulation	11/15/2009	5	14	14	12/18/2009		
Product Data	15082 - Equipment Insulation	1.4B		15082 - Equipment Insulation	11/15/2009	5	14	14	12/18/2009		
Product Data	15083 - Piping Insulation	1.4A		15083 - Piping Insulation	11/15/2009	5	14	14	12/18/2009		
Product Data	15083 - Piping Insulation	1.4B		15083 - Piping Insulation	11/15/2009	5	14	14	12/18/2009		
Manufacturer's Literature	15110 - Valves	1.4A		15110 - Valves	8/31/2009	5	14	90	12/18/2009		
O&M	15110 - Valves	1.4B		15110 - Valves	8/31/2009	5	14	90	12/18/2009		
Drawings	15122 - Expansion Tanks	1.4A		15122 - Expansion Tanks	8/31/2009	5	14	90	12/18/2009		
Product Data	15122 - Expansion Tanks	1.4B		15122 - Expansion Tanks	8/31/2009	5	14	90	12/18/2009		
O&M	15122 - Expansion Tanks	1.4C		15122 - Expansion Tanks	8/31/2009	5	14	90	12/18/2009		
Product Data	15130 - HVAC Pumps	1.4A		15130 - HVAC Pumps	8/31/2009	5	14	90	12/18/2009		

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Certification	15130 - HVAC Pumps	1.4B	Certifications and Statements: 1. For each pump with a motor horsepower greater than 10 hp, submit a certified shop performance test curve indicating capacity, head, horsepower and flow rates from shutoff to 125 percent of design flow. 2. For centrifugal pumps, include certification that pump impeller diameter is less than 85 percent of the published impeller selection range. 3. For pumps, include certification that fabricated structural steel base is of sufficient strength to prevent vibration, warping or misalignment of the pump.	8/31/2009	5	14	90	12/18/2009
Manufacturer's Literature	15130 - HVAC Pumps	1.4C	Submit manufacturer's data on seals, and drives with exact seals and drives identified and selected based on pump operating characteristics and horsepower.	8/31/2009	5	14	90	12/18/2009
Procedures	15130 - HVAC Pumps	1.4D	Provide start-up report detailing pump start-up procedures, including: Pump alignment lubrication, voltage and amperage readings, proper electrical connections, pump balance, discharge and suction gauge readings, and head adjustment.	8/31/2009	5	14	90	12/18/2009
O&M	15130 - HVAC Pumps	1.4E	Provide operation and maintenance manuals.	8/31/2009	5	14	90	12/18/2009
Product Data	15140 - Domestic Water and Sanitary Drainage Piping	1.4A	Include data on pipe materials, pipe fittings, and special fabricated items	6/29/2009	5	14	14	8/1/2009
Product Data	15140 - Domestic Water and Sanitary Drainage Piping	1.4B	Include component sizes, rough-in requirements, service sizes and finish for specialties.	6/29/2009	5	14	14	8/1/2009
O&M	15140 - Domestic Water and Sanitary Drainage Piping	1.4C	Provide operation and maintenance manuals	6/29/2009	5	14	14	8/1/2009
Product Data	15160 - Storm Drainage Piping	1.4A	Include data on roof drains, pipe materials and pipe fittings	6/29/2009	5	14	14	8/1/2009
Data	15183 - Hydronic Piping and Specialties	1.4A	Submit data on pipe materials, pipe fittings and accessories. Include ASTM designations and manufacturing location(s), and indicate all fittings types and accessories.	6/29/2009	5	14	14	8/1/2009
Product Data	15183 - Hydronic Piping and Specialties	1.4B	Submit product data sheets showing all dimensions, code specifications, and accessories (all options and accessories shall be clearly marked) on the following equipment: 1. Air Vents 2. Strainers 3. Pump suction diffusers 4. Thermometers 5. Pressure gauges 6. Air separators	6/29/2009	5	14	14	8/1/2009
Test Reports	15183 - Hydronic Piping and Specialties	1.4C	Provide test reports on the following: 1. Piping welds non-destructive testing report. 2. Pressure test report. Document all tests performed, include test summaries, all repairs/adjustment made, and final test results.	6/29/2009	5	14	14	8/1/2009
Product Data	15185 - Chemical Water Treatment	1.3A	Include product data for all chemical treatment materials, chemicals, and equipment.	12/29/2009	5	14	60	3/18/2010
Installation Instructions	15185 - Chemical Water Treatment	1.3B	Include manufacturer's installation instructions.	12/29/2009	5	14	60	3/18/2010
Shop Drawings	15185 - Chemical Water Treatment	1.3C	Include shop drawings indicating all system schematics, equipment locations and controls schematics.	12/29/2009	5	14	60	3/18/2010
O&M	15185 - Chemical Water Treatment	1.3D	Provide operation and maintenance manuals	12/29/2009	5	14	60	3/18/2010
Data	15189 - Underground Pre-Insulated Piping	1.4A	Submit data on pipe materials, pipe fittings and accessories. Include ASTM designations and manufacturing location(s), and indicate all fittings types and accessories.	6/3/2009	5	14	40	8/1/2009
Data	15189 - Underground Pre-Insulated Piping	1.4B	For high temperature piping systems, the pre-insulated piping manufacturer shall make a complete layout of the system showing anchors, expansion provisions, and building entrance details. Expansion means shall be in pipe offsets or loops.	6/3/2009	5	14	40	8/1/2009
Data	15210 - Natural Gas Piping	1.3A	Include data on pipe materials, pipe fittings, valves, and accessories.	11/15/2009	5	14	14	12/18/2009
Data	15410 - Plumbing Fixtures	1.2A	Include fixtures, sizes, utility sizes, trim and finishes	11/15/2009	5	14	14	12/18/2009
O&M	15410 - Plumbing Fixtures	1.2B	Provide operation and maintenance manuals	11/15/2009	5	14	14	12/18/2009
Product Data	15440 - Plumbing Pumps	1.4A	Product Data: Indicate pump type, capacity, powered requirements, and affected adjacent construction.	11/15/2009	5	14	14	12/18/2009
Certified Pump Curves	15440 - Plumbing Pumps	1.4B	Certified Pump Curves: Show pump performance characteristics with pump and system operating point plotted.	11/15/2009	5	14	14	12/18/2009
O&M	15440 - Plumbing Pumps	1.4C	Include NPSH curve when applicable.	11/15/2009	5	14	14	12/18/2009
Product Data	15480 - Domestic Water Heaters	1.4A	Product Data: 1. Submit heat exchanger dimensions, size of tapings, and performance data. 2. Include dimensions of tanks, tank lining methods, anchors, attachments, lifting points, tapings, and drains.	11/15/2009	5	14	14	12/18/2009
Certification	15480 - Domestic Water Heaters	1.4B	Certification: Include manufacturer's certificate that pressure vessels meet or exceed specified requirements.	11/15/2009	5	14	14	12/18/2009
O&M	15480 - Domestic Water Heaters	1.4C	Provide operation and maintenance manuals	11/15/2009	5	14	14	12/18/2009
Product Data	15513 - Water-Tube Boilers	1.4A	Product Data: Submit general layout and dimensions. Include size and location of water, fuel, electric and vent connections, electrical characteristics, weight and mounting loads.	8/1/2009	5	14	120	12/18/2009
Test Reports	15513 - Water-Tube Boilers	1.4B	Test Reports: Indicate specified performance and efficiency is met or exceeded. Provide combustion test that include boiler firing rate, over fire draft, gas flow rate, heat input, burner manifold gas pressure, percent carbon dioxide (CO), percent oxygen (O), percent excess air, flue gas temperature at outlet, ambient temperature, net stack temperature, percent stack loss, percent combustion efficiency, and heat input.	8/1/2009	5	14	120	12/18/2009
Manufacturer's Installation Instructions	15513 - Water-Tube Boilers	1.4C	Manufacturer's Installation Instructions: Submit assembly, support details, connection requirements, and include start-up instructions.	8/1/2009	5	14	120	12/18/2009
O&M	15513 - Water-Tube Boilers	1.4D	Provide operation and maintenance manuals	8/1/2009	5	14	120	12/18/2009
Test Reports	15514 - Fire-Tube Boilers	1.4B	Test Reports: Indicate specified performance and efficiency is met or exceeded. Provide combustion test that include boiler firing rate, over fire draft, gas flow rate, heat input, burner manifold gas pressure, percent carbon dioxide (CO), percent oxygen (O), percent excess air, flue gas temperature at outlet, ambient temperature, net stack temperature, percent stack loss, percent combustion efficiency, and heat input.	8/1/2009	5	14	120	12/18/2009

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Item	Code	Description	Quantity	Unit	Start Date	Completion Date
Manufacturer's Installation Instructions	1.4C	15514 - Fire-Tube Boilers	5	14	8/1/2009	12/18/2009
O&M	1.4D	15514 - Fire-Tube Boilers	5	14	8/1/2009	12/18/2009
Shop Drawings	1.4A	15622 - Water-Cooled Centrifugal Chillers	5	14	8/1/2009	12/18/2009
Product Data	1.4B	15622 - Water-Cooled Centrifugal Chillers	5	14	8/1/2009	12/18/2009
Product Data	1.4C	15622 - Water-Cooled Centrifugal Chillers	5	14	8/1/2009	12/18/2009
Performance Data	1.4D	15622 - Water-Cooled Centrifugal Chillers	5	14	8/1/2009	12/18/2009
Certified Test Reports	1.4E	15622 - Water-Cooled Centrifugal Chillers	5	14	8/1/2009	12/18/2009
O&M	1.4F	15622 - Water-Cooled Centrifugal Chillers	5	14	8/1/2009	12/18/2009
Product Data	1.3A	15641 - Induced Draft Cooling Tower	5	14	8/1/2009	12/18/2009
Performance Test	1.3B	15641 - Induced Draft Cooling Tower	5	14	8/1/2009	12/18/2009
Shop Drawings	1.3C	15641 - Induced Draft Cooling Tower	5	14	8/1/2009	12/18/2009
O&M	1.3D	15641 - Induced Draft Cooling Tower	5	14	8/1/2009	12/18/2009
Shop Drawings	1.4B	15721 - Air Handling Units	5	14	8/1/2009	12/18/2009
Product Data	1.4C	15721 - Air Handling Units	5	14	8/1/2009	12/18/2009
Calculations	1.4D	15721 - Air Handling Units	5	14	8/1/2009	12/18/2009
Performance Data	1.4E	15721 - Air Handling Units	5	14	8/1/2009	12/18/2009
Performance Data	1.4F	15721 - Air Handling Units	5	14	8/1/2009	12/18/2009
Report	1.4G	15721 - Air Handling Units	5	14	8/1/2009	12/18/2009
O&M	1.4H	15721 - Air Handling Units	5	14	8/1/2009	12/18/2009
Product Data	1.4A	15725 - Blower Coil Units	5	14	8/1/2009	12/18/2009
Performance Data	1.4B	15725 - Blower Coil Units	5	14	8/1/2009	12/18/2009
O&M	1.4C	15735 - Blower Coil Units	5	14	8/1/2009	12/18/2009
Product Data	1.4A	15735 - Computer Room Chilled Water Air Conditioning Units	5	14	8/1/2009	12/18/2009
Data	1.4B	15735 - Computer Room Chilled Water Air Conditioning Units	5	14	8/1/2009	12/18/2009
Manufacturer's Installation Instructions	1.4C	15735 - Computer Room Chilled Water Air Conditioning Units	5	14	8/1/2009	12/18/2009
O&M	1.4D	15735 - Computer Room Chilled Water Air Conditioning Units	5	14	8/1/2009	12/18/2009
Product Data	1.1A	15771 - Heat Tracing Cable	5	14	11/8/2009	12/18/2009
Shop Drawings	1.1A	15810 - Ductwork	5	14	11/8/2009	12/18/2009

**Exhibit K
Shop Drawing/Submital Schedule (Based on 6/1/09 NTP)**

Item	Code	Description	Start Date	Days	End Date
Shop Drawings	1.1B	15810 - Ductwork	11/8/2009	5	12/18/2009
Product Data	1.1C	15810 - Ductwork	11/8/2009	5	12/18/2009
Product Data	1.4A	15820 - Ductwork Accessories	11/8/2009	5	12/18/2009
Performance Data	1.4B	15820 - Ductwork Accessories	11/8/2009	5	12/18/2009
Performance Data	1.4C	15820 - Ductwork Accessories	11/8/2009	5	12/18/2009
Manufacturer's Installation Instructions	1.4D	15820 - Ductwork Accessories	11/8/2009	5	12/18/2009
O&M	1.4E	15820 - Ductwork Accessories	11/8/2009	5	12/18/2009
Literature	1.4A	15836 - Power Ventilations	9/30/2009	5	12/18/2009
O&M	1.4B	15836 - Power Ventilations	9/30/2009	5	12/18/2009
Manufacturer's Installation Instructions	1.5A	15840 - Air Terminal Units	9/30/2009	5	12/18/2009
O&M	1.5B	15840 - Air Terminal Units	9/30/2009	5	12/18/2009
Factory Test	1.5C	15840 - Air Terminal Units	9/30/2009	5	12/18/2009
O&M	1.5D	15840 - Air Terminal Units	9/30/2009	5	12/18/2009
Product Data	1.4A	15850 - Air Outlets and Inlets	9/30/2009	5	12/18/2009
Requirements	1.4B	15850 - Air Outlets and Inlets	9/30/2009	5	12/18/2009
Manufacturer's Installation Instructions	1.4C	15850 - Air Outlets and Inlets	9/30/2009	5	12/18/2009
O&M	1.3A	15862 - Air Filters	9/30/2009	5	12/18/2009
Product Data	1.3B	15862 - Air Filters	9/30/2009	5	12/18/2009
O&M	1.6A	16050 - Electrical General Prov.	6/29/2009	5	8/1/2009
Product Data	1.5A	16060 - Grounding and Bonding Systems	6/13/2009	5	8/1/2009
Test Reports	1.5B	16060 - Grounding and Bonding Systems	6/13/2009	5	8/1/2009
Manufacturer's Installation Instructions	1.5C	16060 - Grounding and Bonding Systems	6/13/2009	5	8/1/2009
Project Record Documents	1.5D	16060 - Grounding and Bonding Systems	6/13/2009	5	8/1/2009
Product Data	1.2A	16075 - Electrical Identification	6/13/2009	5	8/1/2009
Test Reports	1.3A	16080 - Electrical Testing	6/13/2009	5	8/1/2009
Test Data	1.3B	16080 - Electrical Testing	6/13/2009	5	8/1/2009
Product Data	1.4A	16135 - Indoor Service Poles	12/31/2009	5	2/18/2010
Samples	1.4B	16135 - Indoor Service Poles	12/31/2009	5	2/18/2010
Operation and Maintenance Manuals	1.4C	16135 - Indoor Service Poles	12/31/2009	5	2/18/2010
Samples	1.4A	16141 - Decorator Style Wiring Devices	10/30/2009	5	12/18/2009
Product Data	1.4A	16210 - Service Entrance	10/30/2009	5	12/18/2009

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Shop Drawings	Product Data	Manufacturer's Installation Instructions	Operation and Maintenance Manuals	Product Data	Product Data	Shop Drawings	Line Diagram	Product Data	Operation and Maintenance Manuals	Product Data	Product Data	Operation and Maintenance Manuals	Shop Drawings	Product Data	Certified Documentation	Certified Documentation	Parts List	Test Reports	Operation and Maintenance Manuals	Shop Drawings	Product Data	Certified Documentation	Certified Documentation	Parts List
16231 - Packaged Engine Generator Systems	1.5A	Furnish shop drawings showing plan and elevation views with overall and interconnection point dimensions, fuel consumption rate curves at various loads, ventilation and combustion air requirements, and electrical diagrams including schematic and interconnection diagrams. Show actual room layout and verify combustion air requirements and cooling water requirements.	1.5A	8/1/2009	5	14	120	12/18/2009																
16231 - Packaged Engine Generator Systems	1.5B	Furnish product data showing dimensions, weights, ratings, interconnection points and internal wiring diagrams for engine, generator, control panel, battery, battery pack, battery charger, battery rack, battery charger, exhaust silencer, vibration isolators, day tank and remote annunciator. Submit computer analysis for generator loading, motor starting, critical speed and vibratory stress.	1.5B	8/1/2009	5	14	120	12/18/2009																
16231 - Packaged Engine Generator Systems	1.5C	Furnish manufacturer's installation instructions.	1.5C	8/1/2009	5	14	120	12/18/2009																
16231 - Packaged Engine Generator Systems	1.5D	Provide operation and maintenance manuals	1.5D	8/1/2009	5	14	120	12/18/2009																
16236 - Static Uninterruptible Power Supply	1.4A	Furnish battery pack dimensions	1.4A	8/1/2009	5	14	120	12/18/2009																
16236 - Static Uninterruptible Power Supply	1.4B	Include battery, size, dimensions and weight	1.4B	8/1/2009	5	14	120	12/18/2009																
16236 - Static Uninterruptible Power Supply	1.4C	Included detailed equipment outlines, weight and dimensions	1.4C	8/1/2009	5	14	120	12/18/2009																
16236 - Static Uninterruptible Power Supply	1.4D	Include location of conduit entry and exit.	1.4D	8/1/2009	5	14	120	12/18/2009																
16236 - Static Uninterruptible Power Supply	1.4E	Furnish single line diagram indicating metering, control and external wiring requirements, heart rejection and air flow requirements.	1.4E	8/1/2009	5	14	120	12/18/2009																
16236 - Static Uninterruptible Power Supply	1.4F	Furnish product data for major components, including catalog sheets and technical data sheets to indicate physical data and electrical performance.	1.4F	8/1/2009	5	14	120	12/18/2009																
16236 - Static Uninterruptible Power Supply	1.4G	Provide operation and maintenance manuals	1.4G	8/1/2009	5	14	120	12/18/2009																
16276 - Dry Type Transformers	1.4A	Include outline and support point dimensions of enclosures and accessories, unit weight, voltage, KVA and impedance ratings and characteristics, no load core loss, full load winding conductor loss, full load losses, efficiency at 25 percent, 50 percent, 75 percent and 100 percent rated loads, percent regulation with 80 percent and 100 percent power factor loads, sound level, tap configurations, insulation system type and rated temperature rise	1.4A	8/1/2009	5	14	120	12/18/2009																
16276 - Dry Type Transformers	1.4B	Indicate K-factor where applicable	1.4B	8/1/2009	5	14	120	12/18/2009																
16276 - Dry Type Transformers	1.4C	Base data for electrical characteristics on actual laboratory tests of typical transformers	1.4C	8/1/2009	5	14	120	12/18/2009																
16276 - Dry Type Transformers	1.4D	Provide operation and maintenance manuals	1.4D	8/1/2009	5	14	120	12/18/2009																
16336 - Transient Voltage Surge Suppressors (High Exposure)	1.3A	Provide an equipment manual that details the installation, operation and maintenance instructions for the specified unit.	1.3A	8/1/2009	5	14	120	12/18/2009																
16336 - Transient Voltage Surge Suppressors (High Exposure)	1.3B	Provide drawings that show unit dimensions, weights, mounting provisions, connection details and layout diagram of the unit.	1.3B	8/1/2009	5	14	120	12/18/2009																
16336 - Transient Voltage Surge Suppressors (High Exposure)	1.3C	Provide data showing UL1449 product listing. Also submit certified documentation of applicable Location Category Testing in full compliance with NEMA LS 1-1992, paragraphs 2.2.10 and 3.1.0.	1.3C	8/1/2009	5	14	120	12/18/2009																
16336 - Transient Voltage Surge Suppressors (High Exposure)	1.3D	Provide certified documentation of the unit's Single Pulse Surge Current Capacity based on ANSI/IEEE C62.41-1991 Standards.	1.3D	8/1/2009	5	14	120	12/18/2009																
16336 - Transient Voltage Surge Suppressors (High Exposure)	1.3E	Provide certified documentation of the unit's Minimum Repetitive Surge Current Capacity Testing based on ANSI/IEEE C62.45-1987 Standards.	1.3E	8/1/2009	5	14	120	12/18/2009																
16336 - Transient Voltage Surge Suppressors (High Exposure)	1.3F	The unit shall include a Diagnostic Signature Card listing factory-established benchmark suppression voltage values for all modes of protection. The suppression voltage values shall be established during final production line testing utilizing the DVS-2 Diagnostic Test Set. This Diagnostic Signature Card shall provide space for subsequent field testing allowing comparison of the initial factory benchmark testing with subsequent field testing suppression voltage values.	1.3F	8/1/2009	5	14	120	12/18/2009																
16336 - Transient Voltage Surge Suppressors (High Exposure)	1.3G	Provide an equipment manual that details the installation, operation and maintenance instructions for the specified unit.	1.3G	8/1/2009	5	14	120	12/18/2009																
16337 - Transient Voltage Surge Suppressors (Medium Exposure)	1.3A	Provide drawings that show unit dimensions, weights, mounting provisions, connection details and layout diagram of the unit.	1.3A	8/1/2009	5	14	120	12/18/2009																
16337 - Transient Voltage Surge Suppressors (Medium Exposure)	1.3B	Provide data showing UL1449 product listing. Also submit certified documentation of applicable Location Category Testing in full compliance with NEMA LS 1-1992, paragraphs 2.2.10 and 3.1.0.	1.3B	8/1/2009	5	14	120	12/18/2009																
16337 - Transient Voltage Surge Suppressors (Medium Exposure)	1.3C	Provide certified documentation of the unit's Single Pulse Surge Current Capacity based on ANSI/IEEE C62.41-1991 Standards.	1.3C	8/1/2009	5	14	120	12/18/2009																
16337 - Transient Voltage Surge Suppressors (Medium Exposure)	1.3D	Provide certified documentation of the unit's Minimum Repetitive Surge Current Capacity Testing based on ANSI/IEEE C62.45-1987 Standards.	1.3D	8/1/2009	5	14	120	12/18/2009																
16337 - Transient Voltage Surge Suppressors (Medium Exposure)	1.3E	The unit shall include a Diagnostic Signature Card listing factory-established benchmark suppression voltage values for all modes of protection. The suppression voltage values shall be established during final production line testing utilizing the DVS-2 Diagnostic Test Set. This Diagnostic Signature Card shall provide space for subsequent field testing allowing comparison of the initial factory benchmark testing with subsequent field testing suppression voltage values.	1.3E	8/1/2009	5	14	120	12/18/2009																
16337 - Transient Voltage Surge Suppressors (Medium Exposure)	1.3F	Provide an equipment manual that details the installation, operation and maintenance instructions for the specified unit.	1.3F	8/1/2009	5	14	120	12/18/2009																

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Item	Description	Code	Quantity	Start Date	End Date
Test Reports	16337 - Transient Voltage Surge Suppressors (Medium Expose)	1.3G	5	8/1/2009	12/18/2009
Operation and Maintenance Manuals	16338 - Transient Voltage Surge Suppressors (Low Expose)	1.3A	5	8/1/2009	12/18/2009
Shop Drawings	16338 - Transient Voltage Surge Suppressors (Low Expose)	1.3B	5	8/1/2009	12/18/2009
Product Data	16338 - Transient Voltage Surge Suppressors (Low Expose)	1.3C	5	8/1/2009	12/18/2009
Certified Documentation	16338 - Transient Voltage Surge Suppressors (Low Expose)	1.3D	5	8/1/2009	12/18/2009
Certified Documentation	16338 - Transient Voltage Surge Suppressors (Low Expose)	1.3E	5	8/1/2009	12/18/2009
Parts List	16338 - Transient Voltage Surge Suppressors (Low Expose)	1.3F	5	8/1/2009	12/18/2009
Test Reports	16338 - Transient Voltage Surge Suppressors (Low Expose)	1.3G	5	8/1/2009	12/18/2009
Product Data	16411 - Disconnect Switches	1.4A	5	9/30/2009	12/18/2009
Classification	16411 - Disconnect Switches	1.4B	5	9/30/2009	12/18/2009
Written Verification	16423 - Contactors	1.2A	5	9/30/2009	12/18/2009
Classification	16423 - Contactors	1.2B	5	9/30/2009	12/18/2009
Operation and Maintenance Manuals	16423 - Contactors	1.2C	5	9/30/2009	12/18/2009
Product Data	16424 - Individual Motor Starters	1.5A	5	9/30/2009	12/18/2009
Classification	16424 - Individual Motor Starters	1.5B	5	9/30/2009	12/18/2009
Operation and Maintenance Manuals	16424 - Individual Motor Starters	1.5C	5	9/30/2009	12/18/2009
Drawings	16441 - Switchboards	1.4A	5	8/1/2009	12/18/2009
Drawings	16441 - Switchboards	1.4B	5	8/1/2009	12/18/2009
Classification	16441 - Switchboards	1.4C	5	8/1/2009	12/18/2009
Legends	16441 - Switchboards	1.4D	5	8/1/2009	12/18/2009
Drawings	16441 - Switchboards	1.4E	5	8/1/2009	12/18/2009
Instructions	16441 - Switchboards	1.4F	5	8/1/2009	12/18/2009
Product Data	16441 - Switchboards	1.4G	5	8/1/2009	12/18/2009
Shop Drawings	16442 - Panel board	1.4A	5	8/1/2009	12/18/2009
Shop Drawings	16451 - Bus way	1.4A	5	8/1/2009	12/18/2009
Product Data	16451 - Bus way	1.4B	5	8/1/2009	12/18/2009
Coordination Drawings	16451 - Bus way	1.4C	5	8/1/2009	12/18/2009
Project Record Documents	16451 - Bus way	1.4D	5	8/1/2009	12/18/2009
Operation and Maintenance Manuals	16451 - Bus way	1.4E	5	8/1/2009	12/18/2009
Product Data	16510 - Lighting Fixtures - Building	1.3A	5	1/30/2010	6/18/2010
Samples	16510 - Lighting Fixtures - Building	1.3B	5	1/30/2010	6/18/2010
Operation and Maintenance Manuals	16510 - Lighting Fixtures - Building	1.3C	5	1/30/2010	6/18/2010
Product Data	16520 - Lighting Fixtures - Site	1.3A	5	1/30/2010	6/18/2010
Samples	16520 - Lighting Fixtures - Site	1.3B	5	1/30/2010	6/18/2010

**Exhibit K
Shop Drawing/Submital Schedule (Based on 6/1/09 NTP)**

Operation and Maintenance Manuals	16520 - Lighting Fixtures - Site	1.3C	Provide operation and maintenance manuals	1/30/2010	5	14	120	6/18/2010
Product Data	16570 - Lighting Relay Panels	1.3A	Include product data for relays, enclosures, switches, and photocells	1/30/2010	5	14	120	6/18/2010
Diagrams	16570 - Lighting Relay Panels	1.3B	Provide wiring diagrams for all components	1/30/2010	5	14	120	6/18/2010
Operation and Maintenance Manuals	16570 - Lighting Relay Panels	1.3C	Provide operation and maintenance manuals	1/30/2010	5	14	120	6/18/2010
Certification	17000 - Building Automation System (BAS)	1.4A	Complete Bill of Material, including manufacturer's certified rating data, description literature, catalog cuts, and shop drawings, for proposal: 1. Control devices and equipment. 2. Control dampers and valves. 3. Control panels. 4. Wiring materials and electrical power equipment.	8/1/2009	5	14	120	12/18/2009
Diagrams	17000 - Building Automation System (BAS)	1.4B	Include control, interlock, and power wiring diagrams and descriptions on operation of all control systems (sequences of operation) and their effect on other equipment and systems.	8/1/2009	5	14	120	12/18/2009
Drawings	17000 - Building Automation System (BAS)	1.4C	Include and HVAC control schematic layout showing, in detail, the exact quantity of function points, printed circuit cards, the relationship of these elements and a description of how they interrelate operationally.	8/1/2009	5	14	120	12/18/2009
Schematics	17000 - Building Automation System (BAS)	1.4D	Include a BACnet protocol Implementation Conformance Statements (PICS) for each type of controller and operator interface included in the submittal.	8/1/2009	5	14	120	12/18/2009
Operation and Maintenance Manuals	17000 - Building Automation System (BAS)	1.4E	Final submittal shall include operation and maintenance manuals.	8/1/2009	5	14	120	12/18/2009
Software	17000 - Building Automation System (BAS)	1.4F	Provide and install, at no additional cost to owner, the latest firmware and software applicable for this project before the expiration of the warranty period.	8/1/2009	5	14	120	12/18/2009
Drawings	17000 - Building Automation System (BAS)	1.4G	Combination Fire/Smoke Dampers and Smoke Dampers: Assign identification numbers for each damper with corresponding number noted on Drawings. Provide air quantity, size, free area of damper, pressure drop and proposed velocity through each damper. Provide manufacturer's data of damper and its accessories or options. Provide power requirements.	8/1/2009	5	14	120	12/18/2009
Product Data	221113 - Facility Water Distribution Piping	1.4A	Product Data: For each type of product indicated.	10/30/2009	5	14	30	12/18/2009
Shop Drawings	221113 - Facility Water Distribution Piping	1.4B	Shop Drawings: Detail precast concrete vault assemblies and indicate dimensions, method of field assembly, and components.	10/30/2009	5	14	30	12/18/2009
Coordination Drawings	221113 - Facility Water Distribution Piping	1.4C	1. Wiring Diagrams: Power, signal, and control wiring for alarms. Coordination Drawings: For piping and specialties including relation to other services in same area, drawn to scale. Show piping and specialty sizes and valves, meter and specialty locations, and elevations.	10/30/2009	5	14	30	12/18/2009
Test Reports	221113 - Facility Water Distribution Piping	1.4D	field quality-control test reports.	10/30/2009	5	14	30	12/18/2009
Operation and Maintenance Manuals	221113 - Facility Water Distribution Piping	1.4E	Operation and Maintenance Data: For water valves and specialties to include in emergency, operation, and maintenance manuals.	10/30/2009	5	14	30	12/18/2009
Product Data	221313 - Facility Sanitary Sewers	1.4A	Product Data: For the following: 1. Expansion joints and deflection fittings. 2. Backwater valves.	6/13/2009	5	14	30	8/1/2009
Shop Drawings	221313 - Facility Sanitary Sewers	1.4B	Shop Drawings: For manholes. Include plans, elevations, sections, details, and frames and covers.	6/13/2009	5	14	30	8/1/2009
Product Certificates	221313 - Facility Sanitary Sewers	1.4C	Product Certificates: For each type of cast-iron soil pipe and fitting, from manufacturer.	6/13/2009	5	14	30	8/1/2009
Reports	221313 - Facility Sanitary Sewers	1.4D	Field quality-control reports. The Communications Contractor shall perform no portion of the work requiring submittal and review of record drawings, shop drawings, product data, or samples until the respective submittal has been approved by PG&A Technology Planning Group and the Engineer. Such work shall be in accordance with approved submittals.	6/13/2009	5	14	30	8/1/2009
Data	270500 - Communications General	1.11A	Review of record drawings, shop drawings, product data, or samples until the respective submittal has been approved by PG&A Technology Planning Group and the Engineer. Such work shall be in accordance with approved submittals.	10/30/2009	5	14	30	12/18/2009
Data	270500 - Communications General	1.11B	Communications Contractor's BICSI Registered Communications Distribution Designer (RCDD) supervisor shall review, approve and stamp all documents prior to submitting Qualifications. The Contractor shall submit qualification data sheets for firms and persons as specified in the "Quality Assurance", Section 1.13 of this specification. Provide evidence of applicable registration or certification.	10/30/2009	5	14	30	12/18/2009
Qualifications Data	270500 - Communications General	1.11C	Review of record drawings, shop drawings, product data, or samples until the respective submittal has been approved by PG&A Technology Planning Group and the Engineer. Such work shall be in accordance with approved submittals.	10/30/2009	5	14	30	12/18/2009
Product Data	270500 - Communications General	1.11D	Proposed product data sheets. The Communications Contractor shall submit catalogue cut sheets that include manufacturer, trade name, and complete model number for each product specified. Model number shall be handwritten and/or highlighted to indicate exact selection. Identify applicable specification section reference for each product performance for each component specified for approval prior to purchase and installation.	10/30/2009	5	14	30	12/18/2009
Samples	270500 - Communications General	1.11E	Samples: For workstation outlet connectors, jack assemblies, housings and faceplates for color selection and evaluation of technical specifications and requirements. Confirm with Architect, Interior Designer, and Owner representative for color before purchasing materials.	10/30/2009	5	14	30	12/18/2009
Product Certification	270500 - Communications General	1.11F	Product Certificates: Signed by manufacturer of cables, connectors, and terminal equipment certifying that products furnished comply with requirements.	10/30/2009	5	14	30	12/18/2009
Field Test Reports	270500 - Communications General	1.11G	Field Test Reports: Upon completing testing of the installed system, test reports shall be submitted. See Section 3.4 of this documentation for details.	10/30/2009	5	14	30	12/18/2009

**Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)**

Item	Description	Quantity	Unit	Start Date	End Date
Warranty	270500 - Communications General 1.11H Warranty: Deliver manufacturer's signed 20-year Extended Product and System Assurance Warranty of installed cabling system to include all components that comprise the complete cabling system. Delivery to be effective within two weeks of the time of final punch list review. Failure of any component to pass system component tests shall be promptly ameliorated. Communications Contractor shall coordinate with manufacturer for warranty paperwork and procedures prior to the start of the project. Communications Contractor must clearly identify any resubmitted drawing sheets, documents or cut sheets either by using a color to highlight or cloud around resubmitted information. Maintain drawing numbering or page/sheet scheme consistency as per previously issued drawings/documents. Cable Testing Plan: The Communications Contractor shall provide a test plan for media testing as described in Section 3.4, c. (this specification) prior to beginning cable testing. The following minimal items shall be submitted for review: 1. All testing methods 2. Product data for test equipment 3. Certifications and qualifications of all persons conducting the testing 4. Calibration certificates indicating that equipment calibration meets National Institute of Standards and Technology (NIST) standards and has been calibrated at least once in the previous calendar year 5. Examples of test reports, including all graphs, tables, and charts necessary for display of test results. Cable Testing Reports: The Communications Contractor shall submit cable test reports as follows: 1. Submit certified test reports of Communications Contractor-performed tests in accordance with the Section 3.4 of this document. 2. The tests shall clearly demonstrate that the media and its components fully comply with the requirements specified herein. 3. Electronic and hardcopy versions of test reports shall be submitted together and clearly identified with cable identification. Record Drawings: Furnish "as built" CAD drawings of completed work including cable numbers, labeled in accordance with Section 1.1.2 within this document. Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Shop Drawings	270500 - Communications General 1.11I Product Data: Manufacturers' catalog data, installation procedures and instructions for handling and storage. Record Drawings: Furnish "as built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Testing	270500 - Communications General 1.11J Product Data: Manufacturers' catalog data, installation procedures and instructions for handling and storage. Record Drawings: Furnish "as built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Test Reports	270500 - Communications General 1.11K Product Data: Manufacturers' catalog data, installation procedures and instructions for handling and storage. Record Drawings: Furnish "as built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Record Drawings	270500 - Communications General 1.11L Product Data: Manufacturers' catalog data, installation procedures and instructions for handling and storage. Record Drawings: Furnish "as built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Qualifications Data	270528 - Grounding and Bonding for Communication Systems 1.3A Product Data: Manufacturers' catalog data, installation procedures and instructions for handling and storage. Record Drawings: Furnish "as built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Product Data	270528 - Grounding and Bonding for Communication Systems 1.3B Product Data: Manufacturers' catalog data, installation procedures and instructions for handling and storage. Record Drawings: Furnish "as built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Record Drawings	270528 - Grounding and Bonding for Communication Systems 1.3C Product Data: Manufacturers' catalog data, installation procedures and instructions for handling and storage. Record Drawings: Furnish "as built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Qualifications Data	270528 - Hangers and Supports for Communication Systems 1.3A Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Data	270528 - Hangers and Supports for Communication Systems 1.3B Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Record Drawings	270528 - Hangers and Supports for Communication Systems 1.3C Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Qualifications Data	270528 - 33 - Conduits and Pull Boxes for Communication Systems 1.3A Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Data	270528 - 33 - Conduits and Pull Boxes for Communication Systems 1.3B Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Record Drawings	270528 - 33 - Conduits and Pull Boxes for Communication Systems 1.3C Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Qualifications Data	270528 - 36 - Cable Tray for Communication Systems 1.3A Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Data	270528 - 36 - Cable Tray for Communication Systems 1.3B Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Record Drawings	270528 - 36 - Cable Tray for Communication Systems 1.3C Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Qualifications Data	271100 - Communications Equipment Room Fittings 1.3A Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Data	271100 - Communications Equipment Room Fittings 1.3B Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Equipment Layout Drawing	271100 - Communications Equipment Room Fittings 1.3C Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009
Record Drawings	271100 - Communications Equipment Room Fittings 1.3D Product Data: Manufacturers' data, including part numbers, cut sheets and detailed descriptions, for all proposed equipment. Record Drawings: Furnish "As-Built" CAD drawings of completed work Qualifications: Demonstrate compliance with requirements of Paragraph 1.4.A below.	5		10/30/2009	12/18/2009

**Exhibit K
Shop Drawing/Submital Schedule (Based on 6/1/09 NTP)**

Item	Item Description	Item Code	Start Date	Duration (Days)	End Date
Data	271300 - Communications Backbone Cabling and Terminations	1.3A	10/30/2009	5	12/18/2009
Data	271300 - Communications Backbone Cabling and Terminations	1.3B	10/30/2009	5	12/18/2009
Qualifications Data	271300 - Communications Backbone Cabling and Terminations	1.3C	10/30/2009	5	12/18/2009
Product Data	271300 - Communications Backbone Cabling and Terminations	1.3D	10/30/2009	5	12/18/2009
Testing	271300 - Communications Backbone Cabling and Terminations	1.3E	10/30/2009	5	12/18/2009
Testing	271300 - Communications Backbone Cabling and Terminations	1.3F	10/30/2009	5	12/18/2009
Data	271300 - Communications Backbone Cabling and Terminations	1.3G	10/30/2009	5	12/18/2009
Documentation	311000 - Site Clearing	1.5A		5	6/1/2009
Record Drawings	311000 - Site Clearing	1.5B		5	6/1/2009
Product Data	312000 - Earth Moving	1.5A		5	6/1/2009
Samples	312000 - Earth Moving	1.5B		5	6/1/2009
Qualifications Data	312000 - Earth Moving	1.5C		5	6/1/2009
Test Reports	312000 - Earth Moving	1.5D		5	6/1/2009

The Communications Contractor shall perform no portion of the work requiring submittal and review of record drawings, shop drawings, product data, or samples until the respective submittal has been approved by PG&L Technology Planning Group and the Engineer. Such work shall be in accordance with approved submittals.

Communications Contractor's BCSI Registered Communications Distribution Designer (RCDD) supervisor shall review, approve and stamp all documents prior to submitting.

Qualifications: The Communications Contractor shall submit qualification data sheets for firms and persons as specified in the "Quality Assurance" article of this specification to demonstrate their capabilities and experience.

Proposed product data sheets: The Communications Contractor shall submit catalogue cut-sheets that include manufacturer, trade name, and complete model number for each product specified. Model number shall be handwritten and/or highlighted to indicate exact selection. Identify applicable specification section reference for each product.

Cable Testing Plan: The Communications Contractor shall provide a test plan for media testing as described in the article "Field Quality Control" prior to beginning cable testing. The following minimal items shall be submitted for review:

- All testing methods
- Product data for test equipment
- Certifications and qualifications of all persons conducting the testing
- Calibration certificates indicating that equipment calibration meets National Institute of Standards and Technology (NIST) standards and has been calibrated at least once in the previous calendar year
- Examples of test reports, including all graphs, tables, and charts necessary for display of test results.

Cable Testing Reports: The Communications Contractor shall submit cable test reports as follows:

- Submit certified test reports of Communications Contractor-performed tests in accordance with the "Field Quality Control" article of this document.
- The tests shall clearly demonstrate that the media and its components fully comply with the requirements specified herein.
- Electronic and hardcopy versions of test reports shall be submitted together and clearly identified with cable identification.

Cable Inventory Data shall be submitted for all optical fiber and multi-pair copper cabling and termination equipment. Submit data electronically on CD-ROM in a format approved by Fort Bend County IT, listing products furnished, including:

- Manufacturer's name
- Manufacturer's part numbers
- Cable numbers
- Location and riser assignments
- Record Drawings: Furnish "as-built" CAD drawings of completed work including cable numbers, labeled in accordance with 3.3.F below.

Existing Conditions: Documentation of existing trees and plantings, adjoining construction, and site improvements that establishes preconstruction conditions that might be misconstrued as damage caused by site clearing.

- Use sufficiently detailed photographs or videotape
- Include plans and notations to indicate specific wounds and damage conditions of each tree or other plants designated to remain.

Record Drawings: Identifying and accurately showing locations of capped utilities and other subsurface structural, electrical, and mechanical conditions.

Product Data: For each type of the following manufactured products required:

- Geotextiles.
- Controlled low-strength material, including design mixture.
- Geofabric.
- Warning tapes.

Samples for Verification: For the following products, in sizes indicated below:

- Geotextile: 12 by 12 inches (300 by 300 mm).
- Warning Tape: 12 inches (300 mm) long, of each color.

Material Test Reports: For each [on-site] [and] [borrow] soil material proposed for fill and backfill as follows:

- Classification according to ASTM D 2487.
- Laboratory compaction curve according to [ASTM D 698].

Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)

Item	Description	Quantity	Unit	Start Date	End Date
Test Reports	312300 - Building Earthwork	5	14	7	6/1/2009
	1.5A				
	1.4A				
	1.4C				
Certificates	312500 - Lime Stabilized Subgrade	5	14	7	6/1/2009
	1.4A				
	1.4C				
	1.4D				
Tickets	312500 - Lime Stabilized Subgrade	5	14	7	6/1/2009
	1.4A				
	1.4C				
	1.4D				
Data	312500 - Lime Stabilized Subgrade	5	14	7	6/1/2009
	1.4A				
	1.4C				
	1.4D				
Product Data	313116 - Termite Control	5	14	7	7/2/2009
	1.3A				
	1.3B				
	1.3C				
Qualifications Data	313116 - Termite Control	5	14	7	7/2/2009
	1.3A				
	1.3B				
	1.3C				
Report	313116 - Termite Control	5	14	7	7/2/2009
	1.3A				
	1.3B				
	1.3C				
Warranty	313116 - Termite Control	5	14	7	7/2/2009
	1.3A				
	1.3B				
	1.3C				
Shop Drawings	315000 - Excavation Support and Protection	5	14	30	8/1/2009
	1.4A				
	1.4B				
	1.4C				
Design Data	315000 - Excavation Support and Protection	5	14	30	8/1/2009
	1.4A				
	1.4B				
	1.4C				
Record Drawings	315000 - Excavation Support and Protection	5	14	30	8/1/2009
	1.4A				
	1.4B				
	1.4C				
Concrete Mix Design	316324 - Driller and Underreamed Footings	5	14	7	7/2/2009
	1.9A				

Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)

Category	Item Description	Code	Start Date	Duration	End Date
Drilling Records	316324 - Drilled and Underreamed Footings	1.9B	6/6/2009	5	7/2/2009
Shop Drawings	316324 - Drilled and Underreamed Footings	1.9C	6/6/2009	5	7/2/2009
Product Data	316324 - Drilled and Underreamed Footings	1.9D	6/6/2009	5	7/2/2009
Qualifications Data	316324 - Drilled and Underreamed Footings	1.9E	6/6/2009	5	7/2/2009
Alternates	316324 - Drilled and Underreamed Footings	1.9F	6/6/2009	5	7/2/2009
Post Construction Survey	316324 - Drilled and Underreamed Footings	1.9G	6/6/2009	5	7/2/2009
Product Data	316329 - Drilled Concrete Piers and Shafts	1.4A	6/6/2009	5	7/2/2009

Drilling Records: The Drilling Contractor and the Owner's Geotechnical Engineer or other authorized inspector shall submit copies of the drilling record for each pier to the Architect/Engineer immediately after drilling. The reports shall indicate the name of the job, name of Drilling Contractor, and name of drilling superintendent. For each pier installed, the report shall indicate the following information:

1. Pier number and location
2. Pier shaft diameter
3. Pier underream diameter
4. Bottom elevation
5. Top elevation
6. Pier length
7. Theoretical volume of concrete in pier
8. Actual volume of concrete placed
9. Reinforcing steel size and depth actually placed
10. Drilling start and finish time
11. Concreting start and finish time
12. Variation from specified tolerances including surveyed location and plumbness
13. Construction method (dry method, or casing method)
14. Groundwater conditions (rate of water infiltration and depth of water in hole prior to concreting for dry piers; water elevation in hole for wet piers)
15. Elevation of top and bottom of any casing left in place
16. Description of temporary or permanent casing (including purpose, diameter, wall thickness and length)
17. Description and elevation of any obstructions encountered and whether removal was obtained
18. Description of pier bottom including amount and extent of loose material
19. Method of concrete placement
20. Any difficulties encountered in drilling or concreting operations
21. Any deviations from specifications.

Reports prepared by the Owner's Geotechnical Engineer or authorized inspector shall be compiled and signed by a licensed professional engineer in the state where the project is located. Reports prepared by the Drilling Contractor shall be compiled and signed by the drilling superintendent.

Shop Drawings:

1. Reinforcing Steel: Submit shop drawings for all drilled pier and pier cap reinforcing steel.
2. Installation Method: Submit detailed procedures of the installation method, including (where applicable) type and number of drilling rigs and equipment, casing size and length, casing removal method, drilling fluid type, dewatering method, concrete placement, and reinforcing steel securing and placement.

Product Data: Submit manufacturer's product data with application and installation instructions for proprietary materials and items.

Qualification Data:

1. Submit qualification data for firms and persons specified in the article entitled "Qualifications" to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
2. Submit Welding Procedure Specifications (WPS) in accordance with ANSIA WSD 1.1 for all welded joints in steel casing. Submit test reports showing successful passage of qualification tests for all non-qualified WPSs.
3. Provide certification that welders to be employed in work have satisfactorily passed A WS qualification tests as specified. If recertification of welders is required, recertification will be at Contractor's responsibility.

Alternates: The Drilling Contractor shall submit his bid based on the specifications as written without exceptions. He may submit bids for alternates to the specifications or modifications to the design, load test program, or installation specifications for consideration by the Owner's Representative and the Owner.

Post Construction Survey: After completion of pier placement, the Contractor shall provide the Owner's Representative with an as-built survey showing the actual locations of the piers at the top elevations. This survey shall show the plumbness of vertical piers, and all abandoned piers and their replacements. No construction of superstructures shall commence until this survey has been reviewed and accepted by the Owner's Representative. In order to facilitate the progress of the Work, the Contractor shall submit partial pier surveys for approval as the Work proceeds.

Product Data: For each type of product indicated.

Exhibit K
Shop Drawing/Submittal Schedule (Based on 6/1/09 NTP)

Item	Description	Quantity	Start Date	End Date	Notes
Design Mixtures	316329 - Drilled Concrete Piers and Shafts	5	6/6/2009	7/2/2009	Design Mixtures: For each concrete mixture. Submit alternate design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.
Shop Drawings	316329 - Drilled Concrete Piers and Shafts	5	6/6/2009	7/2/2009	1. Indicate amounts of mixing water to be withheld for later addition at Project site. Shop Drawings: For concrete reinforcement detailing fabricating, bending, supporting, and placing.
Qualifications Data	316329 - Drilled Concrete Piers and Shafts	5	6/6/2009	7/2/2009	Qualification Data: For qualified land surveyor.
Certificates	316329 - Drilled Concrete Piers and Shafts	5	6/6/2009	7/2/2009	Material Certificates: For the following, from manufacturer: 1. Steel reinforcement and accessories.
Product Data	321313 - Concrete Paving	5	7/16/2009	8/18/2009	Product Data: For each type of manufactured material and product indicated.
Design Mixtures	321313 - Concrete Paving	5	7/16/2009	8/18/2009	Design Mixtures: See Section 033000, Cast-In-Place Concrete.
Samples	321313 - Concrete Paving	5	7/16/2009	8/18/2009	Samples: 10-lb (4.5-kg) sample of exposed aggregate.
Qualifications Data	321313 - Concrete Paving	5	7/16/2009	8/18/2009	Qualification Data: For testing agency Material Test Reports: From a qualified testing agency indicating and interpreting test results for compliance of the following with requirements indicated, based on comprehensive testing of current materials: 1. Aggregates. Include service record data indicating absence of deleterious expansion of concrete due to alkali-aggregate reactivity. Material Certificates: Signed by manufacturer's certifying that each of the following materials complies with requirements: 1. Cementitious materials. 2. Steel reinforcement and reinforcement accessories. 3. Fiber reinforcement. 4. Admixtures. 5. Curing compounds. 6. Applied finish materials. 7. Bonding agent or epoxy adhesive. 8. Joint fillers.
Test Reports	321313 - Concrete Paving	5	7/16/2009	8/18/2009	1. Aggregates. Include service record data indicating absence of deleterious expansion of concrete due to alkali-aggregate reactivity. Material Certificates: Signed by manufacturer's certifying that each of the following materials complies with requirements: 1. Cementitious materials. 2. Steel reinforcement and reinforcement accessories. 3. Fiber reinforcement. 4. Admixtures. 5. Curing compounds. 6. Applied finish materials. 7. Bonding agent or epoxy adhesive. 8. Joint fillers.
Certificates	321313 - Concrete Paving	5	7/16/2009	8/18/2009	1. Cementitious materials. 2. Steel reinforcement and reinforcement accessories. 3. Fiber reinforcement. 4. Admixtures. 5. Curing compounds. 6. Applied finish materials. 7. Bonding agent or epoxy adhesive. 8. Joint fillers.
Test Reports	321373 - Concrete Paving Joint Sealants	5	7/16/2009	8/18/2009	Product Data: For each joint-sealant product indicated. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2-inch(13-mm-) wide joints formed between two 6-inch(150-mm-)long strips of material matching the appearance of exposed surfaces adjacent to joint sealants. Paving Joint Sealant Schedule: Include the following information: 1. Joint-sealant application, joint location, and designation. 2. Joint-sealant manufacturer and product name. 3. Joint-sealant formulation. 4. Joint sealant color.
Schedule	321373 - Concrete Paving Joint Sealants	5	7/16/2009	8/18/2009	Product Data: For each joint-sealant product indicated. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2-inch(13-mm-) wide joints formed between two 6-inch(150-mm-)long strips of material matching the appearance of exposed surfaces adjacent to joint sealants. Paving Joint Sealant Schedule: Include the following information: 1. Joint-sealant application, joint location, and designation. 2. Joint-sealant manufacturer and product name. 3. Joint-sealant formulation. 4. Joint sealant color.
Qualifications Data	321373 - Concrete Paving Joint Sealants	5	7/16/2009	8/18/2009	Product Data: For each joint-sealant product indicated. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2-inch(13-mm-) wide joints formed between two 6-inch(150-mm-)long strips of material matching the appearance of exposed surfaces adjacent to joint sealants. Paving Joint Sealant Schedule: Include the following information: 1. Joint-sealant application, joint location, and designation. 2. Joint-sealant manufacturer and product name. 3. Joint-sealant formulation. 4. Joint sealant color.
Certificates	321373 - Concrete Paving Joint Sealants	5	7/16/2009	8/18/2009	Product Data: For each joint-sealant product indicated. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2-inch(13-mm-) wide joints formed between two 6-inch(150-mm-)long strips of material matching the appearance of exposed surfaces adjacent to joint sealants. Paving Joint Sealant Schedule: Include the following information: 1. Joint-sealant application, joint location, and designation. 2. Joint-sealant manufacturer and product name. 3. Joint-sealant formulation. 4. Joint sealant color.
Test Reports	321373 - Concrete Paving Joint Sealants	5	7/16/2009	8/18/2009	Product Data: For each joint-sealant product indicated. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2-inch(13-mm-) wide joints formed between two 6-inch(150-mm-)long strips of material matching the appearance of exposed surfaces adjacent to joint sealants. Paving Joint Sealant Schedule: Include the following information: 1. Joint-sealant application, joint location, and designation. 2. Joint-sealant manufacturer and product name. 3. Joint-sealant formulation. 4. Joint sealant color.
Test Reports	321373 - Concrete Paving Joint Sealants	5	7/16/2009	8/18/2009	Product Data: For each joint-sealant product indicated. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2-inch(13-mm-) wide joints formed between two 6-inch(150-mm-)long strips of material matching the appearance of exposed surfaces adjacent to joint sealants. Paving Joint Sealant Schedule: Include the following information: 1. Joint-sealant application, joint location, and designation. 2. Joint-sealant manufacturer and product name. 3. Joint-sealant formulation. 4. Joint sealant color.
Certificates	321913 - Soil Preparation	5	5/16/2010	6/18/2010	1. Materials forming joint substrates and joint-sealant backings have been tested for compatibility with and adhesion to joint sealants. 2. Interpretation of test results and written recommendations for primers and substrate preparation needed for adhesion. Certificates: 1. Submit certification of fertilizer analysis. 2. Delivery tickets of soil amendments. Manufacturer's Product Literature, as applicable Samples 1. 1 gallon sample of Topsoil. 2. 1 gallon sample of Compost. 3. 1 gallon sample of Prepared Soil Mix.
Product Data	321913 - Soil Preparation	5	5/16/2010	6/18/2010	1. Materials forming joint substrates and joint-sealant backings have been tested for compatibility with and adhesion to joint sealants. 2. Interpretation of test results and written recommendations for primers and substrate preparation needed for adhesion. Certificates: 1. Submit certification of fertilizer analysis. 2. Delivery tickets of soil amendments. Manufacturer's Product Literature, as applicable Samples 1. 1 gallon sample of Topsoil. 2. 1 gallon sample of Compost. 3. 1 gallon sample of Prepared Soil Mix.
Samples	321913 - Soil Preparation	5	5/16/2010	6/18/2010	1. Materials forming joint substrates and joint-sealant backings have been tested for compatibility with and adhesion to joint sealants. 2. Interpretation of test results and written recommendations for primers and substrate preparation needed for adhesion. Certificates: 1. Submit certification of fertilizer analysis. 2. Delivery tickets of soil amendments. Manufacturer's Product Literature, as applicable Samples 1. 1 gallon sample of Topsoil. 2. 1 gallon sample of Compost. 3. 1 gallon sample of Prepared Soil Mix.
Literature	328400 - Landscape Irrigation System	5	5/31/2010	8/18/2010	Using hard cover 3 ring notebooks, provide not less than three (3) copies of complete brochures describing equipment and materials, including names of manufacturer's catalog numbers, trade names, instructions for setting, connecting and operation, technical data and any special information requested. Unless resubmission is required, two will be retained and one returned after being reviewed. If resubmission is required, one corrected copy and one original copy will be returned after being reviewed. If resubmission is required, one corrected copy and one original copy will be returned and one will be retained. One approved copy shall be in the file of the Contractor's representative at the project site.

Exhibit L

**Architect's Concurrence with the Design Completion Schedule, Shop Drawing
Schedule and Component Schedule**

To be Provided by PGAL

May 26, 2009

Mr. Don Brady
Director, Facilities Management and Planning
Fort Bend County
1402 Band Road, Suite 100
Rosenberg, Texas 77471

Re: Fort Bend County Justice Center

Dear Don,

We are in receipt of the Final GMP Proposal, dated May 26, 2009 from J. E. Dunn. After review of Exhibits G and K (the Design Completion Schedule and Shop Drawing/Submittal Schedule) contained in the proposal, we are in concurrence with those documents.

Thank you,



David L. Andrews, AIA
Principal
PGAL

RFI Log - GMP (Permit Set)



**PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009**

	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
1	S2.01A	1/12/2009	1/26/2009	Yes, refer to S2.00A. Bearing elevation of this bell will be revised to 54.0'. Bearing elevation of bell at 05 will be revised to 60'-0". Bearing elevation of footing at 06 will be 67'-6". Shaft diameter at 04 and 05 will be revised to 60" (60/168). See revised drawing. (WPMA)
2	S2.01A	1/12/2009	1/26/2009	Yes, refer to S2.00A. Bearing elevation of this bell will be revised to 51.0'. Bearing elevation of bell at 05 will be revised to 57'-0". Shaft diameter at 04 and 05 and 05/G will be revised to 60" (60/168). Foundation at 06 will be revised to a 66/186 underream pier with a bearing elevation of 61'-6". Footings at 7.2 will be a F13x9. Footings at H2-8.2 and H6-8.2 will be F7. See revised drawing. (WPMA)
3	S2.01 and S4.04	1/12/2009	1/12/2009	Delete note that says "8" thick pit walls with 10" thick pit slab typ"
4	Soils Report Section 5.1 and Spec Section 312300	1/16/2009	1/20/2009	Referenced section from Geotechnical Report refers to foundations. Referenced section from specifications relates to slabs-on-grade. Geotechnical engineer on site will verify if the existing material could be used as select fill. (WPMA)
5	C2.10 and C3.10	1/16/2009	1/22/2009	Parking Lot curb to be constructed per C3.26-7. Sheet C3.10, Detail 10 will be eliminated. (PGAL)
6	L Drawings	1/16/2009	1/20/2009	Price irrigation in the R. O. W. as part of the alternate. (PGAL)
7		1/16/2009	1/22/2009	See sheet P5.01, detail 1. (PGAL)

RFI Log - GMP (Permit Set)



**PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009**

	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
8	C2.50, C3.25, and Spec Section 334100	1/16/2009	1/22/2009	Storm manholes and inlets may be precast or brick per note on sheet C3.25 (PGAL)
9	Spec Section	1/16/2009		
10	A0.200, A2.01, A2.01A, and A2.01B	1/16/2009	1/20/2009	Terrazzo flooring terminates at the North edge of the columns along Gridline 6. (PGAL)
11	1/A4.02 and 4/A8.00	1/16/2009	1/20/2009	Terminate stone aligned with the nosing of the bottom stair tread. If referencing enlarged plan 7/A4.02, stone to be on South wall only, extending from the right corner to the nosing of the stair tread on the left. Remainder of South wall to be painted. (PGAL)
12	C2.50	1/16/2009	1/22/2009	All proposed storm sewer inlets and drain lines located within the limits of the parking lot north of the Ring Road are included in Alt. 4. The proposed connecting lateral within the Ring Road ROW is by Others. (PGAL)
13	A6.02	1/16/2009	1/20/2009	Confirmed. Portland cement plaster over CMU w/ elastomeric coating. (PGAL)

RFI Log - GMP (Permit Set)



**PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009**

	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
14	D2.00A - D2.03 Please clarify.	1/16/2009	1/26/2009	Price these doors as follows: Door 80 - price to match Door 78A Door 174A - price to match Door 96A Door 175 - does not exist - omit Door 220A - on the detention door schedule Door 248A - price to match Door 96A Door 10452 - price to match Door 20466 Door 10464 - price to match Door 10462 Door 20524 - price to match Door 20526 Doors 30178 & 30224 - price to match Door 30180 (PGAL) Price a door here per response to RFI 14. (PGAL)
15	On page D2.00A no entrance door is given from corridor 00004 to corridor 00080. Please clarify	1/16/2009	1/26/2009	See revised Sheet A4.03. (PGAL)
16	Single restrooms and Mens rm 10112 indicate there is an enlarged floor plan on A4.03, but there is no enlarged floor plan for those rooms on that page. Please clarify.	1/16/2009	1/20/2009	B1 wood base in both. (PGAL)
17	Sheet A0.20, finish schedule, calls for room 10402 & 10408 to have B2, base, which is rubber base. Is that correct?	1/16/2009	1/20/2009	B1 wood base in all. (PGAL)
18	Sheet A0.22, finish schedule, calls for no base in rooms 30106, 30140, 30156, 30188, 30202, 30234, 30250, & 30284. Is that correct?	1/16/2009	1/20/2009	Correct. This will be revised for future drawing issuances. (PGAL)
19	Sheet A0.22, finish schedule, has a room 30238, Prep. The plan on sheet A2.03A has this as room 30753. This should be changed. This also occurs on room 30752, Storage, on sheet A2.03A, and room 30236, on sheet A0.22.	1/16/2009	1/20/2009	B1 wood base in both. (PGAL)
20	Sheet A0.20, finish schedule, calls for base in rooms 10004 and 10006. Interior elevations 1, 2, & 3 on A8.02 calls for wood base in room 10006. Which is correct? If there is wood base in 10006, does it occur in 1002? This also shows the same on the 2nd and 3rd floors.	1/16/2009	1/20/2009	See revised Sheet A4.03. (PGAL)
21	Sheet A2.00B shows a blowup 19/A4.03 for the lockers, rooms 00028 and 00030. That detail plan is room 00208, male cell. Please advise.	1/16/2009	1/20/2009	B1 wood base in both. (PGAL)
22	Sheet A0.22, finish schedule, has rooms 10100 and 10196 with base B2, rubber base. Sheet A8.01, however shows wood base. Please advise which is correct?	1/16/2009	1/20/2009	Provide painted galvanized railing. (PGAL)
23	On drawing page A7.59, on detail 1 on the second level it states that the handrail and picket rails are to be painted galvanized, whereas on detail 31 it states for the handrail and picket rails to be aluminum. Please clarify.	1/16/2009	1/20/2009	

RFI Log - GMP (Permit Set)



PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009

	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
24	A1.03 and A1.05	1/16/2009	1/20/2009	Provide stainless steel railings. (PGAL)
25	Signage and Graphics	1/16/2009	1/20/2009	See updated signage program, dated 1.5.09 (PGAL)
26	Spec Section 086200	1/16/2009	1/26/2009	Provide segmented barrel vault skylights. (PGAL)
27	A4.01 and A7.78	1/16/2009	1/20/2009	Structural drawings are correct. (PGAL)
28	A4.04	1/16/2009	1/26/2009	This is a means and methods question which we cannot answer. (PGAL)
29	A5.00	1/16/2009	1/20/2009	Structural drawings are correct. (PGAL)
30	A8.05 and A2.02B	1/16/2009	1/20/2009	Elevation 17 is in Room 20236, Elevation 18 is in Locker/Break 00124. (PGAL)

RFI Log - GMP (Permit Set)

PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009



	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
31	A8.11	1/16/2009	1/22/2009	The enclosures around x-ray machines and magnetometers, as well as the half wall and gate, are part of the project, and are to be transparent finish millwork. Provide stone cap. (PGAL)
32	A8.01	1/16/2009	1/20/2009	Areas not shaded as acoustical fabric wrapped panels are to be full height wood veneer panels. (PGAL)
33	Spec Section 064100	1/16/2009	1/20/2009	Price per specifications. Cost savings may be presented as a voluntary alternate. (PGAL)
34	Spec Sections 142100 and 142423	1/16/2009	1/20/2009	Yes. (PGAL)
35	Spec Sections 142100	1/16/2009	1/22/2009	Match finishes of Elevators #3, 6 & 7. (PGAL)
36	A2.04B and Spec Section 142100	1/16/2009	1/20/2009	Confirmed. There is a stop at the roof level for Elevator #4.
37	Spec Section 050510	1/16/2009	1/26/2009	Include corridors 00012 & 00104, Elevators 3, 5, 6 & 7 and their associated lobbies, including Future Elevator Lobby 00024. Do not include courtrooms. (PGAL)
38		1/16/2009	1/26/2009	Reflected Ceiling Plan should govern. (PGAL)
39	Spec 178120 and 078160	1/16/2009	1/26/2009	Price intumescent fireproofing on roof screen steel structure. (PGAL)

RFI Log - GMP (Permit Set)

PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009



	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
40		1/16/2009	1/26/2009	Provide International Cellulose K-13 spray insulation. 3" in pans, 1" on joists. (PGAL)
41	Spec 033000	1/16/2009	1/26/2009	Yes, 8S4.10 (WPMA)
42	Spec 033000	1/16/2009	1/20/2009	Typically no, only needed in exposed cases. (WPMA)
43		1/16/2009	1/26/2009	Provide split system same as shown on 3/M3.01. (Jacobs)
44		1/16/2009	1/26/2009	No security plan needed for Central Plant. Telecom required for elevator in parking garage. Re: E1.00, keyed note 4 for site telecommunications, and E3.02, keyed note 11 for telecommunications in tunnel. (PGAL)
45		1/16/2009	1/20/2009	Pricing should be based on specified container size. (Knudson)
46	A0.02	1/22/2009	1/26/2009	Garage fire sprinkler system will be changed to a dry pipe system (Jacobs)
47	SG4.01 and SG2.01	1/22/2009	1/26/2009	#3@12" EW (WPMA)
48	A8.01	1/22/2009	1/26/2009	See attached sketches SK-0001 & 0002 for flush panel wall sections at jury assembly and typical corridor wainscot. Note that the intent is direct glue fabric wallcovering in the corridors, not acoustical. The paneling is to be plain sawn cherry, book matched. (PGAL)
49	A8.01 and A8.53	1/22/2009	1/26/2009	See attached SK-002. (PGAL)

RFI Log - GMP (Permit Set)



PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009

	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
50	A2.03B	1/22/2009	1/26/2009	Yes, this is millwork. Lower cabinets with plastic laminate finish per detail 31/A8.50. (PGAL)
51	Spec Section 124910	1/22/2009	1/26/2009	Provide for all exterior windows with exception of those at main lobby / dome. (PGAL)
52	A2.00A and A0.33	1/22/2009	1/26/2009	Refer to detention drawings for these windows. (PGAL)
53		1/22/2009	1/26/2009	See attached spec section 11 19 50 - Security Glazing. (PGAL)
54	SG2.01 and SG4.01	1/22/2009	1/26/2009	Refer to attached mark-ups on plan sheets. (WPMA)
55		1/22/2009	1/26/2009	The (+) or (-) is relative to the reference floor elevation. Level 1 reference elevation is 83.55'. The height between the levels is shown on each plan sheet. Refer to attached mark-ups on plan sheets. (WPMA)
56	SG4.01	1/22/2009	1/26/2009	Revise reference to detail 8A (WPMA)
57		1/22/2009	1/26/2009	On column line 3, refer to detail 8/SG4.01. On column line 2, refer to detail 8ASG4.01. (WPMA)
58	AG6.00	1/22/2009	1/26/2009	Refer to structural drawings and response to RFI 57. (PGAL)
59	SG4.01	1/22/2009	1/26/2009	9/SG4.01 has a 2'-0" turnaround. The foundations are spread footings, not piers. (WPMA)
60		1/22/2009	1/26/2009	Revise references to 9/SG4.01 and 10/SG4.01 (at precast). (WPMA)

RFI Log - GMP (Permit Set)

PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009



	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
61	A0.20, A8.11 and A0.23	1/22/2009	1/26/2009	Walls are all glass with painted gyp. bd. above. Details on A8.11 are for security desk only. (PGAL)
62		1/22/2009	1/26/2009	See 18/A8.05. (PGAL)
63	Spec 064100	1/22/2009	1/26/2009	Provide aluminum, as detailed. (PGAL)
64	S1.00	1/22/2009	1/26/2009	The 5000 psi concrete listed for columns and floor systems on S1.00 applies to the garage also. (WPMA)
65		1/22/2009	1/28/2009	See attached specification section. (Jacobs)
66	E Drawings	1/22/2009	1/26/2009	Use quantities shown on electrical drawings. (Jacobs)
67	E Drawings	1/22/2009	1/26/2009	Provide power poles. (Jacobs)
68	T4.01	1/22/2009	1/26/2009	The "typical" floor box shown on T4.01 telecommunication drawings is for reference and coordination. The actual floor boxes or poke-thru assemblies are identified in the Div 16 electrical specifications and drawings. (PGAL)
69	T Drawings	1/22/2009	1/26/2009	The required cable tray should be of aluminum construction. (PGAL)

RFI Log - GMP (Permit Set)

PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009



	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
70	T Drawings	1/22/2009	1/26/2009	Provide pricing for alternate per layout on Sheet T2.03A. (PGAL)
71	M Drawings	1/22/2009	1/26/2009	Provide high exposure TVSS units. (Jacobs)
72	M Drawings	1/22/2009	1/26/2009	No fire alarm, detection or heat. Ventilation only and dry pipe sprinkler system. (Jacobs)
73	M Drawings	1/22/2009	1/26/2009	The secured vehicle storage will have a ventilation system to maintain CO level. (Jacobs)
74	M Drawings	1/22/2009	1/26/2009	Any duct 8/8 and larger thru the security boundary needs to have security bars. (Jacobs)
75	M Drawings	1/22/2009	1/26/2009	No smoke exhaust for court holding. (Jacobs)
76	M Drawings	1/22/2009	1/26/2009	Storage rooms do not require exhaust air. (Jacobs)
77	M Drawings	1/22/2009	1/26/2009	All VAV terminal units have heat. (Jacobs)
78	M Drawings	1/22/2009	1/26/2009	No conditioned air in 2-hour rated stairwells. (Jacobs)
79	M5.01	1/22/2009	1/26/2009	No. General Contractor is free to assign this responsibility to any sub-contractor. (Jacobs)
80	M Drawings	1/22/2009	1/28/2009	Building pressure relief dampers are shown on drawings M2.04A and M2.04B. (Jacobs)
81	E Drawings	1/22/2009	1/26/2009	Utility transformers will be provided by CenterPoint. (Jacobs)
82	E Drawings	1/22/2009	1/26/2009	No additional lighting is required. (Jacobs)
83	A8.10	1/22/2009	1/26/2009	Provide transparent finish wood veneer millwork. (PGAL)
84		1/22/2009	1/26/2009	Square edge, with butted joints. Ease edge of wood millwork. (PGAL)

RFI Log - GMP (Permit Set)

PROJECT: FT. BEND COUNTY COURTHOUSE

UPDATED: 2/12/2009



	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
85		1/22/2009	1/26/2009	This refers to door types D-10 thru D-13. The wood trim around the door frames should be provided as indicated in Details 5, 6, 10 & 11 on A0.34. (PGAL)
86	A0.20, A0.23, A8.01	1/22/2009	1/26/2009	Elevations are correct. Shaded areas are acoustical fabric stretched panels. See also RFI #32 response. (PGAL)
87		1/22/2009	1/26/2009	See section 13851. (Jacobs)
88	Spec 081416	1/22/2009	1/26/2009	Provide plain sliced cherry. (PGAL)
89	Spec 081416	1/22/2009	1/26/2009	Wilsonart 10738-07 Cherry. (PGAL)
90	EP2.01A	1/22/2009	1/26/2009	Main Tele/Data/Security room is to have 100 amp busway. All other IDF rooms to have 60 amp busway. (Jacobs)
91	ES3.01	1/22/2009	1/26/2009	That circuit is no longer required, as the UPS will be provided by Division 16000. (Latta)
92	T3.01.1	1/22/2009	1/26/2009	Detail 2 corresponds to Rooms 10620, 20996, 30712 Detail 3 and 5 correspond to Room 10200. Detail 6 corresponds to Rooms 10096, 20328, 30208 Detail 7 corresponds to Rooms 10232, 20600, 30348 (PGAL)

RFI Log - GMP (Permit Set)



**PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009**

	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
93	T3.01.1 and T5.01 Drawing T3.01.1, Detail 5 Server Room 207 Cabinet Elevation - Indicates one 24 port Cat6 Patch Panel in Cabinet #1, #2, and #3 and 24 Cat6 cable to rack 3, which rack 3? Drawing T5.01 Communications Single Line & Riser Diagrams do not indicate any Cat6 cables to be installed from the Server room 10200. Please advise.	1/22/2009	1/26/2009	The 24 port panel should originate from Rack 3, shown in Detail 3. Twenty (24) Category 6 cables should run from each Cabinet to Rack 3. Sheet T5.01, Detail 2 indicates Category 6 distribution cabling to the work area outlets on the Lower Level. (PGAL)
94	Are details 6 and 7 on drawing T3.01.1 the same room? Is it your intention to have anything other than 100 pair Cat3 copper and 12SM/12MM Fiber cables leaving MER room 10200 going to TR rooms 10620, 10232, 10096, 20996, 20600, 20328, 30712, 30348 and 30208, these are the only cables shown on drawing T5.01 to leave the MER?	1/22/2009	1/26/2009	No. See response to Line Item 92. (PGAL) That is correct. (PGAL)
95	Drawing T3.01.1 details 2, 3, 6, and 7 calls for 10" and 6" vertical managers, the specifications 271100-6 Communications Equipment Room Fittings, Part 2 Products, 2.2 Materials, B Cable Management, calls for Vertical Cable management to be Chatsworth 11729-703 which is 6" wide. Please advise.	1/22/2009	1/26/2009	Specs should indicate Chatsworth 30165-703 for 6" vertical managers and 30166-703 for 10" vertical managers. (PGAL)
96	T3.01.1	1/22/2009	1/26/2009	Some elevators do not currently stop on all floors due to clerks or dist. atty. spaces. Provisions should be made so that elevators can make stops on all floors if needed in the future. (PGAL)
97	Regarding elevators - the drawings show 3 levels with 3 openings. The specifications call for 2 levels. Please clarify.	1/22/2009	1/26/2009	This is in regard to wheelchair lifts in the courtrooms. We have successfully installed lifts of the size shown in previous projects, which have been accepted by the TDLR. While they have not been officially approved for this project, we anticipate that they will. (PGAL)
98	Regarding elevators - specifications and drawings indicate platform lengths that are too short. TAS requires a 60" length for 90 degree platforms. Please clarify.	1/22/2009	1/26/2009	As specified. (PGAL)
99	Are the landing gates supplies by the Elevator Contractor, as specified, or by millwrights as shown on the plans. Please advise.	1/22/2009	1/26/2009	We have not addressed this with the TDLR for this project, but assume that they will waive this requirement. (PGAL)
100	Power door operators are required by TDL&R on 90 degree lift, however they were waived on the Harris County Courthouse. Will they be waived on this project also?	1/22/2009	1/26/2009	Elevators 3, 5, 6 & 7 to be controlled by the security console in the lower level control room. Elevator 8 to be controlled by the security system in the jail. (PGAL)
101	Regarding elevators - Are there any special keying requirements?	1/22/2009	1/26/2009	

RFI Log - GMP (Permit Set)



PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009

	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
102	L4.00	1/22/2009	1/26/2009	All landscape beds to have steel edge except when adjacent to paving (Knudson)
103	S3.07	1/22/2009	1/26/2009	Typically yes. There are a few locations noted on plan that must keep shoring in place until the pour strip is complete. (WPMA)
104		1/22/2009	1/26/2009	Light sandblast finish. (PGAL)
105		1/22/2009	1/26/2009	Set screw fittings are preferred. (Jacobs)
106	Signage and Graphics	1/22/2009	1/26/2009	Refer to GMP issue dated 1.5.09 for drawings 29, 30 & 35. See attached for Drawings 31 thru 34. (The Douglas Group)
107	Signage and Graphics	1/22/2009	1/26/2009	Refer to GMP issue CD package dated 1.5.09. (The Douglas Group)
108	Signage and Graphics	1/22/2009	1/26/2009	The message schedule that should be used is dated 1.5.09. (The Douglas Group)
109	Signage and Graphics	1/22/2009	1/26/2009	Sign counts are located on the message schedule dated 1.5.09. (The Douglas Group)
110		1/22/2009	1/26/2009	Provide products from the same line and/or quality level to those specified. (PGAL)

RFI Log - GMP (Permit Set)

PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009



	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
111		1/22/2009	1/26/2009	Refer to detention drawings for toilet accessories in cells. Detention toilet tissue dispenser is part of the plumbing fixture. (PGAL)
112		1/22/2009	1/26/2009	Elevations for main public restrooms are correct. (PGAL)
113	A4.03	1/22/2009	1/26/2009	Provide multiple fixtures if shown in plan and not labeled. Sanitary napkin dispensers are labeled as TA-13. (PGAL)
114	A0.23	1/22/2009	1/26/2009	There is no C5 in the project. (PGAL)
115		1/22/2009	1/26/2009	Bid Cirrus #574 where 2x2 ceiling is shown. At 2x4 ceiling, bid Armstrong Cirrus #533. (PGAL)
116		1/22/2009	1/26/2009	Sec. Conf. to have security ceilings. Atty. Conf. to have 2 x 2 lay-in ceilings. See also detention drawings for security ceiling locations. (PGAL)
117		1/22/2009	1/26/2009	No - provide exposed ceilings. (PGAL)

RFI Log - GMP (Permit Set)



**PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009**

	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
118		1/22/2009	1/26/2009	Follow the ceiling plans. For Alternate #1, provide ceilings shown in the same areas as shown on A3.03A. (PGAL)
119	A0.23	1/22/2009	1/26/2009	Correct. (PGAL)
120		1/22/2009	1/26/2009	Not wall panels in the lobby and corridors - direct glue fabric. Include columns. (PGAL)
121	A8.53	1/22/2009	1/26/2009	1 1/2" acoustic wall panels. High impact should be used to 6' height above the floor, min. (PGAL)
122		1/22/2009	1/26/2009	Security wall panels. (PGAL)
123	A7.55	1/22/2009	1/26/2009	This should be chain link, and occurs in Stair No. 1 & 4. Provide manufacturer standard hinges and panic hardware. (PGAL)
124	S2.02C and S4.13	1/22/2009	1/26/2009	Revise reference to 14/S4.03. (WPMA)
125	A0.23	1/22/2009	1/26/2009	Quartz composite should be S2. (PGAL)
126	A0.35	1/22/2009	1/26/2009	Not used. (PGAL)

RFI Log - GMP (Permit Set)



**PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009**

	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
127	Spec 064100	1/22/2009	1/26/2009	Provide plain sawn cherry throughout. (PGAL)
128		1/22/2009	1/26/2009	Plain sawn. (PGAL)
129	A8.52	1/22/2009	1/26/2009	Plain sawn cherry. (PGAL)
130		1/22/2009	1/26/2009	S1, 1/2" thickness with rounded edge. (PGAL)
131	A8.00	1/22/2009	1/26/2009	Stone W20. See also response to RFI #11. (PGAL)
132	A7.59	1/22/2009	1/26/2009	Plain sliced cherry to match the other millwork in the building. (PGAL)
133	A8.05	1/22/2009	1/26/2009	2" x 4 1/2" aluminum frame. (PGAL)
134		1/22/2009	1/26/2009	Refer to 1/S3.02 for under-slab moisture retarder. (WPMA)
135		1/22/2009	1/26/2009	Provide below grade waterproofing. (PGAL)
136	A0.35	1/22/2009	1/26/2009	Self adhered wall flashing is intended at these locations. (PGAL)
137		1/22/2009	1/26/2009	Provide self adhered. (PGAL)
138	A7.75, A7.76, A7.77, A7.78	1/22/2009	1/26/2009	Provide Rubberized-asphalt flashing in lieu of metal per spec section 042000. (PGAL)
139	A7.77	1/22/2009	1/26/2009	This is a standard detail that can be used if termination bars are required, and is not referenced by specific details. Provide standard warrantable details per the roofing manufacturer selected for this project. (PGAL)

RFI Log - GMP (Permit Set)



**PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009**

	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
140	A7.90 Sheet A7.90 shows details for CETCO's Voltex DS, which is a bentonite waterproofing, to be installed at the below grade locations. Spec Section 071300 - Below Grade Waterproofing is written around WR Grace's Preprufe and Procor products. Which product are we to price for the below grade waterproofing at the basement walls and the tunnel? If bentonite is acceptable can you provide a specification and allow Tremco's Paraseal LG and CCW Carlisle's Miraclay to be included in the specification as approved alternates?	1/22/2009	1/26/2009	Provide bentonite waterproofing for these areas. Other manufacturers' equal products will be evaluated after the proposal. (PGAL)
141	Where is Spec Section 071311 - Self-Adhered Sheet Waterproofing to be installed?	1/22/2009	1/26/2009	At window and door heads, jambs & sills, and over thruwall flashing. (PGAL)
142	Is Spec 071300 only to be used at elevator pits?	1/22/2009	1/26/2009	Yes. (PGAL)
143	Can you provide a specification for the Traffic Coating that is called out on the top level of the parking garage?	1/22/2009	1/28/2009	Provide Kelmar FWC III by Technical Barrier Systems, Inc., or approved equal. (PGAL/WPMA)
144	Which waterproof membrane are we to provide at the planters per sheet A1.03?	1/22/2009	1/26/2009	Grace Procor or equal. Also to be used on vertical walls of planters. (PGAL)
145	Does all exterior exposed masonry receive a water repellent?	1/22/2009	1/26/2009	Yes. (PGAL)
146	Are we to caulk every joint in the cast stone veneer or just the control joints?	1/22/2009	1/26/2009	Caulk at control joints only. (PGAL)
147	Spec Section - 071900 - Water Repellents specifies White Roc 10 by Sonneborn. This product is no longer manufactured and is not available. Will Enviroseal 40 VOC by Hydrozo be an acceptable alternate?	1/22/2009	1/26/2009	Yes. (PGAL)
148	The cabinets shown in the MER - three are shown as server cabinets, and four are shown to be for security. Should the telecommunications contractor provide any/all of these cabinets? If yes, size, or C/P part number?	2/10/2009	2/12/2009	The security cabinets will be provided and installed by the security contractor. The server cabinets will be provided by and installed by the communications contractor. Note: An allowance of \$15,000 should be carried for these cabinets subject to specification. (PGAL)
149	24 port patch panels are shown in the server cabinets - Please reference Drawing T3.01.1 - detail 5. It is unclear if this detail is describing a total of (3) 24 port patch panels, or (6). Please clarify. This detail also states that 24 cat 6 cables shall run from each server cabinet to rack number three in the MER. Please confirm this is correct.	2/10/2009	2/12/2009	From each Server Cabinet, twenty-four (24) Category 6 cables run (originate) and terminate in Rack 3 denoted in Detail 3. At each Cabinet and Rack 3, the cables will be terminated to 24-port Category 6 patch panels. (PGAL)

RFI Log - GMP (Permit Set)

**PROJECT: FT. BEND COUNTY COURTHOUSE
 UPDATED: 2/12/2009**



	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
150	Should poke thru's (Wiremold RC3A shown on Drawing T4-01, detail 14) be provided by telecommunications contractor, or electrical? Same question for floor boxes (Detail 16). What differentiates the use of a poke thru from a floor box? Assume to be shown on E drawings.	2/10/2009	2/12/2009	All floor boxes or poke-thru assemblies will be provided and installed by the electrical contractor. Reference E-drawings and legend sheet for specific details of these devices that will support the communication cabling and terminations. Boxes and poke through devices shown on T drawings are for reference only, for the cabling contractor, of typical types of termination conditions. (PGAL)
151	Please identify recommended cable pathway for backbone cables feeding from MER to TR's in area A of each floor (1 through 3). There does not look to be any vert. riser directly above the MER - therefore assume backbone must be pulled to 1st floor TR's and then routed vertically. First floor seems to identify 4" conduits feeding from cable tray to Security 10450, then from this room, conduits to the 1st floor TR in area A (cabling zone 10620). Is this the correct pathway for backbone to area A TR's feeding from MER?	2/10/2009	2/12/2009	There is no vertical riser in the MER to the floors above. Backbone cables will route horizontally on the 1st Floor to the respective TR and then make the vertical transition for the 2nd and 3rd Floor TR's. The identified and assumed pathway to TR 10308 - Area A is correct. (PGAL)
152	Please clarify - Section 27 05 00, Part 2, item 2.2 specifies acceptable manf/products. This list identifies OSP product (Building entrance frames, copper splicing materials, etc.) Please clarify that this list is a general list and not used to indicate the actual use of every stated item listed. Telecommunications prints do not seem to identify the use of building entrance frames, or OSP cable - we would therefore assume they are not required. Please confirm this is correct.	2/10/2009	2/12/2009	The identification of OSP termination and splicing components is for general use and is not necessarily representative of each required component. (PGAL)
153	Fiber backbone cable - the specified 12MM 50 micron/12SM cable hybrid- Specification (27 13 00- item 2.2) states this is to be an ONFP cable run in innerduct. Can an armored plenum fiber cable be substituted?	2/10/2009	2/12/2009	An armored, interlocking plenum fiber cable can be utilized in lieu of standard indoor construction fiber and innerduct. However, proper break-out, grounding and termination procedures are required. (PGAL)
154	Please specify quantity and lengths for LC-LC duplex fiber patch cords that should be included in our price.	2/10/2009	2/12/2009	Fiber jumpers at 7' should be provided to accomplish 100% patching of the terminated fiber strands. (PGAL)

RFI Log - GMP (Permit Set)



**PROJECT: FT. BEND COUNTY COURTHOUSE
UPDATED: 2/12/2009**

	REFERENCE	DATE REQUESTED	DATE ANSWERED	RESPONSE FROM PGAL
156	Please clarify the cable tray type specified for use for cable pathways throughout the facility. Section 27 05 28.36 seems to address several cable tray types. The drawing set seems to only refer to a typical tray as 12"W x 4"D tray. Should this be a basket type tray? Or an aluminum, or steel tray? Solid, ventilated, or ladder type? Please clarify.	2/10/2009	2/12/2009	Cable tray should be of aluminum construction, ladder-type. (PGAL)
157	Reference drawing T0.01, conduit, note 7. Note states that Backbone cable conduits for fiber optical cables shall be provided with multiple inner-ducts... reference note 8 as well. Please clarify - should the electrical contractor that is installing the conduits populate the conduit with innerducts, or the telecommunications contractor? If the use of armored fiber is approved, will innerduct still be required as stated in the referenced notes?	2/10/2009	2/12/2009	If armored, interlocking fiber is utilized, then innerduct will not be required in conduits. If a standard construction fiber optic cable is utilized, then innerduct shall be provided by the communication contractor for the entirety of the pathway. (PGAL)
158	Specification lists a CPI 11729-703 vertical cable manager (6" wide) drawings call for the use of 6" and 10" wide vertical cable managers. This particular double sided vertical manager only comes in the 6" wide version. Can we substitute a CPI MCS vertical manager so that both the 6" and 10 wide managers will be of the same style?	2/10/2009	2/12/2009	Utilize the following CPI part numbers: 6" = 30162-703 and 10" = 30163-703 (PGAL)
159	By the drawings, the voice riser cable is terminating on 110 blocks in the MER and TRs. Is this correct?	2/10/2009	2/12/2009	That is correct. (PGAL)
160	By the specs, all cables will be terminated on patch panels. Is this correct?	2/10/2009	2/12/2009	All Category 6 horizontal distribution cables will terminate on modular patch panels. (PGAL)

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Wednesday, April 01, 2009 10:08 AM
To: Kenny Eldridge
Subject: RE: FBCJC - Int Alum Frames

I agree - actually, I checked with Bruce on this a couple days ago. We're updating the details to show hollow metal, but I'll look over the other comments you had to make sure we update.

Thank you,
Paul Bonnette

PGAL

Alexandria
[T] 703 836 0588 [F] 703 836 8027
Atlanta
[T] 404 602 3800 [F] 404 602 3810
Austin
[T] 512 236 1005 [F] 512 853 6126
Boca Raton
[T] 561 988 4002 [F] 561 988 3002
Boston
[T] 617 848 0530 [F] 617 314 6196
Dallas
[T] 972 871 2225 [F] 972 871 2228
Ft. Lauderdale
[T] 954 527 5001 [F] 954 527 4177
Houston
[T] 713 622 1444 [F] 713 968 9333
Las Vegas
[T] 702 435 4448 [F] 702 435 4470
Los Angeles
[T] 310 645 3276 [F] 310 645 3026
Phoenix
[T] 602 324 7760 [F] 602 324 7768

<http://www.PGAL.com>

-----Original Message-----

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Wednesday, April 01, 2009 9:49 AM
To: Paul Bonnette
Subject: FBCJC - Int Alum Frames

Spec 081200 Int Alum Frames is not used.

All the door frames per the schedule are HM, Detention or Alum Storefront. The Int windows (W26-W30) were bid as HM also.

We don't have any Raco product.

Check it out and let me know this is the intent.

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Thursday, April 02, 2009 12:39 PM
To: Kenny Eldridge
Subject: RE: FBCJC - Paint

No paint is required for the structural steel at the underside of the metal roof.

As we discussed, the framing and deck for the central plant roof receives the spray fire resistive material, so it doesn't need paint.

Thank you,

Paul Bonnette

PGAL

Alexandria

[T] 703 836 0588 [F] 703 836 8027

Atlanta

[T] 404 602 3800 [F] 404 602 3810

Austin

[T] 512 236 1005 [F] 512 853 6126

Boca Raton

[T] 561 988 4002 [F] 561 988 3002

Boston

[T] 617 848 0530 [F] 617 314 6196

Dallas

[T] 972 871 2225 [F] 972 871 2228

Ft. Lauderdale

[T] 954 527 5001 [F] 954 527 4177

Houston

[T] 713 622 1444 [F] 713 968 9333

Las Vegas

[T] 702 435 4448 [F] 702 435 4470

Los Angeles

[T] 310 645 3276 [F] 310 645 3026

Phoenix

[T] 602 324 7760 [F] 602 324 7768

<http://www.PGAL.com>

-----Original Message-----

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]

Sent: Thursday, March 26, 2009 3:51 PM

To: Paul Bonnette

Subject: FBCJC - Paint

Is the galvanized steel framing and the underside of the roof deck for the roof structure on top of the courthouse required to be painted? This used to receive intumescent fireproofing. Is the primed steel roof framing and underside of the roof deck at the Central plant required to be painted?

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Friday, April 03, 2009 9:48 AM
To: Kenny Eldridge
Subject: RE: FBCJC - Int Alum Frames

We'll go with the USG Eclipse, and the Olympia Micro (the mid-level option) for the DA & Clerks areas.

I think we're going to stick with the Daltile product for now on the floor/wall tile. We just like the look a little better than the Crossville. If cost starts to become an issue again, we can re-evaluate.

Thanks,
Paul Bonnette

PGAL

Alexandria

[T] 703 836 0588 [F] 703 836 8027

Atlanta

[T] 404 602 3800 [F] 404 602 3810

Austin

[T] 512 236 1005 [F] 512 853 6126

Boca Raton

[T] 561 988 4002 [F] 561 988 3002

Boston

[T] 617 848 0530 [F] 617 314 6196

Dallas

[T] 972 871 2225 [F] 972 871 2228

Ft. Lauderdale

[T] 954 527 5001 [F] 954 527 4177

Houston

[T] 713 622 1444 [F] 713 968 9333

Las Vegas

[T] 702 435 4448 [F] 702 435 4470

Los Angeles

[T] 310 645 3276 [F] 310 645 3026

Phoenix

[T] 602 324 7760 [F] 602 324 7768

<http://www.PGAL.com>

-----Original Message-----

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Wednesday, April 01, 2009 10:36 AM
To: Paul Bonnette
Subject: RE: FBCJC - Int Alum Frames

Ok, thanks

Did you get the acoustical and hard tile VE samples on Friday?

>>> Paul Bonnette <PBonnette@pgal.com> 4/1/2009 10:07 AM >>>

I agree - actually, I checked with Bruce on this a couple days ago. We're updating the details to show hollow metal, but I'll look over the other comments you had to make sure we update.

Thank you,
Paul Bonnette

PGAL

Alexandria

[T] 703 836 0588 [F] 703 836 8027

Atlanta

[T] 404 602 3800 [F] 404 602 3810

Austin

[T] 512 236 1005 [F] 512 853 6126

Boca Raton

[T] 561 988 4002 [F] 561 988 3002

Boston

[T] 617 848 0530 [F] 617 314 6196

Dallas

[T] 972 871 2225 [F] 972 871 2228

Ft. Lauderdale

[T] 954 527 5001 [F] 954 527 4177

Houston

[T] 713 622 1444 [F] 713 968 9333

Las Vegas

[T] 702 435 4448 [F] 702 435 4470

Los Angeles

[T] 310 645 3276 [F] 310 645 3026

Phoenix

[T] 602 324 7760 [F] 602 324 7768

<http://www.PGAL.com>

-----Original Message-----

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]

Sent: Wednesday, April 01, 2009 9:49 AM

To: Paul Bonnette

Subject: FBCJC - Int Alum Frames

Spec 081200 Int Alum Frames is not used.

All the door frames per the schedule are HM, Detention or Alum Storefront. The Int windows (W26-W30) were bid as HM also.

We don't have any Raco product.

Check it out and let me know this is the intent.

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Thursday, April 16, 2009 1:46 PM
To: Kenny Eldridge
Cc: DonBrady; Bob Drouillard; John D. Strong; Mike Linscomb; Chi-Wai Chau; David L. Andrews
Subject: RE: FW: FORT BEND CRIMINAL JUSTICE CENTER/ RFI'S
Attachments: Kilgore RFIs 1-14.pdf

Kenny,

Attached are our responses to RFIs No. 1 - 14 from Kilgore.

Thank you,
Paul Bonnette

PGAL

Alexandria

[T] 703 836 0588 [F] 703 836 8027

Atlanta

[T] 404 602 3800 [F] 404 602 3810

Austin

[T] 512 236 1005 [F] 512 853 6126

Boca Raton

[T] 561 988 4002 [F] 561 988 3002

Boston

[T] 617 848 0530 [F] 617 314 6196

Dallas

[T] 972 871 2225 [F] 972 871 2228

Ft. Lauderdale

[T] 954 527 5001 [F] 954 527 4177

Houston

[T] 713 622 1444 [F] 713 968 9333

Las Vegas

[T] 702 435 4448 [F] 702 435 4470

Los Angeles

[T] 310 645 3276 [F] 310 645 3026

Phoenix

[T] 602 324 7760 [F] 602 324 7768

<http://www.PGAL.com>

-----Original Message-----

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Tuesday, April 14, 2009 11:23 AM
To: Paul Bonnette
Subject: Fwd: FW: FORT BEND CRIMINAL JUSTICE CENTER/ RFI'S

Final GMP RFI's related to plumbing, attached.

Please respond ASAP.

Thanks

>>> "Russell Roan" <rroan@kilgoreind.com> 4/14/2009 10:32 AM >>>

Kenny,

Hello, hope you are doing well. Here are some RFI'S that we will need some clarification on. If you have any questions please feel free to contact me at your earliest convenience.

Thank you,

Russell Roan

Project Manager - KILGORE INDUSTRIES

Office:(713) 924-4900 Cell: (281) 960-9807 / Fax: (281) 664-7371 rroan@kilgoreind.com

KILGORE

REQUEST FOR INFORMATION

Date: April 14, 2009 Project Name: FBCJC

RFI#: P 001 Subject: STORM DRAIN PIPING

On plan P2.01b the 6" storm drain between column line O & O.8 @ column 03 does not go to the basement plan P2.00B & does not go to the roof plan P2.04B. Is this storm drain riser needed?

On plan P2.03A between column A.3 & B @ column 03 shows 6" storm but does not go to floors below or roof plan P2.04A. Is this storm drain riser needed?

Submitted By: _____

Title: _____

BOTH OF THESE STORM DROPS FROM BOTH QUESTIONS GO AWAY. LOCATIONS WERE FROM PREVIOUS PLANS AND NEVER REVISID.

STORM DRAIN LINES ARE TO BE DELETED (THOSE IN QUESTION)

Signature: J. Strong

Date: 04.16.09

Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202 TACL# 017666C

Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# M-37953

KILGORE INDUSTRIES, L.P.
10050 Houston Oaks Drive
Houston, Texas 77064
(713) 924-4900 (phone) · (713) 924-5900 (fax)



REQUEST FOR INFORMATION

Date: April 14, 2009

Project Name: FBCJC

RFI#: P 002

Subject: DOMESTIC WATER PIPING



On plan P2.00B The 2" waterline just west of column O goes up @ column 7.2, is on the street pressure, P 2.01B shows this water line to be 2 1/2" and feed the 2 nd floor restroom on P2.02B. The notes say street pressure is to feed basement & 1st floors only. Please advise>

Blank lines for response

Submitted By: _____

Title: _____



STREET PRESSURE LINE SHOULD BE 2" AND SERVE FIXTURES IN TOILET ROOMS AND JANITOR CLOSET BETWEEN COLS. O AND P AND Q AND O.B.

ONLY TWO TOILET ROOMS UP FED FROM FIRST FLOOR CEILING. ROOMS 2074 AND 2076 CAN BE ON STREET PRESSURE

Blank lines for response

Signature: J. Strong

Date: 04.16.09

Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202* TACL# 017666C
Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# M-37953

KILGORE

REQUEST FOR INFORMATION

Date: April 14, 2009 Project Name: FBCJC

RFI#: P 003 Subject: SANITARY SEWER

[REDACTED]
In basement Area "A" P2.00A between colmn 02&03 there is a 4" sanitary line that feeds area "B", this sanitary line passes thru the tunnel @ column G -H & 2.5 NORTH OF 02. Could this line be brought off the 6" sanitary in area "B" between colmn K & L. Please advise.

Submitted By: _____

Title: _____

[REDACTED]
YES..... SANITARY CAN GO TO THE 6" SANITARY NOTED ABOVE.

Signature: J. Strong

Date: 04.16.09

Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202 TACL# 017666C

Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# M-37953

KILGORE INDUSTRIES, L.P.
10050 Houston Oaks Drive
Houston, Texas 77064
(713) 924-4900 (phone) · (713) 924-5900 (fax)



REQUEST FOR INFORMATION

Date: April 14, 2009

Project Name: FBCJC

RFI#: P 004

Subject: SANITARY SEWER

In area "A" P2.01A @ column 10 & D, there is a 4" sanitary drop that feeds area "A" P2.02A. This sanitary riser is not on the basement plan P2.00A. Please advise.

Submitted By:

Title:

CONTINUE 4" DROP DOWN THROUGH BASEMENT AND TO BELOW BASEMENT SLAB. CONNECT WITH 6" SANITARY BELOW BSMT. SLAB BETWEEN COL. A3 AND B AND B.2 AND C9

Signature: J. Strong

Date: 04.16.09

*Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202 TACL# 017666C
*Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# M-37953

KILGORE

REQUEST FOR INFORMATION

Date: April 14, 2009 Project Name: FBCJC

RFI#: P 005 Subject: SANITARY SEWER

[REDACTED]

On plan P2.01B there is a 4" sanitary drop @ column 08 & 03 , this line goes up @ column O & O2, there is not anything on the 2nd floor drawing P2.02B that requires this drain. Please advise.

Submitted By: _____

Title: _____

[REDACTED]

4" SAN. RISER AT 08 BETWEEN O AND O2 PICKS UP TOILET ROOM ON P2.02B.

4" RISER AT 03 AND O CAN BE DELETED

Signature: J. Strong

Date: 04.16.09

Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202 TACL# 017666C
Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# M-37953



REQUEST FOR INFORMATION

Date: April 14, 2009 Project Name: FBCJC

RFI#: P 006 Subject: Floor drains

[Redacted]

Do all the restrooms get floor drain FD-1, or only the restrooms shown on the plans? Please advise.

Submitted By:

Title:

[Redacted]

ONLY TOILET ROOMS SHOWN ON PLANS. FLOOR DRAINS WERE REMOVED FROM SINGLE TOILET ROOMS EXCEPT CELL TOILETS (BASEMENT, 1, 2 & 3)

Signature: J. Strong

Date: 04.16.09

*Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202 TACL# 017666C
*Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# M-37953



REQUEST FOR INFORMATION

Date: April 14, 2009 Project Name: FBCJC

RFI#: P 007 Subject: Floor drains

[Redacted]

On plan P4.01 in the fixture schedule there is floor drain labeled FD-3-ACORN #1699, is this floor drain to be used?

On the revised plan P 4.01 dated 03/30/09 under general notes, they added note #4, "floor drains in holding cells are to to have vandal resistant screws" is this in place of the FD-3? Please advise.

[Blank lines for response]

Submitted By: _____

Title: _____

[Redacted]

THIS FLOOR DRAIN IS FOR THE TWO ISOLATION CELLS

[Blank lines for response]

Signature: J. Strong

Date: 04.16.09

Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202 TACL# 017666C
Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# 14-37953



REQUEST FOR INFORMATION

Date: April 14, 2009

Project Name: FBCJC

RFI#: P 008

Subject: SUMP PUMPS

[Redacted]

On plan P3.02 there are sump pumps for the tunnel @ the stairwells, where are these pumps going to pump to?
Please advise.

Submitted By: _____

Title: _____

[Redacted]

DISCHARGE THROUGH WALL TO GRADE AS PER PLANS —

Signature: J. Strong

Date: 04.16.09

"Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202" TACL# 017666C
"Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78763, 1-800-845-6584" TPL# M-37953



REQUEST FOR INFORMATION

Date: April 14, 2009

Project Name: FBCJC

RFI#: P 009

Subject: SUMP PUMPS

On the plan P 2.00A dated 03/30/09 there are clouds around the SP-1 in the elevator pits, they were originally labeled SP-1. It does not appear that they have changed. Please advise.

Submitted By: _____

Title: _____

ELEVATOR LOCATION SHIFTED FROM ORIGINAL PLANS TO SP-1
SUMP LOCATION SHIFTED AS WELL.

Signature: J. Frang

Date: 04.16.09

Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202 TACL# 017666C
Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# M-37953



REQUEST FOR INFORMATION

Date: April 14, 2009 Project Name: FBCJC

RFI#: P 010 Subject: STORM DRAIN PIPING

On plan P0.01 under Piping Materials note #4B says above ground storm is to be SV hub & spigot cast iron w/ compression gaskets, under specifications 15160-2.1B says above grade storm can be service weight hubless w/ no hub clamps. Please advise.

Submitted By:

Title:

ALL STORM PIPING ABOVE GRADE TO BE SV HUB AND SPIGOT CAST IRON W/ COMPRESSION GASKETS

Signature: J. Strang

Date: 04.16.09

Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202 TACL# 017666C
Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# M-37953

KILGORE

REQUEST FOR INFORMATION

Date: April 14, 2009 Project Name: FBCJC

RFI#: P 011 Subject: STORM DRAIN PIPING

On P 4.01 there is not a deck drain under the fixture schedule or in specifications 15140 (2.6) or in 15160, but the drain is on P3.03 & P3.04. Can you provide a specification? Please advise.

Submitted By: _____

Title: _____

J.B. SMITH # 2230 PER 4" AND 6" DRAINS WITH WIDE DECK FLANGE AND HEAVY DUTY GRATE.

PER LARGEST SIZE, J.B. SMITH # 2141 WITH WIDE DECK FLANGE AND HEAVY DUTY GRATE.

Signature: J. Strong

Date: 04.16.09

Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202 TACLA# 017666C
Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# M-37953

KILGORE INDUSTRIES, L.P.
10050 Houston Oaks Drive
Houston, Texas 77064
(713) 924-4900 (phone) • (713) 924-5900 (fax)

17/53



REQUEST FOR INFORMATION

Date: April 14, 2009 Project Name: FBCJC

RFI#: P 012 Subject: Heat tracing



On the revised drawings dated 03/30/09, plans P2.00A & P2.00B call for crawlspace domestic wter piping to be insulated & metal jacketed, does this include Heat Tracing? If it does, is the specification 15771 the correct spec.? Please advise.

Multiple horizontal lines for response.

Submitted By: _____

Title: _____



THIS DOES NOT INCLUDE HEAT TRACING... INSULATED AND METAL JACKET ONLY.

Multiple horizontal lines for response.

Signature: J. Strong

Date: 04.16.09

Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202 TAQL# 017666C
Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# M-37953

KILGORE

REQUEST FOR INFORMATION

Date: April 14, 2009

Project Name: FBCJC

RFI#: P 013

Subject: PLUMBING FIXTURE L-2

On revised drawings dated 03/30/09 the lavatory labeled L-2 KOHLER#2006R does not exist. The supplier says it should read model# 2005 R, but would need to be w/ 4" center faucet, if the soap dispenser is needed, also, will need a specification on the soap dispenser. Please advise.

Submitted By: _____

Title: _____

REVISE TO K-2005R WITH 4" CENTERS TO ACCOMMODATE THE
CLEAN OPTIMA PLUS FAUCET. SOAP DISPENSER TO BE ON
RIGHT SIDE

RE: ARCHITECT FOR DISPENSER STYLE

DISPENSER STYLE BASIS OF DESIGN IS BOBRICK B-822
PER SPEC SECTION 10 28 13 TOILET ACCESSORIES

Signature: J. Strong

Date: 04-16-09

Paul D. Bonnette
PAUL D. BONNETTE - REAL
4/16/09

Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-833-9202 TAOL# 017666C

Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# M-37953

KILGORE INDUSTRIES, L.P.
10050 Houston Oaks Drive
Houston, Texas 77064
(713) 924-4900 (phone) • (713) 924-5900 (fax)

KILGORE

REQUEST FOR INFORMATION

Date: April 15, 2009

Project Name: FBCJC

RFI#: P 014

Subject: HOT WATER @ GANG RESTROOM

On plumbing drawing P2.01A the public restroom between colmn G & H @ column 6 &7 does not have any hot water supplying these restrooms. Do you want to add instaneous water heaters to supply these restrooms? If so which model # ? Please advise.

On plumbing drawing P2.01B the public restrooms between column I.2 & J @ column O7 does not have hot water suppling these restrooms. Do you want to add instaneous water heaters? Please advise.

On drawing p 2.01B the restrooms @ column O & O8 @ between O7 & O8 does not have any hot water suppling these restrooms or janitors room. Please advise.

This problem exist on 2nd & 3 rd floor gang restrooms. Please advise.

Submitted By: _____

Title: _____

PUBLIC TOILET ROOMS ARE TO HAVE COLD WATER ONLY.

Signature: J. Strong

Date: Oct. 16, 09

Regulated by the Texas Department of Licensing and Regulations, P.O. Box 12157, Austin, Texas 78711, 1-800-803-9202 TACL# 017666C
Regulated by the Texas State Board of Plumbing Examiners, P.O. Box 4200, Austin, TX, 78765, 1-800-845-6584 TPL# M-37993

KILGORE INDUSTRIES, L.P.
10050 Houston Oaks Drive
Houston, Texas 77064
(713) 924-4900 (phone) - (713) 924-5900 (fax)

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Thursday, April 16, 2009 2:22 PM
To: Kenny Eldridge
Cc: Don Brady; Chi-Wai Chau; David L. Andrews
Subject: RE: ft. bend

Kenny,

No - where Q, Q1 or Q2 walls are called out, make them P, P1 and P2 walls respectively.

Thank you,
Paul Bonnette

PGAL

Alexandria

[T] 703 836 0588 [F] 703 836 8027

Atlanta

[T] 404 602 3800 [F] 404 602 3810

Austin

[T] 512 236 1005 [F] 512 853 6126

Boca Raton

[T] 561 988 4002 [F] 561 988 3002

Boston

[T] 617 848 0530 [F] 617 314 6196

Dallas

[T] 972 871 2225 [F] 972 871 2228

Ft. Lauderdale

[T] 954 527 5001 [F] 954 527 4177

Houston

[T] 713 622 1444 [F] 713 968 9333

Las Vegas

[T] 702 435 4448 [F] 702 435 4470

Los Angeles

[T] 310 645 3276 [F] 310 645 3026

Phoenix

[T] 602 324 7760 [F] 602 324 7768

<http://www.PGAL.com>

-----Original Message-----

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]

Sent: Wednesday, April 15, 2009 3:40 PM

To: Paul Bonnette

Subject: Fwd: ft. bend

Drywall question below

>>> "Jim Chamberlain" <JChamberlain@appliedfinishsystems.com> 4/15/2009

>>> 3:08 PM >>>

Kenny, on the lower level the q2 wall is still on the plan but not on the partition type page. Advise

James Chamberlain

Executive Vice President

jchamberlain@appliedfinishsystems.com

<http://appliedfinishsystems.com/index.html>

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Tuesday, April 21, 2009 1:39 PM
To: Kenny Eldridge
Subject: FW: Piers at North side
Attachments: image001.gif

Kenny,

See the below response from Walter P. Moore.

Thank you,
Paul Bonnette

PGAL

Alexandria [T] 703 836 0588 [F] 703 836 8027	Atlanta [T] 404 602 3800 [F] 404 602 3810
Austin [T] 512 236 1005 [F] 512 853 6126	Boca Raton [T] 561 988 4002 [F] 561 988 3002
Boston [T] 617 848 0530 [F] 617 314 6196	Dallas [T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale [T] 954 527 5001 [F] 954 527 4177	Houston [T] 713 622 1444 [F] 713 968 9333
Las Vegas [T] 702 435 4448 [F] 702 435 4470	Los Angeles [T] 310 645 3276 [F] 310 645 3026
Phoenix [T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

From: Andy Stoebner [mailto:AStoebner@walterpmoore.com]
Sent: Tuesday, April 21, 2009 1:38 PM
To: Paul Bonnette
Cc: Steve Hegyesi; Muhammad Cheema
Subject: RE: Piers at North side

Bottom of pier elevation is still 71'-0". The smaller piers at the stairs are 18/36 with a bottom of pier elevation of 71'-0".

Andrew M. Stoebner, P.E.
Senior Associate
WALTER P MOORE

Walter P. Moore and Associates, Inc.
1301 McKinney, Suite 1100
Houston, Texas 77010
713.630.7329
713.630.7396 fax
281.520.9546 mobile
astobner@walterpmoore.com
www.walterpmoore.com

THE CONTENTS OF THIS E-MAIL AND ANY ATTACHMENT(S) ARE CONFIDENTIAL AND THE PROPERTY OF WALTER P. MOORE AND ASSOCIATES, INC.

From: Paul Bonnette [mailto:PBonnette@pgal.com]
Sent: Tuesday, April 21, 2009 1:22 PM

To: Andy Stoebner; Steve Hegyesi; Muhammad Cheema
Subject: Fwd: Piers at North side

Please respond.

Paul Bonnette-PGAL

Begin forwarded message:

From: Kenny Eldridge <Kenny.Eldridge@jedunn.com>
Date: April 21, 2009 12:25:21 PM CDT
To: Paul Bonnette <PBonnette@pgal.com>
Subject: Piers at North side

On S2.01C, the piers north of CL 9.3 & 10 for the north side plaza & entry used to indicate a bottom of pier elevation = 71'-0". The latest drawings do not indicate an elevation. Please provide.

Also, the piers at the steps in this same area appear to be a different size than the remainder. In speaking with WPA earlier in the week, they indicated this was the case and they would provide the size for these smaller piers. Please provide.

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Wednesday, April 22, 2009 9:40 AM
To: Kenny Eldridge
Subject: RE: Spray Insulation at Walls of Basement
Attachments: image001.gif

R-19.

Thank you,
Paul Bonnette



Alexandria	Atlanta
[T] 703 836 0588 [F] 703 836 8027	[T] 404 602 3800 [F] 404 602 3810
Austin	Boca Raton
[T] 512 236 1005 [F] 512 853 6126	[T] 561 988 4002 [F] 561 988 3002
Boston	Dallas
[T] 617 848 0530 [F] 617 314 6196	[T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale	Houston
[T] 954 527 5001 [F] 954 527 4177	[T] 713 622 1444 [F] 713 968 9333
Las Vegas	Los Angeles
[T] 702 435 4448 [F] 702 435 4470	[T] 310 645 3276 [F] 310 645 3026
Phoenix	
[T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Monday, April 20, 2009 10:37 AM
To: Paul Bonnette
Subject: Spray Insulation at Walls of Basement

I can't find a thickness or R-value spec'd for the walls. Please provide.
Thanks

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Friday, April 24, 2009 9:15 AM
To: Kenny Eldridge
Subject: Re: Sprinkler Heads - Not at center of tiles

Concealed and centered in courtrooms and jury assembly - semi-recessed and not centered elsewhere.

Paul Bonnette - PGAL

On Apr 23, 2009, at 3:16 PM, "Kenny Eldridge" <Kenny.Eldridge@jedunn.com> wrote:

Let me know where you want them centered and I'll have him price the appropriate credit for the other areas.

From: Paul Bonnette [<mailto:PBonnette@pgal.com>]
Sent: Wednesday, April 22, 2009 11:14 AM
To: Kenny Eldridge
Subject: RE: Sprinkler Heads - Not at center of tiles

I don't see where that got picked up, either. I think we need to add a general note on our ceiling plan sheets to cover it. Was this in all areas, or did it omit courtrooms?

Thank you,

Paul Bonnette

<image001.gif>

Alexandria	Atlanta
[T] 703 836 0588 [F] 703 836 8027 Austin	[T] 404 602 3800 [F] 404 602 3810 Boca Raton
[T] 512 236 1005 [F] 512 853 6126 Boston	[T] 561 988 4002 [F] 561 988 3002 Dallas
[T] 617 848 0530 [F] 617 314 6196 Fort Lauderdale	[T] 972 871 2225 [F] 972 871 2228 Houston
[T] 954 527 5001 [F] 954 527 4177 Las Vegas	[T] 713 622 1444 [F] 713 968 9333 Los Angeles
[T] 702 435 4448 [F] 702 435 4470	[T] 310 645 3276 [F] 310 645 3026

Phoenix

[T] 602 324 7760 [F] 602 324 7768 <http://www.PGAL.com>

From: Kenny Eldridge [<mailto:Kenny.Eldridge@jedunn.com>]
Sent: Wednesday, April 22, 2009 9:17 AM
To: Paul Bonnette
Subject: Sprinkler Heads - Not at center of tiles

I thought the VE to not center heads in the ceiling tiles was acceptable, but I nor the Sprinkler sub have found it noted in the Final GMP doc's.

Is it intended and where is it noted if so?

Kenny Eldridge

From: Kenny Eldridge
Content: Saturday, April 25, 2009 11:08 AM
To: 'Tom Anguiano'; Clifton Eddington
Cc: Whit Pilcher; 'Paul Bonnette'
Subject: RE: Fort Bend County Justice Center

Barring a revised response from the Architect (who is copied on this message), please proceed with pricing based on the following responses:

1. Assume the duplicated door is for the opening #00088 not shown on the schedule 2. Assume cuff pass and security lock is required 3. Assume sliding track box is required. With no spec provided, provide clarification on box bein priced if needed.
4. It looks like the room you mentioned as an example was shown with detention ceiling on the original D dwgs which haven't changed for that area. The Architect was to coordinate the D drawings, the Finish Schedule and the Arch Refl Ceiling plans so they all provided the same information (which in the case of your example, it looks like they did). Follow the D drawings then compare with the Arch Refl Ceiling plan and the Arch Fin Schedule and note any discrepancies. Same for Detention Doors with respect to D drawings and Arch Door Schedule. I believe the D drawings should be the basis for what is required and the Arch drawings should be following their lead.

As an aside, I need CCC to pick up the acoustical insulation above the detention ceilings if you did not already have this in your price. I believe this was discussed previously that you did include this but I don't have it written down.

Thanks

-----Original Message-----

From: Tom Anguiano [mailto:TomA@cccgroupinc.com]
Sent: Friday, April 24, 2009 3:06 PM
To: Clifton Eddington
Cc: Whit Pilcher; Kenny Eldridge
Subject: Fort Bend County Justice Center

Kenny / Cliff,

My apologies for not responding sooner. We have had a very heavy bid schedule these past few weeks. We are finalizing our review of the Final GMP documents that have been revised per the date 3/30/09.

We have found numerous discrepancies regarding our scope of work and need your help clarifying. Below are some of the discrepancies we have identified. We expect to get revised pricing from our suppliers/vendors on Monday:

1. Detention door #00084 is duplicated on the revised detention door schedule on page 1. Is this an error or should this opening be #00088 as this opening is shown on the detention floor plans but not on the schedule?
2. New detention door elevation "B2" notes a cuff pass but does not show the pass opening. Is a pass required with security lock?
3. New lock type "VD" is indicated on the detention door schedule. This lock type requires a sliding track box for overhead manual operation. This is not specified in Section 111930.

4. Security ceiling type "C4" has been added to rooms on the Finish Room Schedule that were not shown on the original finish schedule. For example, Room 10418 is indicated with "C4" in lieu of "C2".

respectfully,
CCC GROUP INC (Detention Systems Division)

Tom Anguiano
Estimating Manager

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Monday, April 27, 2009 9:15 AM
To: Kenny Eldridge
Subject: RE: Security Sealants

Kenny,

Security sealants are not required in the locations that you mentioned (between the top of full height secure walls and the structure). However, there will most likely be a number of places where we will need them. On past projects, we've used it in cells where the CMU abuts cast-in-place concrete columns, sealing under and around the plumbing fixtures, plumbing walls, around detention doors, etc. In the cells, we have used a two-part epoxy with a Shore number of 80 - 90. In holding areas where prisoners would be escorted, use in similar locations, but with a lower Shore number of 55 - 62.

Thank you,
Paul Bonnette

PGAL

Alexandria
[T] 703 836 0588 [F] 703 836 8027
Atlanta
[T] 404 602 3800 [F] 404 602 3810
Austin
[T] 512 236 1005 [F] 512 853 6126
Boca Raton
[T] 561 988 4002 [F] 561 988 3002
Boston
[T] 617 848 0530 [F] 617 314 6196
Dallas
[T] 972 871 2225 [F] 972 871 2228
Ft. Lauderdale
[T] 954 527 5001 [F] 954 527 4177
Houston
[T] 713 622 1444 [F] 713 968 9333
Las Vegas
[T] 702 435 4448 [F] 702 435 4470
Los Angeles
[T] 310 645 3276 [F] 310 645 3026
Phoenix
[T] 602 324 7760 [F] 602 324 7768

<http://www.PGAL.com>

-----Original Message-----

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Monday, April 20, 2009 9:38 AM
To: Paul Bonnette
Subject: Security Sealants

I can't find this shown or specified. Particularly, it's not in the Div 7 Sealants spec and it's not shown on the Partition Types.
The only hint is in the Detention Schedule Spec security sealants are referenced as work specified elsewhere.
Is this required?

Kenny Eldridge

From: Kenny Eldridge
Sent: Saturday, April 25, 2009 12:47 PM
To: 'Paul Bonnette'
Subject: Int Fence and Gate at Stairs

Keynote 3 not used on A4.05 to identify fence and gates. Subsequent stair sheets look like they identify 1 each at each of Stair 1 & 2. Is this correct?

Would be clearer to show it in plan on A4.05 but for now if there is a total of 2 each barriers, we have that covered.

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Monday, May 04, 2009 4:06 PM
To: Kenny Eldridge
Subject: RE: Flush paneling at Courtrooms
Attachments: image001.gif

Kenny,

Yes, you are correct that those areas you tagged on your attachment are intended to be flush wood panels. The detail will be slightly different than 25/A8.53 because the flush panels in courtrooms will have crown molding, and will have a reveal at 3'-2" a.f.f. in lieu of the 6" chair rail.

With regard to the left side of 13/A8.00, we intend that to be flush wood paneling. Is that what is currently priced?

Paul Bonnette



Alexandria [T] 703 836 0588 [F] 703 836 8027	Atlanta [T] 404 602 3800 [F] 404 602 3810
Austin [T] 512 236 1005 [F] 512 853 6126	Boca Raton [T] 561 988 4002 [F] 561 988 3002
Boston [T] 617 848 0530 [F] 617 314 6196	Dallas [T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale [T] 954 527 5001 [F] 954 527 4177	Houston [T] 713 622 1444 [F] 713 968 9333
Las Vegas [T] 702 435 4448 [F] 702 435 4470	Los Angeles [T] 310 645 3276 [F] 310 645 3026
Phoenix [T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Monday, May 04, 2009 1:43 PM
To: Paul Bonnette
Subject: Flush paneling at Courtrooms

One of the cost items we discussed on Friday was the Flat Paneling vs Raised Paneling at the Courtrooms. We show a deduct of \$8,270 on the Final GMP because this was an item we discussed earlier and I assumed it was not shown in the Final GMP doc's by mistake.

See attached copies of A8.00 dated 3/30/09 with Details 13, 14 & 16. I've inserted a cut for 25/A8.53 where we believe the flush paneling should occur (similar to that which is shown on 4/A8.01 which does depict the flat paneling with the correct detail).

Other areas on this and other sheets that do not show acoustical panels or raised paneling would be assumed to also be flush paneling per 25/A8.53

Also, look at the left hand side of 13/A8.00 where I've indicated that 25/A8.53 should apply. Notes on this detail, but not copied on my attachment, indicate this area should be acoustical wall panels but the area is not shaded to indicate this like other acous. wall panel areas. Is this specific area intended to be flat paneling or acoustical wall panels?

Let me know for all above and call if you have questions.

Thanks

Kenny Eldridge

From: Kenny Eldridge
Sent: Tuesday, May 05, 2009 5:29 PM
To: 'Paul Bonnette'
Subject: RE: Bentonite waterproofing
Attachments: image001.gif

Tremco is the product we are planning to use.

From: Paul Bonnette [mailto:PBonnette@pgal.com]
Sent: Tuesday, May 05, 2009 4:35 PM
To: Kenny Eldridge
Subject: Bentonite waterproofing

Kenny,

I've been talking to Cetco, but it occurred to me that they may not be the manufacturer selected for this project. Is it a problem if I send them the spec?

Paul Bonnette

PGAL

Alexandria	Atlanta
[T] 703 836 0588 [F] 703 836 8027	[T] 404 602 3800 [F] 404 602 3810
Austin	Boca Raton
[T] 512 236 1005 [F] 512 853 6126	[T] 561 988 4002 [F] 561 988 3002
Boston	Dallas
[T] 617 848 0530 [F] 617 314 6196	[T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale	Houston
[T] 954 527 5001 [F] 954 527 4177	[T] 713 622 1444 [F] 713 968 9333
Las Vegas	Los Angeles
[T] 702 435 4448 [F] 702 435 4470	[T] 310 645 3276 [F] 310 645 3026
Phoenix	
[T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Friday, May 08, 2009 11:21 AM
To: Kenny Eldridge
Cc: Brady, Don; David L. Andrews
Subject: FW: Stabilized sand under footings
Attachments: image001.gif

Kenny,

The requirement for cement stabilized backfill under the retaining wall footings can be removed.

Thank you,
Paul Bonnette



Alexandria [T] 703 836 0588 [F] 703 836 8027	Atlanta [T] 404 602 3800 [F] 404 602 3810
Austin [T] 512 236 1005 [F] 512 853 6126	Boca Raton [T] 561 988 4002 [F] 561 988 3002
Boston [T] 617 848 0530 [F] 617 314 6196	Dallas [T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale [T] 954 527 5001 [F] 954 527 4177	Houston [T] 713 622 1444 [F] 713 968 9333
Las Vegas [T] 702 435 4448 [F] 702 435 4470	Los Angeles [T] 310 645 3276 [F] 310 645 3026
Phoenix [T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

From: Jeff Talbott
Sent: Friday, May 08, 2009 9:43 AM
To: Paul Bonnette
Subject: Stabilized sand under footings

Paul,

We have removed the note from our FBJC retaining wall drawings which called for cement stabilized backfill under the retaining wall footings. This note was from the beginning of the project when we did not have the geotechnical report and was intended as insurance against poor soils. We have since received the geotechnical report and it indicates that there is adequate bearing capacity so no ground improvement is needed.

Jeff Talbott, PE
Senior Associate



Alexandria [T] 703 836 0588 [F] 703 836 8027	Atlanta [T] 404 602 3800 [F] 404 602 3810
Austin [T] 512 236 1005 [F] 512 853 6126	Boca Raton [T] 561 988 4002 [F] 561 988 3002
Boston [T] 617 848 0530 [F] 617 314 6196	Dallas [T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale	Houston

[T] 954 527 5001 [F] 954 527 4177
Las Vegas
[T] 702 435 4448 [F] 702 435 4470
Phoenix
[T] 602 324 7760 [F] 602 324 7768

[T] 713 622 1444 [F] 713 968 9333
Los Angeles
[T] 310 645 3276 [F] 310 645 3026
<http://www.PGAL.com>

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Monday, May 11, 2009 3:24 PM
To: Kenny Eldridge
Subject: RE: E Ext Wall Insulation
Attachments: image001.gif

The rigid will be enough. No need for the batt.

Paul Bonnette



Alexandria [T] 703 836 0588 [F] 703 836 8027	Atlanta [T] 404 602 3800 [F] 404 602 3810
Austin [T] 512 236 1005 [F] 512 853 6126	Boca Raton [T] 561 988 4002 [F] 561 988 3002
Boston [T] 617 848 0530 [F] 617 314 6196	Dallas [T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale [T] 954 527 5001 [F] 954 527 4177	Houston [T] 713 622 1444 [F] 713 968 9333
Las Vegas [T] 702 435 4448 [F] 702 435 4470	Los Angeles [T] 310 645 3276 [F] 310 645 3026
Phoenix [T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Monday, May 11, 2009 3:21 PM
To: Paul Bonnette
Subject: E Ext Wall Insulation

Look at 18/A5.00 for an example of this question. It shows 2" rigid insulation on the sheathing but then shows batt insulation inside the stud. Do you want both?

Right now, I have the rigid covered but not the batt because there are other details just showing the rigid without the batt.

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Tuesday, May 12, 2009 10:30 AM
To: Kenny Eldridge
Subject: RE: Louver finish
Attachments: image001.gif

Kynar coated should be included in the GMP.

Thank you,
Paul Bonnette



Alexandria	Atlanta
[T] 703 836 0588 [F] 703 836 8027	[T] 404 602 3800 [F] 404 602 3810
Austin	Boca Raton
[T] 512 236 1005 [F] 512 853 6126	[T] 561 988 4002 [F] 561 988 3002
Boston	Dallas
[T] 617 848 0530 [F] 617 314 6196	[T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale	Houston
[T] 954 527 5001 [F] 954 527 4177	[T] 713 622 1444 [F] 713 968 9333
Las Vegas	Los Angeles
[T] 702 435 4448 [F] 702 435 4470	[T] 310 645 3276 [F] 310 645 3026
Phoenix	
[T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Tuesday, May 12, 2009 10:30 AM
To: Paul Bonnette
Subject: FW: Louver finish

Decision on this one? Trying to finish up qualifications.

From: Kenny Eldridge
Sent: Wednesday, May 06, 2009 1:25 PM
To: 'Paul Bonnette'
Subject: Louver finish

Changing louvers from clear anodized to kynar finish adds about \$2,000 for the architectural louvers. I don't have a number for any HVAC supplied louvers.

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Tuesday, May 12, 2009 11:03 AM
To: Kenny Eldridge
Subject: RE: FBCJC - Vertical Lifts in Courtrooms

Sounds fine.

Paul Bonnette

PGAL

Alexandria

[T] 703 836 0588 [F] 703 836 8027

Atlanta

[T] 404 602 3800 [F] 404 602 3810

Austin

[T] 512 236 1005 [F] 512 853 6126

Boca Raton

[T] 561 988 4002 [F] 561 988 3002

Boston

[T] 617 848 0530 [F] 617 314 6196

Dallas

[T] 972 871 2225 [F] 972 871 2228

Ft. Lauderdale

[T] 954 527 5001 [F] 954 527 4177

Houston

[T] 713 622 1444 [F] 713 968 9333

Las Vegas

[T] 702 435 4448 [F] 702 435 4470

Los Angeles

[T] 310 645 3276 [F] 310 645 3026

Phoenix

[T] 602 324 7760 [F] 602 324 7768

<http://www.PGAL.com>

-----Original Message-----

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Tuesday, May 12, 2009 10:56 AM
To: Paul Bonnette
Subject: FW: FBCJC - Vertical Lifts in Courtrooms

I had a note from the last meeting that you were going to look back at this VE option. I think David said "cheapest option, they're never used".

The different drive needs a 20A circuit and breaker vs 15A for the hydraulic drive. It looks like Electrical is showing a 20A on the panel schedules.

I'm going to qualify using the alternate drive and apply the VE, unless you say otherwise.
Thanks

-----Original Message-----

From: Kenny Eldridge
Sent: Wednesday, April 08, 2009 10:42 AM
To: Paul Bonnette
Subject: RE: FBCJC - Vertical Lifts in Courtrooms

Was their a decision on this?

Message sent 3/31:

They quoted Garaventa Lifts and say it's the same as used at the Harris County Justice Center.

See link to website <http://www.garaventa.ca/vertical-elevator/drv.html>

>>> Paul Bonnette < PBonnette@pgal.com > 3/31/2009 4:49 PM >>>
Possibly. Is this particular to one of the manufacturer's products?

-----Original Message-----

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Tuesday, March 31, 2009 4:48 PM
To: Paul Bonnette
Subject: FBCJC - Vertical Lifts in Courtrooms

We have a voluntary alternate that didn't make it onto the VE Log.
It's worth about \$20k credit.
Uses ACME screw drive power systems vs. hydraulic drive system as specified.
Is this something you're interested in?

Thanks

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Tuesday, May 12, 2009 11:58 AM
To: Kenny Eldridge
Subject: RE: ft bend cooling tower
Attachments: image001.gif

Kenny,

I've been corrected on this. The top of PIER needs to be 4'-0" above the finished floor level in the CHILLER ROOM (i.e. Central Plant.)

Paul Bonnette



Alexandria [T] 703 836 0588 [F] 703 836 8027	Atlanta [T] 404 602 3800 [F] 404 602 3810
Austin [T] 512 236 1005 [F] 512 853 6126	Boca Raton [T] 561 988 4002 [F] 561 988 3002
Boston [T] 617 848 0530 [F] 617 314 6196	Dallas [T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale [T] 954 527 5001 [F] 954 527 4177	Houston [T] 713 622 1444 [F] 713 968 9333
Las Vegas [T] 702 435 4448 [F] 702 435 4470	Los Angeles [T] 310 645 3276 [F] 310 645 3026
Phoenix [T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

From: Paul Bonnette
Sent: Tuesday, May 12, 2009 11:04 AM
To: 'Kenny Eldridge'
Subject: RE: ft bend cooling tower

Top of steel needs to be 48" above the finished grade.

Paul Bonnette



Alexandria [T] 703 836 0588 [F] 703 836 8027	Atlanta [T] 404 602 3800 [F] 404 602 3810
Austin [T] 512 236 1005 [F] 512 853 6126	Boca Raton [T] 561 988 4002 [F] 561 988 3002
Boston [T] 617 848 0530 [F] 617 314 6196	Dallas [T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale [T] 954 527 5001 [F] 954 527 4177	Houston [T] 713 622 1444 [F] 713 968 9333
Las Vegas [T] 702 435 4448 [F] 702 435 4470	Los Angeles [T] 310 645 3276 [F] 310 645 3026
Phoenix [T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Tuesday, May 12, 2009 10:31 AM
To: Paul Bonnette
Subject: FW: ft bend cooling tower

Did you get the top of steel elevation? Trying to refine the Allowance as best as possible.

From: Kenny Eldridge
Sent: Thursday, May 07, 2009 9:20 AM
To: 'Paul Bonnette'
Subject: RE: ft bend cooling tower

What is top of steel with regards to the surrounding paving (i.e. how high above grade is top of steel)?

Did you look at the location and elevations of the piers with relation to the ret. wall footings? It looks too close and in conflict to just have a note to coordinate. The cooling tower will have to move north off of the wall to allow for this coordination. There may be enough room to do this based on the site layout. Take a look and see what you think.

From: Paul Bonnette [mailto:PBonnette@pgal.com]
Sent: Thursday, May 07, 2009 8:43 AM
To: Kenny Eldridge
Cc: Brady, Don; David L. Andrews
Subject: FW: ft bend cooling tower

Kenny,

Attached is a hand sketch from Walter P. Moore to base your pricing on for the cooling tower. Let me know if you have questions or need more information.

Thank you,
Paul Bonnette




Alexandria
[T] 703 836 0588 [F] 703 836 8027
Austin
[T] 512 236 1005 [F] 512 853 6126
Boston
[T] 617 848 0530 [F] 617 314 6196
Fort Lauderdale
[T] 954 527 5001 [F] 954 527 4177
Las Vegas
[T] 702 435 4448 [F] 702 435 4470
Phoenix
[T] 602 324 7760 [F] 602 324 7768

Atlanta
[T] 404 602 3800 [F] 404 602 3810
Boca Raton
[T] 561 988 4002 [F] 561 988 3002
Dallas
[T] 972 871 2225 [F] 972 871 2228
Houston
[T] 713 622 1444 [F] 713 968 9333
Los Angeles
[T] 310 645 3276 [F] 310 645 3026
<http://www.PGAL.com>

WALTER P MOORE

JOB NAME: FRCJC	
JOB NO: 07055 -01	DATE: 5/7/09
ENGINEER: AMS	DWG. REF:
TAB NO.:	SHEET NO.:

SCHEMATIC COOLING TOWER FRAMING



- ALL STEEL TO BE HOT-DIP GALVANIZED
- FOUNDATIONS TO BE COORDINATED SO AS NOT TO CONFLICT WITH RETAINING WALL FOUNDATIONS

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Thursday, May 14, 2009 10:28 AM
To: Kenny Eldridge; David L. Andrews
Subject: RE: Haworth Information

Should be fine.

Paul Bonnette

From: Kenny Eldridge [Kenny.Eldridge@jedunn.com]
Sent: Thursday, May 14, 2009 10:22 AM
To: Paul Bonnette; David L. Andrews
Subject: FW: Haworth Information

See below from Sub addressing your concerns.

I'll keep the qualification included to use this system unless otherwise instructed.

Thanks

From: Mickey Gibson [mailto:mgibson@alliedinteriors.com]
Sent: Thursday, May 14, 2009 10:13 AM
To: Kenny Eldridge
Subject: RE: Haworth Information

Kenny,

This system is a bolted panel system. In other words, the panel is bolted in each corner to the pedestal underneath. This method assures no movement in the system and provides outstanding lateral support. The system is cementitious filled, providing a quiet environment. Keep in mind; this is the only system that was specifically designed for a general office use. All of the other systems, including Tate, are computer room systems that have been modified to work.

Thanks,

Mickey Gibson

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Thursday, May 14, 2009 10:02 AM
To: joeygibson@alliedinteriors.com; Mickey Gibson
Subject: FW: Haworth Information

See below for Architect's concerns with this or any system. Can you address this?

From: Paul Bonnette [mailto:PBonnette@pgal.com]
Sent: Thursday, May 14, 2009 9:03 AM
To: Kenny Eldridge
Cc: David L. Andrews
Subject: RE: Haworth Information

Overall, it looks to be comparable to the Tate system that was specified. I do have some contacts at Gensler, who I may be able to discuss this with. I think it's fine to include, so long as they can address those acoustical issues (i.e. "hollow" sound, and creaking.)

Thank you,
Paul Bonnette

From: Kenny Eldridge [Kenny.Eldridge@jedunn.com]
Sent: Wednesday, May 13, 2009 9:26 AM
To: Paul Bonnette
Subject: FW: Haworth Information

I'm trying to get installed locations/contact info for the proposed access floor.
See below - Do you know anybody at Gensler to talk to?

From: Mickey Gibson [mailto:mgibson@alliedinteriors.com]
Sent: Wednesday, May 13, 2009 9:16 AM
To: Kenny Eldridge
Subject: RE: Haworth Information

Kenny,

We are putting together a list of users and architects that have used this system. We have millions of square feet of this system installed and the owners are very happy with it. **Gensler is a big architect that uses this material and the new Sysco Foods headquarters utilized 400,000 SF.** I have a call in to the contractor for the Sysco Corporation to get more info and see if we can get in to see the installation. Give me a little longer and I will have all of the info to you.

Thanks,

Mickey Gibson

Kenny Eldridge

From: Kenny Eldridge
Sent: Monday, May 11, 2009 11:31 AM
To: 'Paul Bonnette'
Subject: FW: FBJC Fixtures
Attachments: FBJC Bid Package Fixtures.pdf; FBJC VE Fixtures.pdf

Here are the Site fixtures as priced from the Final GMP Set, along with a VE fixture package.

The VE fixtures would save \$32,550 off of the add pricing we reviewed for the attached "bid package" fixtures.

From: Walter Coffey [mailto:wcoffey@e3electric.com]
Sent: Friday, May 08, 2009 3:54 PM
To: Kenny Eldridge
Cc: Walter Coffey
Subject: FBJC Fixtures

Kenny,

The two attachments are the cut sheets for the fixtures as requested. The pricing for the bid package fixtures is the pricing you've received in our line item pricing.

The pricing for the "VE" fixtures is as follows.

- Type "SA" – Deduct <\$390.00 each> x 2 each
- Type "SP" – Deduct <\$410.00 each> x 7 each
- Type "SQ" – Deduct <\$1,800.00 each> x 8 each
- Type "SR" – Deduct <\$2,900.00 each> x 5 each

Thanks very much for your patience.

E3 Electric, Ltd.

Walter Coffey
Estimator
Off. 713-622-1222
Cell 713-245-6710

Kenny Eldridge

From: Kenny Eldridge
Sent: Friday, May 15, 2009 12:09 PM
To: 'Paul Bonnette'
Cc: 'Walter Coffey'
Subject: FW: FBJC Fixtures

E3 has been told the SA fixture mfr. is out of business.
For now, I'm sticking with the "Bid Package" for the added site fixtures.

FYI for E3 - Architect will consider the "VE Package" but would like to see a photometric study. Can your rep do this if PGAL provides a CAD file?

From: Walter Coffey [mailto:wcoffey@e3electric.com]
Sent: Friday, May 15, 2009 11:47 AM
To: Kenny Eldridge
Subject: RE: FBJC Fixtures

I was just told that "Spero" (the manufacturer) is out of business. Their web site is still up so we can get cut sheets but nothing else.

Thanks,

E3 Electric, Ltd.

Walter Coffey
Estimator
Off. 713-622-1222
Cell 713-245-6710

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Friday, May 15, 2009 11:35 AM
To: Walter Coffey
Subject: RE: FBJC Fixtures

Do you have an answer on the SA yet?

From: Walter Coffey [mailto:wcoffey@e3electric.com]
Sent: Thursday, May 14, 2009 12:16 PM
To: Kenny Eldridge
Subject: RE: FBJC Fixtures

I've tried to resend the 8 – page VE attachment but you may not be getting it. Attached is the page you're missing.
I'll get an answer on the SA.

E3 Electric, Ltd.

Walter Coffey
Estimator
Off. 713-622-1222
Cell 713-245-6710

From: Kenny Eldridge [mailto:Kenny.Eldridge@jedunn.com]
Sent: Thursday, May 14, 2009 11:56 AM
To: Walter Coffey
Subject: FW: FBJC Fixtures

Architect wants you to price the exact SA fixture on the fixture schedule.
I've forwarded him the additional SR VE sheets, he just hasn't seen them before sending the message below.

From: Paul Bonnette [mailto:PBonnette@pgal.com]
Sent: Thursday, May 14, 2009 11:42 AM
To: Kenny Eldridge
Subject: RE: FBJC Fixtures

Kenny -

Could you price the SA fixture that is on the electrical schedule? The County may want the exact same fixture, so we should show them that as an option, then show them the alternatives.

As we discussed by phone, I didn't see the fixture for the top of the pedestrian poles in the V/E information. Please confirm their intent. As long as the wattage/voltage and lamping is the same, I think it's worth considering, but, again, the County may have the last word.

Thanks,
Paul Bonnette
PGAL

Kenny Eldridge

From: Kenny Eldridge
Sent: Monday, May 18, 2009 11:01 AM
To: 'Paul Bonnette'
Cc: 'David L. Andrews'; bradydon@co.fort-bend.tx.us
Subject: RE: Stone Tops

As agreed upon with Paul on Friday, Zodiac Vela Brown will be changed to Silestone Coffee Brown. Also, Rojo Alicante will be changed to Zodiac Rosso Verona. This helps to reduce the Draft pricing that we reviewed on 5/1 by approx. \$63,500. Paul - Please confirm.
Thanks

From: Kenny Eldridge
Sent: Thursday, May 14, 2009 1:25 PM
To: 'Paul Bonnette'
Cc: David L. Andrews; bradydon@co.fort-bend.tx.us
Subject: RE: Stone Tops

Pricing below. I have the requested samples and I will be delivering those to Paul this evening.

1st - There was a miscommunication between myself and the sub on the pricing sent yesterday. The Sonora Gold they priced was intended by myself to be a color similar to the Rojo Alicante but still a natural stone. What they priced was the Silestone Sonora Gold. So the pricing below for the Silestone Sonora Gold matches the credit I mentioned yesterday.

Here is the VE pricing (all in comparison to the Permit Set pricing):

1. Use Silestone Coffee Brown vs Zodiac Vela Brown at areas noted as S2, including Lobby Column Wainscot (\$17,916)
2. For areas previously noted as S2 now noted as ST1 in the Courtrooms:
 - A. Natural Stone Rojo Alicante +\$57,545
 - B. Zodiac Rossa Verona +\$11,973
 - C. Silestone Sonora Gold (\$18,431)
 - D. Silestone Santa Fe Brown (\$18,431)

Thanks

From: Paul Bonnette [mailto:PBonnette@pgal.com]
Sent: Thursday, May 14, 2009 9:03 AM
To: Kenny Eldridge; David L. Andrews; bradydon@co.fort-bend.tx.us
Subject: RE: Stone Tops

Kenny,

We found an alternate Zodiac surfacing that we like - could you price the Rosso Verona for the courtrooms?

The Silestone Coffee Brown does look close to the specified Vela Brown (by looking at them on the website), so that is a possibility. Is there any way you could get a sample for us? We may have one, but may not be able to put our hands on it until Monday or Tuesday.

Thank you,
Paul Bonnette
PGAL

From: Kenny Eldridge [Kenny.Eldridge@jedunn.com]
Sent: Wednesday, May 13, 2009 1:41 PM
To: Paul Bonnette; David L. Andrews; bradydon@co.fort-bend.tx.us
Subject: Stone Tops

I have some alternate information on the stone tops.

The Final GMP Draft spreadsheet we reviewed on 5/12 included an add of \$57,545 for changing courtroom tops from Zodiaq to Stone.

If we change the stone specified in the Final GMP documents from Rojo Alicante to Sonora Gold, the add would actually become a credit of \$18,431. Sonora Gold is the closest color our sub has to the Rojo Alicante.

One other item came up pertaining to the solid surface tops shown in the Final GMP documents - If we change all Zodiaq Vela Brown to Silestone Coffee Brown, there is a savings of \$17,316. This includes changing the lobby column wainscoting and all other solid surface areas.

Let me know if either of the above 2 options are acceptable.

Thanks

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Thursday, May 21, 2009 2:20 PM
To: Joseph Kummer; Kenny Eldridge
Cc: bradydon@co.fort-bend.tx.us; David L. Andrews; Eric Lien
Subject: RE: FBJC - City of Richmond Public Works and Engineering comments
Attachments: image001.gif

To clarify Item 1, the existing drive that we're showing between the two buildings and back to the Central Plant is 24' wide – that will be increased to 30', moving the line of parking 6' closer to the courthouse building.

Thank you,
Paul Bonnette



Alexandria [T] 703 836 0588 [F] 703 836 8027	Atlanta [T] 404 602 3800 [F] 404 602 3810
Austin [T] 512 236 1005 [F] 512 853 6126	Boca Raton [T] 561 988 4002 [F] 561 988 3002
Boston [T] 617 848 0530 [F] 617 314 6196	Dallas [T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale [T] 954 527 5001 [F] 954 527 4177	Houston [T] 713 622 1444 [F] 713 968 9333
Las Vegas [T] 702 435 4448 [F] 702 435 4470	Los Angeles [T] 310 645 3276 [F] 310 645 3026
Phoenix [T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

From: Paul Bonnette
Sent: Thursday, May 21, 2009 11:18 AM
To: Joe Kummer (joseph.kummer@jedunn.com); 'Kenny Eldridge'
Cc: bradydon@co.fort-bend.tx.us; David L. Andrews; Eric Lien
Subject: FBJC - City of Richmond Public Works and Engineering comments
Importance: High

Joe, Kenny,

Below is a synopsis the comments received recently from the City of Richmond that will affect pricing. Please include pricing for these items in your GMP.

1. Add drive for fire truck access between the parking garage and building. Curb cut to be 35' wide (almost immediately across from the drive entering the parking area North of the ring road), drive to be 30' wide. Turning radii will need to be modified based on the specs for the fire engine that the City uses.
2. The existing driveway culvert from the ring road to the existing parking area needs to be removed (East side existing driveway access to parking area).
3. The portion of the landscaped area immediately South of the levee easement will need to be graded to the East and West so that storm water coming off of the levee will be directed to the low points at the corners of the parking areas.
4. In parking areas where we call for 8" PVC, provide 12" HDPE (352 lf.) For other 12" piping, provide HDPE in lieu of RCP. Two stubouts from manholes that are part of the trunk line will need to be removed and replaced to accommodate this, as they have already been installed (Manholes T-7 & T-10). Piping serving the upper plaza may remain 8" PVC (or alternatively HDPE).
5. Add a sanitary sewer sampling well in lieu of the 45 degree bend in the 6" sewer line from the building.

6. Move the existing fire hydrant near the flagpoles toward the East. A new fire department connection is to be located in the vicinity of the relocated fire hydrant.
7. There is an existing fire hydrant at the NE corner of the site that needs to be relocated to the opposite side of the ring road. Also, water lines feeding the Precinct One and Gus George Academy will require new taps for the fire and domestic lines when the 8" water line planned to be relocated along the curve of the ring road.
8. Add a minimum of 18 feet of ductile iron piping for the 18" sanitary line each side of and through the tunnel (a total of 54 lf.) The section going through the tunnel will have a 26" diameter steel casing pipe and two hangers.

Feel free to call if you have any questions.

Thank you,
Paul Bonnette



Alexandria [T] 703 836 0588 [F] 703 836 8027	Atlanta [T] 404 602 3800 [F] 404 602 3810
Austin [T] 512 236 1005 [F] 512 853 6126	Boca Raton [T] 561 988 4002 [F] 561 988 3002
Boston [T] 617 848 0530 [F] 617 314 6196	Dallas [T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale [T] 954 527 5001 [F] 954 527 4177	Houston [T] 713 622 1444 [F] 713 968 9333
Las Vegas [T] 702 435 4448 [F] 702 435 4470	Los Angeles [T] 310 645 3276 [F] 310 645 3026
Phoenix [T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

Kenny Eldridge

From: Paul Bonnette [PBonnette@pgal.com]
Sent: Thursday, May 21, 2009 3:19 PM
To: Joseph Kummer; Kenny Eldridge
Cc: David L. Andrews; Gary Davis; bradydon@co.fort-bend.tx.us
Subject: FBJC - telecommunications cabling change

Importance: High

Joe, Kenny,

See below for the cabling type that is acceptable to the County. This is anticipated to be a cost savings from what we currently have specified (Belden 4800LX). Please revise the GMP to reflect the following:

Spec. Section 27 15 00 – COMMUNICATIONS HORIZONTAL CABLING AND TERMINATIONS

Article 2.1, A., 1. – change to read "Belden IBDN System 3600

Article 2.2, B., 1. – change to read "Manufactured by Belden (Datatwist 3613)"

Thank you,
Paul Bonnette

From: Charles King [Charles.King@co.fort-bend.tx.us]
Sent: Tuesday, May 19, 2009 12:11 PM
To: Gary Davis
Cc: Bob Clarkson; Charles Cook; Paul Bonnette; Shane Whatley
Subject: RE: FBJC - JE Dunn Constructability Review

Gary,

We're going to go with DataTwist 3600.

Charles D. King
Customer Services Manager
Fort Bend County Information Technology
Direct 281-341-4584


Bid Package Fixtures - SA, SR, SQ, SP

19 pages

per 5/15/09 Email correspondence



JOB: FT. BEND COUNTY JUDICIAL COMPLEX
 TYPE: SA
 PRODUCT# AME2 T4 400P 5 BOA10 BK 1 S W/
 LAMP



Fixture	A	B	C	Stripe	Max.Watts	Lbs
AME-1	14"	14"	10"	2"	175W Metal Halide Only	35
AME-2	19"	19"	12"	2"	400W Metal Halide, Quartz Halogen, or CFL	50
AME-3	23"	23"	13"	2"	1000W Metal Halide Only	70
AME-4	23"	23"	15"	2"	1000W Metal Halide Only	75

The American Series features the most advanced lighting reflector system available today. Vision's® patent pending, revolutionary new reflector system makes any corner. The flat lens, vertical lamp, IES full cut-off luminaire is Dark Sky Compliant to restrict light trespass, glare and light pollution for nighttime use. It is only outdoor lighting. Convex glass lens is available when required.

American is offered in four enclosure sizes and five distribution patterns, including a special forward throw. 14 A reflector for auto dealer shop front line lighting. Vision's® Reflector System allows the use of lower fixtures and poles with wider spacings, providing substantial equipment, installation and energy cost savings.

The clean, compact housing style features a decorative recess available in complementary or contrasting colors. The patented precision machinery, first quality materials ensure manufacturing to the highest industry standards.

American is a proven performer for auto dealerships, shopping centers, parking lots and general area lighting. A wide selection of light sources from 100 through 1000 watts are offered in Metal Halide, High Pressure Sodium, and the new Pulse Start Metal Halide lamp which provides excellent efficiency, longer maintenance and color.

Model No.	Optics	Wattage	Source	Voltage	Mounting	Finish/ Stripe	Options
AME	14	400	PS	5	BOA10	BK	1 S
Model	Optics	Wattage	Source	Voltage	Mounting	Finish/ Stripe	Options
<input type="checkbox"/> AME-1 14x14x10	<input type="checkbox"/> Type I (T2)	<input type="checkbox"/> 100 (100) <input type="checkbox"/> 150 (150) <input type="checkbox"/> 175 (175)	PS, HPS PS, HPS MH, PS (M), (P), (S) <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	<input type="checkbox"/> 120 (1) <input type="checkbox"/> 208 (2)	<input type="checkbox"/> Bolt-On Arm 6" (BOA6) <input type="checkbox"/> Bolt-On Arm 10" (BOA10) <small>High quality, powder coated steel with EPC, TPO & coated mounting.</small>	<input type="checkbox"/> Bronze (BZ) <input type="checkbox"/> Black (BK) <input type="checkbox"/> White (WH) <input type="checkbox"/> Green (GN) <input type="checkbox"/> Grey (GY) <input type="checkbox"/> Silver Metallic (SL) <input type="checkbox"/> Custom (CC) Color Stripes <input type="checkbox"/> Blue Stripe (S4) <input type="checkbox"/> Red Stripe (R8) <input type="checkbox"/> Green Stripe (G5) <input type="checkbox"/> White Stripe (W6) <input type="checkbox"/> Black Stripe (B6) <input type="checkbox"/> Custom Stripe (C5)	Photocell & Recirculate <small>*Specify voltage</small> <input type="checkbox"/> (PC120) <input type="checkbox"/> (PC208) <input type="checkbox"/> (PC240) <input type="checkbox"/> (PC277) <input type="checkbox"/> (PCR480) <input type="checkbox"/> Photo Receptacle With Shading Cap (PER) <input type="checkbox"/> Quartz Resilink (QR) Fixture <small>*Single or Line Fuse Specify voltage</small> <input type="checkbox"/> (SF120) <input type="checkbox"/> (SF277) <small>*Double or Line Fuse Specify voltage</small> <input type="checkbox"/> (DF208) <input type="checkbox"/> (DF240) <input type="checkbox"/> (DF480) <input type="checkbox"/> House Side Light Shield (LS) <input type="checkbox"/> Convex Glass Lens (VLCG) RPP-1 Round Plate Plate Adapt (RPP) <input type="checkbox"/> Cast Wall Plate (BAWP)
<input type="checkbox"/> AME 2 19x19x12 19x19x12	<input type="checkbox"/> Type II (T3)	<input type="checkbox"/> 250 (250) <input type="checkbox"/> 300 (300) <input type="checkbox"/> 400 (400)	MH, PS, HPS PS MH, PS, HPS (M), (P), (S) <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	<input type="checkbox"/> 240 (3) <input type="checkbox"/> 277 (4) <input type="checkbox"/> 480 (5)	<input type="checkbox"/> Spring Mount (SM) <input type="checkbox"/> Wall Mount (WM) <small>*Cast Wall Plate (BAWP) is sold separately.</small>	<input type="checkbox"/> Blue Stripe (S4) <input type="checkbox"/> Red Stripe (R8) <input type="checkbox"/> Green Stripe (G5) <input type="checkbox"/> White Stripe (W6) <input type="checkbox"/> Black Stripe (B6) <input type="checkbox"/> Custom Stripe (C5)	
<input type="checkbox"/> AME 3 23x23x13	<input type="checkbox"/> Type IV (T4)	<input type="checkbox"/> 400 (400) <input type="checkbox"/> 750 (750) <input type="checkbox"/> 1000 (1000) <small>*Forward Throw 23x14x13x13</small>	MH, PS, HPS PS MH, PS, HPS (M), (P), (S) <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	<input type="checkbox"/> 277 (4) <input type="checkbox"/> 480 (5) <input type="checkbox"/> M-Top (6)	<input type="checkbox"/> Wall Mount (WM) <small>*Cast Wall Plate (BAWP) is sold separately.</small>	<input type="checkbox"/> Blue Stripe (S4) <input type="checkbox"/> Red Stripe (R8) <input type="checkbox"/> Green Stripe (G5) <input type="checkbox"/> White Stripe (W6) <input type="checkbox"/> Black Stripe (B6) <input type="checkbox"/> Custom Stripe (C5)	
<input type="checkbox"/> AME 4 23x23x15	<input type="checkbox"/> Type I/A Automotive (T4A) <small>*Metal Halide AME-4-K-2</small> <input type="checkbox"/> Type V (T5)	<input type="checkbox"/> 750 (750) <input type="checkbox"/> 1000 (1000) <small>*Retrofit Conversion 23x14x15x15</small> <input type="checkbox"/> 55 (55) <input type="checkbox"/> 65 (65) <input type="checkbox"/> 165 (165)	PS MH, PS, HPS (M), (P), (S) <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> Inductor (IND) <small>*Inductor 23x14x15x15 400, 600, 750, 1000W</small>	<input type="checkbox"/> 5-Top (7) Standard to 400W, 600W, MH only, would not be used without appropriate 347V available consult factory	<input type="checkbox"/> Cast Wall Plate (BAWP) is sold separately. RPP-1 RPP-2 RPP-3 RPP-4 RPP-5 RPP-6 RPP-7 RPP-8 RPP-9 RPP-10 RPP-11 RPP-12 RPP-13 RPP-14 RPP-15 RPP-16 RPP-17 RPP-18 RPP-19 RPP-20 RPP-21 RPP-22 RPP-23 RPP-24 RPP-25 RPP-26 RPP-27 RPP-28 RPP-29 RPP-30 RPP-31 RPP-32 RPP-33 RPP-34 RPP-35 RPP-36 RPP-37 RPP-38 RPP-39 RPP-40 RPP-41 RPP-42 RPP-43 RPP-44 RPP-45 RPP-46 RPP-47 RPP-48 RPP-49 RPP-50 RPP-51 RPP-52 RPP-53 RPP-54 RPP-55 RPP-56 RPP-57 RPP-58 RPP-59 RPP-60 RPP-61 RPP-62 RPP-63 RPP-64 RPP-65 RPP-66 RPP-67 RPP-68 RPP-69 RPP-70 RPP-71 RPP-72 RPP-73 RPP-74 RPP-75 RPP-76 RPP-77 RPP-78 RPP-79 RPP-80 RPP-81 RPP-82 RPP-83 RPP-84 RPP-85 RPP-86 RPP-87 RPP-88 RPP-89 RPP-90 RPP-91 RPP-92 RPP-93 RPP-94 RPP-95 RPP-96 RPP-97 RPP-98 RPP-99 RPP-100		

*For more detailed information on warranty, usage or installation requirements, please consult factory literature. Please specify the mounting method. The standard option, except for aluminum fixtures, is use of the information requires the written approval of Visionaire Lighting, LLC. Visionaire Lighting, LLC is not responsible for any damage to property or injury to persons or property resulting from the use of the information provided herein.



American

Housing

- All housings are manufactured using technologically advanced computerized numerical control (CNC) machinery. Precision machined and formed from one piece .080 gauge, corrosion resistant aluminum, with tool-d external finish.
- The computerized CNC machinery enables all American housings to be constructed quickly, efficiently, and adhering to exacting ISO 9002 standards. All external hardware is stainless steel.

Lens and Door Assembly

- Removable Hinged door assembly** is CNC precision machined and formed from one piece .080 gauge, corrosion resistant aluminum, with captive stainless steel fasteners.
- The standard lens is a clear tempered float glass, secured by galvanized lens retainers, and sealed with a triple gasketing to provide complete weather and insect protection.
- An optional curved glass lens is available when required for AME 2, conventional, standard in AME 1.

vision™ Optical System (Patent Pending)

- Reflector is precision CNC machined, multi-faceted, segmented, highly efficient, 30% reflective aluminum. Available in five distribution patterns.
- 14A Automotive Reflector is Field Portable.
- Tool-less interior entry.

Quali-Guard® Finish

- The finish is Quali-Guard® textured, chemically pretreated II tough, a multiple stage wash, electrostatically applied, thermoset polyester powder coat finish, with a minimum of 3.5 mil thickness. Finishes oven baked at 450 degrees Fahrenheit to promote maximum adhesion and abrasion resistance. All finishes are available in standard and custom colors.

Mounting

- A rounded extruded aluminum bolt-on arm (BOA), with an in-pole nut plate, securing (2) 1/2 inch zinc running bolts with stainless steel hardware is standard. A Round Pole Plate Adapter (RPP) is required for mounting to 3" Ø Round Poles.

Electrical Assembly

- All ballasts are premium grade CWA or HPP regulating auto transformers. Ballast is capable of providing consistent lamp starting down to -20 degrees Fahrenheit. Available in:



- Metal Halide (MH)
- Pulse Start Metal Halide (PS)
- High Pressure Sodium (HPS)

Options

- photo cell
- photo receptacle
- convex glass lens
- house side light shields
- fusing
- quartz restrike

Please consult factory for custom options.

Listings

- American is  listed, suitable for wet locations.
- Dark Sky Friendly  certified by the International Dark Sky Association. (Flat lens models only)

Spoke Curves




Size Two

Type III 400w
MH VLF 25ft
Mounting Height

Foot Candle Key:
A=2, B=1, C=5,
D=2, E=1

1 Block-30ft




Size Two

Type V 400w
MH VLF 25ft
Mounting Height

Foot Candle Key:
A=2, B=1, C=5,
D=2, E=1

1 Block-30ft




Size Four

Type V 1000w
MH VLF 42ft
Mounting Height

Foot Candle Key:
A=2, B=1, C=5,
D=2, E=1

1 Block-60ft

Bolt-On-Arm Detail



4" Tall Arm Drill Pattern



6" Tall Arm Drill Pattern




Cast Wall Plate










*For use with standard Bolt-on-Arm

Spider Arm Detail



EPA Data

Fixture with Arm							Spider Mount 
AME-1	1.4	2.0	2.0	3.0	3.3	4.5	1.7
AME-2	2.0	4.0	4.4	5.0	5.7	7.3	2.5
AME-3	3.2	5.8	6.4	8.7	7.4	10.2	3.7
AME-4	4.4	8.5	6.8	9.2	7.8	10.9	3.9


TYPE "SR"






KING LUMINAIRE


K130 SERIES POST TOP LUMINAIRES

SOLID ENGINEERING
SUPERB LIGHTING
PERFORMANCE



TYPE "SR"





Starlight Dome Optical Systems


In selecting which of the K194 optical systems is right for your project, numerous factors, besides the luminaire's lighting characteristics, need to be considered:

- Glare:** Luminaires must provide the ability to see, not just light the ground
- Purpose:** Consideration must be given to the purpose of the lighting (i.e. roadway or area lighting and, if roadway, which type)
- Ambiance:** Light standards provide the finishing architectural touch - 24 hours a day
- Safety:** The project must meet all codes and ordinances
- Uplight:** Consider the project's environment and design accordingly
- Light Trespass:** Put light in the right places, not in people's areas or bedroom windows
- Budget:** Consider both the initial capital investment and, especially, the ongoing maintenance costs.
- Power Usage:** Use as few assemblies as is practical.

With the above points in mind and using the requisite IES files, the lighting designer will be enabled to make an educated decision as to which optical system will be most suitable for any given project.

Starlight Dome Optical System Features

- Heavy-duty aluminum castings
- Tool-less access to lamp and ballast with retolock feature
- Available in durable polycarbonate or high impact UV stabilized acrylic
- 4 designs - 2 optical systems to choose from
- Custom fabric hardware available
- Ease of maintenance - optional globe holder for servicing
- Starlight Dome Option available with external prismatic refractor optical system only



DATA K134-E-AR-8L-11-150 MAG-HPS-277-115-BLK

* For IES requirements, please consult a local office.


How to Catalog for K130 Series luminaires




INTERNATIONAL ILLUMINATION ASSOCIATION

1975-1976
 1977-1978
 1979-1980
 1981-1982
 1983-1984
 1985-1986
 1987-1988
 1989-1990
 1991-1992
 1993-1994
 1995-1996
 1997-1998
 1999-2000
 2001-2002
 2003-2004
 2005-2006
 2007-2008
 2009-2010
 2011-2012
 2013-2014
 2015-2016
 2017-2018
 2019-2020
 2021-2022
 2023-2024

KA16T-2
"FLORENTINE ARM"
 POLE MOUNT VERSION



LETTERING SCHEMATICAL CONFIGURATIONS




LETTERING
 CONFIGURATIONS
 (A) (B) (C) (D) (E) (F) (G) (H) (I) (J) (K) (L) (M) (N) (O) (P) (Q) (R) (S) (T) (U) (V) (W) (X) (Y) (Z)




KA16T-2

KA16T-2


KM95-FC
"NIAGARA PARKS"



CAST IRON POLE - BLACK FINISH



THE BEAUTY OF BOLLARDS







Long Luminaire • StressCrete • Est. 1983

STRESSCRETE
GROUP



INNOVATIVE BOLLARD DESIGN. STYLISH. FUNCTIONAL. AND DURABLE.

King Industries is proud to present an extensive line of lighted and non-lighted bollards. Many have been specifically created to complement an extensive family of matching poles.

Historically bollards were originally used for the purely functional purpose of tying up ships at dockside. Early landscape architects borrowed from the street lighting bollard and started using less massive designs to delineate special areas. At the same time, the bollard's use as a marker began to appear within the rails themselves, sometimes even used to separate lanes of traffic in a given space. Thus, the word "bollard" came to be used to describe almost any sort of vertical influence that separated one area from another when a fence was not desired. In more recent times, the option of lighting these bollards became practical, so that areas could be delineated both by day and by night. Today bollards are specified more frequently on all kinds of landscaping and streetscaping projects.



6104 90-A (E) (4/2013) (11/13)




The Classic

The Classic has been so successful both as a pole and a bollard in spun concrete, that it was decided to offer it in cast aluminum for those occasions when a painted metal finish was preferred. The aluminum version is teamed with a 1 1/2" matching pole. Available lighted or non-lighted, the cast aluminum Classic can be finished in all the colors offered in the Kingpost system.


This bollard, which is available in heavy duty cast aluminum or practically indestructible cast ductile iron "ferrocrete" is a composite of the historic and the contemporary, and is equally at home in either setting. Finished in any of the high quality colors available in the Kingpost system, the Pacific will add distinction to any project.


The Pacific



The Silhouette

The clean uncluttered lines of the Silhouette makes this the go "anywhere" bollard that will fit with any outdoor theme. Constructed in heavy wall extruded aluminum it can be finished in all the colors offered in the Kingpost system. As with all metal bollards it is available for base plate installation only in lighted or non-lighted versions.





Bollards: How to Catalog



King Luminaire • Stresscrete • Est. 1963

STRESSCRETE GROUP

www.kingluminaire.com
email: sales@kingluminaire.com



9200 Energy Lane
Northport, Alabama 36446-3442
(205) 339-0711
1-800-435-6563
Fax: (205) 339-4840

1153 State Route 46 North
P.O. Box 296
Jefferson, Ohio 44047
1-800-269-7808
Fax: (905) 632-8116

14503 Watlick Road
Atchison, Kansas 66002
(913) 255-3112
1-800-837-1024
Fax: (913) 255-3124

840 Walkers Line, P.O. Box 7
Burlington, Ontario L7R 3X9
(905) 632-9330
1-800-269-7809
Fax: (905) 632-8116


Fixture TYPE-"SQ"




  The StressCrete Group
PACIFIC

M E T A L F O O T I N G S P E C S


Classic



Canterbury







Colonial



Pacific

Silhouette



Paracyl™

Paracyl Large

page 1 of 3

10/11

TS-1


PCL-L

LENS OPTIONS	MOUNTING OPTIONS	LAMP/BALLASTS	COLOR	OPTIONS
--------------	------------------	---------------	-------	---------

PCL-L

Paracyl Large,
luminaire

IP= 53 E-PA = 3.5
Weight = 40 lbs.



2 LENS OPTIONS

- F** Flat glass lens, 150° beam
- P** Polycarbonate projecting lens, 180° beam

3 MOUNTING OPTIONS

- SJO** Surface mount, 2-Box by others
- SJM** Surface mount, 2-Box by Mullerplast
- RJO** Recessed mount, 2-Box by others (up to 175MH/150HPS only)
- RJM** Recessed mount, 2-Box by Mullerplast (up to 175MH/150HPS only)
- PJO** Pedestal mount, (box by others)
- PM1** Post mounting, slips over 2 3/8" o.d. x 4" long tube
- PM2** Twist fixture (180°) post mounting, slips over 2 3/8" o.d. x 4" long tube

Please see Pg.3 for mounting dimensions.

EMERGENCY BACKUP MOUNTING

5 COLOR

- | | |
|--|---|
| <input checked="" type="checkbox"/> WHT white | <input type="checkbox"/> VGR verde green |
| <input type="checkbox"/> BLK black | <input type="checkbox"/> CRT carbon |
| <input type="checkbox"/> MTB matte black | <input type="checkbox"/> MAL matte aluminum |
| <input type="checkbox"/> DGN dark green | <input type="checkbox"/> MDG medium grey |
| <input type="checkbox"/> DBZ dark bronze | <input type="checkbox"/> ATG antique green |
| <input type="checkbox"/> WRZ weathered bronze | <input type="checkbox"/> LGY light worm grey |
| <input type="checkbox"/> BRM metallic bronze | <input type="checkbox"/> RAL/CUSTOM COLOR: |

4 LAMP/BALLASTS

- 175 MH** Metal halide 120/208/240/277 volt, mogul base ED 28
- 250 MH** Metal halide 120/208/240/277 volt, point mogul base ED 28
- 400 MH** Metal halide 120/208/240/277 volt, point mogul base ED 35
- 150 HPS** High pressure sodium 120/208/240/277, mogul base ED 25/27
- 200 HPS** High pressure sodium 120/208/240/277, mogul base ED 30
- 250 HPS** High pressure sodium 120/208/240/277, mogul base ED 35
- 400 HPS** High pressure sodium 120/208/240/277, mogul base ED 35

All ballasts are factory wired for 277 volts. Lamps not included

150P/150-150 PULSE START MH, 120/208/240/277

6 OPTIONS

- FS1** Single Fuse Holder, Fuse by others
- FS2** Double Fuse Holder, Fuse by others
- PCR** Twist lock photo control receptacle, not for recessed mounting (photo cell by others)
- TRH** Tamper resistant hardware
- PSB** Pulse start ballast for 175MH, 250MH, and 400MH lamps. Provides faster re-ignition of the lamp, longer life, and improved color consistency
- 347V** 347 volt ballast (120/277/347-v)
- 480V** 480 volt ballast (not available for 175MH)
- QL** Sealed for a 1/4" rain, rain or frozen lamp. Must be field wired in a separate 120 volt circuit, maximum 250 watt.
- QRS** Quartz re-ignition starter and socket for a T-4 standard halogen lamp, maximum 250 watt

SOLD

PO #


JOB NAME

Approved


Architectural Area Lighting

14749 Arcola Blvd / La Mirada, CA 90638
714.994.2700 / Fax 714.994.0522 / www.aal.net
Vandal Proof is a registered trademark of Mullerplast
Designed in CA, printed in USA


RECESSED MOUNT




SURFACE MOUNT



POST MOUNT



PEDESTAL MOUNT



Architectural Area Lighting
 14249 Artesia Blvd • La Mirada, CA 90638
 714.994.0700 / Fax 714.994.0522 / www.aal.net
 Photo: © Copyright: Greg Clark of M.A. Reed
 www.aal.net © Copyright 2013

Specifications

HOUSING

Housing shall consist of heavy gauge aluminum construction. Housing for the Small Paracyl shall be diecast. Housing shall include a gasketed, hinged door frame. Door frame shall be heavy duty cast aluminum and retained by two stainless steel bolts or screws when opened for relamping or rotation of the adjustable reflector assembly. All exterior hardware shall be stainless steel. Note: An overlapping 3/4" door frame assembly shall be furnished when the recessed, poured concrete mounting option (RJC) is specified, recessing the line between outer edge of recessed housing and the surrounding concrete opening.

LENS

Projected lens shall be vandal resistant, U.V. stabilized injection molded polycarbonate, capable of spreading light horizontally at a full 180° with minimal vertical distortion. Flat lens shall be tempered glass, capable of spreading light horizontally at a full 180° with minimal vertical distortion. Lens shall be gasketed and secured from inside. The cast aluminum door frame

ELECTRICAL

Fixture shall be UL listed and CSA approved for use in outdoor wet locations. Ballast shall be high power factor multi-tap type (120/208/240/277V), 347V (120/277/240/47V) and 480V (480V) ballasts shall be available as options. Note: All ballasts (except 480V) are shipped from the factory wired for 277V.

OPTICAL SYSTEM

Optical system shall be adjustable, sharp cutoff type consisting of a hydroformed specular Alzak primary reflector with both parabolic and cylindrical reflecting surfaces, auxiliary reflecting elements and a support frame. Reflector assembly shall be rotatable to permit adjustment of cutoff from 70° through 80° above beam. Internal cutoff scale, calibrated in degrees, shall be provided to indicate the exact cutoff angle.

FINISH

Finish on housing shall consist of cleaning, etching and rinsing followed by a protective polymer primer, deionized water rinse, oven dry off and top coated with a thermoset 100% super polyester powder coat finish. Finish shall meet the AAMA 606.2 performance specification which includes passing a 3000 hour salt spray test for corrosion resistance.

WARRANTY

Product shall be warranted against defects in material and workmanship for a period of three (3) years from the date of original invoice, except for ballasts which shall carry the ballast manufacturer's warranty.



We have performed a constructability review of the plans and specifications dated 12/8/08 (Updated 1/5/09). These items were reevaluated based upon the 3/30/09 Final GMP drawings. The items noted below that are not struck-through still need to be addressed. The costs that may be associated with the outstanding items have not been incorporated into the Final GMP Proposal dated 4/29/09 unless otherwise indicated below.

It is the policy of J.E. Dunn Construction to review construction documents on our projects and make suggestions that may improve the integrity of our construction. This is done to ensure a safe and high quality building for the Owner. With this team concept and spirit, we would like to submit the following suggestions and questions for review of the Architect. It is not intended that such remarks override the authority of the Architect and no changes in the work suggested herein shall occur without the Architect's authorization.

General Construction Items

- 1) ~~Sheet C2.10: At the parking area north of Ring Road, there is a remark to "See Note 16". Note 16 doesn't exist on this sheet.~~
2) Sheet C2.10: At the east end of the site along Ring Road, Keynote10 is noted which is a note to provide a concrete driveway. This location is adjacent to the retention pond and should not be depicted at this location.
3) Sheet C2.30: Keynote 2 & 6 is part of the future trunk line work by others.
4) Sheet C2.50: At the northeast corner of the site inside Ring Road, an additional MH or storm line may be needed between MH T3 and the existing outfall of the 30" storm drain crossing Ring Road. This work is part of the trunk line work indicated to be installed by others.
5) ~~Sheet C2.68: Details and routing of site communications conflict with same shown on Sheet E1.00.~~
6) Sheet C5.12: Sections noted at Detail 4 refer to sections shown on S5.12 instead of C5.12.
7) ~~Sheet S2.00A: Footing Between Gridlines H2.5 & H3 / On Gridline 04; Notes section to be 7/S3.01. This Detail shows a Slab On Grade Floor Depression detail. Please provide the correct section for this location.~~
8) Sheet S2.00A: Review top of pier/footing elevations and coordinate w/slab thickness. Coverage between footing and bottom of slab = 11".
9) ~~S2.00A: Two piers H2.5 & H5.5/04 show bottom of pier at 56', both piers are shown under footing, coordinate footings as well as sump pit.~~
10) Sheets S2.04A & S2.04B / M2.04A & M2.04B: Verify all roof penetrations are shown on the Structural drawings, as it relates to actual size and locations of the mechanical openings to confirm opening reinforcement is acceptable or additional beams will be required. Reference S3.05.
11) Sheets S2.05, S2.05A & S2.05B: Top of roof slab varies. Structural drawings should indicate the exact elevations within the roof slab plans for each varying location. Please provide elevations.
12) ~~Sheet S3.07: Note 4 at Detail 7 & 7A indicates concrete in the pour strip shall not be poured until 90 days after Beams 2 & 4. Please change this requirement to 60 days per previous conversations during 50% DD review.~~
13) ~~Detail 11/S3.11 includes a plate and clip angle at each side of the top of CMU wall. Both clip angles are shown to be welded above the CMU and would need to be installed prior to the CMU but this blocks any pocket for being able to grout the top course. We have included only the interior clip angle welded to the embed plate and bolted to the CMU. We can discuss other options if this is not acceptable.~~
14) ~~Sheet SG2.01: For The Garage Level 1 and Foundation Plan, the detail that is found On Gridline 2 / Between Gridlines E & F references 10A /SG4.01. Detail 10A /SG4.01 is not found. Please provide this Detail. N/A~~

ATLANTA
AUSTIN
CHARLOTTE
COLORADO SPRINGS
DALLAS
DENVER
DES MOINES
> HOUSTON
KANSAS CITY
MINNEAPOLIS
MYRTLE BEACH
NASHVILLE
ORLANDO
PHOENIX
PORTLAND
SEATTLE
TOPEKA



Fort Bend County Justice Center

Constructability Review – 4/29/09

- 15) Sheet A0.10: Partitions Details 1 & 5 (for Partition types A, A1, E & E1) have a Note that states the following: 3 5/8" Metal Studs braced to structure as required. Provide spacing for bracing of wall partitions. Suggestion: 4' O.C.
- ~~16) Sheet A0.10: No Partition "J" Found In Contract Documents. Remove partition from contract documents or provide locations where the partition is to be used.~~
- 17) Sheets A0.20-A0.22 – Verify Finish Schedule for ceilings is coordinated with ceiling finishes shown on the RCP Sheets A3.00-A3.03.
- 18) Sheet A1.05: Detail 1/A1.05 references Detail 5/A1.05. Please provide 5/A1.05, which will provide an elevation for the HC Ramp & Stairs at the Judge's Parking.
- 19) Sheets A2.01A/M2.01A: The VAV box that is located in court room 10400 needs to be relocated outside of the room for trouble-free maintenance and removal. Other courtroom VAV boxes are located outside of the room.
- 20) Sheet A2.05A/A2.05B: The Roof Plans call for section details 1/A6.50 and 1/A6.51 however, these Details are not found on Sheets A6.50 and A6.51. Please provide these details.
- 21) Sheet A3.01: Reference Escalators in Lobby 10004. Please provide a section through the underside of the escalator soffits as none is currently provided.
- 22) Sheet A4.11: Need Elevator Details. Please provide Elevator Head and Sill Details. The Sections found on A4.11 reference wall sections found on Sheet A7.59.
- 23) Sheet A7.52: Detail 7 Wall section has incorrect detail key (19/A7.75) at wall/floor transition or detail should be labeled "SIM". Enlarged detail shows window sill.
- ~~24) Sheet A7.53: Detail 1 Wall section shows incorrect detail key at dock leveler (25/A7.77) Correct Detail is (31/A7.77)~~
- ~~25) Sheet A7.53: Detail 2 Wall section shows incorrect detail key (7/A7.75) at floor/stair transition. Enlarged detail does not show stair or stair tie in.~~
- 26) Sheet A7.55: Detail 1 Wall section is missing three detail callouts.
- 27) Sheet A7.55: Detail 13 Wall section show incorrect detail callouts (21/A7.77) for headers at level 2 and level 3. If this is correct detail it should be labeled "SIM".
- 28) Sheet A7.57: Detail 1 Wall section detail callout (29/A7.75) is incorrect or should be labeled "SIM".
- 29) Sheet A7.60: Detail 1 Wall section shows incorrect detail key at dock leveler (25/A7.77) Correct Detail is (31/A7.77).
- 30) Sheet A7.60: Detail 1 Wall section detail key at wall/roof intersection on columnline 01 is incorrectly labeled as (4/A7.76) the correct detail key is (4/A7.75).
- 31) Sheet A7.60: Detail 1 Wall section detail key (3/A7.76) at Level two wall/floor transition on columnline 1.3 is incorrect.
- 32) Sheet A7.62: Detail 19 Wall section detail key (21/A7.75) at window sills on Level 1 and 2 should read "OP.H & SIM".
- 33) Sheet A7.75: Detail 4 Typical parapet wall shows no coatings on the CMU between the roof termination and the coping flashing.
- ~~34) Sheet AG2.02: Please provide a section through the trench drain that is located on Column Line L and between Lines 2 & 3. Currently there are no Details provided for this drain. N/A~~
- ~~35) Sheet FS1.1 Note E: References corner guards on outside corners in foodservice area. Currently, there are no Corner Guards found in the Contract Documents. Please identify Corner Guard locations and provide Specifications or remove the notation.~~
- 36) Sheet S3.12: Structural steel shelf angles are not shown at or below Level 1 on the Building Elevations included in the Structural drawings.

A handwritten signature in black ink, appearing to read 'Kenny Eldridge'.

Kenny Eldridge
Senior PM

Exhibit N
Architectural Constructability Review

Project: Name: Fort Bend Country
Project Number: 07962
Drawing Set: March 30, 2009 – Final GMP Pricing Set
Date: April 17, 2009
QA Staff Reviewer: Todd Harper

The purpose of this review is to provide an assessment of the roofing, waterproofing, and exterior weatherproofing related items regarding general system design and material selection, and constructability. The following text presents our opinions/comments for this review and to be considered general and/or conceptual in nature. Please note that no changes suggested are, or will be, incorporated without direction from the Architect. If you have any questions please feel free to contact us.

Exterior Skin Materials:

- Materials per Specifications
 1. Exposed Flashing – (Per Spec 04 20 00)
 - Drawings call out Stainless Steel Flashing for multiple details?
 2. Flashing, Weep Holes, Cavity Drainage, and Vents – (Per Spec 04 20 00)
 - Section 3.10.B still mentions the asphalt-coated flashing which we are no longer using. This section needs to be modified to coordinate with Rubberized-Asphalt Flashing
 3. Ext. Sheathing – (Per Spec 06 16 00)
 - Densglass Gold for wall applications
 - Plywood sheathing for roof applications
 - Use FRT/Rated plywood where applicable.
 4. Exterior Metal Wall Panels (Per Spec 07 41 30)
 - Section Removed in Final GMP Specification
 5. Joint Sealants (Per Spec 07 92 00)
 - Note: for single component sealants Dow 795 is preferred.
 6. Overhead Coiling Grilles (Per Spec 08 33 26)
 - Section Removed in Final GMP Specification
 7. Glazed Aluminum Curtainwall (Per Spec 08 44 13)
 - This Spec Section is missing from Specifications please clarify.
 - It appears this section was renamed/numbered (08 51 13)
 8. Portland Cement Plaster (Per Spec 09 24 00)
 - This spec section is missing in Final GMP Specification

- Detail Items per Permit Drawings
 1. S2.00A – Review top of pier/footing elevations and coordinate w/slab thickness. Coverage between footing and bottom of slab = 11”.

Exhibit N
Architectural Constructability Review

2. S2.00A – two piers H2.5 & H5.5/04 show bottom of pier at 56', both piers are shown under footing, coordinate footings as well as sump pit.
3. A0.34/16 – Jamb detail does not show flashing. This jamb will need flashing and SAF to sufficiently protect the joint from ext. moisture. (Detail now shows SAF, but we would prefer metal flashing in this application w/SAF as tie-in material)
4. A0.34/17 – Head detail shows self adhered flashing but no drip. We would prefer using a metal flashing w/drip on top of lintel, set in mastic to separate metals, and extend past face of window. (SS flashing added w/drip edge in place of self-adhered flashing) We would then lap the self-adhered flashing (SAF) over the metal drip to seal the joint. The metal flashing material choice/installation needs to be studied so we don't run into a problem with dissimilar metals. This is why separating w/mastic might be a nice option if we can be assured we're keeping flashing/lintel separated.
5. A0.34/22 – Same comments as Detail A0.34/17
6. A0.34/23 – If this is exterior detail it would be nice to have a drip in the stone soffit transition or at the door head. We also need to add sealant to the CMU/Tube intersection to prevent moisture intrusion.
7. A0.34/24 – Same comments as Detail A0.34/17. Detail also labeled as Door Jamb but appears to be Door Head Detail, please confirm.
8. A0.35/13 – (Detail Removed)
9. A0.35/19 – (Detail Removed)
10. A0.35/22 – Window sill detail looks like it has correct components but detail is unclear. We need to make sure the sill pan flashing is set in mastic and applied to rowlock. We should be sealing window system directly to metal for best possible bond.
11. A0.35/24 – (Detail Removed)
12. A0.35/28 – Window head needs flashing if it has exterior exposure. Please confirm. If this detail is an exterior detail we need to add head flashing with drop edge. Tie-in flashing to wall with SAF.
13. A0.35/29 – Not sure if window jamb detail has exterior exposure. If it does need flashing. This will be complicated detail to execute, must be looked at carefully from a material/sequencing standpoint.
14. A0.36/1 – Window sill flashing should extend past face of window to beginning of stone sill slope. Our preference would be for window to seal directly to flashing for maximum bond strength. (Sill pan has been added, we need to provide end dams as well. Also sealant & backer rod are not shown)
15. A0.36/2 (A0.36/3) – Jamb Detail needs metal flashing extending past face of window system to separate window from cavity moisture. This provides the maximum amount of protection. The metal flashing should be applied and sealed with SAF. We should be sealing the window system directly to flashing for maximum bond strength. (The sealant & backer rod should start at the face of the window jamb instead of outboard as shown in the detail.)
16. A0.36/5 – Detail looks good, sealant & backer rod should start at face of window extrusion.

Exhibit N
Architectural Constructability Review

17. A0.36/13 – Window sill detail looks good. We just need to make sure sill pan is set in mastic and applied to lintel/rowlock. We also need to make sure we're sealing window system directly to metal flashing for best bond. (Sill pan has been added, we need to provide end dams as well. Also sealant & backer rod are not shown)
18. A0.36/15 – Window jamb needs metal flashing. (Ref. notes for Detail A0.36/3.)
19. A0.36/17 – Also more difficult to execute with notched masonry. Are we notching masonry? Please confirm? (Need to move the sealant & backer rod back flush with face of window head extrusion.)
20. A0.36/25 – See notes for A0.36/1
21. A0.36/27 – See notes for A0.36/3
22. A0.36/29 – Sealant & backer rod need to be moved back to align with face of window head extrusion.
23. A0.37/1 – Sill detail needs sealant & backer rod and sill pan should have end dams typical.
24. A0.37/3 – We should turn SAF out towards sealant & backer instead of in as shown in jamb detail. We would prefer adding metal flashing over Steel Angle leg and out past face of window system and seal window to metal flashing.
25. A0.37/5 – Need to move the sealant & backer rod back to the face of window head for adequate protection. Need to coordinate the sealant line with the jamb detail.
26. A0.37/13 – Need to make sure the sill pan has end dams, typ. Also detail is missing sealant & backer rod.
27. A0.37/15 – We should turn SAF out towards sealant & backer instead of in as shown in jamb detail. We would prefer adding metal flashing over Steel Angle leg and out past face of window system and seal window to metal flashing.
28. A0.37/17 – Need to move the sealant & backer rod back to the face of window head for adequate protection. Need to coordinate the sealant line with the jamb detail.
29. A0.37/25 – Sill detail needs sealant & backer rod and sill pan should have end dams typical.
30. A0.37/27 – We would prefer 90 degree metal flashing at the exterior jambs in lieu of SAF flashing if possible.
31. A0.37/29 – We would prefer having head flashing and drip installed at this location. Sealant & backer rod location needs to be coordinated with jamb sealant & backer rod.
32. A0.38/1 – Sill pan needs to extend past sealant line and be set in mastic. We also need end dams tied into sill pan typical.
33. A0.38/2 – We would prefer having 90 degree metal jamb flashing here in lieu of membrane flashing. As detailed it would be our preference to have the membrane flashing turn out towards the sealant line instead to encapsulate the cavity. Sealant & backer rod need to be coordinated carefully with head flashing.

Exhibit N
Architectural Constructability Review

34. A0.38/5 – We need to add metal flashing with drip edge at the window head.
35. A0.38/13 – Sill detail needs sealant & backer rod and sill pan should have end dams typical.
36. A1.07/11 – Thru wall flashing above canopy needs SAF on vertical leg.
37. A5.00/1 – (Detail/Detail Callout Corrected)
38. A5.00/2 – Pipe penetrations shown in metal stud track.
39. A5.00/3, 4– Plan detail needs callout for jamb condition. Pipe penetrations shown in metal stud track.
40. A5.00/5 – Plan details need callout for jamb condition.
41. A5.00/6 – Plan detail callout A0.36/15 SIM is not really similar condition. We should have new detail for this condition.
42. A5.00/8 – Plan details need callout for jamb condition.
43. A5.00/10, 11, 12 – Plan detail needs callouts for jamb conditions.
44. A5.00/14 - Plan detail callout A0.35/31 is not drawn/shown yet. Please add detail and ref. comments for appropriate flashing techniques.
45. A5.00/15 - Plan detail needs callout for jamb condition. Pipe penetrations shown in metal stud track.
46. A5.00/16 – Plan detail needs callout to detail waterproofing behind cmu in front of conc. column.
47. A5.00/18, 19, 20 - Plan details need callout for jamb condition.
48. A5.00/21 – Plan detail needs callouts for jamb condition. This could be a very difficult detail to execute/flash properly.
49. A5.00/23 – Plan details need callouts for jamb conditions.
50. A7.52/7 – Wall section has incorrect detail key (19/A7.75) at wall/floor transition or detail should be labeled “SIM”. Enlarged detail shows window sill.
51. A7.53/1 – Detail key (20/A7.76) @ overhead door head should be labeled “SIM”
52. A7.53/1 – Detail key (5/A7.76) @ Beam level should be labeled “SIM”
53. A7.53/2 – Wall section shows incorrect detail key (11/A7.75 SIM) at lower roof level @ clock tower.
54. A7.57/1 – Wall section detail callout (29/A7.75) is incorrect or should be labeled “SIM”
55. A7.60/1 - Wall section shows incorrect detail key (4/A7.76) at level 2 top of wall/roof intersection. Detail should be labeled (4/A7.75)
56. A7.75/1 –Apply SAF over top leg thru-wall metal flashing, typ.
57. A7.75/3 – (Detail Corrected)
58. A7.75/4 - We should also apply a layer of SAF at cmu/concrete ceiling joint for secondary protection should moisture get pasts damproofing.
59. A7.75/6 – We should add metal thru-wall flashing at the steel angle tied into the wall with SAF. We should also apply SAF at the wall/floor line.
60. A7.75/7 – Section detail calls for metal sill pan but not clear on execution at this scale. Sill pan needs to be set in mastic on cast stone sill. Sill pan drip should extend to start of cast stone slope. Sill pan also needs end dams typical. Window needs to seal directly to metal flashing/sill pan. Apply SAF over top leg of brick ledge metal flashing.

Exhibit N
Architectural Constructability Review

61. A7.75/9 –Metal flashing should be sealed with SAF, typical.
62. A7.75/10 – Ref. notes for Detail A7.75/7.
63. A7.75/11 – Section detail needs metal thru-wall flashing with drip edge at angle support. Tie in flashing with SAF, typ. We also need to add SAF at the floor/wall & ceiling/wall transitions to add extra layer of moisture protection.
64. A7.75/12 – SS Flashing needs drip edge, tie in flashing with SAF typical.
65. A7.75/13 – Window sill detail sill pan needs end dams typical. Set sill in mastic typical. Detail is too small to see flashing sequence; Architect should create enlarged detail to illustrate. Tie-in all metal thru-wall flashing with SAF typical.
66. A7.75/15 – Section detail needs to have SAF lapped over metal flashing at shelf angle. Flashing should also extend past shelf angle and have drip edge. The SAF we apply to vertical leg of metal flashing should extend 6”-8” past floor line for secondary protection. See notes for Detail A7.75/7 for window sill condition.
67. A7.75/17 – Sill detail needs SAF over interior leg of support angle. Extend sill pan flashing past face of window to cast stone sill slope. Set sill pan flashing in mastic and seal window directly to metal for max bond. Seal CMU/grade beam intersection with layer of SAF. Sill pan needs end dams typical. Need enlarged detail of sill to see flashing sequence.
68. A7.75/18 – Section detail needs metal flashing w/drip edge over steel lintel to extend past face of window. SAF should lap over cmu, steel tube, metal flashing to encapsulate joint.
69. A7.75/19 - Section detail calls for metal sill pan but not clear on execution at this scale. Sill pan needs to be set in mastic on cast stone sill. Sill pan drip should extend to start of cast stone slope. Window needs to seal directly to metal flashing/sill pan. Apply SAF over top leg of brick metal flashing at floor line. Sill pan needs end dams typical.
70. A7.75/21 – Ref. notes for Detail A7.75/17.
71. A7.75/23 – Head detail shows metal thru-wall flashing over cast stone header. The waterproofing/sealant @ window head is not clear b/c the detail is too small. We would prefer enlarged detail to study the flashing sequence and would prefer bringing the thru-wall flashing out at the window head over the lintel.
72. A7.75/27 – Install SAF at wall/floor line intersection for additional moisture protection.
73. A7.75/28 – Tie in metal thru-wall flashing to wall with SAF.
74. A7.75/29 – Add SAF to top leg of thru-wall flashing to tie into wall.
75. A7.75/35 – Section detail needs SAF for secondary protection shelf angles and at cmu wall/ceiling line. (Detail Corrected)
76. A7.76/1 – Ref. notes for Detail A7.75/4.
77. A7.76/2 - Section detail needs SAF over vertical flashing legs and flashing needs to extend past face of stone and have drip edge.
78. A7.76/3 –We need a layer of SAF over vertical leg of flashing, typ.
79. A7.76/5 – Section detail needs flashing to have drip edge and extend into stone reveal.

Exhibit N
Architectural Constructability Review

80. A7.76/6 – Section detail needs SAF over CMU/Concrete intersection at ceiling line for added protection (Corrected). We need to pay careful attention to the flashing at the cast stone/metal panel intersection.
81. A7.76/8 – Make sure thru-wall flashing has drip edge.
82. A7.76/10 – Make sure thru-wall flashing has drip edge and lap SAF over vertical flashing leg. Also add SAF to floor/wall intersection for additional protection.
83. A7.76/11 – Section detail shows no metal thru wall flashing. Investigate detail further to make sure flashing not needed at galvanized steel angles. Add SAF at floor/wall and ceiling/wall intersections and tie in thru-wall flashing with SAF.
84. A7.76/14 – (Detail Corrected)
85. A7.76/16 – Section detail thru wall flashing should extend past brick and to sloping portion of cast stone coping or to cast stone edge.
86. A7.76/17 – Enlarged detail shows notched stone. We will need to coordinate flashing to stay over lintel with drip edge. Tie-in top of flashing with SAF, typ.
87. A7.76/18 – See comments for A7.76/17
88. A7.76/20 – Section detail needs SAF lapped over vertical legs of thru wall flashing, typ. Flashing at window sill should extend past face of stone with drip edge. Sill pan should be set in mastic and extend to sill stone slope. Seal Alum window system to metal flashing at sill for max bond. Sill pan needs end dams, typ.
89. A7.76/22 – Extend flashing under sill past face of brick and add drip edge. Extend sill pan to beginning of stone sill slope, set in mastic. Seal Alum window to sill flashing for max bond. Sill pan needs end dams, typ.
90. A7.76/24 – Section detail needs SAF at CMU/Concrete ceiling intersection for extra layer protection. (Detail Corrected)
91. A7.76/25 – Section detail does not show sill pan for window system. This is needed and is typical on all storefront windows. Sill pan also needs end dams, typical.
92. A7.76/26 – Section detail does not show window head flashing. Window needs head flashing w/drip edge. We also need SAF at vertical leg of flashing.
93. A7.77/2 – Sill detail is too small to see flashing sequencing, need enlarged detail. Window needs sill pan w/end dams set in mastic typ. All thru wall flashing needs metal drip and should be ties into wall with SAF, typ.
94. A7.77/5 – Section detail shows thru wall flashing at various spots. Extend all thru wall to face of material and add drip edge. All vertical flashing legs sealed with SAF, typ. Need head flashing window head and enlarged detail would be preferred.
95. A7.77/14 – Section detail needs head flashing at lower window over steel lintel. We also need flashing in the cavity wall to extend to face of stone and have drip edge. Seal vertical flashing legs with SAF, typ. Sill pan flashing should be set in mastic and extend to beginning of stone slope for proper drainage. Sill pan needs to have end dams, typ.

Exhibit N
Architectural Constructability Review

96. A7.77/20 – Sill pan should have end dams and be set in mastic typ.
97. A7.77/21 – Section detail needs head flashing to extend past face of window with drip edge. Seal vertical flashing leg with SAF.
98. A7.77/24 – Ref. notes for Detail A7.75/20.
99. A7.77/28 – (Detail Corrected)
100. A7.77/29 – (Detail Corrected)
101. A7.78/3 – See flashing above door head but it's not called out. Seal top leg of flashing with SAF, typ.
102. A7.78/2 – Tie in thru-wall metal flashing with SAF. Seal wall/floor and ceiling/floor transitions with SAF.
103. A7.78/3 – Section detail at louver needs sill pan w/end dams.
104. A7.78/7 – Sill pan should have end dams and needs to extend past face of window and be set in mastic. Tie in all thru-wall flashing with SAF, typ.
105. A7.78/9 – (Detail Corrected)
106. A7.78/10 – Seal vertical leg of thru-wall flashing with SAF.
107. A7.78/11 – Metal head flashing needs drip edge. Tie in flashing to wall with SAF at vertical leg.
108. A7.78/16 – Seal vertical leg of head flashing with SAF.
109. A7.78/19 – Seal top of thru-wall flashing with SAF. Add layer of SAF at wall/floor line for extra protection.\
110. A7.78/22 – Add metal door head flashing with metal drip, tie flashing into wall with SAF.
111. A7.78/25 – Ref. notes for Details A7.78/7
112. A7.80/22 – Seal concrete/cmu intersection with SAF behind rigid insulation.

- Overall construction items
 1. Stainless Steel thru-wall flashing has been added. We need to make sure flashing has drip edge typical.
 2. We need to be careful with our dissimilar metals. We need to make sure our metal flashing is compatible with the steel lintels/angles or that we're separating with mastic or some other material to resolve this issue.
 3. Since thru wall flashing needs to extend to face of ext. skin material or past it, we'll need to confirm the aesthetic with Architect. This might affect the material or finish for our flashings.
 4. Sill pan end dams are not called out/shown in drawings but are called out in specification. We need to make sure all sill pans have end dams, typical.

- The Architect addressed a lot of the comments from the January 26, 2009 Permit Set Drawing/Spec Review. There are various details that lack consistency in showing SAF, flashing, drip edges, & notation. There are also some callouts that still need to be coordinated throughout the set. The only other big issue we'd like resolved is some of the head/jamb/sill details are still "too small" to really see the Architect's flashing intent. We'd like enlarged drawings of these details if possible; otherwise

Exhibit N
Architectural Constructability Review

most of our comments have been addressed in some form or fashion. I've highlighted all the changes from the initial permit review in Red Text for clarification.

Exhibit N
MEP Constructability Review

Project Name: Ft. Bend County Courthouse



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
		<u>HVAC</u>			
1	Specific ations	The specification for the boilers needs to be deleted.	X		
2		There is no specification for the air cooled chiller.	X		
3		There is no specification for dirt separators for the chilled water or condenser water.	X		
4		The specification for the air handlers is unclear as to how and where the VFDs are to be mounted in the units. Is there supposed to be a service vestibule? Or do the VFDs just mount in the fan sections? If so will there be sufficient clearance for maintenance for the fan and the drive, in particular the 3 foot clearance in front of the drive.	X		
5		The electrical specification for the engine generator does not list the minimum run time for fuel storage and does not specify the size of the fuel tank. This information could not be found on the drawings either.	X		
6	General Notes	None of the ductwork has been drawn in 2D or 3D. The design needs to be fully coordinated to sure all duct will fit in the spaces indicated and if there is proper clearances for maintenance and service to HVAC equipment and other systems. There are several locations where duct fittings will not work because once the duct is drawn in properly the branch connection will not work. or will be noisy.	X		
7		The terminal units were detailed with the required code clearance next to the control panel for service to the electric heaters. However approximately 50% of all of the terminal units have clearance issues that can not be corrected by means and methods. NEC requires 36" in front of all 277V and 480 V components. The engineer and detailer also need to allow for bottom access to fan powered terminal units require for maintenance and removal of the fan sections.	X		
8		There are terminal units that have potential return air flow problems at the entrance to the box because the box is too close to a wall or other obstruction.	X		

Exhibit N
MEP Constructability Review

Project Name: Ft. Bend County Courthouse



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
9		There is a note for every fan coil unit to pipe the condensate drain to a floor drain but no where on the drawings does it indicate which one. If you go to the nearest floor drain they will be in restrooms and in the basement they will be in holding cells. Drains on the floors of rest rooms is not a desirable condition and drains in holding cells should not be done. hub drains should be added for drains for all fan coil units.	X		
10		No where on the mechanical drawings does it appear there is air conditioning or heating for the major stair wells.	X		
11		The return air boots that come out of the shafts in these drawings don't appear they will work. With the bottom of concrete at 13 feet and a 36" deep boot and the requirement to have to have the openings on top. Please provide a detail of this boot at the shafts indicating the space clear above the boot at the opening , the fire smoke dampers and the structure including the ceiling below.	X		
12		In general there are not elevations on the ductwork drawing leaving it up to the contractors to determine the routing. This leaves substantial openings for change orders as there are no fittings for duct rises or drops indicated. The bidding contractors will want additional funds for these fittings not shown or indicated in some manner.	X		
13		There are no details on any of the mechanical sheets indicating how the supply air takeoffs are to occur at the shafts. If you try and use Detail #4 on M6.04, there is not sufficient room in the shaft to allow the 45° Clinch collar in the detail. Trying to install a fire damper directly into the side of the supply air duct risers will be difficult at best and will be the source of significant pressure drop and noise.	X		
14		The chilled water piping should be shown in all of the shafts as it is intended. In the shaft at Column 4/H.5 the supply air duct needs to move and the location of the piping on the roof plan has the piping running through concrete beams. Has the penetration of the beams with chilled water lines been approved by the structural engineer? This is typical for all shafts.	X		

Exhibit N
MEP Constructability Review

Project Name: Ft. Bend County Courthouse



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
15	M2.00A	The ductwork from VF-B7,B6 and TEF-B1 is stacked along the north wall of the shell space at column line 1.8. The designer should calculate the bottom of duct for all three ducts and figure out how to fix the low duct problem. Preliminary indications is the bottom of the lowest duct is 7'2" AFF.	X		
16		The ductwork indicated above is not properly detailed to indicate all of the rises etc that will have to occur. The designer should cut a section through this area.	X		
17		There are 3 fan coils on this drawing that should have hub drains added for the condensate.	X		
18		There are 2 terminal units that have potential clearance problems on this sheet.	X		
19		There are 3 terminal units that have potential return air flow problems at the entrance to the box because the box is too close to a wall or other obstruction.	X		
20		There are 3 fire smoke dampers located in ductwork at column line 6/H.2 that should be detailed in double line to ensure there is proper clearance between the middle duct and the two outside ducts to fit the damper actuator in on the side of the fire damper and to be able to remove it. Some of the ductwork may have to be offset to make it work.	X		
21	M2.00B	There are 2 terminal units with access problems on this sheet.	X		
22		At the shaft at column line H.5 there is a 34/30 duct that is not labeled. It appears it might be a return air duct coming from the shaft but it goes nowhere and has no opening except for a symbol for a reducer at the north end.	X		
23		The shaft at col H.5 does not exist at this level. The fire smoke dampers shown in the ducts will have to be moved to the floor as horizontal units. Backgrounds need to be coordinated with the architectural.	X		
24		There is no indication where the elevator mechanical room is for elevator 5 at column H.5	X		
25		There is 1 fan coil and two other locations on this drawing that should have hub drains added for the condensate.	X		



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
26	M2.01A	The Duct leaving the shaft at column E/4 may not work. Drawn in single line it appears to work fine but reality is the duct will be a lot wider then the one line on the drawings. Problems include not enough room for fittings after the fire damper, crossing over the corner of the data room which will effect the framing of that room, no room for access door for the fire smoke damper.	X		
27		The shafts on the west side of the building do not go all the way to the floor level of the first floor. They stop at the slab of the second floor. Just look at the backgrounds from the architect. The fire smoke dampers need to be located at the floor level as horizontal fire smoke dampers. typical for all shafts except Supply air riser #3 on the east half of the building. The Drawing needs to be corrected.	X		
28		The north shaft appears to be missing fire smoke dampers please correct when the drawings are fixed from the item above.	X		
29		The two terminal units in Room 10316 on the north side of the main corridor are not ducted the same as others units on the primary side of the box. Is this intended and if so why?	X		
30		There are at least 13 terminal units on this sheet that have clearance problems, Refer to the general notes above.	X		
31		There are at least 9 Terminal units on this sheet that have potential return air problems.	X		
32		In the Jury Deliberation room at column line 2/A.7 there is a potential conflict with a return air boot and the exhaust duct. Provide duct elevations and detail boot in double line to make sure there is proper clearance.	X		
33		There are 10 fan coils on this drawing that should have hub drains added for the condensate.	X		
34	M2.01B	The two shafts on the east side of the building at column line L, do not go all the way to the floor level of the first floor. They stop at the slab of the second floor. Please review the backgrounds from the architect. The fire smoke dampers need to be located at the floor level as horizontal fire smoke dampers. typical for all shafts except Supply air riser #3 on the east half of the building.	X		
35		Refer to #11 in the general notes section of this document regarding return air boots at the shaft at column H.5 only.	X		



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
36		The south shaft at column line L has a low pressure duct detailed to pass through the shaft. Please provide a detail on how this is to happen and interface with the return air duct shown.	X		
37		In the shaft at column line 04/H5 The chilled water risers are not shown, had they been drawing in the detailer would have found a conflict between the 12" chilled water risers and the Supply air duct. Please provide revised details and drawings. This can be verified by looking at the basement plans and the roof plans.	X		
38		Please provide a detail of how the revised supply air duct on the north will come out of the bottom of the shaft and pass through and or over the fire wall at passport clerks office at col 6.7/L.	X		
39		There are at least 4 terminal units on this sheet that have clearance problems, Refer to the general notes above.	X		
40		There are at least 3 Terminal units on this sheet that have potential return air problems.	X		
41		At Column line 9/M.6 there is a spin in and MVD missing.	X		
42		There are 4 fan coils on this drawing that should have hub drains added for the condensate.	X		
43	M2.02A	The Duct leaving the shaft at column E/4 may not work. Drawn in single line it appears to work fine but reality is the duct will be a lot wider then the one line on the drawings. Problems include not enough room for fittings after the fire damper, crossing over the corner of the data room which will effect the framing of that room, no room for access door for the fire smoke damper.	X		
44		The Duct leaving the shaft at column E/7 may not work. Drawn in single line it appears to work fine but reality is the duct will be a lot wider then the one line on the drawings. Problems include not enough room for fittings after the fire damper, crossing over the corner of the SEC Conference room which will effect the framing of that room, no room for access door for the fire smoke damper.	X		
45		At col 1.4/D.5 there is a terminal unit shown on top of a restroom wall which is probably going to be a full height wall. Please provide installation details for this application.	X		
46		There are at least 27 terminal units on this sheet that have clearance problems, Refer to the general notes above.	X		

Exhibit N
MEP Constructability Review

Project Name: Ft. Bend County Courthouse



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
47		There are at least 20 Terminal units on this sheet that have potential return air problems.	X		
48		At col 10/D there is a terminal unit shown on top of a Jury Room wall which is probably going to be a full height wall. Please provide installation details for this application.	X		
49		The four terminal units shown on the north side of court room 20466 have issues with clearances and maintenance issues.	X		
50		Refer to #11 in the general notes section of this document regarding return air boots at the shafts.	X		
51		There are 6 fan coils on this drawing that should have hub drains added for the condensate.	X		
52	M2.02B	In the shaft at column line 04/H5 The chilled water risers are not shown, had they been drawing in the detailer would have found a conflict between the 12" chilled water risers and the Supply air duct. Please provide revised details and drawings. This can be verified by looking at the basement plans and the roof plans.	X		
53		At Column line 9.1/K there is a box on top of a wall causing a problem with access and clearance.	X		
54		The high pressure take off to the terminal unit BH at column 5.5/I.2 will not work. Even if the fittings would physically fit there would not be the specified upstream duct diameters required for air flow measurement at the terminal unit inlet.	X		
55		At column line 7.5/O.8 there will be a conflict between the return air boot and the low pressure supply branch duct.	X		
56		In the assistant office 20240 at column line 5/J.7 there is a fire damper in the return air opening but none in the supply, please confirm no fire damper is required in the supply.	X		
57		There are at least 14 terminal units on this sheet that have clearance problems, Refer to the general notes above.	X		
58		There are at least 18 Terminal units on this sheet that have potential return air problems.	X		
59		Refer to #11 in the general notes section of this document regarding return air boots at the shafts.	X		



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
60		At the shaft at column line 5/H.5 there is a supply diffuser located under the already tight R/A boot and there is a low pressure duct running over the top of the boot. Please provide details on how this is all supposed to fit in the overhead clearance available.	X		
61		At column line 6/L there is a low pressure duct indicated to be running into the R/A boot at the shaft, is this intended?	X		
62		There are 4 fan coils on this drawing that should have hub drains added for the condensate.	X		
63	M2.03A	The Duct leaving the shaft at column E/4 may not work. Drawn in single line it appears to work fine but reality is the duct will be a lot wider then the one line on the drawings. Problems include not enough room for fittings after the fire damper, crossing over the corner of the data room which will effect the framing of that room, no room for access door for the fire smoke damper.	X		
64		The Duct leaving the shaft at column E/7 may not work. Drawn in single line it appears to work fine but reality is the duct will be a lot wider then the one line on the drawings. Problems include not enough room for fittings after the fire damper, crossing over the corner of the SEC Conference room which will effect the framing of that room, no room for access door for the fire smoke damper.	X		
65		At col 1.4/D.5 there is a terminal unit shown on top of a restroom wall which is probably going to be a full height wall. Please provide installation details for this application.	X		
66		There are at least 24 terminal units on this sheet that have clearance problems, Refer to the general notes above.	X		
67		There are at least 14 Terminal units on this sheet that have potential return air problems.	X		
68		The terminal units at column lines 2/B, 2/C.3, 2/E, 2/G, 9/B, 9.3/C, 9.3/B, 9/H, 8/H, 7.8/H are on top of a wall to a corridor, is this intended if so please provide a detail of how box is to get access for maintenance and NEC code clearance.	X		
69		There are 6 fan coils on this drawing that should have hub drains added for the condensate.	X		
70		Refer to #11 in the general notes section of this document regarding return air boots at the shafts.	X		



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
71	M2.03B	In the shaft at column line 04/H5 The chilled water risers are not shown, had they been drawing in the detailer would have found a conflict between the 12" chilled water risers and the Supply air duct. Please provide revised details and drawings. This can be verified by looking at the basement plans and the roof plans.	X		
72		The Grand Jury space at column lines 6/I.2 to 9/I.2 appears to be lacking return air openings to the shell space allowing return air to get back to the shaft.	X		
73		There are at least 7 terminal units on this sheet that have clearance problems, Refer to the general notes above.	X		
74		There are at least 13 Terminal units on this sheet that have potential return air problems.	X		
75		There are 4 fan coils on this drawing that should have hub drains added for the condensate.	X		
76		The terminal units at column lines 2/J, 2/L, 2/O, are on top of a wall to a corridor, is this intended if so please provide a detail of how box is to get access for maintenance and NEC code clearance.	X		
77		Refer to #11 in the general notes section of this document regarding return air boots at the shafts.	X		
78	M2.04A & B	No heat or cooling in stair head house.	X		
79		The direction to route the piping above the roof is a improper. Supporting piping from the roof will cause either problems with the roof or an excessive number of pitch pockets which will be hard to maintain and keep from leaking. Is it intended to hang the piping from the steel supporting the false roof? is there sufficient clearance in the locations shown? Have the loads been approved by the structural engineer?	X		
80		The piping and ductwork penetrations indicated on the drawings will not work. Roofers typically require 18" between roof curbs and adjoining obstructions for proper flashing and sealing. The only way to locate these penetrations is to build a dog house for everything but the ducts will have to be offset to allow them to be sealed and insulated. This is not a good method for doing this. Suggest the engineer look at specifying semi custom units that incorporate the return air, supply air and piping penetrations in the foot print of the unit. It will be a little more first cost but the roofing problems will be minimized.	X		



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
81		Routing of the chilled water risers needs to be coordinated down through all of the floors.	X		
82		There are no pipe sizes indicated on the drawing. These need to be added.	X		
83	M2.04B	The piping to the two fan coil units on the roof is not shown on the plan, Please correct this issue. Be sure to include hub drains.	X		
84	M3.01	There is no reference to cooling towers or frames on the structural drawings. Architectural drawings refer the plan reader to the civil drawings which indicate the towers are to sit on pads. This raises several questions: How is the external equalization line that has to be piped under the towers going to work? If the towers are not elevated so the bottom of the cold water basin is above the center line of the condenser water pumps by at least 3 feet, or the piping will air lock and the pumps will not be able to draw water from the towers.	X		
85		Continuing the above thought - Note #23 requires the centerline of the condenser water pump header to be 1" above the centerline of the pump suction as a minimum. The engineer needs to perform the NPSHA calculation and make sure the distance is not greater than 1" to ensure proper flow. Also how does the engineer expect the mechanical contractor to pipe up these large pipe diameters with a one inch offset between the center lines of the header and pump. The pump suction piping is 10" not easy to offset a small distance without a long run. Also if a suction diffuser is used the header will have to be a lot higher, thus making the tower higher. This issue needs to be addressed before any pumps or piping is ordered and before the piers are completed.	X		
86		The design engineer needs to provide details of how the tower is to be mounted. Suggest cutting a section through the plant and tower location and performing the net positive pump suction head calculation.	X		

Exhibit N
MEP Constructability Review

Project Name: Ft. Bend County Courthouse



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
87		The condenser water pumps are scheduled on M5.01 as end suction pumps, the detail on Drawing 8/M6.03 indicates there is a minimum of 4 pipe diameters between the pumps and the suction diffuser. The layout in the plant does not provide sufficient distance between the pump header and the suction of the pump for the 4 pipe diameters or suction diffuser.	X		
88	M4.01	The pumps indicated on the drawing are indicated as double suction horizontal split case pumps not End suction pumps as specified. Makes a difference as to how they are piped and what devices are on them.	X		
89		The chemical feed system for the cooling towers is not indicated on this flow diagram, at least the connection points should be indicated.	X		
90		There is not a dirt separator or tower sweeper system indicated anywhere on the plans. System will become very dirty very fast especially with the towers at ground level.	X		
91		There is no central air or dirt separator indicated in the chilled water system, there are air vents shown at the top of the risers on M4.02,3 but typically there is a master air and dirt separator in the plant.	X		
92		There is a flow meter indicated in the chilled water supply piping between the discharge of the last pump and the minimum flow bypass but there is no flow meter in the return line from the building. The return flow from the building is the only true indication of building load, suggest adding a flow meter in the return before the minimum bypass.	X		
93		How does the control system know how much water is flowing through the bypass? How is the bypass control valve to be actuated?	X		
94	M4.02	The piping to the fan coil units in the basement should be changed from 2" to 1-1/2" to be consistent with the piping on the remainder of the sheet.	X		
95		The piping to the fan coils units on the first floor west should be up sized to 2-1/2".	X		
96	M4.03	The CHWS and CHWR between OAHU-1 and AHU -2 could be downsized from 8 to 6" to be consistent with the pipe sizing on the rest of the sheet.	X		



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
97		The 1-1/2" piping between the fans coils in the upper right hand corner of the sheet is not consistent with similar fan coils on the sheet. The 1-1/2" should be 1" and the branch feeding both units should be 1-1/4" to be consistent.	X		
98		Why is the chilled water piping routed to the top of the building and then routed down. This could cause air locking problems. The distribution to the fan coil risers or the entire system could be done on the first floor if desired. This would reduce the number of roof penetrations significantly. It should also be less expensive, and it is possible to reduce the riser to the roof to a 10" or make all of the risers feed their respective air handlers and fan coils, reducing most of the risers to 4 or 5" pipe which has lower cost fittings and fab time. Should also reduce the number of pipe supports on the roof.	X		
99		5 of the Keyed notes at the bottom center of the sheet have no numbers, are they used on this sheet and if so where?	X		
100	M4.04 - Detail #1, 2, 4, 5	Where is the 72x20 R/A duct? It is not indicated on the plans anywhere? If it is to be the return air the units the velocity is 4000 FPM - very noisy. The roof plan shows a 108x44 R/A duct which is 1212 FPM. Indicate the return air to the units as required.	X		
101		The shaft does not extend below the second floor slab, coordinate with the architectural plans and located fire smoke dampers in the 2nd floor slab. Rework ductwork accordingly.	X		
102		Verify the size of the return air boots out of the shaft on all levels and make sure there is clearance above the ceiling for the boot, the ceiling and room above the boot.	X		
103	M4.04 - Detail #3	Where is the 24x20 & 30x20 R/A duct? It is not indicated on the plans anywhere? The roof plan shows a 108x44 R/A duct which is 1212 FPM.	X		
104		The shaft does not extend below the first floor slab, coordinate with the architectural plans and located fire smoke dampers in the 2nd floor slab. Rework ductwork accordingly. Indicate the return air to the units as required.	X		
105	M5.01	The end suction pump detail on M6.03 indicates suction diffusers but none are scheduled in the pump schedule.	X		

Exhibit N
MEP Constructability Review

Project Name: Ft. Bend County Courthouse



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
106		The pump schedule should include the Net positive suction available, NPSHA and the Net Positive Suction Required, NPSHR for the condenser water pumps.	X		
107	M5.02	In the terminal unit schedule there is a box neck size "C" indicated but there is no table for the C neck size below?	X		
108		Does the air cooled chiller have a heat trace circuit required on the chiller barrel? If so coordinate with the electrical plan - there is no circuit shown on the electrical plan.	X		
109	M6.01	Detail # 2 does not apply to this project.	X		
110	M6.03	Detail #1 - could not find a roof top mounted packaged A/C unit on the plans? What does this detail pertain to? If it is meant to be for the roof top mounted air handlers it is not correct.	X		
111		Detail #5 is a problem waiting to happen, this will cause many roof leaks and should be avoided. Suggest finding a different method to support the piping above the roof or distribute the chilled water below the roof.	X		
112		Detail #8 - The design of the central plant did not take into account the 4 pipe diameters required between the suction diffusers and the pump suction. Typically you use a pump suction diffuser to reduce the space requirements and most manufacturers will allow and even suggest bolting them directly to the pump suction. The engineer either needs to revise the detail so it works with the current design or he needs to redesign the plant.	X		
113		If the chilled water plant is a separate slab or structure from the main building the use of spring isolators on the inertia pad is not required. Typically the pumps can be bolted directly to the floor/housekeeping pad and use the entire mass for inertia dampening.	X		
114	M6.04	Detail #1 Many of these R/A boots indicated on the drawings may have clearance problems with other ducts in the plan or other items. Suggest the designer show these units at least per the detail in the plans and resolve any conflicts before the final set is issued.	X		
115		Detail #2 - - does not show the required NEC clearance for access to the 277 V or 480 V control panel for the electric heat, please add to the detail.	X		

Exhibit N
MEP Constructability Review

Project Name: Ft. Bend County Courthouse



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
116		Detail #2 This detail does not work for several of the box locations, suggest the engineer detail up all of the terminal units in plan per this detail and make sure there is sufficient room for the 2 duct diameters of hard pipe, the flex length and the fittings or elbows upstream of the unit.	X		
117		Detail #4 - does not work for the shaft riser duct. Duct is too large to allow the take offs shown. Engineer needs to modify the duct to allow for the 45 deg clinch fitting.	X		
118	EP2.00A	There are at least 22 locations on this sheet that should have power for fire/smoke or smoke dampers but none is shown. Please add the circuits and fire relays for these dampers. Coordinate the number with the mechanical engineer and detailer.	X		
119	EP2.00B	There are at least 9 locations on this sheet that should have power for fire/smoke or smoke dampers but none is shown. Please add the circuits and fire relays for these dampers. Coordinate the number with the mechanical engineer and detailer.	X		
120	EP2.01A	There are at least 7 locations on this sheet that should have power for fire/smoke or smoke dampers but none is shown. Please add the circuits and fire relays for these dampers. Coordinate the number with the mechanical engineer and detailer.	X		
121	EP2.01B	There are at least 18 locations on this sheet that should have power for fire/smoke or smoke dampers but none is shown. Please add the circuits and fire relays for these dampers. Coordinate the number with the mechanical engineer and detailer.	X		
122		Could not find any circuits for a disposal under the sink in the kitchen. Please verify there is no disposal circuit required.	X		
123	EP2.02A	There are at least 7 locations on this sheet that should have power for fire/smoke or smoke dampers but none is shown. Please add the circuits and fire relays for these dampers. Coordinate the number with the mechanical engineer and detailer.	X		
124	EP2.02B	There are at least 12 locations on this sheet that should have power for fire/smoke or smoke dampers but none is shown. Please add the circuits and fire relays for these dampers. Coordinate the number with the mechanical engineer and detailer.	X		
125	EP2.03A	There are at least 7 locations on this sheet that should have power for fire/smoke or smoke dampers but none is shown. Please add the circuits and fire relays for these dampers. Coordinate the number with the mechanical engineer and detailer.	X		



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
126	EP2.03B	There are at least 12 locations on this sheet that should have power for fire/smoke or smoke dampers but none is shown. Please add the circuits and fire relays for these dampers. Coordinate the number with the mechanical engineer and detailer.	X		
127	EP2.04A & B	VFDs are indicated to be supplied by the electrical contractor but the air handler specifications indicate the VFDs for the air handler are by the manufacturer. Please clarify. Also add language to the specifications that make the air handler manufacturer responsible for the location and clearances required by the NEC for the drives.	X		
128		For disconnects not mounted on the drives or in plain sight of the drive JED recommends adding a micro switch to the disconnect handle that is wired to the emergency stop circuit in the drive so that when the power is cut off at the disconnect the drive is actually de-energized. Typical all drives meeting this criteria	X		
129		Could not find any power circuits dedicated to power up the DDC panels that are sure to be on the roof. Please add as necessary.	X		
130		Is there a lightning protection plan?	X		
131		Have the security camera positions been coordinated with the false roof etc?	X		
132	E3.01	No where in the specification or on the drawings is the size of the fuel tank indicated for the generator nor is there a minimum run time specified in hours or days without refueling. Please provide this information in the specifications and on the drawings.	X		
133		Is the circuit for the transformer ETC in the duct bank, should there be a homerun circuit shown indicating which panel it is wired from inside the building?	X		
134		Should note number 5 read "Via the VFD in..."	X		
135		Please verify the air cooled chiller does not need a separate circuit for the heat tape on the chiller barrel.	X		
136		There are no circuits shown for the cooling tower sump heaters that are specified with the towers. Please add the circuits and any other connection information required for the sub to do a complete job.	X		
137		Show wiring for cooling tower vibration switches.	X		
138		Provide circuits for heat tape on domestic cold water lines - coordinate with the plumbing engineer.	X		



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
139	E3.01 & E4.01 & 2	For disconnects not mounted on the drives or in plain sight of the drive JED recommends adding a micro switch to the disconnect handle that is wired to the emergency stop circuit in the drive so that when the power is cut off at the disconnect the drive is actually de-energized. Typical all drives meeting this criteria Show wiring for the safety circuit.	X		
140		Verify the large centrifugal chillers do not need a 120 volt control power circuit.	X		
141	E3.10	Please verify there is no disposal and corresponding circuit required.	X		
142	E4.03	Indicate circuits for cooling tower sump heaters.	X		These may have been deleted.
143	E7.01, 2, & 3	Should relay panels be indicated for the fire alarm relays required for fire smoke dampers?	X		
144	P2.00A	The notes on the sheet for the roof drain overflow pipes indicate the pipe is to extend outside the building and turn down. This means there will be a large elbow outside the building projecting at least 1.5 times the diameter of the pipe so it can be properly sealed., Is that what the Architect wants?	X		
145		Are there going to be splash blocks provided for the overflow drains?	X		
146		There are 3 locations where hub drains should be added for FCU's/	X		
147	P2.00B	The notes on the sheet for the roof drain overflow pipes indicate the pipe is to extend outside the building and turn down. This means there will be a large elbow outside the building projecting at least 1.5 times the diameter of the pipe so it can be properly sealed., Is that what the Architect wants?	X		
148		Are there going to be splash blocks provided for the overflow drains?	X		
149		There are 4 locations where hub drains should be added for FCU's/	X		
150	P2.01A	There at least 5 locations where hub drains should be located for FCU's and or where FCU's can be combined into one hub drain.	X		
151	P2.01B	There at least 2 locations where hub drains should be located for FCU's and or where FCU's can be combined into one hub drain.	X		
152		What is the type of sink to be provided by Division 15 for the kitchen?	X		
153		Notes in the kitchen are hard to read should consider providing a larger plan detail.	X		
154		Please verify there are no disposals required in the kitchen.	X		



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
155	P2.02A	There at least 3 locations where hub drains should be located for FCU's and or where FCU's can be combined into one hub drain.	X		
156	P2.02B	There at least 2 locations where hub drains should be located for FCU's and or where FCU's can be combined into one hub drain.	X		
157	P2.03A	There at least 3 locations where hub drains should be located for FCU's and or where FCU's can be combined into one hub drain.	X		
158	P2.03B	There at least 2 locations where hub drains should be located for FCU's and or where FCU's can be combined into one hub drain.	X		
159	P2.04B	Add two hub drains for the fan coil units on the roof.	X		
160	P3.01	Where does the water go when the cooling towers are emptied or cleaned? What about the dirt form the tower?	X		
161		Is there a meter on the cold water make up to the tower? Does the city or utility allow the owner to account for the evaporated water to be deducted from the sewer bill?	X		
162		Please consider adding a hose bibb at the cooling tower make up line.	X		
163		There are no electrical circuits indicate on the electrical plans for the heat tracing on the cold water piping, please coordinate with the electrical engineer.	X		
164		There is no oil separator in the central plant, what happens if one of the centrifugal chillers blows a oil circulation line? Does the Owner have a containment program? Will it be washed down the drain?	X		
165		There are no rest rooms in the central plant. The design team might want to rethink this as periodic maintenance on the chillers and towers can take several hours, if this is done by outside contractors there could be potential for these contractors to have to go in and out of the building. Better to leave them in the plant. A one stall room should be sufficient.	X		
166		Consider adding drains at both ends of the chillers. Maintenance on the tubes requires the removal of both ends and brushing the tubes with water, there is no way to avoid having a lot of water on the floor during this procedure, better to have drains at both ends.	X		
167		Consider moving the floor drain by the domestic water booster pump skid for service purposes.	X		
168	P-500	Should the emergency shower and eye wash have a flow alarm on it back to the BAS? The plant is remote and someone could be in the plant, have an accident and no one would know.	X		

Exhibit N
MEP Constructability Review

Project Name: Ft. Bend County Courthouse



DATE: 4-24-09

SCOPE OF WORK: MEP Drawings of 3-30-09

BID DOCUMENTS REVIEW/INQUIRIES

Item #	Drawing Number	Description	Response Required	Observation Only	Comments
169	P5.02	Fire pumps details - is a water gong required?	X		
170		Is there a roof header required	X		
171		What is the terminal connection device or valves on the fire pump test header.	X		