

PO 125199

44 R

CHANGE ORDER

FORT BEND COUNTY ENGINEERING

- Distribution:
- FBC Engineering
 - FBC Judge
 - FBC Purchasing
 - Contractor
 - Consultant

Address: 301 Jackson Street
 Richmond, Texas 77469
Phone: 281-633-7500
Fax: 281-342-7366
Web site: www.FortBendCountyTx.gov

PROJECT:
 Paving, Drainage, and Water Line for Sansbury Blvd
 From Grand Estates Drive to Canyon Lake Drive

CHANGE ORDER NUMBER 01
 DATE..... 07-10-15
 PROJECT NUMBER 15-065
 CONTRACT FOR \$1,153,196.50
 CONTRACT DATE 04-30-15
 FBC PURCHASE ORDER NO 125199

CONTRACTOR:
 Rodriguez Construction Group, LLC
 2647 Jo Ann Street
 Stafford, TX 77477

The contract is changed as follows:

See attached Change Order no. 1 Breakdown


Not valid until signed by Fort Bend County and Contractor.

The Original (Contract Sum)	\$	1,153,196.50
Net change by previously authorized Change Orders	\$	0.00
The (Contract Sum) Prior to this Change Order was	\$	1,153,196.50
The (Contract Sum) will be <input checked="" type="checkbox"/> increased or <input type="checkbox"/> decreased or <input type="checkbox"/> unchanged by this Change Order in the amount of		
.....	\$	7,198.20
The new (Contract Sum) including this Change Order will be	\$	1,160,394.70


The Contract Time will be increased **or** decreased **or** unchanged by _____ days.
 The Date of Substantial Completion as of this Change Order therefore is
 changed **or** unchanged to **07-30-15**.

Authorized:


Fort Bend County Engineering
 Clay Forister, P.E.
 301 Jackson
 Richmond, Texas 77469

By: 
(signature)
 DATE: 17 JUL 15

Rodriguez Construction Group, LLC
 Roy Rodriguez, President
 2647 Jo Ann Street
 Stafford, TX 77477

By: 
(signature)
 DATE: 7/10/15

Fort Bend County Judge
 Honorable Robert E. Hebert
 301 Jackson St., #719
 Richmond, Texas 77469

By: 
(signature)
 DATE: 7-28-15



JULY 17, 2015
CHANGE ORDER NO. 1 - BREAKDOWN

FORT BEND COUNTY ENGINEERING - SANBURY BLVD FROM CANYON LAKES TO GRAND ESTATES
PURCHASE ORDER NO. 125199

ITEM NO. 1 - ADDITIONAL 12" GATE VALVE AT EAST WET CONNECTION

TOTAL ITEM NO. 1				\$2,206.40
-------------------------	--	--	--	-------------------

ITEM NO. 2 - THE CARMAX STORM SEWER TIE-IN REQUIRED AN UPSIZE IN THE RCP AT STATION 10+00 TYPE C MANHOLE #A2:

ADD	60LF	42"RCP	\$140.75/LF	\$8,445.00
DEDUCT	60LF	36"RCP	\$102.37/LF	-\$6,142.20
DEDUCT	1 EA	BRICK PLUG	\$250.00/EA	-\$250.00
TOTAL ITEM NO. 2				\$2,052.80

ITEM NO. 3 - REVISED THE PROPOSED 5' CONCRETE SIDEWALKS FROM 6" THICKNESS TO 4.5" THICKNESS:

DEDUCT	15,030 SF	SIDEWALK	\$0.55/SF	-\$8,266.50
TOTAL ITEM NO. 3				-\$8,266.50

ITEM NO. 4 - ADD 8" DRIVEWAY TO SERVE CARMAX DEALERSHIP AT STATION 2+60

ADD	90 SY	8" DRIVEWAY	\$59.55/SF	\$5,359.50
TOTAL ITEM NO. 4				\$5,359.50

ITEM NO. 5 - INSTALL 6" SEWER STACK TO CORRECT CONFLICT OF EXISTING 4" SEWER LEAD WITH STORM SEWER AT STATION 1+20

ADD	1 LUMP SUM	SEWER STACK	\$5,846.00	\$5,846.00
TOTAL ITEM NO. 5				\$5,846.00

TOTAL ADD				\$15,464.70
TOTAL DEDUCT				-\$8,266.50
TOTAL CHANGE ORDER NO. 1				\$7,198.20