



Monday 3-6-23

FORT BEND AGRICULTURE EXTENSION

1402 BAND

Rosenberg, Texas

Attn: Justin

Project: 1402 BAND = Install new underground piping for FDC

Fire Sprinkler Repair Price: \$34,724.00 (Excludes Sales Tax)

EXPECTED SCOPE: The expected scope is to excavate existing underground fire line, replace approximately 40 LF of 4" piping with C-900 DR-18 PVC pipe, reset FDC head on new MJ 90 Ell, provide new vertical FDC pipe with ball drip, install a new 4" ductile iron riser from 5' out to 1' above finished floor outside, core hole in front exterior wall, install new above grade pipe and fittings through wall, and connect to existing vertical FDC piping inside upstream of check valve. Existing in slab riser shall be abandoned in place and paving R&R is included in this scope as necessary to complete the scope of work.

Note:

1. Our trenches shall be backfilled with excavated soils.
2. Should the Authority having Jurisdiction require changes in design or additional appurtenances, those changes and/or additions would be negotiated prior to commencement of work.
1. The above pricing is subject to an additional 3% surcharge if client pays with a credit card.

Exclusions from this proposal:

3. Knox caps, new FDC Siamese connection and/or Storz connection are not included in this proposal.
4. Landscaping, irrigation, and/or grass replacement/repair.
5. Structure, tree, & other obstruction removal and/or replacement.
6. Washing, cleaning, & final cleanup of concrete.
7. Engineering
8. Wall penetration.
9. Performance Bonds.
10. Umbrella G.L. Insurance.
11. All work not specifically listed in this proposal.

12. Fire plans, submittal, permits, and or inspections, if desired are not in this quote

Please feel free to contact me if you have any questions concerning this quotation.

Sincerely,

**Wesley Dempsey
Sprinkler / Fire Pump Service Sales
Mobile: 832-497-3097
Office: 281-499-1500**